

School of Civil and Environmental Engineering

Structural Engineering, Mechanics and Materials Research Report No. 02-5

Transfer and Development Length of High Strength Lightweight Concrete Precast Prestressed Bridge Girders

Task 5 Report

DISTRIBUTION STATEMENT A
Approved for Public Release
Distribution Unlimited

Prepared for

Office of Materials and Research Georgia Department of Transportation

GDOT Research Project No. 2004

by

Karl F. Meyer, Lawrence F. Kahn James S. Lai, and Kimberly E. Kurtis

June 2002

20020604 069

Contract Research GDOT Research Project No. 2004

Behavior of High-Strength/High-Performance Lightweight Concrete Prestressed Girders

Prepared for

Office of Materials and Research Georgia Department of Transportation

by

Karl F. Meyer, Lawrence F. Kahn James S. Lai, and Kimberly E. Kurtis

June 2002

The contents of the report reflect the views of the authors who are responsible for the facts and the accuracy of the data presented herein. The contents do not necessarily reflect the official views of policies of the Georgia Department of Transportation. This report does not constitute a standard, specification or regulation.

EXECUTIVE SUMMARY

This report presents the findings of a study that developed and tested high-strength lightweight concrete (HSLC) mixes having strengths from 8,000 psi to 12,000 psi made using slate lightweight aggregate. Based on optimized mix designs, 6 pretensioned AASHTO Type II girders were constructed using 8,000 psi and 10,000 psi slate HSLC and were prestressed using 0.6-inch diameter LOLAX strands tensioned to 75% of strand ultimate stress. The strands received no special preparation prior to girder casting.

After initial curing for approximately 24 hours, transfer length measurements were taken from time of release until the beams reached an age of 14 days. The current AASHTO and ACI code provisions conservatively predicted transfer length for slate HSLC; modification of the current code specifications for transfer length was not necessary for slate HSLC.

A direct pullout test was performed on both concrete design strengths to determine the bond between the slate lightweight concrete and the prestressing strand. A somewhat lower bond stress developed between the prestressing strand and the lightweight concrete when compared to similar strengths of normal-weight concrete. However, the average pullout strength for both series exceeded the minimum required value for 0.6-inch diameter strand of 43.2 kips.

Tests were conducted on each girder end to determine development length characteristics. The distance from the girder end to the load point was varied from

between 70 and 100 percent of the AASHTO specified development length. Strand slip was measured on each test. The current AASHTO and ACI code provisions conservatively predicted development length for slate HSLC; modification of the current code specifications for development length was not necessary for slate HSLC.

Tests were conducted on the center span of each girder to examine shear characteristics of HSLC. The combined center span and girder end shear results showed the current AASHTO Standard specification provided a conservative prediction of concrete and ultimate shear capacity when shear steel capacity was capped at a yield strength of 60 ksi. The alternate design procedure listed in ACI-318 Section 11.4.2.2 for predicting concrete shear strength produced some unconservative predictions for concrete compressive strengths over 10,000 psi. The current AASHTO LRFD specification provided a conservative prediction of ultimate shear capacity for slate HSLC.

An evaluation of girder flexural behavior showed the current prediction of cracking stress and cracking moment, when examined for slate HSLC, showed indications of becoming unconservative as concrete compressive strengths approached 11,000 psi. The use of a lambda factor (λ) of 0.85 for slate HSLC produced conservative results on average for compressive strengths below 11,000 psi. The modulus of rupture test, ASTM C 78, did not accurately predict the cracking stress of HSLC girders. The current AASHTO procedure for ultimate moment calculation was conservative for slate HSLC girders with normal weight concrete decks having a compressive strength under 6,000 psi.

ACKNOWLEDGEMENTS

This research was sponsored by the Georgia Department of Transportation under Georgia DOT Task Order No. 97-22, Research Project No. 2004. Carolina Stalite Company donated all lightweight aggregate for this project. Grace Construction Products donated chemical admixtures and silica fume. Boral Industries donated all class "F" fly ash. Lafarge Corporation (previously Blue Circle Materials) and CEMEX donated all Type III cement. INSTEEL donated all 0.6-inch diameter prestressing strand. General Steel donated all reinforcing steel. Tindall Corporation, Jonesboro, Georgia, provided Georgia Tech researchers with equipment, manpower, and materials for the field production study. These sponsors and their advice and cooperation are gratefully acknowledged.

The conclusions and opinions expressed herein are those of the authors and do not necessarily represent the opinion, conclusions or policies of the Georgia Department of Transportation or of the other sponsors.

The effort of student researchers Brandon Buchberg, Adam Slapkus, Mauricio Lopez, Natalie Hodges and Maria Wilmhoff during all phases of this project is acknowledged and greatly appreciated. Professors Jim Lai and Kim Kurtis provided expert assistance throughout the project.

Charles Freeman and Ken Harmon from Carolina Stalite, Joe Wolfe from Grace Construction Products, and Corey Grieka and Mark Zirbel from Tindall Corporation provided valuable advice and assistance throughout the project.

TABLE OF CONTENTS

	ve Summary	
Acknov	vledgements	iv
List of	Tables	ix
List of	Figures	xv
Notatio	n	xxiii
Chapte	er I – Introduction	1
1.1	Definitions	
1.2	Research Objective	2
1.3	Need for Research	
1.4	Analytical and Experimental Program	3
1.5	Organization of Report	
Chapte	er II – Background Review	6
$2.\overline{1}$	Introduction	
2.2	Terms and Definitions Related to LWC	7
2.3	Production of Slate Lightweight Aggregate	7
2.4	Use of HSLC in Prestressed Bridge Applications	
2.5	HSLC Mix Designs	
2.6	Field Production of HSLC	15
2.7	HSLC Short and Long-Term Properties	16
2.8	Transfer Length	
2.9	Flexural Behavior	26
2.10	Shear Behavior	27
2.11	Development Length	30
2.12	Elements of Bond	38
Chapte	er III – Analytical Investigation of HSLC for Pretensioned Bridge	Girders41
3.1	Introduction	
3.2	Parametric Study	
3.3	Determination of Modulus of Elasticity of HSLC	46
3.4	Girder Design	
3.5	Analysis Results and Discussion	49
3.6	Conclusions	57
Chapte	er IV – Production of HSLC	59
4.1	Introduction	59
4.2	HSLC Components and Properties	59
4.3	Moisture Control	64
11	HSLC Mix Designs	69

4.5	Concrete Mixer	71
4.6	Order of Mixing	
4.7	HSLC Properties	
4.8	Preparation of Specimens	
4.9	Specimen Curing	
4.10	Specimen Testing	
Chapte	er V – Development of HSLC Mix Designs	82
5.1	Introduction.	
5.2	Specimen and Curing Plan	
5.3	Initial Mix Designs from Carolina Stalite	
5.4	Plan for Mix Development	
5.5	Final Mix Designs	
Chapte	er VI — Field Production of HSLC	95
6.1	Introduction	
6.2	Concrete Plant Equipment Description	
6.3	Description of Materials Available at Tindall Concrete	
6.4	Area for Casting Specimens	
6.5	Field Production of HSLC Mixes	
6.6	Results of Field Mixing	
6.7	Conclusions	
Chapte	er VII – Mechanical Properties of HSLC	114
7.1	Introduction	114
7.2	Overview of HSLC Material Testing Program	114
7.3	Specimen Casting Plan	116
7.4	Mix Designs as Determined in Phase 1	117
7.5	Mixes as Batched and Wet Concrete Properties	118
7.6	Compression Strength Results	122
7.7	Modulus of Elasticity Results	
7.8	Modulus of Rupture Results	
7.9	Conclusions	
Chapte	er VIII – Design and Construction of HSLC Pretensioned Bridge Gir	ders142
8.1	Introduction	142
8.2	Design of Experiment	143
8.3	Girder Instrumentation	160
8.4	Girder Construction	
8.5	Composite Deck Construction	
8.6	Direct Pullout Test	
8.7	Material Properties	
8.8	Effective Prestressing Stress and Losses	195
8.9	Girder Section Properties	

Chapte	r IX – Transfer Length Test Results and Discussion	
9.1	Introduction	201
9.2	Definition	201
9.3	Importance of Transfer Length	
9.4	Current Code Provisions	203
9.5	Test Specimens	204
9.6	Measurement of Transfer Length Data	205
9.7	Discussion of Results	
9.8	Comparison of Results with Code Provisions and Proposed Equations	218
9.9	Development of an Improved Transfer Length Equation	227
9.10	Conclusions	237
Chapte	r X – Girder Test Set-up and Procedure	239
10.1	Introduction	
10.2	Test Set-up	
10.3	Instrumentation	
10.4	Data Acquisition System	
10.5	Conduct of Girder Test	245
_	r XI – Flexural Behavior Results and Discussion	
11.1	Introduction	
11.2	Experimental Results	
11.3	Results at Cracking	
11.4	Results at Ultimate	
11.5	Conclusions	271
Chapte	er XII – Shear Behavior Results and Discussion	
12.1	Introduction	
12.2	AASHTO 1996 Standard Shear Design Approach	
12.3	ACI Alternate Approach	275
12.4	AASHTO LRFD Shear Design Approach	
12.5	Variable Angle Truss Model	
12.6	Experimental Measurement of Shear Behavior	
12.7	Experimental Results	
12.8	Conclusions	301
	er XIII – Development Length Test Results and Discussion	
13.1	Introduction	
13.2	Definition	
13.3	Importance of Development Length	
13.4	Current Code Provisions	
13.5	Measurement of Development Length	305

13.6	Development Length Test Results	307
13.7	Discussion of Results	
13.8	Comparison of Results with Code Provisions and Proposed Equations	325
13.9	Development of an Improved Development Length Equation	334
13.10		
C Ib ===4.	www.combatanana.h	• • •
-	er XIV - Conclusions and Recommendations	
14.1	Conclusions	
14.2	Recommendations	346
Referen	1ces	350
Appen	lices	359
Α	Input File Creator for GDOT Computer Program	359
В	Mix Design Spreadsheet	
C	Material Properties	
D	Girder Design Spreadsheet	
E	Load Cell Calibration	
F	Prestressing Stress Calculation	
G	Transfer Length Determination Spreadsheet	
H	Concrete Surface Strain and Other Data	444
I	Smoothed Concrete Surface Strain Profiles	464
J	Transfer Length Data from Other Researchers	477
K	Girder "As-Built" Analysis Spreadsheet	481
L	Load – Deflection and Moment – Curvature Plots	505
M	Photos of Center Span Shear Tests	539
N	Variable Angle Truss Model Plots of Strand Force and Bond Stress	
O	Development Length Data Acquisition Output Processing Spreadsheet	547
P	Development Length Concrete Surface Strain Data Processing Spreadshee	t558
Q	Photos and Strand Stress Plots from Development Length Tests	575
R	Applied Shear vs. Strand Slip and Concrete Surface Strain	
S	Vibrating Wire Strain Gage and Concrete Surface Strain Data	

LIST OF TABLES

Table 2.1	Strength, Weight and Elasticity Modulus Values for Slate HSLC	17
Table 3.1	Critical Girder Design Variables That Remained Constant	46
Table 3.2	Slate HSLC Unit Weight Values	
Table 3.3	Permitting Requirements for Overweight Cargo in Georgia	54
Table 4.1	Stalite LWA Specifications	
Table 4.2	Brown Brothers Natural Concrete Sand Specifications	62
Table 4.3	Material Testing Sheet	70
Table 4.4	Elasticity Modulus and Poisson's Ratio Test Data Sheet	80
Table 5.1	Initial HSLC Mix Designs from Carolina Stalite	
Table 5.2	Air Content Study	85
Table 5.3	Parameters Held Constant in Step 1	86
Table 5.4	Results of Varying Coarse to Fine Aggregate Ratio – Step 1	86
Table 5.5	Parameters Held Constant in Step 2	88
Table 5.6	Results of Varying Percent Cement Paste – Step 2	88
Table 5.7	Parameters Held Constant in Step 3	90
Table 5.8	Results of Varying Percent Cement Paste – Step 3	90
Table 5.9	Mixes for "Strength Ceiling" Study	92
Table 5.10	Results of "Strength Ceiling" Study	
Table 5.11	Objective 8,000, 10,000, and 12,000 psi Mix Designs for Field Testing.	94
Table 6.1	Number of Specimens Cast During Each Field Mixing Test	
Table 6.2	8,000 psi (8F) Field Production Mix	103
Table 6.3	10,000 psi (10F) Field Production Mix	105
Table 6.4	12,000 psi (12F) Field Production Mix	106
Table 6.5	Results of Field Mixing	108
Table 6.6	Resulting Strengths and Allowable Design Strengths	112
Table 7.1	HSLC Material Testing Program Specimen Designation	
Table 7.2	Specimens Cast During Laboratory Verification Batches (Phase 3)	116
Table 7.3	Specimens Cast During Girder Construction Batches (Phase 4)	117
Table 7.4	Objective 8,000, 10,000 and 12,000 psi Mix Designs from Phase 1	
Table 7.5	Girder Construction Batch Information	118
Table 7.6	8,000 psi HSLC Mixes (8F and 8L)	
Table 7.7	8,000 psi HSLC Mixes (G1)	119
Table 7.8	10,000 psi HSLC Mixes (10F and 10L)	120
Table 7.9	12,000 psi HSLC Mixes (12F and 12L)	121
Table 7.10	12,000 psi HSLC Mixes (G2A)	121

Table 7.11	12,000 psi HSLC Mixes (G2B)	122
Table 7.12	Results of 4 x 8 Cylinder Compression Strength Testing	
Table 7.13	Results of 6 x 12 Cylinder Compression Strength Testing	
Table 7.14	Comparison of 4 x 8 to 6 x 12 Cylinder Compression Strengths	128
Table 7.15	Results of Statistical Study	
Table 7.16	Modulus of Elasticity Results	131
Table 7.17	Modulus of Rupture Results	139
Table 8.1	Girder Test Configurations	
Table 8.2	Mix Designs for Girder Placements (2 cubic yard mix)	
Table 8.3	Placement Time; Hours Until Form Removal, Release of Prestress	
Table 8.4	Direct Pull-Out Test Results	
Table 8.5	Girder Concrete Properties	
Table 8.6	Deck Concrete Properties	
Table 8.7	Prestressing Strand Properties	
Table 8.8	Effective Prestressing Stress and Losses	
Table 8.9	Comparison of AASHTO Predicted Losses to Experimental Losses	
Table 8.10	AASHTO Type II Girder Section Properties (Non-Composite Girder)	
Table 8.11	Composite Section Properties	200
Table 9.1	CSS Transfer Length Results (inches)	
Table 9.2	Statistical Analysis of Transfer Length Data	
Table 9.3	Concrete Strength Data	
Table 9.4	Modulus of Elasticity Data	
Table 9.5	Prestressing Levels	
Table 9.6	Summary of Transfer Length Equations	
Table 9.7	Overview of Results Sorted by Equation Source	
Table 9.8	Review of Top Five "Best-Fit" and "Design" Equations	
Table 9.9	Results of Evaluation of the Proposed Equations	236
Table 10.1	Data Acquisition System Components and Functions	244
Table 11.1	Overview of Experimental Results	251
Table 11.2	Cracking Moment Results	
Table 11.3	Cracking Stress Results	265
Table 11.4	Deflection Results at Cracking	
Table 11.5	Moment Results at Ultimate	269
Table 11.6	Deflections at Ultimate	270
Table 12.1	Measured Crack Angles	279
Table 12.2	Overview of Initial Cracking Shears	
Table 12.3	Normalized Diagonal Tension Strength Factors, ξ _t	296
Table 12.4	Predicted vs. Experimental V _u Values	298
Table 12.5	Predicted vs. Experimental V ₁₁ Values for Tests Failing in Shear	299

Table 12.6	Variable Angle Truss Model Results	301
Table 13.1	Embedment Lengths Tested as Percent of AASHTO Predicted Values	306
Table 13.2	Development Length Test Results	308
Table 13.3	Experimentally Determined Development Lengths	
Table 13.4	Applied Shear vs. Strand Slip Results for Single Stirrup Density	319
Table 13.5	Applied Shear vs. Strand Slip Results for Double Stirrup Density	321
Table 13.6	VATM Bond Stress Prediction vs. Strand Slip Results	325
Table 13.7	Concrete Strengths and Prestressing Levels	327
Table 13.8	Summary of Development Length Equations	328
Table 13.9	Overview of Development Length Prediction Results for HSLC	330
Table 13.10	Review of Top Five "Best-Fit" Equations	
	Review of Top Five "Design" Equations	
	Comparison of Proposed Best-Fit Equation With Other Equations	
	Comparison of Proposed Design Equation With Other Equations	
	Proposed Equation Evaluation for Use on HSLC	
Table A.1	Input Values for Girder Design	360
Table A.2	Calculated Values	
Table A.3	Input File for GDOT Prestressed Girder Computer Program	
Table B.1	Mix Design Spreadsheet	364
Table C.1	16-Hour Curebox Cured Specimens	372
Table C.2	24-Hour Curebox Cured Specimens	
Table C.3	28-Day Curebox Cured Specimens	
Table C.4	56-Day Curebox Cured Specimens	
Table C.5	56-Day ASTM Cured Specimens	
Table D.1	Section and Material Properties for Girder Design.	394
Table D.2	Support Conditions, Moment Furnished and Predicted Ultimate Load	
Table D.3	Loss Calculations	
Table D.4	Non-Composite Stress Calculations	397
Table D.5	Composite Stress Calculations	398
Table D.6	Girder Shear Design Calculations (Left of Load)	399
Table D.7	Girder Shear Design Calculations (Right of Load)	
Table D.8	Deck / Girder Interface Shear Calculations	
Table F.1	Prestressing Strand Stress Values at Tensioning and Before Release	409
Table F.2	Calculation of Prestressing Strand Stress Values for Test G1C-W	
Table G.1	Transfer Length Data Taking Sheet	416
Table G.2	Data Worksheet for Girder G1C	417
Table G.3	North Side Gage Locations	

Table G.4	South Side Gage Locations	419
Table G.5	CSS Reading Sheet for 30-inch Top L Embed Strip on North Side	
Table G.6	CSS Reading Sheet for 48-inch Bottom L Embed Strip on North Side	
Table G.7	CSS Reading Sheet for 24-inch Top C Embed Strip on North Side	422
Table G.8	CSS Reading Sheet for 24-inch Bottom C Embed Strip on North Side	
Table G.9	CSS Reading Sheet for 30-inch Top R Embed Strip on North Side	424
Table G.10	CSS Reading Sheet for 48-inch Bottom R Embed Strip on North Side	
Table G.11	CSS Reading Sheet for 30-inch Top L Embed Strip on South Side	
Table G.12	CSS Reading Sheet for 48-inch Bottom L Embed Strip on South Side	
Table G.13	CSS Reading Sheet for 24-inch Top C Embed Strip on South Side	
Table G.14	CSS Reading Sheet for 24-inch Bottom C Embed Strip on South Side	
Table G.15	CSS Reading Sheet for 30-inch Top R Embed Strip on South Side	
Table G.16	CSS Reading Sheet for 48-inch Bottom R Embed Strip on South Side	
Table G.17	Raw Concrete Surface Strains for North Side of Girder G1C	
Table G.18	Raw Concrete Surface Strains for South Side of Girder G1C	
Table G.19	Smoothed Concrete Surface Strains for North Side of Girder G1C	
Table G.20	Smoothed Concrete Surface Strains for South Side of Girder G1C	435
Table G.21	Averaged Raw Concrete Strains for Girder G1C	
Table G.22	Averaged Smoothed Concrete Surface Strains for Girder G1C	
	•	
Table H.1	G1A Girder Data	446
Table H.2	Raw Concrete Surface Strain Data for Girder G1A-North	447
Table H.3	Raw Concrete Surface Strain Data for Girder G1A-South	
Table H.4	G1B Girder Data	
Table H.5	Raw Concrete Surface Strain Data for Girder G1B-North	
Table H.6	Raw Concrete Surface Strain Data for Girder G1B-South	
Table H.7	G1C Girder Data	
Table H.8	Raw Concrete Surface Strain Data for Girder G1C-North	
Table H.9	Raw Concrete Surface Strain Data for Girder G1C-South	
Table H.10	G2A Girder Data	
Table H.11	Raw Concrete Surface Strain Data for Girder G2A-North	
Table H.12	Raw Concrete Surface Strain Data for Girder G2A-South	
Table H.13	G2B Girder Data	458
Table H.14	Raw Concrete Surface Strain Data for Girder G2B-North	
Table H.15	Raw Concrete Surface Strain Data for Girder G2B-South	460
	G2C Girder Data	
	Raw Concrete Surface Strain Data for Girder G2B-North	
Table H.18	Raw Concrete Surface Strain Data for Girder G2B-South	463
Table J.1	Transfer Length Data from Other Researchers Using 0.6-inch Strand	
Table J.1	Continued	
Table J.1	Continued	
Table K.1	Data Acquisition System Output	
Table K.2	Calculated Load, Shear, Moment, Strain and Curvature Values	485

Table K.3	Calculated Principal Strains, Angles, and Maximum Shear Strain	486
Table K.4	Input Values for Girder Tests	
Table K.5	Section Properties for Girder "As-Built"	488
Table K.6	Support Conditions, Reactions, Max Load and Moment Furnished	489
Table K.7	AASHTO Loss Calculations	
Table K.8	Girder Shear Capacity by 1996 AASHTO Standard Procedure	491
Table K.9	Deflection Calculations	492
Table K.10	Variable Angle Truss Model	493
Table K.11	Theoretical Moment-Curvature Stages 1-3 (Elastic Portion)	496
Table K.12	Theoretical Moment-Curvature Stages 4-7 (Cracked Portion)	497
Table K.13	Girder Shear Capacity by 1996 AASHTO LRFD Procedure	500
Table K.14	Girder-Deck Interface Shear Calculations	501
Table K.15	Prestressing Strand Tension Test Curve	502
Table K.16	Principal Strain and Maximum Shear Strain Plots	
Table K.17	Overview of Girder Test Results	
Table L.1	Dimensions "a" and L ₁ for Girder Tests	514
Table O.1	Input Variables	549
Table O.2	Data Acquisition Output	550
Table O.3	Prestressing Strand Tension Curve	551
Table O.4	Load, Shear, Deflection and Strain Values	552
Table O.5	Strand Slip	
Table P.1		561
Table P.2	Initial Readings Prior to Release and Testing; 14-Day Readings (N)	562
Table P.3	Initial Readings Prior to Release and Testing; 14-Day Readings (S)	563
Table P.4	CSS Data Taken During Development Length Testing (N)	564
Table P.5	CSS Data Taken During Development Length Testing (S)	565
Table P.6	Calculated Raw Strains (N)	
Table P.7	Calculated Raw Strains (S)	567
Table P.8	Average Raw Strains	568
Table P.9	Smoothed Strains	
Table P.10	Strand Stress Values Based on Smoothed CSS Values	570
Table P.11	Smoothed CSS Data for Tracking Effect of Surface Cracking	572
Table P.12	Plot of CSS with Information About Crack Formation	573
Table P.13	Prestressing Strand Tension Curve	574
Table S.1	Vibrating Wire Strain Gage Data From Development Length Tests	604
Table S.2	Raw CSS Data for Development Length Test G1A-East	605
Table S.3	Raw CSS Data for Development Length Test G1A-West	606
Table S.4	Raw CSS Data for Development Length Test G1B-East	607
Table S.5	Raw CSS Data for Development Length Test G1B-West	
Table S.6	Raw CSS Data for Development Length Test G1C-East	

Table S.7	Raw CSS Data for Development Length Test G1C-West	610
Table S.8	Raw CSS Data for Development Length Test G2A-East	611
Table S.9	Raw CSS Data for Development Length Test G2A-West	
Table S.10	Raw CSS Data for Development Length Test G2B-East	
	Raw CSS Data for Development Length Test G2B-West	
	Raw CSS Data for Development Length Test G2C-East	
	Raw CSS Data for Development Length Test G2C-West	

LIST OF FIGURES

Figure 3.1	AASHTO Type II – V Sections	43
Figure 3.2	AASHTO-PCI Bulb Tee 54, 63 and 72 Shapes	
Figure 3.3	Diagram of Bottom Flange of Modified Bulb Tee	
Figure 3.4	Modulus of Elasticity vs. Concrete Strength	
Figure 3.5	Modulus of Elasticity vs. Unit Weight of Concrete	
Figure 3.6	Concrete Strength vs. Maximum Length for AASHTO Girders	
Figure 3.7	Concrete Strength vs. Maximum Length for Bulb-Tee Girders	
Figure 3.8	Concrete Strength vs. Maximum Length for Modified Bulb-Tee Girde	
Figure 3.9	Gross Vehicle Weight by Girder Type Based on 8 ksi NWC	
Figure 3.10	Gross Vehicle Weight vs. Maximum Girder Length	56
Figure 4.1	Crushed Slate LWA (3/4-inch Particles) From Carolina Stalite	
Figure 4.2	Close-up of Slate LWA Clinker Showing Voids	
Figure 4.3	Exterior Aggregate Hoppers	
Figure 4.4	Interior Aggregate Hoppers and Cement / Admixture Station	
Figure 4.5	Misting Device Installed Over Interior Aggregate Hoppers	
Figure 4.6	Screens Covering LWA During Moisture Test	
Figure 4.7	Lancaster Model 30 DP Pan Mixer	
Figure 4.8	Casting 4 x 4 x 14 Modulus of Rupture Specimens at Tindall Concrete	
Figure 4.9	Specimen Mold for Creep and Shrinkage Testing	
Figure 4.10	Construction of Block for Cored Cylinder Testing at Tindall Concrete	
Figure 4.11	Casting of Block for Direct Pullout Test at Tindall Concrete	
Figure 4.12	Insulated Curebox Used for Accelerated Curing	
Figure 4.13	Modulus of Elasticity Testing Frame	
Figure 4.14	Modulus of Rupture Test Set-up	81
Figure 5.1	Results of Varying Coarse to Fine Aggregate Ratio	87
Figure 5.2	Results of Varying Percent Cement Paste	
Figure 5.3	Results of Varying Percent Silica Fume	
Figure 5.4	Results of "Strength Ceiling" Study	
Figure 5.5	Strength Results of Laboratory Developed HSLC Mix Designs	94
Figure 6.1	Tindall Concrete Plant, Jonesboro, Georgia	95
Figure 6.2	Tindall Aggregate Bin With Sprinkler	
Figure 6.3	Auger-Type Mixer at Tindall Concrete	
Figure 6.4	Manual Addition of Fly Ash and Silica Fume to Concrete Mixer	98
Figure 6.5	Mix Tower and Tuckerbilt Concrete Transport Vehicle	
Figure 6.6	Casting Specimens at Tindall Concrete	
Figure 6.7	Strength Gain for 4 x 8 Curebox and ASTM Cylinders to 56 Days	
Figure 6.8	Strength Gain for 4 x 8 Curebox and ASTM Cylinders to 365 Days	

Figure 7.1	Compression Strength vs. Cylinder Age for 8,000 psi Mixes	.124
Figure 7.2	Compression Strength vs. Cylinder Age for 10,000 psi Mixes	.124
Figure 7.3	Compression Strength vs. Cylinder Age for 12,000 psi Mixes	.125
Figure 7.4	Modulus of Elasticity vs. Equilibrium Unit Weight	.133
Figure 7.5	Modulus of Elasticity vs. Compression Strength	.133
Figure 7.6	Experimental Modulus of Elasticity Values Normalized by (f _c ') ^{0.5}	.135
Figure 7.7	Low, Mean, and High Unit Weight Values Plotted Using Equation 7.4	.137
Figure 7.8	Low, Mean, and High Unit Weight Values Plotted Using Equation 2.1	.138
Figure 7.9	Low, Mean, and High Unit Weight Values Plotted Using Equation 7.3	.138
Figure 8.1	Concept of Girder Testing Sequence	
Figure 8.2	Test Configuration 1	
Figure 8.3	Test Configuration 2	.151
Figure 8.4	Test Configuration 3	
Figure 8.5	Test Configuration 4	
Figure 8.6	Test Configuration 5	.152
Figure 8.7	Test Configuration 6	.152
Figure 8.8	Test Configuration 7	
Figure 8.9	Test Configuration 8	.153
Figure 8.10	Test Configuration 9	.153
Figure 8.11	Girder Layout A	.154
Figure 8.12	Girder Layout B	.154
Figure 8.13	Girder Layout C	.154
Figure 8.14	Girder Layout A	.157
Figure 8.15	Girder Layout B	
Figure 8.16	Girder Layout C	.159
Figure 8.17	Diagram of DEMEC Embedment Strip Construction and Installation	
Figure 8.18	DEMEC Embedment Strip Placement on Girder	.162
Figure 8.19	Attachment Points for Taut Wire	.162
Figure 8.20	Use of Taut Wire for Deflection Measurement at Midspan	.163
Figure 8.21	VWSG and Thermocouple Prior to Concrete Placement	.164
Figure 8.22	Strand Load Cells Installed at Passive End of Girder Line	
Figure 8.23	Strand Load Cell Monitoring Equipment	.167
Figure 8.24	Strand Designation, Tensioning Order, and Release Order	.168
Figure 8.25	Tindall Personnel Operating Tensioning Machine	.169
Figure 8.26	Jacking of Prestressing Strand	
Figure 8.27	Installation of Shear Reinforcing Steel Near Girder end	.170
Figure 8.28	Formwork with DEMEC Embedment Strips Being Lifted Into Place	.171
Figure 8.29	Tindall Supervisor Directing Placement of Formwork	.172
Figure 8.30	Elevated Mix Platform	
Figure 8.31	Typical Temperature Curing Curve for Girder G1A	
Figure 8.32	Removal of Screws from DEMEC Embedment Strips	
Figure 8.33	Flame Cutting of Prestressing Strands with Oxy-Acetylene Torch	

Figure 8.34	Movement of Girder to Storage Location Using Overhead Crane	.182			
Figure 8.35	Delivery of Girders to Georgia Tech Structures Lab	.183			
Figure 8.36	Formwork for Composite Deck1				
Figure 8.37	Formwork in Place with Temperature and Shrinkage Steel	.186			
Figure 8.38	Formwork Ready for Concrete Placement				
Figure 8.39	Readymix Truck with Conveyor Attachment	188			
Figure 8.40	Mostafa Prestressing Strand Direct Pull-out Test	.189			
Figure 8.41	Direct Pull-Out Results for G1 Series HSLC				
Figure 8.42	Direct Pull-Out Results for G2 Series HSLC	.191			
Figure 8.43	Force-Strain Curve for Prestressing Strand	197			
Figure 9.1	Diagram of f _{se} vs. Distance From Girder End	202			
Figure 9.2	DEMEC Gage	205			
Figure 9.3	DEMEC Gage in Use				
Figure 9.4	Raw CSS Plot for East End of Girder G1C				
Figure 9.5	Smoothed CSS Plot for East End of Girder G1C	212			
Figure 9.6	Transfer Length Determined Using 95 Percent AMS Method	213			
Figure 9.7	Transfer Length vs. fci'	229			
Figure 9.8	Transfer Length vs. $(1/f_{ci'})^{0.5}$	229			
Figure 9.9	Transfer Length vs. E _{ci}	230			
Figure 9.10	Transfer Length vs. E_{ci}	230			
Figure 9.11	Proposed Best Fit Equation Plotted on Transfer Length Data				
Figure 9.12	Proposed Design Equation Plotted on Transfer Length Data	235			
Figure 10.1	Experimental Test Set-up				
Figure 10.2	Load Frame				
Figure 10.3	LVDTs Configured in Strain Rosette	242			
Figure 10.4	Strand Slip Indicators	243			
Figure 10.5	Dial Gage to Measure Interface Slip	243			
Figure 10.6	Data Acquisition System with Power Supplies and Laptop Computer.	245			
Figure 10.7	Girder Testing Checklist	246			
Figure 10.8	Marking of Cracks During Girder Test	249			
Figure 11.1	Typical Flexural Failure Shown in Girder Test G1B-West				
Figure 11.2	Details of Deck Crushing in Girder Test G1B-West				
Figure 11.3	Example of Longitudinal Deck Cracking in Girder Test G1A-East				
Figure 11.4	Moment-Curvature Plot from Girder Test G1B-West				
Figure 11.5	Load-Deflection Plot from Girder Test G1B-West	255			
Figure 11.6	Flexural Failure During Girder Test G2B-East				
Figure 11.7	Close-up of Girder-Deck Interface in Girder Test G2B-East				
Figure 11.8	Girder Test G2A-Center Showing Pure Shear Failure	257			
Figure 11.9	Moment-Curvature Plot for Girder Test G2A-Center				
Figure 11.10	Load-Deflection Plot for Girder Test G2A-Center				
Figure 11 11	Girder Test G1C-East After Strand Slip Induced Shear Failure	260			

Figure 11.12	Girder Test G1C-East Showing 0.2-inch Wide Shear Cracks	260			
Figure 11.13	Moment-Curvature Plot for Girder Test G1C-East				
Figure 11.14	Load-Deflection Plot for Girder Test G1C-East	261			
Figure 11.15	Normalized Rupture Strength Factor, ξ_{cr} vs. fc'				
Figure 12.1	Figure for Calculation of Vult	282			
Figure 12.2	Variable Angle Truss Model for Girder Test G1C-West	284			
Figure 12.3	VATM Strand Force Reduction Plot for Girder Test G1C-West	286			
Figure 12.4	Bond Stress Plot for Girder Test G1C-West	288			
Figure 12.5	Strain Rosette Made with LVDTs on Girder Test G1C-West	289			
Figure 12.6	Plot of Applied Shear vs. Principal Strains for Girder Test G1C-West	290			
Figure 12.7	Second Principal Strain Direction (Cracking Angle) for G1C-West	291			
Figure 12.8	Concrete Shear Strength, Vc vs. Stirrup Spacing				
Figure 12.9	Normalized Diagonal Tension Strength Factor, ξ _t vs. Stirrup Spacing				
Figure 12.10	Normalized Ultimate Shear Capacity, Vu, vs. Stirrup Spacing				
Figure 13.1	Diagram of Components of Development Length, ld	303			
Figure 13.2	Longitudinal Cracking in Deck of Girder G1A-East				
Figure 13.3	G1 Series Girder Average Strand End Slip vs. Embedment Length	.310			
Figure 13.4	G2 Series Girder Average Strand End Slip vs. Embedment Length	.311			
Figure 13.5	G1B-East Strand Stress vs. Distance from Girder End	.313			
Figure 13.6	G1A-East Strand Stress vs. Distance from Girder End	.314			
Figure 13.7	G2C-West Strand Stress vs. Distance from Girder End	.315			
Figure 13.8	Applied Shear vs. Strand Slip (G1A-East) Showing Slip Initiation	.317			
Figure 13.9	Applied Shear vs. Strand Slip (G2C-West) Showing NO Slip Initiation				
Figure 13.10	G1A-East CSS and Shear Cracking vs. Distance from Girder End	.318			
Figure 13.11	Bond Stress Plot Using VATM for Girder Test G1C-East				
Figure 13.12	Comparison of Design and Best-Fit Equations to AASHTO Equation				
Figure C.1	Stress vs. Strain Plot for Shear Reinforcement Steel				
Figure C.2	Stress vs. Strain Plot for "Doghouse Bar" Reinforcement Steel	.378			
Figure E.1	Calibration Curve for Strand Load Cell # 1				
Figure E.2	Calibration Curve for Strand Load Cell # 2				
Figure E.3	Calibration Curve for Strand Load Cell # 3				
Figure E.4	Calibration Curve for Strand Load Cell # 4				
Figure E.5	Calibration Curve for Strand Load Cell # 5				
Figure E.6	Calibration Curve for Strand Load Cell # 6				
Figure E.7	Calibration Curve for Strand Load Cell # 7	.406			
Figure E.8	Calibration Curve for Strand Load Cell # 8				
Figure E.9	Calibration Curve for Strand Load Cell # 9	.407			
Figure E.10	Calibration Curve for Strand Load Cell # 10				
Figure F.1	Vibrating Wire Strain Gage Reader	.410			

Figure F.2	Strand Force vs. Strain Curve for Prestressing Strand	413
Figure G.1	Raw CSS Data for East End of Girder G1C	437
Figure G.2	Raw CSS Data for West End of Girder G1C	
Figure G.3	Smoothed CSS Data for East End of Girder G1C	440
Figure G.4	Smoothed CSS Data for West End of Girder G1C	
Figure G.5	Transfer Length Determined Using 95 Percent AMS for G1C-East	
Figure G.6	Transfer Length Determined Using 95 Percent AMS for G1C-West	.443
Figure I.1	Concrete Surface Strains for G1A-East	
Figure I.2	14-Day Transfer Length Determined for G1A-East	465
Figure I.3	Concrete Surface Strains for G1A-West	.466
Figure I.4	14-Day Transfer Length Determined for G1A-West	.466
Figure I.5	Concrete Surface Strains for G1B-East	
Figure I.6	14-Day Transfer Length Determined for G1B-East	.467
Figure I.7	Concrete Surface Strains for G1B-West	
Figure I.8	14-Day Transfer Length Determined for G1B-West	.468
Figure I.9	Concrete Surface Strains for G1C-East	.469
Figure I.10	14-Day Transfer Length Determined for G1C-East	.469
Figure I.11	Concrete Surface Strains for G1C-West	.470
Figure I.12	14-Day Transfer Length Determined for G1C-West	.470
Figure I.13	Concrete Surface Strains for G2A-East	.471
Figure I.14	14-Day Transfer Length Determined for G2A-East	.471
Figure I.15	Concrete Surface Strains for G2A-West	
Figure I.16	14-Day Transfer Length Determined for G2A-West	.472
Figure I.17	Concrete Surface Strains for G2B-East	
Figure I.18	14-Day Transfer Length Determined for G2B-East	
Figure I.19	Concrete Surface Strains for G2B-West	
Figure I.20	14-Day Transfer Length Determined for G2B-West	
Figure I.21	Concrete Surface Strains for G2C-East	
Figure I.22	14-Day Transfer Length Determined for G2C-East	
Figure I.23	Concrete Surface Strains for G2C-West	
Figure I.24	14-Day Transfer Length Determined for G2C-West	.476
Figure K.1	Force in Prestressing Strands vs. Distance from Girder End	.494
Figure K.2	Prestressing Strand Bond Stress vs. Distance from Girder End	
Figure K.3	Moment-Curvature Plot	
Figure K.4	Load- Deflection Plot	499
Figure L.1	Todeschini Stress Distribution	
Figure L.2	Diagram Showing Variables for Elastic Deflection Calculations	
Figure L.3	"Modified" Curvature Diagram for Ultimate Deflection Calculations	
Figure L.4	"Normal" Curvature Diagram for Ultimate Deflection Calculations	
Figure L.5	Diagram Showing Ultimate Deflection Calculation	519

Figure L.6	G1A-East Moment vs. Curvature Plot	521
Figure L.7	G1A-East Load vs. Deflection Plot	521
Figure L.8	G1A-West Moment vs. Curvature Plot	522
Figure L.9	G1A-West Load vs. Deflection Plot	522
Figure L.10	G1A-Center Moment vs. Curvature Plot	523
Figure L.11	G1A-Center Load vs. Deflection Plot	523
Figure L.12	G1B-East Moment vs. Curvature Plot	
Figure L.13	G1B-East Load vs. Deflection Plot	524
Figure L.14	G1B-West Moment vs. Curvature Plot	525
Figure L.15	G1B-West Load vs. Deflection Plot	525
Figure L.16	G1B-Center Moment vs. Curvature Plot	526
Figure L.17	G1B-Center Load vs. Deflection Plot	526
Figure L.18	G1C-East Moment vs. Curvature Plot	
Figure L.19	G1C-East Load vs. Deflection Plot	527
Figure L.20	G1C-West Moment vs. Curvature Plot	528
Figure L.21	G1C-West Load vs. Deflection Plot	528
Figure L.22	G1C-Center Moment vs. Curvature Plot	529
Figure L.23	G1C-Center Load vs. Deflection Plot	529
Figure L.24	G2A-East Moment vs. Curvature Plot	530
Figure L.25	G2A-East Load vs. Deflection Plot	530
Figure L.26	G2A-West Moment vs. Curvature Plot	531
Figure L.27	G2A-West Load vs. Deflection Plot	531
Figure L.28	G2A-Center Moment vs. Curvature Plot	532
Figure L.29	G2A-Center Load vs. Deflection Plot	532
Figure L.30	G2B-East Moment vs. Curvature Plot	533
Figure L.31	G2B-East Load vs. Deflection Plot	533
Figure L.32	G2B-West Moment vs. Curvature Plot	534
Figure L.33	G2B-West Load vs. Deflection Plot	534
Figure L.34	G2B-Center Moment vs. Curvature Plot	535
Figure L.35	G2B-Center Load vs. Deflection Plot	
Figure L.36	G2C-East Moment vs. Curvature Plot	
Figure L.37	G2C-East Load vs. Deflection Plot	
Figure L.38	G2C-West Moment vs. Curvature Plot	
Figure L.39	G2C-West Load vs. Deflection Plot	
Figure L.40	G2C-Center Moment vs. Curvature Plot	538
Figure L.41	G2C-Center Load vs. Deflection Plot	538
Figure M.1	G1A-Center Crack Patterns	540
Figure M.2	G2A-Center Crack Patterns	540
Figure M.3	G1B-Center Crack Patterns.	
Figure M.4	G2B-Center Crack Patterns	
Figure M.5	G1C-Center Crack Patterns	
Figure M.6	G2C-Center Crack Patterns	542

Figure N.1	G1A-East Strand Force Plot	544				
Figure N.2	G1A-East Bond Stress Plot					
Figure N.3	G1B-East Strand Force Plot					
Figure N.4	G1B-East Bond Stress Plot					
Figure N.5	G1C-East Strand Force Plot.					
Figure N.6	G1C-East Bond Stress Plot	546				
Figure O.1	Load vs. Deflection Plot for Girder Test G1C-West					
Figure O.2	Applied Shear vs. Average Strand Slip for Girder Test G1C-West					
Figure O.3	Load vs. Top of Deck Strain for Girder Test G1C-West	556				
Figure O.4	Load vs. Total Strand Strain for Girder Test G1C-West	557				
Figure P.1	Plot of Strand Stress vs. Distance from Girder End	571				
Figure Q.1	G1A-East Crack Patterns from Development Length Test					
Figure Q.2	G1A-East Strand Stress vs. Distance from Girder End					
Figure Q.3	G1A-West Crack Patterns from Development Length Test					
Figure Q.4	G1A-West Strand Stress vs. Distance from Girder End					
Figure Q.5	G1B-East Crack Patterns from Development Length Test					
Figure Q.6	G1B-East Strand Stress vs. Distance from Girder End					
Figure Q.7	G1B-East Crack Patterns from Development Length Test					
Figure Q.8	G1B-East Strand Stress vs. Distance from Girder End					
Figure Q.9	G1C-East Crack Patterns from Development Length Test	581				
Figure Q.10	G1C-East Strand Stress vs. Distance from Girder End					
Figure Q.11	G1C-East Crack Patterns from Development Length Test					
Figure Q.12	G1C-East Strand Stress vs. Distance from Girder End					
Figure Q.13	G2A-East Crack Patterns from Development Length Test	583				
Figure Q.14	G2A-East Strand Stress vs. Distance from Girder End	583				
Figure Q.15	G2A-West Crack Patterns from Development Length Test	584				
Figure Q.16	G2A-West Strand Stress vs. Distance from Girder End	584				
Figure Q.17	G2B-East Crack Patterns from Development Length Test	585				
Figure Q.18	G2B-East Strand Stress vs. Distance from Girder End					
Figure Q.19	G2B-West Crack Patterns from Development Length Test					
Figure Q.20	G2B-West Strand Stress vs. Distance from Girder End					
Figure Q.21	G2C-East Crack Patterns from Development Length Test	587				
Figure Q.22	G2C-East Strand Stress vs. Distance from Girder End	587				
Figure Q.23	G2C-West Crack Patterns from Development Length Test	588				
Figure Q.24	G2C-West Strand Stress vs. Distance from Girder End					
Figure R.1	G1A-East Applied Shear vs. Average Strand Slip	591				
Figure R.2	G1A-East CSS and Shear Cracking vs. Distance from Girder End					
Figure R.3	G1A-West Applied Shear vs. Average Strand Slip					
Figure R.4	G1A-West CSS and Shear Cracking vs. Distance from Girder End					
Figure R.5	G1B-East Applied Shear vs. Average Strand Slip					

Figure R.6	G1B-East CSS and Shear Cracking vs. Distance from Girder End	593
Figure R.7	G1B-West Applied Shear vs. Average Strand Slip	594
Figure R.8	G1B-West CSS and Shear Cracking vs. Distance from Girder End	594
Figure R.9	G1C-East Applied Shear vs. Average Strand Slip	595
Figure R.10	G1C-East CSS and Shear Cracking vs. Distance from Girder End	595
Figure R.11	G1C-West Applied Shear vs. Average Strand Slip	596
Figure R.12	G1C-West CSS and Shear Cracking vs. Distance from Girder End	596
Figure R.13	G2A-East Applied Shear vs. Average Strand Slip	597
Figure R.14	G2A-East CSS and Shear Cracking vs. Distance from Girder End	597
Figure R.15	G2A-West Applied Shear vs. Average Strand Slip	598
Figure R.16	G2A-West CSS and Shear Cracking vs. Distance from Girder End	598
Figure R.17	G2B-East Applied Shear vs. Average Strand Slip	599
Figure R.18	G2B-East CSS and Shear Cracking vs. Distance from Girder End	599
Figure R.19	G2B-West Applied Shear vs. Average Strand Slip	600
Figure R.20	G2B-West CSS and Shear Cracking vs. Distance from Girder End	600
Figure R.21	G2C-East Applied Shear vs. Average Strand Slip	601
Figure R.22	G2C-East CSS and Shear Cracking vs. Distance from Girder End	601
Figure R.23	G2C-West Applied Shear vs. Average Strand Slip	602
Figure R.24	G2C-West CSS and Shear Cracking vs. Distance from Girder End	602

NOTATION

Report	ACI 318- 99	AASHTO Standard	Description
A_{c}			Cross sectional area of composite girder (combined area of girder and deck)
A _{nc}			Cross sectional area of girder
AASHTO			American Association of State Highway and Transportation Officials
A_{ps}	A_{ps}	A _s *	Cross sectional area of prestressing strand
A_{pse}			Effective area of prestressed reinforcement adjusted inside the transfer or development length regions
BCL			Distance from bottom of girder to center line of bottom row of prestressing strands
CM			Cementitious Materials
CSS			Concrete Surface Strain
DAQ			Data Acquisition
d_b	d _b	D	Diameter of prestressing strand
DEMEC			Detachable Mechanical Strain Gage
d_p	d_p	d	Distance from compression fiber to centroid of prestressed reinforcement
Ec	Ec	Ec	Modulus of elasticity of concrete based on 6 x 12 cylinder
Eci			Modulus of elasticity of concrete based on 6 x 12 cylinder at strand release
f _c '	f _c '	f _c '	Concrete compressive strength at specified time
f _{ci} '	f _{ci} '	f _{ci} '	Concrete compressive strength at strand release
f_r	f _r	f_r	Modulus of rupture of concrete
$ m f_{pc}$	f_{pc}	$ m f_{pc}$	Resultant compressive stress at the centroid of the composite section or at the junction of the web and flange when the centroid lies within the flange due to both prestress and moments resisted by the precast member acting alone.
\mathbf{f}_{ps}	f _{ps}	f _{su} *	Stress in prestressed reinforcement at nominal strength of member
f_{pt}			Stress in prestressing strand just prior to strand release
f_{pu}	f_{pu}	fs'	Specified tensile strength of prestressed reinforcement
f_{se}	f _{se}	f _{se}	Effective prestressing stress after losses
$ m f_{si}$		wi.en	Stress in prestressing strand just after strand release
f _y	f_y	\mathbf{f}_{sy}	Specified yield strength of non-prestressed reinforcement

Report	ACI 318- 99	AASHTO Standard	Description
h	h	h	Overall depth of the composite girder
I_c			Moment of inertia of composite girder (girder and deck)
I_{nc}			Moment of inertia of girder
l_d	l _d		Development length of prestressing strand (In AASHTO Standard, l _d refers to non-prestressed reinforcement development length)
l _{fb}			Flexural bond length. Additional length over which the strand should be bonded so the stress f_{ps} may develop in the strand at the nominal strength of the member.
1 _t			Transfer length of prestressing strand
LOLAX			Low relaxation loss prestressing strand
$M_{ m DL}$	1		Moment due to Dead Load
n	n		Modular Ratio
S _{top-nc}			Top section modulus for non-composite girder
S _{bot-nc}	1		Bottom section modulus of non-composite girder
S _{top-c}	1		Top section modulus for composite girder
S _{bot-c}	-		Bottom section modulus for composite girder
TCL	-	4 00 660	Distance from top of girder to center line of top row of prestressing strands
W/CM			Water to Cementitious Materials Ratio
V _c	V_{c}	V_c	Nominal shear strength provided by concrete
V _{ci}	V_{ci}	$ m V_{ci}$	Nominal shear strength provided by concrete when diagonal cracking results from combined shear and moment
V _{cw}	V_{cw}	V _{cw}	Nominal shear strength provided by concrete when diagonal cracking results from excessive principal tensile stress in the web
V_{s}	V_s	V_s	Nominal strength provided by shear reinforcing steel
VWSG			Vibrating Wire Strain Gage

CHAPTER I

INTRODUCTION

Advances in concrete quality and engineering practices have enabled the design and construction of precast prestressed concrete bridge girders that approach 200 feet in length. Problems occur when trying to move and erect these long and heavy girders. In order to facilitate easier road movement and erection, high-strength lightweight concrete (HSLC) can be used to reduce member self-weight while still allowing a large load carrying capacity.

Previous research conducted relating to lightweight concrete (LWC) used in prestressed applications involved concrete with compressive strengths less than 7,500 psi. While this research is important and in most cases relevant, it does not verify current design procedures for use on higher strength lightweight concretes. There appears to have been little to no research conducted focusing on the use of HSLC for the construction of pretensioned bridge girders despite the fact that current articles indicate a belief that its use would be very beneficial.¹

Additional research efforts are necessary in many areas before engineers can safely and confidently use HSLC in the design of pretensioned bridge girders.

1.1 Definitions

Transfer length is defined as the distance required to transfer the effective prestressing force from the strand to the surrounding concrete. Development length is defined as the sum of the "transfer length" and the "flexural bond length." The flexural bond length is the additional length of pretensioning strand beyond the transfer length over which bond is developed to allow the strand to reach the stress level f_{ps} at the nominal flexural strength of the member. Development length can also be defined as the minimum distance from the end of the member beyond which the application of a point load will result in a flexural failure. Transfer length and development length are covered in detail in Chapters 9 and 13.

1.2 Research Objectives

The research objectives of this project were as follows:

- 1. To determine the transfer length, l_t, characteristics of 0.6-in prestressing strand used with slate HSLC.
- 2. To determine the development length, l_d, characteristics of 0.6-in prestressing strand used with slate HSLC.
- To verify current code provisions for transfer and development length as appropriate for use with slate HSLC and to suggest more appropriate equations if necessary.
- To determine the effect of shear reinforcement spacing on strand slip,
 development length, and shear capacity of pretensioned slate HSLC
- 5. Findbreemine the shear strength, V_c, of pretensioned slate HSLC.

- 6. To verify current code provisions for shear strength of slate HSLC.
- To verify the current code-specified reduction factor, λ, for sand
 lightweight concrete as related to concrete tensile strength, and suggest a
 more appropriate factor if necessary.

1.3 Need for Research

This research was necessary because girders constructed with slate HSLC with a strength approaching 12,000 psi and 0.6-in pretensioning strand had not been tested previously. The Georgia Department of Transportation wanted to use precast prestressed bridge girders with spans of 150 ft and with gross weights less than 150 kips. To achieve such designs, concrete with strengths of about 10,000 psi and unit weights less and 125 pcf would be required. Neither the concrete materials nor behavior of girders made with such material shad been investigated previously.

1.4 Analytical and Experimental Program

The analytical and experimental program involved the following six phases:

- 1. Analytically evaluate if HSLC bridge girders using 0.6-in diameter strand could achieve the 150 ft and 150 kip gross weight requirements.
- 2. Develop slate HSLC mix designs to meet objective strengths of 8,000, 10,000 and 12,000 psi under laboratory conditions.
- 3. Produce the laboratory-developed HSLC mix designs in a field environment at a commercial concrete plant.
- 4. Determine the mechanical properties of the slate HSLC.

- Design, construct, and test six full-scale AASHTO Type II pretensioned girders using the slate HSLC to determine transfer and development length, shear, and flexural behavior characteristics.
- 6. Evaluate the girder behavior with respect to current design specifications.

1.5 Organization of Report

This report begins with a background review in Chapter II that covers the manufacture of slate lightweight aggregate, the use and field production of HSLC, HSLC short and long-term properties, the origins of transfer and development length, and shear behavior in pretensioned girders.

Chapters III through VII focus on HSLC as a material. Chapter III provides an analytical investigation to determine required HSLC properties to construct the objective pretensioned bridge girders. Chapter IV provides information on the components of HSLC, moisture control, mixing, and preparation and testing of specimens. Chapter V discusses the development of HSLC mix designs. Chapter VI discusses the field production of HSLC mix designs in a commercial concrete plant. Chapter VII covers the mechanical properties of HSLC as required for the evaluation and testing of the six HSLC girders. Chapter VIII provides details on the design and construction of the AASHTO Type II girders. Chapter IX covers the determination of transfer length, evaluation of current code provisions, and the development of a new equation to predict transfer length. Chapter X addresses the procedures for test set-up and conduct of the test. Chapter XI provides flexural behavior results of the 18 girder

behavior results to include an evaluation of current code provisions. Chapter XIII covers development length test results, examines the effect of cracking in the transfer region, examines current code provisions, and suggests a new equation to predict development length.

Chapter XIV provides conclusions and recommendations based upon this research project.

CHAPTER II

BACKGROUND REVIEW

2.1 Introduction

Much research has been published on lightweight concrete, however, only a small portion of it focuses on high-strength lightweight concrete used for pretensioned bridge girders. In most cases the research involved concrete with compressive strengths less than 7,500 psi. While this research is important and in most cases relevant, it does not verify current code provisions for use on higher strength lightweight concretes (HSLC) commercially available today. In addition, since the properties of lightweight aggregate (LWA) vary based on the raw material from which it is made and the production technique, a direct comparison is not always possible.

This review provides information on both HSLC and normal weight concrete. Initially, the review covers terms and definitions related to lightweight concrete. The production of slate lightweight aggregate is described and a review of the use of HSLC in prestressed bridge applications is provided. Previously developed HSLC mix designs are described and comments about their production in a field environment are discussed. The development of equations to predict transfer length in normal weight concrete is reviewed and current research on transfer length is summarized. Information on shear relating to findings in this research is provided as well as a review of other ongoing research. The

review culminates with a summary of the development of equations to predict prestressing strand development length as well as a review of other related research.

2.2 Terms and Definitions Related to Lightweight Concrete

The following terms are used throughout this report:

Lightweight Aggregate (LWA) – Aggregate with a dry, loose unit weight of 70 lb/ft³ or less.²

Lightweight Concrete (LWC) - A general term that includes "all-lightweight concrete" and "sand-lightweight concrete" defined below.²

All-Lightweight Concrete (ALWC) - Concrete containing all lightweight aggregate and does not exceed 115 lb/ft³.²

Sand-Lightweight Concrete (SLWC) - Lightweight concrete in which all the all of the fine aggregate consists of normal weight sand.²

Normal-Weight Concrete (NWC) - Concrete having a unit weight of approximately 145 lb/ft³.

High-Performance Concrete (HPC) – Concrete having a strength over 6,000 psi and/or having durability characteristics in excess of minimally accepted standards.

High-Strength Lightweight Concrete (HSLC) - Concrete meeting the conditions of lightweight concrete and having a compressive strength greater than 6,000 psi.

2.3 Production of Slate Lightweight Aggregate

The expanded slate LWA used in this research is produced from argillite slate found in the foothills region of North Carolina east of Charlotte. Found in a geologic

formation known as the "Tillery Formation," the slate is a thinly laminated, fine-grained siltstone composed of clastic (transported) rock fragments. The slate was from rock fragments of volcanic ash origin, which were deposited in a water environment and later solidified into solid rock. Subsequent burial and tectonic pressure changed the rock into argillite slate. Currently, the Tillery Formation is the only source of slate used to produce expanded slate LWA.³

Expanded slate LWA is produced using a rotary kiln approximately 11 feet in diameter and 160 feet in length. The rotary kiln is constructed on a slight incline on large bearings. The inside of the kiln is lined with insulation and a refractory material to protect the thick outer steel casing. Raw slate enters the kiln through pre-heaters that slowly heat the rock. Once in the kiln, the raw slate slowly tumbles within as it moves down the slight incline towards the "burn zone" where the raw material ultimately reaches temperatures in excess of 2200 degrees Fahrenheit. The kilns are normally heated by injecting coal dust or natural gas at the low end. In the "burn zone" the slate becomes sufficiently plastic for small gas pockets within the slate to expand forming masses of small, unconnected cells. As the expanded slate cools, the cells remain providing the material its low unit weight and absorption characteristics. The expanded material called clinker, exits the kiln and is either air or water cooled depending on the manufacturing process and is then crushed to the desired gradations.³

2.4 Use of LWC for Prestressed Bridge Applications

The following comments describe many of the known uses of LWC and in some cases HSLC in bridge applications. Many of the applications were not in pretensioned

bridge girders, but demonstrate the feasibility of LWC and HSLC in prestressed construction.

Raithby and Lydon⁴ described the use of LWC for highway bridges in North

America and various countries in Europe. Their overall summary of said bridges was
that performance was satisfactory and durability was at least as good as NWC. In cases
where performance was not satisfactory, improper detailing or quality control was at
fault. They describe several advantageous aspects of LWC including weight savings and
reduced superstructure requirements, reduced cost of foundations, and reduced handling
costs.

Bender⁵ made many of the same conclusions as Raithby and Lydon after performing a cost analysis on the construction of a prestressed concrete bridge. His main assertion was that the reduced weight of LWC allowed the casting of fewer larger pieces thus less total pieces were required to be moved during construction.

Brown and Davis⁶ conducted a study on the long-term performance of a prestressed LWC used in a bridge in Fanning Springs, Florida. Initially built in the early 1960s with 121.5-ft AASHTO Type IV girders using 6,500-psi concrete weighing 120 pcf; the bridge underwent a comprehensive load test in 1968 and again in 1992. In comparing data from the two tests, the deflections were very close. Taking into account a margin of error, there was no change in the deflection values. Overall, Brown and Davis felt the bridge performed very well.

Janssen⁷ wrote about the Shelby Creek Bridge in Pike County, Kentucky. The use of 7,000 psi HSLC reduced hauling and lifting weights and reduced dead loads on the

structure. The post-tensioned girders were 8.5 feet deep and were made with SLWC having a unit weight of 130 pcf.

Roberts⁸ reported on the use of LWC for bridges in California again emphasizing the importance of reduced weight. He noted that successful use of LWC demanded accurate knowledge of shrinkage, creep and modulus coefficients.

Murillo, Thoman and Smith¹ described the use of LWC for design on the Benicia-Martinez Bridge across San Pablo Bay, California. In addition to being the least expensive alternative, the reduced weight of the structure was also more appealing from the standpoint of seismic design.

A publication from the Expanded Shale, Clay and Slate Institute (ESCSI)⁹ provided a listing of the most significant uses of LWC for bridges worldwide. Of particular note were three bridges using pretensioned bridge girders including the Coronado Bay Bridge in California, the Lewiston Pump-Generating Plant Bridge in New York, and the Sebastian Inlet Bridge in Florida. All constructed in the 1960s, the bridge girders used LWC with a compressive strength between 5,000 and 6,000 psi. When the publication was issued in 1994, all the bridges were reported to be in excellent condition.

Melby, Jordet and Hansvold¹⁰ described the use of HSLC for long-span bridges in Norway. The authors commented that LWC has been used for bridges in Norway since 1987. Their recommendations focused on testing mix designs thoroughly and ensuring excellent quality control to obtain consistent properties. They stated that the use of LWC was economical for long span bridges, but that bridge geometry would determine the

amount of savings. Compressive strengths up to 8,700 psi with a unit weight of 125 pcf were successfully used to construct the Raftsundet Bridge.

Holm and Bremner¹¹ noted that LWC was a very promising alternative for the replacement of functionally obsolete bridges throughout the United States. In many cases, the use of LWC for deck replacement would allow upgrading bridge capacity based on lower deck dead load. The authors cited as an example the Woodrow Wilson Memorial Bridge in Washington, D. C. By replacing the bridge deck with LWC, engineers reduced the dead load on the structure and were able to add an additional lane of traffic without exceeding the load carrying capacity of the structure.

2.5 HSLC Mix Designs

2.5.1 Coarse Aggregate

Coarse aggregate is a primary factor in developing a mix design that is lightweight, high-strength, and cost effective. Manufactured lightweight coarse aggregates include expanded clays, expanded shales, expanded slates, expanded perlite, exfoliated vermiculite, and sintered fly ash. Lightweight coarse aggregates also occur naturally in the form of pumice and tuff. Depending on the source of the aggregate, the particle shape and surface texture vary significantly impacting all other aspects of the mix design and the placement characteristics of the concrete. Numerous authors commented on the need for specifications by particular aggregate manufacturer or source with respect to design characteristics. 12,13,14

The raw material from which the LWA is produced determines the strength of the aggregate and thus the strength that can be achieved in the concrete. Expanded slate aggregates are normally recognized as being one of the LWA products able to produce the highest compressive strength and modulus of elasticity.

The porosity of the LWA determines the degree to which the aggregate will absorb and release water and varies significantly between LWA types. Based on an absorption test using ASTM C 127¹⁵ and ASTM C 128¹⁶, the absorption of LWA can vary from 5 percent to over 25 percent moisture by mass of dry aggregate as compared to less than 2 percent for normal weight aggregate. Knowledge of the exact absorption characteristics of the chosen LWA is important in properly batching LWC. In addition, handling and quality control must be more exact when working with LWA. Bremner and Newman¹⁷ found that the internal microstructure of each type of LWA was independent of the source.

A reduction in the maximum size of coarse aggregate can increase compressive strength without increasing the cement content or reducing the water-cement ratio. 18

2.5.2 Fine Aggregate

The addition of fine LWA to a mix design further lowers the unit weight of the concrete; however, other characteristics are impacted. In a study by Pfeifer, various amounts of the lightweight fine aggregate fraction were replaced with normal weight sand. The results showed that increasing the proportion of normal weight sand increased both compressive strength and modulus of elasticity.

2.5.3 Portland Cement

In HSLC mixes, the cement paste matrix must carry a higher portion of the load imposed on the concrete. As the strength limit of the cement paste matrix is reached, strength of the aggregate and interface between the aggregate and cement paste become the limiting factors.³

The type of cement used in the mix determined its curing characteristics. Use of a Type I/II cement results in lower initial strengths, but slightly higher strengths after 28 days. The use of Type III cement yields higher compressive strengths initially, which was desirable for prestressed construction, but results in slightly lower strengths at 28 days compared to Type I/II.

2.5.4 Silica Fume

The inclusion of silica fume in LWC mix designs was reported to significantly improve strength and other performance characteristics. Fujii et al.²⁰ reported results of a study where they showed a silica fume blended cement to provide superior strength results compared to a belite-rich cement. In a study including high-strength NWC and HSLC, Leming²¹ reported that silica fume was particularly effective in increasing the compressive strength of any concrete. Mor²² reported the dramatically improved bond strength between LWC and reinforcing steel based on the use of silica fume, an occurrence that was verified during this research.

2.5.5 Moisture Content

Control of moisture in HSLC is critical. In order to produce concrete having the water to cementitious materials ratio desired, the exact absorbed (moisture within the pore structure of the LWA) and adsorbed (moisture on the outside surface of the LWA – free moisture) moisture of the aggregate must be known. The amount of absorbed moisture directly impacts the specific gravity of the LWA as proportioned and mixed. Smeplass²³ made this point very clear by stating "The consequence of this observation may be that the mix water absorption of LWA must be determined in the actual initial moisture condition, as under concrete production, and as often as necessary to detect variation."

Based on the porosity of LWA, the determination of absorbed moisture content and specific gravity must be handled differently than with normal weight aggregate. Holm and Valsangkar²⁴ suggested a 1-day soak of LWA prior to determining specific gravity using a pycnometer. After soaking the aggregate for 24 hours, the additional water absorbed in the pycnometer during specific gravity testing is minimal. Based on the then determined absorbed moisture content, the dry specific gravity could be determined by dividing the 24-hour soak specific gravity by (1 + absorbed moisture content).

2.5.6 Mix Proportioning

Mix proportioning of LWC is covered in ACI 211.2-91. The current guide does not cover mix designs for concrete in excess of 6,000 psi strength.

2.6 Field Production of HSLC

Comments on field production of HSLC were limited. Holm and Bremner¹¹ suggested four basic principles including well-proportioned, workable mixtures that use a minimum amount of water, equipment capable of expeditiously moving the concrete, proper consolidation in the forms, and quality workmanship in finishing. If the concrete is to be pumped, they suggested insuring the aggregate absorbed moisture content was maintained at a high level by presoaking. In the event of low absorbed moisture, pumping could force mix water into the LWA pores reducing the workability of the mix.

Valum and Nilsskog²⁵ reported on field production of HSLC having a compressive strength of 8,700 psi for the construction of the Raftsundet Bridge in Norway. Field production included steps to insure expanded slate aggregate absorption was maintained at between 7 and 9 percent to prevent mix water absorption. The time from batching until concrete placement could be as long as 2 hours. In addition, bulk density and surface moisture were determined prior to each concrete placement to insure proper mix proportioning. Prior to a concrete truck leaving the batch plant, concrete temperature, slump, air content and wet density were checked for compliance with design specifications. Any results out of specification resulted in the mix being discarded. While these standards would be common for the production of normal weight HPC, the more exacting control of aggregate moisture content was evident for HSLC. In addition, exact control of moisture also enabled better control of unit weight.

Hoff²⁶ described field production of HSLC for offshore platform construction.

Many of the same steps were followed as mentioned by Valum and Nilsskog. Hoff

reiterated the importance of moisture control and the impact it could have on slump loss during placement and also commented that excessive moisture could result in unsuitable resistance to freezing and thawing damage.

2.7 HSLC Short and Long-Term Material Properties

The following sections address specific material properties and material related phenomenon where differences were noted between HSLC and NWC.

2.7.1 Modulus of Elasticity

An in-depth explanation of the determination of modulus of elasticity is covered in Chapter 3, Analytical Investigation on HSLC for Pretensioned Bridge Girders.

The current ACI² equation for modulus of elasticity is:

$$E_c = 33w_c^{1.5}\sqrt{f_c^{'}} {(2.1)}$$

An equation by Morales²⁷ (Equation 2.2) was suggested for use with lightweight concrete.

$$E_c = (40,000\sqrt{f_c'} + 1,000,000) \left(\frac{w_c}{145}\right)^{1.5}$$
 (2.2)

Table 2.1 lists compressive strengths, dry (equilibrium) unit weights and modulus values reported by various authors for slate HSLC mix designs having compressive strengths between 6,000 and 12,000 psi.

Table 2.1 Reported Strength, Weight and Elasticity Modulus Values for Slate HSLC

	Compressive	Dry Unit	Modulus of
A41(-)	Compressive		1
Author(s) or	Strength	Weight	Elasticity
Source	f _c '	w	E_{c}
	(psi)	(pcf)	(million psi)
Brown	6.500	100	2 22
Davis ⁶	6,500	120	3.90
Leming ²⁸	7,180	116.4	3.58
FIP Committee ²⁹	7,500	118.6	3.55
Harmon ³	8,170	111.7	3.27
Bilodeau			
Chevrier	9,090	119.2	4.06
Malhotra			
Hoff ³⁰			
Valum	9,550	123.0	3.41
Nilsskog ²⁵			
Mor ²²	9,650	130.0	3.91
Holm	9,856	117.0	3.50
Bremner ³¹			
Carolina Stalite Company ³²	10,281	126.0	4.10
Harmon ³	10,980	119.2	3.95
Harmon ³	11,500	134.0	4.40
Carolina Stalite Company ³²	11,588	132.0	4.40
Harmon ³	11,850	122.0	4.56

2.7.2 Strength Ceiling

Harmon³ discussed a strength ceiling for HSLC being in the region of 12,000 to 13,000 psi based on the limiting strength of the slate LWA. Holm³³ also discussed the strength ceiling with respect to smaller maximum size of aggregate. As the maximum size of aggregate is reduced, strength increases to some upper limit determined by the

strength ceiling. Beyond the strength ceiling, additional binder does not increase the concrete's strength.

Bremner and Holm³⁴ addressed the elastic mismatch between LWA and the highstrength cement paste matrix. As the HSLC strength increases, the difference between the elasticity modulus values becomes more pronounced. Under load, the "elastic mismatch" results in fracture that begins as transverse splitting of the LWA. This splitting action is indirectly responsible for the strength ceiling of HSLC.

Holm³³ also reported a tensile strength ceiling for LWC. Since the LWA is approximately one half voids, its tensile strength will be reduced in comparison to NWA. Holm suggested the LWA tensile strength ceiling might also be responsible for compression strength limitations.

2.7.3 Internal Curing

Internal curing results when absorbed water in the LWA provides an internal reservoir to enhance cement hydration and extend the curing process. Several authors have commented on this phenomenon as related to LWC and HSLC. 21,33,35 Bremner, Holm and Ries 36 performed a study in which LWA was added to NWC mixes to provide additional internal cure water in mixes having strengths from 6,400 psi to 8,700 psi. The internal curing is reported to not only add in strength gain, but positively impacts durability characteristics by providing a higher quality and denser matrix.

2.8 Transfer Length

Transfer length is defined as the distance required to transfer the effective prestressing force from the strand to the surrounding concrete. The transfer length is developed when the pretensioning strands are released by flame cutting or other method from the restraining abutments. Numerous factors are thought to contribute to determining the transfer length including size and surface condition of the prestressing strand, concrete strength and modulus of elasticity at time of strand release, level of prestressing in the strand, and the amount of confining steel and concrete consolidation in the transfer length region. Many experimental programs have focused on the above factors in determining a relation to predict transfer length.

The Master's Thesis by Chris Reutlinger,³⁷ "Direct Pull-Out Capacity and Transfer Length of 0.6-Inch Diameter Prestressing Strand in High Performance Concrete" provides very thorough coverage of the history and development of equations to predict transfer length. The following is a summary of current code provisions and other proposed equations as determined for NWC. There are no known proposed equations specifically addressing transfer length for HSLC.

2.8.1 Janney, 1954

Initial transfer length testing by Janney³⁸ in 1954 concluded that transfer length and the general shape of the stress transfer distribution were attributable to diameter and surface condition of the prestressing wire and concrete strength. Janney did not suggest a relation for predicting transfer length.

2.8.2 Hanson and Kaar, 1959

Although the focus of Hanson and Kaar's³⁹ work was on flexural bond, an appendix included comments on an assumed average transfer bond stress of 400 psi. Equation 2.3 was proposed as a way to determine the transfer bond stress.

$$u_t = \frac{A_{ps} f_{se}}{\Sigma_0 l_t} \tag{2.3}$$

 A_{ps} is the area of prestressing strand, f_{se} is the effective prestressing stress at transfer, Σ_{o} is the actual perimeter of the prestressing strand, l_{t} is the transfer length and u_{t} is the transfer bond stress.

2.8.3 Kaar, LaFraugh and Mass, 1963

Kaar et al.³⁷ concluded that transfer length varied directly based on strand diameter for ¼-inch and ½-inch strands but did not follow this same direct proportion for 0.6-inch strand. Kaar et al. found concrete strength did not impact transfer length, but affected the shape of the stress distribution. Higher concrete strength allowed the concrete to pick up stress more quickly when compared to lower strength specimens. Kaar et al. also reported differences in transfer length between "dead" and "cut" ends.

2.8.4 Mattock, 1963

In 1963, Mattock³⁷ used Equation 2.3 with an assumed average transfer bond stress of 400 psi to derive the current ACI² equation for transfer length. The factors 0.725 and 4/3 were used to determine the actual area and perimeter respectively.

$$l_{i} = \frac{\left(0.725 \frac{\pi d_{b}^{2}}{4}\right) f_{se}}{\left(\frac{4}{3} \pi d_{b}\right) 0.4} = \frac{1}{2.94} f_{se} d_{b}$$
 (2.4)

Equation 2.4 was simplified to Equation 2.5, which is the current ACI¹²² expression.

$$l_t = \frac{f_{se}d_b}{3} \tag{2.5}$$

Mattock assumed the effective stress, f_{se} , for 250 ksi strand was 150 ksi and further simplified Equation 2.5 to Equation 2.6, which was adopted by ACI in 1963 and AASHTO⁴⁰ in 1973.

$$l_t = 50d_b \tag{2.6}$$

Equation 2.6, currently maintained by AASHTO, is based on a limited number of tests where strand ultimate strengths were less than products available today.³⁷

2.8.5 Martin and Scott, 1976

Martin and Scott⁴¹ re-evaluated previous testing by Hanson and Kaar based on prestressing strand having an ultimate strength, f_{pu}, of 270 ksi, and commonly encountered strand surface conditions, and they recommended the implementation of Equation 2.7.

$$l_t = 80d_b \tag{2.7}$$

2.8.6 Zia and Mostafa, 1977

Based on an extensive review of transfer length testing, Zia and Mostafa⁴² proposed Equation 2.8 to account for the effects of strand diameter, initial level of prestress, and concrete strength at transfer. Equation 2.9 was reported to be applicable for concrete strengths from 2,000 to 8,000 psi. This evaluation is reported in Chapter 9.

$$l_{t} = 1.5 \frac{f_{si}}{f_{ci}} d_{b} - 4.6 \tag{2.8}$$

2.8.7 FHWA Memorandum, 1988

Based on testing at the University of North Carolina in 1986 where poor transfer and development length results were recorded, the FHWA issued a memorandum specifying four interim restrictions, one of which was the restriction from using 0.6-inch

prestressing strand.³⁷ This restriction prevented the prestressed concrete industry from fully utilizing the benefits of higher strength concretes in larger members. Several research programs were initiated based on the FHWA restrictions.

2.8.8 Deatherage, Burdette and Chew, 1989

Deatherage et al.⁴³ conducted experimental testing on 20 AASHTO Type I girders with varying strand diameters and spacings. Their conclusions were that 0.6-inch diameter strand should be allowed and that strand spacing of 1.75 inches should be allowed for ½-inch diameter strand. Equation 2.10 was suggested for the calculation of transfer length for ½-inch, ½-inch special and 9 /₁₆-inch diameter prestressing strand. Equation 2.9 was conservative and acceptable for use on 0.6-inch strand, but further research was recommended.

$$l_t = \frac{f_{si}d_b}{3} \tag{2.9}$$

2.8.9 Russell, 1992

Russell⁴⁴ performed an extensive series of testing of rectangular, scale model

AASHTO-type and full-sized Texas Type C cross sections as part of a PhD Thesis under
the supervision of Dr. Ned Burns. The specimens were all prestressed with ½-inch or
0.6-inch strand spaced at 2 inches, except for three rectangular sections that were
prestressed with 0.6-inch strand spaced at 2.25 inches. In many of the specimens, strands
were debonded to various distances from the girder ends. Russell concluded that larger

cross sections had shorter transfer lengths, larger strand diameters required longer transfer lengths, strand spacing greater than 2 inches for 0.6-inch strand was not required, debonded strands had transfer lengths similar to fully bonded, strands and confining reinforcement did not affect transfer length. Russell suggested Equation 2.10 for predicting transfer length.

$$l_t = \frac{f_{se}d_b}{2} \tag{2.10}$$

2.8.10 Mitchell, Cook, Khan and Tham, 1993

Mitchell et al.⁴⁵ based their research on determining the effect of concrete strength on transfer length. They examined strand diameters of 3/8-inch, 1/2-inch and 0.6-inch used to prestress rectangular sections made using normal weight concretes having strengths from 4,500 to 12,900 psi at 28 days. The method of strand release was gradual which was reported to provide a better comparison to the sudden strand release used in most prestressing operations. Based on their results, Mitchell et al. proposed Equation 2.11.

$$l_t = 0.33 f_{si} d_b \sqrt{\frac{3}{f_{ci}}}$$
 (2.11)

2.8.11 Buckner, 1994

Buckner⁴⁶ noted that inconsistencies existed between the methods used by various researchers to determine transfer length. After an evaluation of results, Buckner concluded that the 95 Percent Average Mean Strain (AMS) Method provided the best overall prediction of transfer length. Furthermore, he recommended Equation 2.12 for predicting transfer length. Buckner noted that 1250/E_{ci} was about 3 for compressive strengths greater than 3,500 psi; thus, his findings endorsed Equation 2.9 as well.

$$l_{t} = \frac{1250 \, f_{si} \, d_{b}}{E_{ci}} \tag{2.12}$$

2.8.12 FHWA Study, 1996

In addition to the numerous studies aforementioned, the FHWA⁴⁷ also published findings from their own study addressing the bond of prestressing strand in NWC and HPC. The FHWA study addressed the following variables:

- 1. Concrete compressive strength at 28 days, fc'
- 2. Square root of concrete compressive strength at 28 days, fc'
- 3. Concrete compressive strength at transfer, fci
- 4. Square root of concrete compressive strength at transfer, fci'
- 5. Concrete modulus of elasticity at 28 days, E_c
- 6. Concrete modulus of elasticity at transfer, Eci
- 7. Prestressing strand diameter

- 8. Prestressing strand area
- 9. Stress in prestressing strand prior to transfer, fsi
- 10. Effective prestress, f_{se}

Based on FHWA results and their analysis of other research results, the restriction on the use of 0.6-inch strand was lifted. The FHWA proposed Equations 2.13 and 2.14 for "best-fit" and to provide a 95% confidence interval, respectively.

$$l_{t} = 4 \frac{f_{pt} d_{b}}{f_{c}^{'}} - 21 \tag{2.13}$$

$$l_{t} = 4 \frac{f_{pt} d_{b}}{f_{c}^{'}} - 5 \tag{2.14}$$

2.8.13 Summary of Transfer Length Review

Again, there are currently no equations specifically for predicting transfer length in girders made with LWC or HSLC. Chapter 9, Transfer Length, uses Equations 2.5 through 2.14 for an evaluation of transfer length results from this research program to determine which variables are most applicable for HSLC girders and to suggest a better equation for predicting transfer length.

2.9 Flexural Behavior

A review indicates that only limited research has been conducted on the flexural behavior of composite HSLC girders. Prior to the onset of flexural cracking and the

point at which flexural cracking occurs, the behavior of the HSLC is important. Beyond the cracking state, the behavior of the NWC deck is the governing concern. To the author's knowledge, no background information was available related to the findings and conclusions identified in this research for flexural behavior. The general flexural behavior of normal weight prestressed composite girders made with normal strength concrete is well understood and discussed in standard text books. 48,49,50

2.10 Shear Behavior

Similar to flexural behavior, only a limited amount of research has been conducted on prestressed HSLC. Comments are provided for both HSLC and normal weight HPC as well as for LWC as applicable to this research.

2.10.1 Hanson, 1961

The origination of the lambda factor for use with LWC was based on work done by Hanson. Using the results of testing performed at PCA and at the University of Texas Hanson determined a good correlation between diagonal tensile strength in beams with the splitting tension test. Hanson then determined that the ratio of splitting tension strength in lightweight concrete to that for normal weight concrete of the same compression strength was in general about 0.85 for concrete strengths below 5,000 psi. This relation was first reported in the 1963 ACI 318 Code. In the early 1970's, the reduction factor was formalized as lambda, λ , as 0.85 for sand LWC and 0.75 for all LWC. Based on the high degree of variability of LWA, concerns exist today that the lambda factors may become unconservative for concrete strengths over 5,000 psi. 51

2.10.2 Johnson and Ramirez, 1989

Johnson and Ramirez⁵² conducted research on non-prestressed beams, but made some observations that may be applicable for prestressed HSLC and normal weight HPC. One conclusion reached in their research was that in higher strength beams, shear reinforcement spacing was greater creating a deficiency in reserve shear strength. Once the upper limit of concrete shear capacity was exceeded, the shear force transferred to shear reinforcement would cause it to yield and rupture. They suggested applying either an upper limit to the term $(f_c^2)^{1/2}$ to limit the increase in V_c due to increasing f_c^2 or increasing the minimum shear reinforcement requirement as concrete strength increases. The 1989 ACI 318 code has included a specification reflecting this recommendation.⁵³

2.10.3 Shahawy and Batchelor, 1996

Shahawy and Batchelor⁵⁴ conducted a research program examining the shear behavior of full-scale prestressed concrete girders made from 6,000 psi NWC. Of particular interest in their findings were comments that the AASHTO LRFD provisions for shear were very conservative and required modification to improve their reliability.

2.10.4 Barnes, Burns and Kreger, 1999

Barnes, Burns and Kreger⁵⁵ conducted an extensive research program at the University of Texas at Austin using 0.6-inch diameter prestressing strand in I-shaped prestressed girders made with normal weight HPC having strengths from 5,000 to 11,000 psi. The authors recommended limiting the principal tensile stress in the region from the composite section centroid to the extreme tensile fiber to $4(f_c^2)^{1/2}$. This recommendation

corresponds with ACI 318-99 Section 11.4.2.2² but extends the applicable area to include the section from the composite centroid to the extreme tension fiber.

2.10.5 Ma, Tadros and Baishya, 2000

Ma, Tadros, and Baishya⁵⁶ examined shear behavior in pretensioned I-girders made with 8,000 psi normal weight HPC. They concluded that both the AASHTO Standard and LRFD Specifications produced conservative predictions of girder shear capacity. When considering the results of their study, it must be recognized that prestressing strands were anchored in end diaphragms thus eliminating the possibility of slip and possibly increasing shear capacity at the girder ends.

2.10.6 Ramirez, Olek, Rolle, and Malone, 2000

Ramirez, Olek, Rolle, and Malone⁵⁷ conducted research on HSLC pretensioned girders made with ½-inch, and 0.6-inch diameter prestressing strands. The HSLC was made using expanded shale aggregate; the resulting concrete strengths ranged from 6,500 to 10,000 psi. The research at Purdue is thought to be the only other research conducted using 0.6-inch diameter prestressing strand in HSLC. As with Ma et al.,⁵⁶ an additional 1-meter anchorage was provided for the prestressing strand behind the center of bearing. Their conclusions related to shear were that the current AASHTO Standard and LRFD procedures were conservative for shear. Additionally they reported that the minimum amount of shear reinforcement for HSLC pretensioned girders must be further investigated based on a lower ratio of measured/calculated shear capacity with increased concrete strength.

2.10.7 ACI Committee 213, 2001

In a draft copy of Chapter 5, ACI 213,⁵⁸ shear and diagonal tension strength is covered in Section 5.8. Committee 213 reports that lightweight concrete members behave in fundamentally the same manner as normal weight concrete members. They recommend that the permissible shear capacity may be determined by substituting the splitting tensile strength, $f_{ct}/6.7$ for $(f_c)^{1/2}$ in the shear provisions of Chapter 11, ACI 318.²

2.11 Development Length

Development length of prestressing strands is the sum of the transfer length and the flexural bond length. Development length can be defined as the minimum distance from the end of the member beyond which the application of a point load will result in a flexural failure. As in transfer length, many factors are thought to affect development length. Many experimental programs have addressed development length resulting in suggested equations for its prediction.

The Master's Thesis by Chris Reutlinger,³⁷ "Direct Pull-Out Capacity and Transfer Length of 0.6-inch diameter Prestressing Strand in High Performance Concrete provides very thorough coverage of the history and development of equations to predict development length. The following is a summary of current code provisions and other proposed equations as determined for NWC. The summary closely mirrors the development of transfer length equations. There are no known equations specifically addressing development length for HSLC.

2.11.1 Janney, 1954

Initial development length testing by Janney³⁸ in 1954 was based on the use of 5/16-inch wire having two different surface conditions prestressed to 0, 60, 120 and 165 ksi in beams made with NWC having strengths from 4,500 to 4,800 psi. Janney reported a "wave of flexural bond stress concentration" and noted that once general bond slip occurred, the beam failed shortly thereafter. Janney contributed bond in the transfer region predominantly to the Hoyer effect, which was the confining pressure applied to the wire by the concrete. Janney also reported improve bond characteristics for slightly rusted wire.

2.11.2 Hanson and Kaar, 1959

Hanson and Kaar³⁹ conducted a study involving 47 small-scale concrete beams reinforced with various sizes of Grade 250 stress-relieved strand. The tests focused on five factors including strand diameter, embedment length, concrete strength, percentage of reinforcement, and strand surface condition. All beams were loaded until failure. Hanson and Kaar reported observations similar to those of Janney.³⁸ The results of Hanson and Kaar's research were the basis for the current AASHTO development length expression shown in Equation 2.16 and developed by Mattock.³⁷ Equation 2.15 simplifies to Equation 2.16.

$$l_d = l_t + l_{fb} = \frac{f_{se}d_b}{3} + (f_{su}^* - f_{se})d_b$$
 (2.15)

$$l_d = (f_{su}^* - \frac{2}{3} f_{se}) d_b \tag{2.16}$$

Shortly after the development of Equation 2.16 concerns developed based on the introduction and common use of Grade 270 prestressing strand.³⁷

2.11.3 Martin and Scott, 1976

Martin and Scott⁴¹ re-evaluated the currently suggested equation (Equation 2.16) and determined that inconsistencies may have been responsible for the collapse of a 20-ft span slab under construction loads. They suggested two new equations that did not determine development length, but specified a maximum strand stress based on a given embedment length. The two equations are shown below for the given location l_x.

For l_x less than $80d_b$:

$$f_{su}^* \le \frac{l_x}{80d_b} \left(\frac{135}{d_b^{\frac{1}{6}}} + 31 \right) \tag{2.17}$$

For l_x greater than $80d_b$:

$$f_{su}^* \le \frac{135}{d_b^{\frac{1}{6}}} + \frac{0.39l_x}{d_b} \tag{2.18}$$

Equation 2.18 was rewritten in terms of l_x in Table 13.8 in order to determine its accuracy in predicting l_d .

2.11.4 Zia and Mostafa, 1977

Zia and Mostafa⁴² also realizing the inconsistencies with Equation 2.16 suggested a new equation as well (Equation 2.19) which incorporated their suggested transfer length equation, Equation 2.8.

$$l_d = l_t + l_{fb} = \left(1.5 \frac{f_{si}}{f_{ci}^{*}} d_b - 4.6\right) + 1.25 (f_{su}^{*} - f_{se}) d_b$$
 (2.19)

2.11.5 FHWA Memorandum, 1988

Based on testing at the University of North Carolina in 1986 where poor transfer and development length results were recorded, the FHWA issued a memorandum specifying 4 interim restrictions as listed in Section 2.8.7.³⁷ Several research programs were initiated based on the FHWA restrictions.

2.11.6 Deatherage, Burdette and Chew, 1989

Deatherage et al.⁴³ conducted experimental testing on 20 AASHTO Type I girders with varying strand diameters and strand spacings and concrete design strengths of 5,000 psi. They suggested the flexural bond component suggested by AASHTO⁴⁰ should be increased by 50 percent as shown in Equation 2.20 below.

$$l_d = l_t + l_{fb} = \frac{f_{si}d_b}{3} + 1.50(f_{su}^* - f_{se})d_b$$
 (2.20)

2.11.7 Russell, 1992

Russell⁴⁴ performed an extensive series of testing of rectangular, scale model AASHTO-type and full-sized Texas Type C cross sections as part of a PhD Thesis under the supervision of Dr. Ned Burns. The specimens were all prestressed with ½-inch or 0.6-inch strand spaced at 2 inches except three rectangular sections that were prestressed with 0.6-inch strand spaced at 2.25 inches. In many of the specimens, strands were debonded to various distances from the girder ends. Russell concluded that "shear cracking through the transfer region will cause its bond to fail and that if cracks do not occur that the strand will develop is prestressing force plus any additional tension required by external loads." To prevent cracking from occurring through the transfer region, Russell developed the criteria listed in Equation 2.21 where l_t was calculated using Equation 2.10.

$$M_{cr} > l_t V_u \tag{2.21}$$

In addition, Russell specified that if V_u >Vcw that vertical and longitudinal mild steel shear reinforcement should be provided to prevent web shear cracking from passing through the transfer region.

2.11.8 Mitchell, Cook, Khan and Tham, 1993

Mitchell et al.⁴⁵ based their research on determining the effect of concrete strength on develop length. They examined strand diameters of ³/₈-inch, ½-inch and 0.6-inch used to prestress rectangular sections made using concretes having strengths from 3,000 to 7,310 psi at release and from 4,500 to 12,900 psi at 28 days. Based on experimental results, Equation 2.22 was suggested.

$$l_d = 0.33 f_{si} d_b \sqrt{\frac{3}{f_{ci}'}} + (f_{su} - f_{se}) d_b \sqrt{\frac{4.5}{f_{c}'}}$$
 (2.22)

2.11.9 Buckner, 1994

Buckner⁴⁶ noted that there was an interaction between transfer length, effective prestress and design stress. Buckner recommended using a procedure similar to that of Hanson and Kaar.³⁹ He also theorized that the development length expression should be based also on ultimate strain and suggested Equations 2.23 and 2.24.

$$l_{d} = l_{t} + l_{fb} = \frac{f_{si} d_{b}}{3} + \lambda (f_{su}^{*} - f_{se}) d_{b}$$
 (2.23)

$$1.0 \le [\lambda = (0.6 + 40\varepsilon_{ps})] \le 2.0 \tag{2.24}$$

In Equation 2.24, ε_{ps} is the strain corresponding with f_{su}^* .

2.11.10 FHWA Study, 1996

In addition to the numerous studies aforementioned, the FHWA⁴⁷ also published findings from their own study addressing the bond of prestressing strand in NWC and HPC. The FHWA study addressed variables as specified previously in 2.8.12. Based on FHWA results and the results of other research programs, the restriction on the use of 0.6-inch strand was lifted. The FHWA proposed Equations 2.25 and 2.26 for "best-fit" or "mean" and to provide a "95% confidence interval," respectively.

$$l_d = l_t + l_{fb} = \left(4\frac{f_{pt} d_b}{f_c} - 21\right) + \left(\frac{6.4(f_{su} - f_{se})d_b}{f_c} + 26\right)$$
(2.25)

$$l_{d} = l_{t} + l_{fb} = \left(4 \frac{f_{pt} d_{b}}{f_{c}'} - 5\right) + \left(\frac{6.4(f_{su} - f_{se})d_{b}}{f_{c}'} + 15\right)$$
(2.26)

2.11.11 Barnes, Burns and Kreger, 1999

Barnes, Burns and Kreger⁵⁵ tested 36 AASHTO Type I normal weight HPC girders having release strengths from 4,000 to 7,000 psi and strengths at testing from 5,700 to 11,000 psi. All prestressing strand was 0.6-inch diameter Grade 270 ksi LOLAX strand in either a "bright" or "rusted" surface condition. Included in the test program were girders with fully bonded strands and debonded strands. One of the outcomes of the research program was Equation 2.27 for predicting development length.

$$l_{d} = \frac{5}{4} \left(\frac{f_{pl}}{\sqrt{f_{ci}^{'}}} + (f_{ps} - f_{pe}) \right) d_{b}$$
 (2.27)

2.11.12 Peterman, Ramirez, Olek, 2000

Peterman, Ramirez, and Olek^{59,60} conducted research on HSLC bridge girders as referenced in Section 2.10.5. Their research is the only other research known where HSLC girders using 0.6-inch diameter strands were tested. Their report indicated that all multiple strand specimens were reinforced with sufficient stirrups to prevent web-shear cracking at the member ends. The prevention of shear cracking in the transfer region has been shown to result in strand slip causing premature shear failure.

2.11.13 Kolozs, 2000

Kolozs,⁶¹ under the supervision of Professors Ned Burns and John Breen, tested HSLC girders with strengths between 6,000 and 8,000 psi prestressed with ½-inch diameter Grade 270 LOLAX strand. Kolozs found the current AASHTO⁴⁰ equation for development length was conservative.

2.11.14 Summary of Development Length Review

Again, there are currently no specific equations for predicting development length for girders made with HSLC. Chapter 13, Development Length, uses Equations 2.16 through 2.20 and 2.22 through 2.27 for an evaluation of development length results from this research program to determine which variables are most applicable for HSLC girders and to suggest a better equation for predicting development length.

2.12 Elements of Bond

There are three mechanisms that allow the development of bond stress between the prestressing strand and the concrete to include adhesion, frictional bond due to Hoyer's effect, and mechanical interlock.⁴⁴ Slipping of the prestressing strand relative to the concrete is required to develop bond stress. In general, bond resistance of seven-wire prestressing strand remains constant or increases after initial slip.⁶²

2.12.1 Adhesion

Adhesion occurs in a very thin layer at the interface between the concrete and prestressing strand. Acting like an "adhesive," adhesion exhibits rigid-brittle behavior preventing slip of the strand relative to the concrete up to a critical stress level. During the transfer of prestress or girder testing, adhesion is lost when the bond stress exceeds the critical stress level. Once the critical stress level is exceeded, the adhesion portion of bond is lost. In the case of seven-wire prestressing strand, the loss of adhesion is often replaced by other mechanisms of bond. He Because failure of the adhesive bond occurs at a very small displacement, the overall contribution of adhesion to bond is minor. He

2.12.2 Frictional Bond Due to Hoyer's Effect

Research by E. Hoyer in 1939 using small diameter smooth piano wire resulted in the identification of a mechanism of bond now known by his name.⁴⁴ When wire or prestressing strand is tensioned, Poisson effects cause the diameter to become smaller.

After tensioning, concrete is cast around the strands and allowed to cure to some initial required strength. At strand release, the strand attempts to return elastically to its initial

length prior to tensioning. As the strand becomes shorter, Poisson effects cause an increase in strand diameter creating radial compression stress between the strand and concrete.⁶³ The resulting increase in strand diameter upon release is most pronounced at the free end of the strand and becomes less to a point where it becomes constant at a distance approximately equal to the transfer length from the end of the member. After initial end slip at strand release, the resulting frictional bond resistance and wedge action shown in Figure 2.1 restrain the strand and maintain tension in it.




Figure 2.1 Wedge Action Resulting from Hoyer's Effect

During the application of load to a girder, the stress in the strand increases. At the point where the stress exceeds the stress in the strand at transfer in the transfer region, the wedge action begins to diminish.⁴⁴

2.12.3 Mechanical Interlock

Standard seven-wire prestressing strand is manufactured by wrapping six wires around a seventh center wire in a helical pattern. Concrete placed around the strand fills the narrow spaces (interstices) between the individual wires completely encapsulating the strand. When the strand is prevented from twisting, the concrete ridges acting on the outside wires of the strand restrict movement by mechanical interlock. In order to prevent twisting, the wedge action created by Hoyer's effect must exist. 44 Mechanical interlock is reported to enhance the frictional bond component at strand release. 63

CHAPTER III

ANALYTICAL INVESTIGATION OF HSLC FOR PRETENSIONED BRIDGE GIRDERS

3.1 Introduction

The potential advantages of using high strength HPC for precast prestressed bridge girders may be lost if those girders are too heavy to be transported. The advantages of using HPC for pretensioned girders presented by Kahn and Saber⁶⁴ included spans up to 40 percent longer than when normal strength (6 ksi) concrete was used, wider girder spacing and greater durability. Mr. Paul Liles, Georgia State Bridge Engineer, stated that the girders for spans over about 120 feet would weigh too much and that they would require a "super-load" permit for transportation. A gauge of the transportation problem is the necessity to obtain hauling permits or "super-load" permits.

In Georgia when the gross vehicle weight (GVW, weight of girder plus tractor-trailer rig) exceeds 150 kips, a "super permit" is required. This permit requires the hauler to obey certain additional restrictions that may include stopping before every bridge, proceeding over the bridge at a speed less than 5 miles per hour and that an escort vehicle lead and follow the truck. In addition, the state department of transportation must carefully review the route and evaluate the load capacity of each bridge. There may be no acceptable route. The slow rate over a bridge crossing can significantly disrupt traffic.

The established goal for this phase of the research was to achieve a 150 foot long pretensioned girder with a weight that when added to that of a tractor-trailer rig, was less than 150 kips; that is, create a 150-foot long girder that does not require a "super permit." A further goal was too have a minimum girder spacing of 7 feet for overall bridge efficiency. Use of either an all-lightweight or sand-lightweight concrete would be needed to achieve these goals. It was known from previous research⁶⁴ that AASHTO Type IV girders constructed with 15,000 psi NWC using 0.6-inch diameter prestressing strands and a girder spacing of 5 feet could achieve the span but with a GVW of about 185,000 lbs.

Therefore, the purpose of this analytical investigation was to determine if HSLC could be used to build pretensioned bridge girders with a length of 150 feet and girder spacing of 7 feet whose GVW did not exceed 150 kips. Standard AASHTO (American Association of State Highway and Transportation Officials) and AASHTO-PCI (Precast/Prestressed Concrete Institute) sections were considered. The range of girder strengths was 8, 10 and 12 ksi. The strength of the 7-inch thick, normal weight composite deck was 3,500 psi.

The scope of this study was limited to investigating AASHTO Type II-V and AASHTO-PCI Bulb-Tee 54, 63 and 72 sections (Standard and Modified) as shown in Figures 3.1, 3.2 and 3.3. For reference purposes, AASHTO-PCI Bulb-Tees were listed as "Bulb-Tees." A Modified AASHTO-PCI Bulb-Tee was listed as a "Modified Bulb-Tee."




Figure 3.1 AASHTO Type II - V Sections




Figure 3.2 AASHTO-PCI Bulb Tee 54, 63 and 72 Shapes




Figure 3.3 Diagram of Bottom Flange of Modified Bulb Tee

The Modified Bulb-Tee sections consisted of a Standard Bulb-Tee with one additional row of 12 strands added to the bottom flange. The additional row of 12 strands added 2 inches to the depth of the member, all in the bottom flange. The inclusion of the Modified Bulb-Tee sections was precipitated by discussions with Georgia precast concrete producers who had previously constructed and recommended the section.

Prestressing strands were 0.6-inch diameter, 270 ksi low relaxation strands spaced at 2 inches.

The HSLC in this study assumed the use of regionally available expanded slate LWA. Based on the requirement to produce concrete compressive strengths up to 12 ksi, it was thought that the use of slate LWA would be necessary. Furthermore, available

HSLC test data indicating strengths upwards of 12 ksi predominantly used slate LWA. 3,12,21,31

It was possible that HSLC using other types of LWA (expanded shale or clay) could achieve upwards of 12 ksi strength, but available data were limited. An extensive literature search focusing on HSLC used for prestressed applications indicated that neither shale nor clay LWA had been used where concrete strengths approached 12 ksi. 65

3.2 Parametric Study

All girder designs in this research were based on the 16th Edition of the AASHTO Standard Specification for Highway Bridges⁴⁰ and used the Georgia DOT bridge design program with modification by the authors to enable the use of HSLC. A spreadsheet to create input files for the bridge program is shown in Appendix A. Several steps were necessary prior to using the program to design HSLC bridge girders.

It was assumed that prestress losses would be the same for HSLC as for normal strength concrete. Other ongoing research by the author indicates that for normal weight and lightweight HPC, the creep and shrinkage losses were less than for normal strength concretes. Yet, consideration of deflection was a major concern.

The parameters that were varied were concrete strength, unit weight, and girder type. Other variables that remained constant are listed in Table 3.1.

Table 3.1 Critical Girder Design Variables That Remained Constant.

Allowable top fiber tension stress at release	$3\sqrt{f_c}$
Allowable final bottom fiber tension stress	$6\sqrt{f_c}$
Release strength as percent of 28-day compressive strength	75 percent
Composite deck thickness	7 inches
Composite deck strength	3500 psi
Pretensioning strand diameter	0.6 inches
Pretensioning strand spacing	2 inches
Pretensioning strand ultimate strength, f _{pu}	270 ksi
Type of pretensioning strand	LOLAX
Percent of strand ultimate strength allowed at time of pretensioning	75 percent
Girder spacing	7 feet

3.3 Determination of Modulus of Elasticity

A critical requirement for design was to accurately predict the modulus of elasticity at both the time of release (E_{ci}) and at 28 days (E_{c}) for HSLC made using slate LWA. Accurate values of the modulus of elasticity were necessary to determine prestress losses and girder deflections. Experimental data from thirteen mixes using slate LWA were used to investigate the appropriate modulus values as shown in Table 2.1. The current ACI^2 and $AASHTO^{40}$ equation for E_c is:

$$E_c = 33w_c^{1.5} \sqrt{f_c^{1}}$$
 (2.1)

When used with HSLC, Equation 2.1 was found to overpredict the modulus values for strengths over 7,000 psi. The equation was specified for use on concretes having unit weights between 90 and 155 pcf. Morales²⁷ proposed Equation 2.2 for use with LWC:

$$E_c = (40,000\sqrt{f_c'} + 1,000,000) \left(\frac{w_c}{145}\right)^{1.5}$$
 (2.2)

Equation 2.2 more closely predicted modulus values; however, when used with HSLC made using slate LWA, the predicted values were low for strengths below 10 ksi and high for strengths over 10 ksi when compared to experimental data. In order to more accurately predict modulus values, Equation 3.1 was developed similar in form to the Morales equation, but based on a "best fit" analysis of the experimental data from the thirteen slate mixes.

$$E_c = (33,000\sqrt{f_c'} + 4,000,000)(w_c/242)^{0.9}$$
 (3.1)

Figures 3.4 and 3.5 plot the experimental data and the three equations for modulus of elasticity versus compressive strength and versus unit weight, respectively. Equation 2.3 was used for all further analyses.

3.4 Girder Design

The computer program was used to find the maximum span length for each girder type in the study. The variable parameters were concrete strength and concrete unit weight. Other critical variables were kept constant at AASHTO⁴⁰ specified or other values as shown in Table 3.1.




Figure 3.4 Modulus of Elasticity vs. Concrete Strength




Figure 3.5 Modulus of Elasticity vs. Unit Weight of Concrete

The concrete strengths used were 8, 10 and 12 ksi.. When designing with high strength NWC, it was assumed the concrete weight was 150 pcf, and the modulus was determined with Equation 2.1 based upon previous high-strength NWC research in Georgia.⁶⁶ When using HSLC, Equation 2.3 was used with different unit weights.

Based on the study of the thirteen slate mixes, it was apparent that variations in unit weight existed for a given strength. A range of unit weights was established for each HSLC strength based on observed upper and lower limits. Table 3.2 shows the range of unit weights used in the study.

Table 3.2 Slate HSLC Unit Weight Values

Concrete strength		Unit Weight	
f _c '	Low	Average	High
(psi)	(pcf)	(pcf)	(pcf)
8,000	113	119	126
10,000	117	124	131
12,000	122	128	135

The variation in unit weights caused variations in modulus values as well as girder weights. Each bridge and girder design accounted for the differing modulus at release and final conditions. It is noted that of the strengths in Table 3.2, only the low unit weight 8,000 psi mix qualified as structural lightweight concrete according to the ACI definition.²

3.5 Analysis Results and Discussion

Figures 3.6 through 3.8 present the composite girder maximum simple-span length versus the girder's concrete compressive strength for AASHTO Type II through V sections, Bulb-Tee 54, 63 and 72 sections, and Modified Bulb-Tee 54, 63 and 72

sections. Shown in the figures are girders of high strength NWC and HSLC. The unit weights shown for HSLC are the "low" and "high" values listed in Table 3.2 to provide the range of results by concrete unit weight for each concrete strength.

3.5.1 Effect of Concrete Strength and Unit Weight on Girder Span Length

3.5.1.1 AASHTO Type II – V Sections

Girder span lengths using 8 ksi HSLC could be extended by up to about 4 percent (7 feet for 140-foot girders) as shown in Figure 3.6. The most significant length increases resulted from the use of the lightest concrete unit weight. The increase in length for Type II and III sections was less than for Type IV and V sections implying the use of HSLC provided the most significant benefit for girders with lengths over approximately 105 feet. Figure 3.6 also indicates there is little benefit to using concrete over 10 ksi strength in Type V sections. Length increase is proportional to the amount of reinforcement that can be located in the bottom flange. At maximum lengths for Type V sections, the total strands possible were used in the bottom flange with 10 ksi concrete.

HSLC girder maximum live load deflections resulting from HS 20-44 loading increased between 15 and 22 percent on average when compared to girders of high-strength NWC. The lighter concrete unit weights experienced the greatest deflections; however, deflections were at most 85 percent of the AASHTO⁴⁰ maximum allowable L/800 requirement (where L is the span length) compared to 57 percent for high-strength NWC. Further, the natural period of vibration increased by less than 19 percent when HSLC was used compared to high-strength NWC for the 10 ksi Type IV girders.




Figure 3.6 Concrete Strength vs. Maximum Length for AASHTO Girders

3.5.1.2 Bulb-Tee Sections

Figure 3.7 shows trends similar to those for AASHTO sections. HSLC with a strength of 8 ksi provided a length increase up to about 3 percent (3 feet for 110 foot girders). The major difference from AASHTO sections was that Bulb-Tee sections showed a consistent benefit from using concrete strengths up to 12 ksi. Based on the improved efficiency of the Bulb-Tee sections, there was not an observed plateau within the strength range investigated for the constant 7-foot girder spacing. Live load deflections of Bulb-Tee sections averaged at most 70 percent of the AASHTO maximum

allowable L/800. The natural period of vibration for a HSLC 135-foot, 63-inch deep Bulb-Tee girder increased by less than 17 percent compared to that of a high-strength NWC girder.




Figure 3.7 Concrete Strength vs. Maximum Length for Bulb-Tee Girders

3.5.1.3 Modified Bulb-Tee Sections

Figure 3.8 shows that Modified Bulb-Tee sections behaved in a similar manner to the Standard Bulb-Tee sections. The greatest percent increase in length was gained with 8 ksi HSLC at about 3 percent (4 feet for 146-foot girders). The addition of a row of pretensioning strands in the bottom flange allowed an increase in length of about 10 feet

at all strengths of concrete for all sections in comparison to Standard Bulb-Tee sections. Live load deflections were again well within the maximum allowable L/800 limit and averaged 64 percent of the allowable.

The additional strands and 2-inch increase in depth would allow designers to use a shallower section to reach lengths previously achievable only with the next larger size Bulb-Tee section. For the HSLC 156-foot, 65-inch deep Modified Bulb-Tee girders, the natural period of vibration increased by less than 15 percent compared to that of a high-strength NWC girder.

3.5.2 Weight Reduction Based on the Use of HSLC

The most significant advantage gained through the use of HSLC was overall girder weight reduction. Through the use of HSLC, it was possible to lower the GVW below the 150 kip threshold for the target 150-foot girder. The GVW was determined by adding the resulting girder weight to the estimated weight of an appropriate transport truck and trailer. Table 3.3 shows information related to Georgia permitting requirements for overweight cargo as provided by the Georgia DOT.




Figure 3.8 Concrete Strength vs. Maximum Length for Modified Bulb-Tee Girders

Table 3.3 Permitting Requirements for Overweight Cargo in Georgia.

Load	Gross vehicle	Estimated	Maximum	Permit	No. of
category	weight range	vehicle weight	girder weight	type	axles
	(kips)	(kips)	(kips)		required
1	$0 < \text{GVW} \le 80$	40	40	None	NA
2	$80 < \text{GVW} \le 125$	40	85	Regular	6
3	$125 < \text{GVW} \le 150$	45	105	Regular	7
4	$150 < \text{GVW} \le 160$	50	110	Superload	8
5	$160 < \text{GVW} \le 175$	52.5	122.5	Superload	9
6	$175 < \text{GVW} \le 180$	55	125	Superload	10
7	180 < GVW	55+	125+	Superload	>10

Note: 1 kip = 454.5 kg.

It was difficult to provide exact data on weights and permitting requirements due to variations in tractor-trailer rig configurations and capabilities; however, Table 3.3 provides some average values that would be expected. Figure 3.9 illustrates the GVW for each of the maximum length girders for the ten sections using high-strength NWC at 8 ksi strength. Similar graphs were created for 10 and 12 ksi high-strength NWC and HSLC. The collective results of GVW, maximum girder length, and section type are shown in Figure 3.10. Since it was seen that AASHTO Type II and III girders showed little benefit from HSLC, they were not included in graph.




Figure 3.9 GVW by Girder Type, With Maximum Length Labeled, Based on 8 ksi NWC

Within Figure 3.10, there are three data points for each section listed. The three points correspond with the three strengths of concrete. In each case, the leftmost of the

three points represents 8 ksi. The center point represents 10 ksi, and the rightmost point represents 12 ksi. The average unit weight given in Table 3.2 was used for the lightweight (L) sections while a constant 150-pcf unit weight was used for the normal weight (N) sections.




Figure 3.10 Gross Vehicle Weight vs. Maximum Girder Length

The most important finding was that it was possible to reach the target span of 150 feet without exceeding the 150 kip GVW limit through the use of HSLC. There were three HSLC girders that satisfied the requirement: Modified BT-63 (12 ksi), BT-72 (10

ksi) and Modified BT-72 (8 ksi). Further economic analysis and a review of site constraints would be required to select the best possible alternative. For spans between 125 feet and 135 feet, Type IV lightweight girders were less than the 150 kip GVW while Type IV normal weight girders exceed the 150 kip GVW limit. Based on the parameters of this study, AASHTO Type IV and V sections were less efficient than similar height Bulb-Tee sections, both Standard and Modified.

If the AASHTO Type IV and V sections are removed from the chart, there are noticeable trendlines for the remaining normal weight and lightweight Bulb-Tee girders. The trendlines demonstrate the benefit in terms of GVW that result from the use of HSLC. The trendlines converge for girder lengths less than 105 ft (32 m) and diverge as girder lengths increase from that point.

3.6 Conclusions

Based on the results of this analytical investigation, the following conclusions were made:

The use of HSLC has the potential to increase the length of simple span AASHTO sections up to four percent and Bulb-Tee sections up to three percent.

For spans between 125 feet and 155 feet, the use of LWC can reduce the gross vehicle weight to less than 150 kips (68,200 kg) so that a superload permit is not required for transport of long span girders as compared to the need for a superload permit when normal weight concrete is used.

AASHTO Type II and III sections do not benefit appreciably from the use of HSLC. The Modified Bulb-Tee section extended the length of a Standard Bulb-Tee by 10 feet using 8, 10 and 12 ksi HSLC or high-strength NWC.

Bulb-Tee (Standard or Modified) sections provided longer spans at less weight for girders over 105 feet in length when compared to AASHTO sections.

CHAPTER IV

MATERIALS, MIXING AND TESTING OF HSLC

4.1 Introduction

The purpose of this chapter is to discuss the materials used, the methods of mixing, and the testing methods used in designing and then producing HSLC. Specific comments on mix design development, field production and material properties are addressed in Chapters 5, 6 and 7, respectively.

4.2 HSLC Components and Properties

4.2.1 Coarse Aggregate

The most important factor in creating a lightweight concrete that has high strength and high modulus of elasticity is the LWA. The coarse aggregate used during this project was a slate LWA provided by the Carolina Stalite Company, Salisbury, North Carolina. As described in Chapter 2, the Stalite LWA is a high-quality aggregate with a tight pore structure. Three different size gradations were used during this research including 3/8-inch, 1/2-inch and 3/4-inch. The 1/2-inch gradation was used predominantly during development and testing. The 3/8-inch aggregate was used in trying to exceed 12,000 psi strength. The 3/4-inch aggregate had a very limited use during this project because of its lower strength plateau.

When crushed, Stalite LWA takes on an angular appearance as shown in Figure 4.1. Figure 4.2 shows the LWA in clinker form, the way it appears upon exiting the rotary kiln. Note the voids in the LWA clinker that reduce its weight and specific gravity. Table 4.1 provides the specific gravity, weight, and gradation for the 3/8-inch and 1/2-inch aggregate used during this research.




Figure 4.1 Crushed Slate LWA (3/4-inch Particles) From Carolina Stalite



Figure 4.2 Close-up of Slate LWA Clinker Showing Voids

Table 4.1 Stalite LWA Specifications

Aggregate Size	3/8-inch		1/2-inch	
Oven Dry Specific Gravity	1.52		1.44	
Unit Weight Damp Loose (pcf)	50 - 54		48 – 52	
Absorption 24-hr Soak After Oven Dry (Maximum Absorption)	6 % (10 %)		6 % (10 %)	
Sieve Size	Percent Passing	ASTM ⁶⁷ C 330 Specification	Percent Passing	ASTM ⁶⁷ C 330 Specification
³¼-inch	100	100	100	100
½-inch	100	100	90	90-100
³/ ₈ -inch	100 75-100		53	40-80
#4	33	20-45	12	0-20
#8	3	0-15	5	0-10
#100	2	0-10	NA	NA

LWA specific gravity values were checked on several occasions using a technique outlined by Holm as addressed in Section 2.5.5.²⁴ For comparison purposes, normal weight aggregate has a specific gravity in the range of 2.60-2.65 and a maximum absorption of about 2 percent.

4.2.2 Fine Aggregate

Initially, lightweight fines were used in mix development. Low strength values and the inability to control water absorption resulted in termination of lightweight fines. Locally available normal weight fine aggregate known as Brown Brothers (BB) natural concrete sand was used. BB sand was approved for structural concrete use by GDOT and resulted in better strength and mixes that were easier to control. The BB sand had a fineness modulus of 2.36, which is low for use in structural concrete. Table 4.2 lists the specifications of BB sand and shows how the sand meets DOT specifications but fails to meet ASTM specification C 33.⁶⁸

Table 4.2 Brown Brothers Natural Concrete Sand Specifications

Oven Dry Specific Gravity	· 2.62					
Fineness Modulus	2.36					
Percent Absorption		0.5 %				
Sieve Size	Percent	ASTM C 33	DOT 801.02D			
Sieve Size	Passing	Percent Passing	Percent Passing			
# 4	100	95-100	95-100			
# 8	98.6	80-100				
# 16	90.3	50-85 *	45-95			
# 30	59.3	25-60				
# 50	14.8	10-30	8-30			
# 100	1.3	2-10 *	1-10			
Pass / Fail (*)		Fail	Pass			

4.2.3 Overall Aggregate Gradation

Evaluations of the overall gradation of the coarse LWA and fine NWA combined indicated gaps in the grading for the #8 and #16 sieve sizes, but overages in the 3/8-inch, #4, and #50 sieve sizes.

4.2.4 Portland Cement

Type III cement supplied by Blue Circle Materials (now LaFarge) was used throughout mix design development based on the need to achieve early strength for prestressed girder construction. Type III cement has a higher Blaine fineness modulus than Type I and has higher contents of C₃S and C₃A causing hydration to occur more rapidly.⁶⁹

The field-mixing phase (Chapter 6) of the research project was conducted at Tindall Concrete in Jonesboro, Georgia. Tindall used only Demopolis Type III Cement produced by CEMEX-Southdown Corporation. It was discovered that the Demopolis Type III provided better early strength than the Blue Circle – LaFarge Type III.

Demopolis Type III cement was also used for girder production.

Cement grind specifications were not available for either brand of cement. Plant officials and quality control inspectors reported that the cements were ground in accordance with ASTM C 150.⁷⁰

4.2.5 Mineral Admixtures

Silica fume and Class F fly ash were used in this research to improve concrete quality and durability, workability, and economy. The silica fume used in this project

was provided by Grace Construction Products under the name of Force 10,000. The silica fume had a specific gravity of 2.2 and was included in mix designs in amounts of 2 to 10 percent of total cementitious materials by weight.

Boral Material Technologies provided the Class F fly ash used in this project under the name of "Bowen" ash. The fly ash was produced at the Georgia Power Generating Plant located in Bowen, Georgia. The Bowen fly ash had a specific gravity of 2.28 and was included in mix designs as 15 percent of cementitious materials by weight. The fly ash satisfied the requirements of ASTM C 618.⁷¹

4.2.6 Chemical Admixtures

The chemical admixtures, all provided by Grace Construction Products, included ADVA Flow, a high-range water reducer (HRWR), WRDA 35, a water reducer/set retarder, and Daravair 1000, an air-entraining admixture (AEA). ADVA Flow satisfied the requirements of ASTM C 494⁷² Type F; the WRDA 35 satisfied the requirements of ASTM C 494⁷² Type A and D; the Daravair 1000 satisfied the requirements of ASTM C 260.⁷³

4.3 Moisture Control

Control of moisture and accurate determination of moisture content were two of the most important steps involved in making high quality HSLC. Low absorbed moisture in the LWA can result in mix water being absorbed thus reducing workability and changing the water cement ratio. Excess adsorbed water that is not properly accounted for in the mix design also impacts the mix by affecting the aggregate proportion and also

the water cement ratio. The following sections describe steps taken during the project to insure moisture was properly controlled in the lab. Moisture control in the field is addressed in Chapter 6.

4.3.1 Laboratory Material Storage

The LWA was initially stored in large sacs in the lab. Prior to using the aggregate, it was soaked in buckets overnight to insure the absorbed moisture content was adequate. The trouble with soaking aggregate in buckets was that the method was not something possible under plant conditions for the production of large amounts of HSLC. If a method did not transfer to plant operations, it was not used in the lab.

Aggregate storage hoppers were procured and installed outside the lab facility. A misting device was installed in the top of each hopper and run continuously until the aggregate had adequate absorbed moisture. Adequate absorbed moisture was 6 percent; anything below 6 percent was unacceptable.

The initial stages of mix development were conducted during the winter months when outside temperatures often dipped well below freezing at night. Often times, the water misted onto the LWA froze requiring that it be chipped from inside the hoppers. In the event this occurred, the aggregate was allowed to warm inside the lab prior to mixing concrete. Later in the development phase, hoppers were installed inside the lab where the temperature was above 55 degrees Fahrenheit at all times. Figures 4.3, 4.4, and 4.5 show the aggregate hoppers (outside and inside) and the misting devices as installed inside the lab facility. The misting devices were constructed with nozzles having an output of approximately 3 gallons per hour. The water flow through the aggregate was minimized

to prevent segregation of fine particles from occurring. To reduce the gradient of free moisture inside the hoppers, the water was turned off 24 hours prior to concrete mixing.

The normal weight BB sand was also stored inside the lab in a hopper.




Figure 4.3 Exterior Aggregate Hoppers



Figure 4.4 Interior Aggregate Hoppers and Cement / Admixture Proportioning Station




Figure 4.5 Misting Device Installed Over Interior Aggregate Hoppers

4.3.2 Determination of Moisture Content

Prior to mixing HSLC, a representative sample was taken from the aggregate hopper or stockpile. Moisture contents in the "as-is" and "saturated surface dry (SSD)" condition were determined from the representative sample by cooking the LWA over hotplates at a medium heat for approximately 1 hour or until all moisture had been removed. When LWA is heated, the internal pore water boils and explodes in a violent manner. To prevent flying aggregate particles from injuring people close by, screens were placed over top of the pan during cooking as shown in Figure 4.6.




Figure 4.6 Screens Covering LWA During Moisture Test

When performing the "SSD" moisture check, the aggregate sample was placed on several layers of paper towels and patted dry prior to weighing. It was important to dry the aggregate sample to a point where there was no longer a shine on the surface.

Two methods were useful for determining when all moisture had been cooked from the aggregate. If no moisture accumulated on a piece of glass held over the cooking aggregate, it was dry. In addition, if the aggregate no longer "popped" it was considered dry.

Moisture content checks were also performed on the BB sand whenever a mix was made. Absorbed moisture was assumed to be 0.5 percent.

A material testing sheet was created as shown in Table 4.3 to simplify the testing procedure and reduce chances for error. The moisture content calculation procedure is explained on the sheet. Also covered in Table 4.3 is the determination of specific gravity using a pycnometer, which is covered in ACI 211.2-91.¹⁸

4.4 HSLC Mix Designs

As addressed in Chapter 2, there was no method available "off-the-shelf" for determining a mix design to achieve 12,000 psi HSLC. Previous mix designs and guidance from Stalite representatives provided the initial HSLC mix designs in this research. Based on suggestions from several sources, a mix design spreadsheet was developed to automate the numerous calculations required for a HSLC mix design. Appendix B provides an example of the spreadsheet and gives details on its use. The development of mix designs is covered in detail in Chapter 5, Development of HSLC Mix Designs.

Table 4.3 Material Testing Sheet

Lightweight Concrete Material Testing Sheet				
Test Date / Location				
Technician Name				
Aggregate Moistu	re Content Testing			
Time Test Started	Time Test Finished			
Test Description				
A – Weight of Wet Aggregate and Pan				
B – Weight of Pan				
C – Weight of Wet Aggregate (A – B)				
D – Weight of Dry Aggregate and Pan				
E - Weight of Dry Aggregate (D - B)				
F - Weight of Water (C - E)				
G – Percent Moisture (F/E) x 100				
Aggregate Specif	ic Gravity Testing			
Time Test Started	Time Test Finished			
Test Description				
A – Wt. of Pycnometer w/Agg. & Water				
B - Wt. of Pycnometer w/ Water				
C – Wt. of Aggregate				
SG = C / (C + B - A)				

4.5 Concrete Mixer

The concrete mixer used for all laboratory mixes was a pan mixer, model 30 DP, manufactured by Lancaster and shown in Figure 4.7.




Figure 4.7 Lancaster Model 30 DP Pan Mixer

The Lancaster mixer operated with a shearing type action. The maximum amount of concrete that could be mixed in one batch was 1.75 cubic feet. Some trial mixes were made in a 4 cubic foot rotary mixer. The resulting mixes were poor; cylinder strengths were significantly lower than identical mixes made using the Lancaster mixer.

The concrete mixer used for field mixes is addressed in Chapter 6.

4.6 Order of Mixing

Components were added to the HSLC mixes in the following specific order. This order was developed over time and produced the best results.

- 1. Coarse Aggregate (Slate LWA)
- 2. Fine Aggregate (BB Natural Sand)
- 3. Approximately 2/3 of mix water combined with WRDA 35 (LRWR)
- 4. Daravair 1000 (AEA)
- 5. ADVA Flow (HRWR)
- 6. Type III Portland Cement
- 7. Class F Fly Ash
- 8. Remaining water / WRDA 35 mixture
- 9. Silica Fume
- 10. Additional ADVA Flow to achieve the desired workability

When mixing during the winter months, hot water (approximately 100 degrees F) was added to compensate for the cold aggregate to promote early strength gain. Steps 1-5

were performed immediately following each other. The components in the pan after step 5 were allowed to mix for one minute to insure consistent distribution of the AEA and water reducing admixtures. After the addition of the silica fume, the components were allowed to mix for approximately 2-3 minutes to insure thorough mixing. Additional ADVA (Step 10) was tracked on the mix design sheet for future reference. The same component addition sequence was used for lab and field mixing with good success.

4.7 HSLC Properties

After batching the HSLC, four properties of the concrete were tested. The slump was measured using a standard slump cone per ASTM C 143.⁷⁴ The unit weight was measured with a 1/4 cubic foot bucket per ASTM C 138.⁷⁵ The temperature of the concrete was measured using ASTM C 1064.⁷⁶ The air content was measured with a roll-a-meter per ASTM C 173.⁷⁷

A common misconception is that air content can be determined for LWC with a pressure meter per ASTM C 231.⁷⁸ Since the LWA is a porous material, the pressure test can force water into the pore structure resulting in an incorrect (high) air content reading. Close examination of ASTM C 231 reveals that the test is not to be used for LWC.

4.8 Preparation of Specimens

Specimens were made per ASTM C 31.⁷⁹ Cylinders size 4 inches x 8 inches (4 x 8) were cast for determining compressive strength per ASTM C 39.⁸⁰ Cylinders size 6 inches x 12 inches (6 x 12) were cast for determining modulus of elasticity per ASTM C 469.⁸¹ Beams size 4 inches x 4 inches x 14 inches (4 x 4 x 14) were cast to perform the

modulus of rupture test per ASTM C 78.⁸² Cylinders size 4 inches in diameter x 15 inches with DEMEC gage inserts were cast in steel molds for creep testing per ASTM C 512.⁸³ Figures 4.8 and 4.9 show casting a beam and creep specimen molds, respectively.



Figure 4.8 Casting 4 x 4 x 14 Modulus of Rupture Specimens at Tindall Concrete Plant




Figure 4.9 Specimen Mold for Creep and Shrinkage Testing

In addition to the standard specimen molds, a block measuring 24 inches x 12 inches x 36 inches was cast to allow coring cylinders for strength testing. During girder construction, a similar block 24 inches deep was cast to perform the prestressing strand direct pullout test. Figures 4.10 and 4.11 show construction of these two blocks.




Figure 4.10 Construction of Block for Cored Cylinder Testing at Tindall Concrete Plant



Figure 4.11 Casting of Block for Direct Pullout Test at Tindall Concrete Plant

4.9 Specimen Curing

After casting specimens, the method of curing varied. Specimens were initially cured either on site or in the lab as per ASTM C 31, or were placed in a curebox to retain the heat of hydration. Accelerated curing using a curebox (Figure 4.12) was not covered by any ASTM specification, but had been shown to closely replicate girder curing conditions in previous research. After 24 hours, all specimens (except cored cylinder blocks and direct pullout test blocks which remained on site for 56 days) were removed from molds and placed in a fog room for curing through the time of testing. The fog room maintained 100 percent humidity and a temperature of approximately 73 degrees Fahrenheit. Moduli of rupture specimens were cured in a lime bath in the fog room until the time of testing.




Figure 4.12 Insulated Curebox Used for Accelerated Curing

After placing specimens in the curebox, any remaining empty space around the specimens was filled with an insulating fabric.

4.10 Specimen Testing

Specimen testing was performed at specified times depending on the type of mix and phase of the research project. All tests were performed in accordance with the appropriate ASTM specification as follows.

4.10.1 Compressive Strength

Compressive strength testing was performed according to ASTM C 39⁸⁰ using hard rubber caps seated in steel end caps according to ASTM 1231.⁸⁵ The hard rubber caps were cut from 1/2-inch conveyor belt material and reused as long as the surface condition did not show signs of wear. Based on testing HSLC, a set of rubber caps could be used to test from 30 to 50 cylinders prior to replacement. Prior to testing, the cylinder ends were smoothed as necessary to remove ridges or bumps that could affect strength results.

4.10.2 Modulus of Elasticity

Modulus of elasticity testing was performed according to ASTM C 469⁸¹ using 6 x 12 cylinders and hard rubber end caps as described in 4.10.1. Prior to performing the test, the average compressive strength of three 4 x 8 cylinders was determined. Based on the 4 x 8 strength, the predicted ultimate load was calculated for the 6 x 12 as well as 40 and 60 percent of the ultimate value. The modulus test frame (Figure 4.13) was installed on the 6 x 12 cylinder and the specimen placed in the 400-kip Baldwin load test machine. The specimen was initially loaded to 40 percent of ultimate to seat the cylinder and modulus test frame.




Figure 4.13 Modulus of Elasticity Testing Frame

After unloading the specimen, gages were zeroed and the specimen loaded to 60 percent of its ultimate strength. A data-taking sheet (Table 4.4) was created to simplify the test procedure. Data from the sheet was entered into a spreadsheet, which then determined the modulus of elasticity and Poisson's ratio. Critical to properly calculating the modulus of elasticity and Poisson's ratio values were determination of lengths and gage ratios from the test frame as per ASTM C 469.

Table 4.4 Elasticity Modulus and Poisson's Ratio Test Data Sheet

Elasticity Modulus and Poisson's Ratio Data Sheet				
Spec. Number	Date / Time	Est. Ult.	_ kips (4x8)	
40% Est. Ult kips	60% Est. Ult kips	Ult. Load	kips (6x12)	
Initial load to 40% of estima	ated ultimate accomplished to	o seat cylinder - yes	/ no.	
Load cylinder (Tests A,B) to	o 60% of estimated ultimate	while recording data	below.	

Longitudinal	Test A		Test B		
Gage	Load	Lateral	Load	Lateral	
Reading		Gage Reading		Gage Reading	
(inches)	(kips)	(inches)	(kips)	(inches)	
0.00000					
0.0008					
0.001					
0.002					
0.003					
0.004					
0.005					
0.006					
0.007					
0.008					
0.009					
0.010					
0.011					
0.012					
0.013					
0.014					
0.015					
0.016					
0.017					
0.018					
0.019					
0.020					
0.021					
0.022					
0.023					
0.024					
0.025					
0.026					

4.10.3 Modulus of Rupture

The modulus of rupture was determined in accordance with ASTM C 78^{82} using 4 x 4 x 14 beams tested using third-point loading. Figure 4.14 shows the modulus of rupture test set-up.




Figure 4.14 Modulus of Rupture Test Set-up

CHAPTER V

DEVELOPMENT OF HSLC MIX DESIGNS

5.1 Introduction

The purpose of this chapter is to discuss the laboratory development of the HSLC mix designs that were later tested under field conditions and ultimately used to construct pretensioned girders. The goal of this laboratory development phase was to configure HSLC mix designs that would achieve 8, 10 and 12 ksi design compressive strengths at 28 days; the target mean compressive strengths were 1,400 psi greater than the design strengths. In order to achieve those strengths, over 75 test mixes were batched and over 700 4 x 8 cylinders were tested.

5.2 Specimen and Curing Plan

The specimens cast during this phase predominantly 4 x 8 cylinders. The interest initially was to configure mix designs to achieve the objective strengths. Thus, 9 each 4 x 8 cylinders were cast from each mix and cured initially in cureboxes. After 24 hours in the curebox, 3 of the 9 cylinders were tested for compressive strength; the remaining 6 were placed in the fog room to continue curing for strength testing at 3 and 28 days.

5.3 Initial Mix Designs From Carolina Stalite

The starting points for the three objective HSLC mix design strengths were suggested mix designs received from experts at Carolina Stalite and shown in Table 5.1.

Table 5.1 Initial HSLC Mix Designs from Carolina Stalite

Concrete Components to Produce		Concrete Strength (psi)			
1 Cubic Yard of HSLC		8,000	10,000	12,000	
1/2-inch Stalite LWA	(lbs)	950	950	950	
Normal Weight Fine Aggregate	(lbs)	1221	1063	905	
Class F Fly Ash	(lbs)	200	200	200	
Silica Fume	(lbs)	35	45	56	
Cement	(lbs)	500	650	800	
Water	(gals)	32	33	34	
Air Content	(percent)	4	4	4	
Water / Cementitious Materials Ratio	(W/CM)	0.36	0.31	0.27	
Theoretical Equilibrium Unit Weight	(pcf)	117.5	117.9	118.3	

The coarse aggregate used in all initial mixes was the 1/2-inch Stalite LWA. Dosing on chemical admixtures was not initially specified in the Stalite mixes. Literature from Grace Construction Products and guidance from the local sales representative served as starting points.

5.4 Plan for Mix Development

Below are listed the steps followed in determining the optimum HSLC mix designs to meet the objective strengths.

Holding all other parameters steady, vary the ratio of coarse LWA to fine NWA
over a wide range from approximately 1 to 2. Determine if an optimum coarse to
fine aggregate ratio exists in that range.

- 2. Using the result of Step 1 and holding all other parameters steady, vary the percent cement paste in the mix from approximately 33 percent to 45 percent. Cement paste was defined as all components in the mix design except the aggregate. Determine if an optimum percent cement paste exists in that range.
- 3. Using the result of Steps 1 and 2 and holding all other parameters steady, vary the percent of silica fume in the mix from approximately 4 to 12 percent of the total cementitious materials (CM). Determine if an optimum percent silica fume exists in that range.
- 4. Using the results of Steps 1-3 (if possible), test the apparent optimum mix design with different size aggregates to determine the effect.

Based on the objective strength of 12,000 psi, a water to cementitious materials (W/CM) ratio of 0.23 was selected for mix proportioning.

5.4.1 Initial Mixes and Entrained Air

During the execution of Step 1, manufacturer suggested dose rates were followed for chemical admixtures. The first major problem encountered involved excessive air content. It became apparent over time that the air-entraining agent (AEA) was enhanced by the use of high-range water reducing (HRWR) admixture. In some cases, the resulting air contents approached 10 percent.

In order to determine specific details about the source of the air, and whether it was entrapped or entrained air, a study was conducted that was not part of the original development plan. The study involved making three batches of concrete as described in

Table 5.2. The 8,000 psi suggested mix design from Carolina Stalite was used for the test mixes.

Table 5.2 Air Content Study

Type of Coarse Aggregate Admixtures Used		Resulting Percent Air Content
Normal Weight (Granite)	ADVA and WRDA 35	2.0
1/2-inch Stalite LWA	ADVA and WRDA 35	2.0
1/2-inch Stalite LWA	No Admixtures	2.0

The resulting air contents shown in Table 5.2 indicated that neither the use of LWA or the use of ADVA and WRDA 35 had an impact on air content. Since the air content was the same for each mix, it was apparent that the mix most likely had 2 percent "entrapped" air. In order to achieve 4 percent air content total, only 2 additional percent were required. This was an indication that most likely a small dose of AEA would result in 4% total air content. Future mixes were dosed with only 0.75 to 1.0 fluid ounces of Daravair 1000 (AEA) per 100 weight of cementitious materials. Since the HRWR enhanced the effectiveness of the AEA, less AEA was required at higher HRWR dose rates. Based on manufacturer literature, 0.75 fluid ounces per 100 weight of CM was the lowest recommended AEA dose rate.

5.4.2 Variation of Coarse to Fine Aggregate Ratio - Step 1

The coarse to fine aggregate ratio was defined as the volume of coarse aggregate divided by the volume of fine aggregate. The parameters in Table 5.3 were held constant throughout all mixes in Step 1:

Table 5.3 Parameters Held Constant in Step 1

Water / Cementitious Materials Ratio	0.23
Percent Cement Paste	39
Fly Ash as Percent of Total Cementitious Materials	15
Silica Fume as Percent of Total Cementitious Materials	8
Type III Cement as Percent of Total Cementitious Materials	77

The results of Step 1 are shown in Table 5.4 and graphed in Figure 5.1.

Table 5.4 Results of Varying Coarse to Fine Aggregate Ratio - Step 1

Coarse to Fine	1-Day	3-Day	28-Day
	Compressive	Compressive	Compressive
Aggregate Ratio By Volume	Strength	Strength	Strength
By volume	(psi)	(psi)	(psi)
0.94	8,070	8,960	10,100
1.09	8,550	8,860	10,350
1.26	8,980	9,090	10,360
1.46	9,130	10,440	11,020
1.71	7,830	9,370	10,020
2.01	6,820	7,970	10,610

Figure 5.1 indicates that the optimum coarse to fine aggregate ratio using 1/2-inch Stalite LWA was approximately 1.46. The resulting strengths did not vary significantly, yet indicated a trend.

A similar study using 3/8-inch Stalite LWA showed the optimum ratio also to be approximately 1.5.




Figure 5.1 Results of Varying Coarse to Fine Aggregate Ratio

5.4.3 Variation of Percent Cement Paste - Step 2

Using the optimum coarse to fine ratio of 1.46 determined in Step 1, mixes were configured for Step 2 where the percent cement paste was varied between 33 and 39 percent. For a well-graded aggregate profile, 33 percent cement paste was considered optimum. The aggregate grading for this project contained gaps in the #8 and #16 particle sizes. Thus, it was thought that by examining the range from 33 to 39 percent that the additional paste would effectively fill the gaps in the smaller particle sizes. The parameters in Table 5.5 were held constant throughout all mixes in Step 2:

Table 5.5 Parameters Held Constant in Step 2

Water / Cementitious Materials Ratio	0.23
Coarse to Fine Aggregate Ratio by Volume	1.46
Fly Ash as Percent of Total Cementitious Materials	15
Silica Fume as Percent of Total Cementitious Materials	8
Type III Cement as Percent of Total Cementitious Materials	77

The results of Step 2 are shown in Table 5.6 and graphed in Figure 5.2.

Table 5.6 Results of Varying Percent Cement Paste – Step 2

Percent	1-Day	3-Day	28-Day
Cement	Compressive	Compressive	Compressive
Paste	Strength	Strength	Strength
rasic	(psi)	(psi)	(psi)
33	6,760	7,880	9,420
35	8,950	9,350	8,360
37	8,810	9,420	10,280
39	8,920	9,360	10,550




Figure 5.2 Results of Varying Percent Cement Paste

The results of Step 2 indicated the optimum percent cement paste was not at 33 percent based on the known gap grading in the aggregate profile. The need for additional cement paste appeared necessary. Figure 5.2 did not indicate an optimum value, but appeared to show a plateau that encompassed 39 percent based on 28-day strength. The drop in strength at 28 days for the 35 percent tests could not be explained. Thirty nine percent was chosen as the optimal percent cement paste value and was implemented in Step 3.

A similar study performed using 3/8-inch Stalite LWA and varying the percent cement paste from 35 to 45 percent also showed the optimum value to be around 39 percent. Based on gap grading in the overall aggregate profile considering 3/8-inch Stalite LWA and BB sand proportioned at a coarse to fine aggregate ratio of 1.5, this higher level of cement paste also was justifiable.

5.4.4 Variation of Percent Silica Fume-Step 3

Using the optimum coarse to fine ratio of 1.46 determined in Step 1, and the optimum percent cement paste of 39 percent determined in Step 2, mixes were configured for Step 3 where the percent silica fume was varied from 4 to 12 percent of total cementitious materials by weight. Based on the literature, it was thought that 8 percent silica fume was the upper limit for useful mix designs.⁶⁹ The parameters in Table 5.7 were held constant throughout all mixes in Step 3. Since the percent of silica fume varied during this step, the percent of cement had to vary as well in order to maintain a constant percent cement paste and W/CM ratio.

Table 5.7 Parameters Held Constant in Step 3

Water / Cementitious Materials Ratio	0.23
Coarse to Fine Aggregate Ratio by Volume	1.46
Percent Cement Paste by Volume	
Fly Ash as Percent of Total Cementitious Materials	15

The results of Step 3 are shown in Table 5.8 and graphed in Figure 5.3.

Table 5.8 Results of Varying Percent Silica Fume – Step 3

Percent	1-Day	3-Day	28-Day
Silica	Compressive	Compressive	Compressive
Fume	Strength	Strength	Strength
rume	(psi)	(psi)	(psi)
4	8,540	8,710	10,660
6	8,920	9,470	10,550
8	8,820	9,400	10,930
10	10,620	11,190	11,330
12	10,200	10,500	11,080




Figure 5.3 Results of Varying Percent Silica Fume

Figure 5.3 indicates that silica fume used as 10 percent of the total cementitious materials by weight provided the best strength results at 1, 3 and 28 days.

The use of 10 percent silica fume required the use of additional HRWR to provide necessary workability.

5.4.5 Strength Ceiling

The concept of a strength ceiling was discussed in Section 2.7.2. During mix development, it was noticed that a reduction of the W/CM ratio below 0.23 did not result in higher strengths. The strength ceiling also appeared to be inversely related to LWA size. The use of smaller aggregate resulted in higher compressive strengths. In order to investigate this phenomenon, a series of mixes was conducted as specified in Table 5.9. The high-strength normal weight concrete (HSNWC) listed in Table 5.9 was used for two sets of specimens. The first set incorporated all components in the mix design as listed. The second set of specimens contained only the portion of the mix that would pass through a 3/8-inch screen. The mix was screeded through a 3/8-inch screen in an attempt to remove the larger size coarse aggregate for purposes of determining the strength of the paste. While there may have been some small particles of the granite remaining in the paste, the vast majority was removed during screeding. The volume of coarse aggregate was identical for both mixes; the weight difference between the LWA and NWA is an indication of the weight reduction achieved with HSLC.

Table 5.9 Mixes for "Strength Ceiling" Study

_	Concrete Components to Produce 1 Cubic Yard		
# 67 Crushed Granite	(lbs)		1,574
½-inch Stalite LWA	(lbs)	948	
BB Sand	(lbs)	1100	1100
Class F Fly Ash	(lbs)	152	151
Silica Fume	(lbs)	101	101
Type III Cement	(lbs)	760	758
WRDA 35	(fl oz)	61	61
ADVA Flow	(fl oz)	132	173
Daravair 1000	(fl oz)	7.5	7.5
Water	(gal)	28.1	27.8

Slump	(inches)	4	5
Plastic Unit Weight	(pcf)	122.4	147.6
Temperature	(def F)	81	82

The results of the strength ceiling study are listed in Table 5.10. The HSNWC paste had the highest strength followed by the HSNWC then the HSLC. It would appear from the data that the strength ceiling for HSLC made with 1/2-inch Stalite LWA is around 11,400 psi. This result is in keeping with values estimated by Harmon.⁴⁵ Figure 5.4 shows a graph of the results in Table 5.10.

Table 5.10 Results of "Strength Ceiling" Study

Concrete Type	1-Day Strength	3-Day Strength	28-Day Strength	
	(psi)	(psi)	(psi)	
HSNWC Paste	11,780	13,160	13,380	
HSNWC	11,740	12,050	13,060	
HSLC	10,800	11,190	11,390	




Figure 5.4 Results of "Strength Ceiling" Study

5.5 Final Mix Designs

Using the optimum values determined in Steps 1, 2 and 3 (1.46 coarse to fine ratio, 39 percent cement paste, and 10 percent silica fume) and results of strength testing, the mix designs shown in Table 5.11 were suggested for 8,000, 10,000, and 12,000-psi strengths using 1/2-inch Stalite LWA. It was thought that the use of 1/2-inch aggregate would be more readily accepted in the precast industry than the smaller 3/8-inch aggregate. The mixes were configured by altering the content of CM based on W/CM ratios deemed necessary for each concrete strength.

Strength results of laboratory mixes using the final mix designs are given in Figure 5.5. The 12 mix underwent a drop in strength between 1 and 7 days, but increased in strength between 7 and 28 days.

Table 5.11 Objective 8,000, 10,000, and 12,000 psi Mix Designs for Field Testing

Concrete Components to Produce 1 Cubic Yard of HSLC	ce	Concrete Mix Designation Objective Strength (psi)			
Aggregate Assumed to be at SS	D	8 Mix	10 Mix	12 Mix	
85 8		8,000	10,000	12,000	
1/2-inch Stalite LWA	(lbs)	1022	1030	1030	
Normal Weight Fine Aggregate	(lbs)	947	955	955	
Class F Fly Ash	(lbs)	142	145	150	
Silica Fume	(lbs)	19	50	100	
Type III Cement	(lbs)	783	765	740	
WRDA 35	(fl oz)	57	58	59	
ADVA Flow	(fl oz)	57	65	139	
Daravair 1000	(fl oz)	9.4	9.6	7.5	
Water	(gals)	32.1	29.9	27.3	
Water / Cementitious Materials Ratio	(W/CM)	0.28	0.26	0.23	
Theoretical Equilibrium Unit Weight	(pcf)	115.6	116.2	116.6	




Figure 5.5 Strength Results of Laboratory Developed HSLC Mix Designs

CHAPTER VI

FIELD PRODUCTION OF HSLC

6.1 Introduction

The purpose of this chapter is to describe the field production of the HSLC mix designs developed in the lab and discussed in Chapter 5. The goal of this phase of the research project was to verify that the HSLC mix designs and procedures determined and tested in the lab could be replicated under field conditions.

6.2 Concrete Plant Equipment Description

All field production testing was performed at the Tindall Concrete Plant in Jonesboro, Georgia. The plant (Figure 6.1) specialized in the construction of bridge girders for use on highway and rail applications and double-tee girders used for various applications.



Figure 6.1 Tindall Concrete Plant, Jonesboro, Georgia

Aggregate storage was in large bins behind the mixing tower. Aggregate dropped through control gates at the base of the bins to a conveyor belt, which transported the material into hoppers atop the mixing tower. The bin into which the 1/2-inch Stalite LWA was delivered (Figure 6.2) was equipped with a sprinkler to wet the aggregate prior to use.



Figure 6.2 Tindall Aggregate Storage Bin With Sprinkler

At delivery, the Stalite LWA had an absorbed moisture content of over 6 percent. In order to maintain and improve the level of absorbed moisture, the sprinkler was run continuously until 24 hours prior to concrete placement. At the time of placement, tested moistures indicated absorption levels of at least 7.5 percent, well above the minimum

allowable 6 percent standard established for producing HSLC. As in the lab, the reason for shutting off the sprinkler 24 hours prior to mixing was to reduce the moisture gradient throughout the stockpile. After 24 hours, the excess free water had drained leaving a fairly consistent level of free moisture on the aggregate.

The concrete mixer was a 3 cubic yard auger-style mixer as shown in Figure 6.3. The mixer was charged using conveyor belts for the aggregate and a chute for the cement. The mix tower was only equipped to dispense Portland cement; all silica fume and fly ash was added to the mixer manually as shown in Figure 6.4. After mixing, the concrete was dispensed through an opening in the side of the mixer to a chute that carried the concrete to the Tuckerbilt concrete transport vehicle shown in Figure 6.5.



Figure 6.3 Auger-Type Mixer at Tindall Concrete



Figure 6.4 Manual Addition of Fly Ash and Silica to Concrete Mixer at Tindall Concrete

6.3 Description of Materials Available at Tindall Concrete

The Tindall Plant used only Type III Cement manufactured by CEMEX-Southdown. The particular brand of cement was "Demopolis" named for the city near which it was manufactured in Alabama. The cement had a lower specific gravity (3.08) than the cement received from Blue Circle-LaFarge for mix development, which was about 3.15. The "Demopolis" Type III was reputed for producing exceptional high-early strength gain.




Figure 6.5 Mix Tower and Tuckerbilt Concrete Transport Vehicle

Tindall also used Brown Brothers sand, the same as used during HSLC mix development. Quality control checks on the sand indicated it had a specific gravity of 2.5 and a fineness modulus of 2.38.

Chemical admixtures available were from Grace Construction Products and matched those used during HSLC mix development. Chemical admixtures were dosed automatically from controls in the mix tower.

6.4 Area for Casting Specimens

The Tindall Plant Superintendent, Mr. Todd Davidson, was very accommodating during the field production testing phase. A large, flat area was provided for casting specimens and access was provided to quality control equipment. Figure 6.6 shows casting specimens outside the Tindall quality control shop.



Figure 6.6 Casting Specimens at Tindall Concrete

6.5 Field Production of HSLC Mixes

The following sections address the field placements of the 8,000, 10,000 and 12,000 psi HSLC mixes identified as 8F, 10F and 12F, respectively. Several common actions occurred prior to mixing concrete to include positioning all molds and equipment in the casting area, performing quality control checks (moisture contents on LWA and NW sand), coordination with the plant manager, mix proportioning, and a briefing for student assistants on safety and the correct technique for casting specimens. The

specimens cast during each field-mixing test are specified in Table 6.1. Resulting material properties are covered in Section 6.6.

Table 6.1 Number of Specimens Cast During Each Field Mixing Test

Specimen Type	Time o	f Testin	g After l	Placem	ent (H=	Hours, I	D=Days)
Curing Method	16H	20H	24H	7D	28D	56D	365D
Type of Test	1011	2011					
4 x 8 Cylinder							
Curebox	3	3	3	3	3	3	3
Compressive Strength							
4 x 8 Cylinder							
ASTM			3		3	3	3
Compressive Strength							
6 x 12 Cylinder							
Curebox	3		3		3	3	
Modulus of Elasticity							
6 x 12 Cylinder							
ASTM			1			3	
Modulus of Elasticity							
4 x 4 x 14 Beam							
Curebox			3			3	
Modulus of Rupture							
4 x 8 Cylinder							
Curebox					<u> </u>	3	3
Chloride Permeability							
20 x 36 x 12 Block							
ASTM							
Cored Cylinder						1	
Compressive Strength						1	
(3 Cores Tested)							

The 20 x 36 x 12 (W x L x H) block was cast to replicate curing conditions in the bottom flange of a girder. In addition to the specimens listed above, extra specimens were cast to the greatest extent possible based on space in cureboxes and availability of molds. Extra specimens provided flexibility in the event a specimen was dropped, testing was improperly conducted, or test results were irregular.

After casting, the specimens were covered with plastic lids or other suitable material to provide protection, and placed on a level surface. Thermocouples were inserted into select specimens to monitor the heat of hydration for each type of specimen. After reaching initial set (about 2-3 hours), those specimens identified as curebox specimens were placed into an insulated curebox as pictured in Figure 4.12. The cureboxes had been prepositioned in the back of a van prior to casting. ASTM specimens were placed in open containers and allowed to cure exposed to the ambient temperature. Approximately 12-14 hours after placement (after final set of the concrete), the specimens were transported back to the Georgia Tech Structures Lab and prepared for testing as necessary. The specimens were not removed from the curebox until their specified time of testing or until 24 hours had passed, whichever occurred first. Upon removal from the curebox, the specimen was demolded, labeled with its mix number, date and researchers initials, then either tested or placed in the fog room for additional curing through its time of testing.

6.5.1 Field Production Test #1 - 8,000 PSI HSLC (Designation = 8F)

The first field production test was conducted on March 27, 2001. The weather was ideal for concrete placement with a temperature of 50° F, dry conditions, and no wind. Quality control tests on the aggregate resulted in "absorbed" and "as-is" moistures of 7.83 and 11.00 percent, respectively, for the Stalite LWA. The "as-is" moisture for the NW sand was 4.1 percent. The 8,000 psi mix "as batched" is listed in Table 6.2.

Mixing was initiated using a "buttering mix" to prepare the concrete mixer for future batches. The purpose of the buttering mix was to coat the mixer with cement paste

and prevent mix water from being pulled out of mixes to follow. The buttering mix was 1/4-cubic yard in size and had the same proportions as the mix planned for casting specimens. After buttering the mixer, the buttering mix was discarded.

Table 6.2 8,000 PSI (8F) Field Production Mix

Concrete Components							
to Produce 1 Cubic Yard							
1/2-inch Stalite LWA (lbs) 978							
Brown Brothers Sand	(lbs)	1062					
Class F Fly Ash	(lbs)	142					
Silica Fume	(lbs)	19					
Type III Cement	(lbs)	785					
WRDA 35	57						
ADVA Flow (fl oz) 47+10							
Daravair 1000 (fl oz) 9.5							
Water	(gal)	23.9+0.5					

Slump (ii	nches)	4
Planned Wet Unit Weight	(pcf)	118.1
Actual Wet Unit Weight	(pcf)	118.6
Temperature (def F)	67.5
Air Content (Per	rcent)	3.5
Curing Start Time	3:00 pm	

Mixing proceeded without any major problems. The components of the mix were added in the same order determined during laboratory mix development and listed in Section 4.6. An additional 10 fluid ounces of ADVA was added to provide the required workability. The additional water resulted from a valve that could not be closed completely. It was estimated that 1/2-gallon leaked into the mixer; however it was impossible to determine an exact value.

After mixing, the HSLC was dispensed into the Tuckerbilt and taken to the specimen casting area for quality control checks and then casting. Results of the quality control checks are listed at the bottom of Table 6.2. The resulting mix was within standard for all tests performed.

Several lessons were learned and noted for future placements. The most important issue of note was the valve that allowed water to leak into the concrete mixer. This leak made it impossible to determine the exact amount of water in the batch.

6.5.2 Field Production Test # 2 - 10,000 PSI HSLC (Designation = 10F)

The second field production test was conducted on April 3, 2001. The temperature was 62° F, but the weather was not ideal for concrete placement.

Immediately after beginning to batch the concrete, heavy rain began to fall. The wind picked up to the point where it was raining almost horizontally. In anticipation of the rain, the molds had been moved under cover next to the casting area. Heavy rain continued through the conclusion of casting.

Earlier quality control tests on the aggregate resulted in "absorbed" and "as-is" moistures of 7.88 and 11.19 percent respectively for the Stalite LWA. The "as-is" moisture for the NW sand was 2.98 percent. The 10,000 psi mix as batched is listed in Table 6.3.

Mixing was again initiated using a 1/4-cubic yard "buttering mix.

During this mix, only 15 gallons of the planned 23.4 gallons were added. It appeared that the moisture content of the sand was much higher than determined earlier, which would have reduced the amount of required mix water. Since the aggregate

hoppers in the mix tower were covered, the rain was not the cause of the higher moisture contents.

Table 6.3 10,000 PSI (10F) Field Production Mix

Concrete Components							
to Produce 1 Cubic Yard							
1/2-inch Stalite LWA (lbs) 984							
Brown Brothers Sand	(lbs)	1055					
Class F Fly Ash	(lbs)	146					
Silica Fume	(lbs)	49					
Type III Cement	(lbs)	765					
WRDA 35	(fl oz)	57					
ADVA Flow	(fl oz)	62+2					
Daravair 1000	(fl oz)	9					
Water	(gal)	23.4 (15)					

Slump (inches)	7.5
Planned Wet Unit Weight	(pcf)	118.7
Actual Wet Unit Weight	(pcf)	121.0
Temperature	(def F)	62
Air Content (Pe	ercent)	3.8
Curing Start Time	2:00 pm	

The components of the mix were added in the same order determined during laboratory mix development and listed in Section 4.6. An additional 2 fluid ounces of ADVA was added to provide the required workability.

Results of the quality control checks are listed at the bottom of Table 6.3. The resulting mix had a slump and unit weight that were higher than planned, but still acceptable.

Despite the rain and moisture control problems, the mix produced good results.

6.5.3 Field Production Test #3 – 12,000 PSI HSLC (Designation = 12F)

The third and final field production test was conducted on April 10, 2001. The temperature was 90° F in the shade. Conditions were dry with no wind.

Quality control tests on the aggregate resulted in "absorbed" and "as-is" moistures of 7.69 and 11.12 percent respectively for the Stalite LWA. The "as-is" moisture content of the NW sand was 6.12 percent. The 12,000-psi mix "as batched" is listed in Table 6.4.

Mixing was again initiated using a 1/4-cubic yard "buttering mix.

During this mix, only 14 gallons of the planned 16.7 gallons were added. It appeared that the moisture content of the sand was slightly higher than tested earlier.

Table 6.4 12,000 PSI (12F) Field Production Mix

Concrete Components							
to Produce 1 Cubic Yard							
1/2-inch Stalite LWA (lbs) 985							
Brown Brothers Sand	(lbs)	1088					
Class F Fly Ash	(lbs)	150					
Silica Fume	(lbs)	100					
Type III Cement	(lbs)	740					
WRDA 35	(fl oz)	59					
ADVA Flow	(fl oz)	129+8					
Daravair 1000 (fl oz) 7							
Water	(gal)	16.7 (14)					

Slump	(inches)	4.5
Planned Wet Unit V	Weight (pcf)	119.1
Actual Wet Unit W	eight (pcf)	124.2
Temperature	(def F)	86
Air Content	(Percent)	2.5
Curing Start	4:00 pm	

The components of the mix were added in the same order determined during laboratory mix development and listed in Section 4.6. An additional 8 fluid ounces of ADVA was added to provide the required workability.

Results of the quality control checks are listed at the bottom of Table 6.4. The resulting mix had a low air content that was cause in part for the mix having a higher unit weight than anticipated. The 4.5-inch slump enabled easily casting the specimens.

Despite the heat, the casting went well.

6.6 Results of Field Mixing

The combined results of field mixing are shown in Table 6.5 by specimen type, mix designation, and age of specimen. Each strength or modulus result shown is the average of three tests. The Masters Thesis by Brandon Buchberg, ⁸⁶ "Investigation of Mix Design and Properties of High-Strength/High-Performance Lightweight Concrete" addresses chloride permeability, creep and shrinkage, coefficient of thermal expansion, and provides extensive detail on the results of each mix in this research project. Chapter 7 of this report compares the results of the field testing program (8F, 10F and 12F) with results achieved during a similar laboratory testing program using the same specified 8,000, 10,000, and 12,000 psi mixes (8L, 10L, and 12L) and with the 8,000 and 10,000 mixes (G1 and G2) used in girder construction.

There are several trends seen in Table 6.5 that are addressed further in the following sections.

Table 6.5 Results of Field Mixing

Specimen				Mean Str	ength or			of Testing	5
Curing	Units	Mix			(H=H	ours, D=	Days)		
Test			16H	20H	24H	7D	28D	56D	365D
4 x 8 Cyl		8F	7,920	8,470	8,870	9,570	9,830	10,600	10,830
Curebox	psi	10F	7,710	9,070	9,750	10,010	10,430	11,170	11,520
Comp. Str.		12F	10,990	10,500	11,490	11,250	11,460	11,550	12,140
4 x 8 Cyl		8F			6,760		10,250	11,090	11,800
ASTM	psi	10F			6,200		11,140	11,300	11,680
Comp. Str.		12F			9,330		11,550	11,620	12,280
6 x 12 Cyl	10 ⁶	8F	3.49		3.67		3.85	3.86	
Curebox	1	10F	3.48		3.75		4.22	4.08	
Elast. Mod	psi	12F	3.92		4.12		4.30	4.26	
6 x 12 Cyl	10 ⁶	8F						4.13	
ASTM		10F						4.26	
Elast. Mod.	psi	12F						4.40	
4 x 4 x 14		8F			788			1,089	
Curebox	psi	10F			641			998	
Rupt. Mod.		12F			761			1,014	
Block		8F						9,550	
ASTM	psi	10F						10,270	
Comp. Str.		12F						11,470	

6.6.1 Strength Gain of 4 x 8 Cylinders

For all three mixes, the 1-day curebox strengths showed remarkable early strength gain. The 8F mix continued to gain strength through 365 days ultimately achieving 10,830 psi and 11,800 psi for curebox and ASTM specimens, respectively. The 10F mix also showed remarkable early strength gain and continued to gain strength through 365 days. The 12F mix reached within 650 psi of its ultimate strength after 24 hours based on curebox specimen results. From that point through 365 days, the mix initially lost strength then rose again to reach 12,140 psi and 12,280 psi for curebox and ASTM specimens, respectively. The effect of the silica fume can be seen in mix 12F. After 24

hours, it had achieved a compressive strength 1,700 psi greater than the 10F mix and 2,600 psi greater than the 8F mix. The main differences between the mixes were the silica fume content and W/C ratio. Figures 6.7 and 6.8 show plots of strength gain for the three mixes through 56 and 365 days, respectively.




Figure 6.7 Strength Gain for 4 x 8 Curebox and ASTM Cylinders Through 56 Days




Figure 6.8 Strength Gain for 4 x 8 Curebox and ASTM Cylinders Through 365 Days

6.6.2 Curebox vs. ASTM 4 x 8 Cylinders

After 24 hours of curing, the curebox cylinders had reached a strength between 2,000 and 2,500 psi greater than the ASTM cured cylinders. The insulated cureboxes held in the heat of hydration causing the curebox cylinders to hydrate more quickly and achiever higher early strengths. After 56 days, the ASTM strengths were about 2 percent greater than the curebox strengths for each mix. After 365 days, the 8F ASTM strengths

were about 9 percent greater than curebox strengths; the 10F and 12F ASTM strengths were less than 1 percent greater. Figures 6.7 and 6.8 show how the ASTM and curebox strength gains differed.

6.6.3 Strength Ceiling

The concept of a strength ceiling was discussed in Sections 2.7.2 and 5.4.5.

Examination of Figure 6.8 reveals that an apparent strength ceiling exists at just above 12,000 psi, slightly higher than it was thought to be during the laboratory development phase. The 12F mix provides the best indication of a strength ceiling. After 24 hours, the 12F cylinders had practically reached their maximum strength at 11,490 psi. At 56 days, the 12F cylinders had effectively gained 60 psi strength. 60 psi could be considered as normal variation in testing between the two sets of cylinders. The 12F ASTM cylinders showed a similar trend gaining only 70 psi from 28 through 56 days. After 365 days, the curebox and ASTM cylinders had gained an additional 590 psi and 660 psi, respectively.

6.6.4 Modulus of Elasticity

The modulus of elasticity results showed a slight drop at 56 days for the 10F and 12F cylinders. The ASTM cylinders achieved about 5 percent higher modulus values on average at 56 days in comparison to the curebox cylinders. Further analysis of modulus of elasticity values is covered in Chapter 7, Short and Long-Term Properties.

6.6.5 Modulus of Rupture

Table 6.5 shows how the moduli of rupture results were unpredictable. As the compressive strength increased, the modulus of rupture was expected to have increased.

The 8F mix produced the highest modulus of rupture results of the three tests, but it had the lowest compressive strength. Based on these results it is hypothesized that there is an upper limit for f_r in HSLC. Chapter 7 compares these results with laboratory specimens and specimens created during girder construction.

6.6.6 Target Strengths

According to ACI 318, Section 5.3.2.2,² the required average compressive strength when data are not available to establish a standard deviation is the design strength + 1,400 psi for strengths over 5,000 psi. Table 6.6 outlines the test results for each mix and the allowable design strength based on 56-day results.

Table 6.6 Resulting Strengths and Allowable Design Strengths

Mix	Average	Average	Maximum
Designation	Curebox	ASTM	Specifiable
	Strength	Strength	Design Strength
	(psi)	(psi)	(psi)
8F	10,600	11,090	9,690
10F	11,170	11,300	9,900
12F	11,550	11,620	10,220

Based on ACI requirements, the maximum design strength achievable from the three mixes was 10,220 psi. The maximum specifiable design strength was based on the average ASTM strength results since they were greater. These results indicate that the existence of a strength ceiling at about 11,500 psi limits the specifiable design strength to just over 10,000 psi.

During girder construction, a series of cylinders was cast such that a statistical study could be performed. ACI 318² allows the use of statistical results to reduce the code specified 1,400-psi strength reduction. Chapter 7 includes discussion of the statistical study conducted for HSLC.

6.7 Conclusions

Mixing HSLC in a commercial plant can be accomplished with good success.

The strength results in Table 6.5 indicate that with proper quality control that the same strengths can be achieved in the field as in the laboratory.

Moisture content in slate LWA can be adequately controlled in a field environment by sprinkling the aggregate continuously until just prior to mixing.

Curebox cured specimens achieved greater early strengths at 24 hours, but ultimately did not achieve the strengths reached by ASTM specimens at 56 days.

Moduli of elasticity values for ASTM cured specimens were greater than for curebox-cured specimens.

CHAPTER VII

MECHANICAL PROPERTIES OF HSLC

7.1 Introduction

The purpose of this chapter is to report and compare the mechanical properties from all HSLC mixes determined and tested during this research project and to discuss the aspects that relate directly to girder performance characteristics examined. Specific batch information and test results including compression strength, modulus of elasticity, and modulus of rupture are reported. The results of a statistical study are discussed. The Masters Thesis by Brandon Buchberg⁸⁶ "Mix Design Performance of High Strength — High Performance Lightweight Concrete" provides a more in-depth analysis of all material property related data.

7.2 Overview of HSLC Material Testing Program

The mixing and testing of HSLC was accomplished in four phases with specimens designated as shown in Table 7.1.

Table 7.1 HSLC Material Testing Program Specimen Designation

Objective Mix	Phase 1	Phase 1 Phase 2		Phase 4
Design Strength	Strength Mix Development F		Laboratory	Girder
(psi)	In Laboratory	Production	Verification	Construction
8,000	8 Mix	8F	8L	G1
10,000	10 Mix	10F	10L	
12,000	12 Mix	12F	12L	G2

In Phase 1, mix designs labeled "8 Mix," "10 Mix," and "12 Mix" were developed in order to meet objective design strengths of 8,000, 10,000, and 12,000 psi as described in Chapter 5. A strength ceiling of approximately 12,200 psi prevented the 12,000 psi objective design strength from being reached; the designation was maintained for consistency of reference.

In Phase 2, the mix designs developed during Phase 1 underwent a field production test as described in Chapter 6; the Phase 2 mix designs and specimens were designated 8F, 10F, and 12F to signify the objective design strength of the mix and that it was field-produced at Tindall Concrete.

In Phase 3, the same mix designs developed in Phase 1 and field-produced in Phase 2 were more fully evaluated in the laboratory. The Phase 3 mix designs and specimens were designated 8L, 10L, and 12L to signify the objective strength of the mix and that they were produced in the laboratory. Many individual batches of concrete were required during Phase 3. Every attempt was made to maintain consistency between the batches.

In Phase 4, the same mix designs developed in Phase 1 and field-produced in Phase 2 were used to construct girders; only the 8,000 and 12,000 psi objective strength mixes were used for girder construction. During girder construction, the 8,000 psi mix design and specimens were labeled G1 indicating a Grade 1 concrete. The 12,000 psi objective strength mix design and specimens were labeled G2 indicating a Grade 2 concrete

7.3 Specimen Casting Plan

Table 6.1 listed the specimen casting plan used during each field-production test.

Table 7.2 shows the specimen casting plan during laboratory evaluation (Phase 3). The number in parenthesis indicates the individual batch from which the specimens were cast.

The 10L series of batches had only three matches (1-3) as explained in Section 7.5.3.

Table 7.2 Specimens Cast During Laboratory Verification Batches (Phase 3)

Specimen Type	Time o	of Testin	g After	Placem	ent (H=	Hours, I	D=Days)
Curing Method	16H	20H	24H	7D	28D	56D	365D
Type of Test	1011	2011	2411	7.0	201	301	303D
4 x 8 Cylinder							
Curebox	3(4)	3(4)	3(4)	3(1)	3(1)	3(1)	3(1)
Compression Strength							
4 x 8 Cylinder							
ASTM			3(1)		3(1)	3(1)	3(1)
Compression Strength							
6 x 12 Cylinder							
Curebox	3(4)		3(4)			3(2)	
Modulus of Elasticity							
6 x 12 Cylinder							
ASTM						3(2)	
Modulus of Elasticity							
4 x 4 x 14 Beam							
Curebox			3(3)			3(3)	
Modulus of Rupture			·				
4 x 4 x 14 Beam							
ASTM			3(3)			3(3)	
Modulus of Rupture							
4 x 8 Cylinder							
Curebox						2(2)	2(2)
Chloride Permeability							
4 x 15 Cylinder							
Curebox	5(5)		5(5)				
Creep / Shrinkage							

Table 7.3 shows the specimen casting plan for girder construction (Phase 4). The first number listed is the number of specimens cast from the initial batch of concrete

(G1A1, G1B1, G2A1, G2B1) on each day girders were cast. The number in parenthesis is the number of specimens cast from all subsequent batches of concrete (G1A2-4, G1B2 3, G2A2-5, G2B2-4) on each day girders were cast. The direct pullout test block was only cast during placements G1A and G2A. Extra specimens were cast when possible.

Table 7.3 Specimens Cast During Girder Construction Batches (Phase 4)

Specimen Type	Time o	f Testi	ng After	Placeme	ent (D=Days)
Specimen Type Curing Method Type of Test	1D	7D	28D	56D	Time Of Girder Testing
4 x 8 Cylinder Curebox Compression Strength	3(3)	3	3	3	3(3)
4 x 8 Cylinder ASTM Compression Strength	3	3	3	3(3)	3
6 x 12 Cylinder Curebox Modulus of Elasticity	3	-		3	
6 x 12 Cylinder ASTM Modulus of Elasticity				1(1)	
4 x 4 x 14 Beam Curebox Modulus of Rupture				3	
4 x 4 x 14 Beam ASTM Modulus of Rupture				1(1)	
4 x 15 Cylinder Curebox Creep / Shrinkage	6				
20 x 36 x 24 Block ASTM Direct Pullout Test				1	*

7.4 Mix Designs as Determined in Phase 1

For reference, Table 7.4 lists the resulting mix designs from Phase 1.

Table 7.4 Objective 8,000, 10,000, and 12,000 psi Mix Designs from Phase 1

Concrete Components to Produce		Concrete Mix Designation Objective Strength (psi)			
1 Cubic Yard of HSLC		······································			
Aggregate Assumed to be at SSD		8 Mix	10 Mix	12 Mix	
		8,000	10,000	12,000	
1/2-inch Stalite LWA	(lbs)	1,022	1,030	1,030	
Normal Weight Fine Aggregate	(lbs)	947	955	955	
Class F Fly Ash	(lbs)	142	145	150	
Silica Fume	(lbs)	19	50	100	
Type III Cement	(lbs)	783	765	740	
WRDA 35 Low-Range Water Reducer (LRWR)	(fl oz)	57	58	59	
ADVA Flow High-Range Water Reducer (HRWR)	(fl oz)	57	65	139	
Daravair 1000 Air Entraining Agent (AEA)	(fl oz)	9.4	9.6	7.5	
Water	(gals)	32.1	29.9	27.3	
Water / Cementitious Materials Ratio	(W/CM)	0.28	0.26	0.23	
Theoretical Wet Unit Weight	(pcf)	118.1	118.7	119.1	
Theoretical Equilibrium Unit Weight	(pcf)	115.6	116.2	116.6	

7.5 Mixes as Batched and Wet Concrete Properties

The following sections provide the "as batched" component listings for each batch of concrete produced in Phases 2, 3 and 4. The components listed are based on aggregate at the saturated surface dry (SSD) condition.

7.5.1 Girder Placement Dates, Times and Ambient Temperatures

Table 7.5 Girder Construction Batch Information

Girders	Batch Series	Date/Time	Ambient Temp. ⁰ F	Weather
G1A, G1B	G1A	9 July 01, 1800	87	Dry, Clear
G2A, G2B	G2A	12 July 01, 1000	88	Dry, Clear
G1C	G1B	17 July 01, 1700	90	Dry, Clear
G2C	G2B	17 July 01, 1600	92	Dry, Clear

7.5.2 8,000 psi HSLC Design Strength

Tables 7.6 and 7.7 show batching results for the 8,000 psi design strength mixes.

Table 7.6 8,000 psi HSLC Mixes (8F and 8L)

Concrete Components to Produce 1 Cubic Yard										
Component	Unit	8F	8L1	8L2	8L3	8L4	8L5			
1/2-in LWA	Lbs	947	954	954	954	954	954			
NW Sand	Lbs	1,022	1,029	1,029	1,029	1,029	1,029			
Class F Fly Ash	Lbs	141	140	140	140	140	140			
Silica Fume	Lbs	19	19	19	19	19	19			
Type III Cement	Lbs	780	774	774	774	774	774			
LRWR	fl oz	56	56	56	56	56	56			
HRWR	fl oz	57	81	78	85	90	104			
AEA	fl oz	9.4	9.3	9.3	9.3	9.3	9.3			
Water	Gal	32.0	31.7	31.7	31.7	31.7	31.7			
Slump	in	4.00	4.25	4.5	4.5	4.5	7			

Slump	in	4.00	4.25	4.5	4.5	4.5	7
Wet Unit Wt	pcf	118.6	118.6	119.4	120.3	122.0	123.8
Batch Temp	⁰ F	68	90	89	90	88	89
Air Content	%	3.50	4.00	3.75	4.00		

Table 7.7 8,000 psi HSLC Mixes (G1)

Concrete Components to Produce 1 Cubic Yard										
Component	unit	G1A1	G1A2	G1A3	G1A4	G1A5	G1B1	G1B2	G1B3	
1/2-in LWA	lbs	944	937	925	925	925	941	960	941	
NW Sand	lbs	1,018	1,011	999	999	999	1,029	1,050	1,030	
Class F Fly Ash	lbs	141	140	138	138	138	143	146	143	
Silica Fume	lbs	19	19	19	19	19	19	19	19	
Type III Cement	lbs	780	774	765	765	765	788	804	788	
LRWR	fl oz	56	56	55	55	55	57	58	57	
HRWR	fl oz	64	64	63	63	63	58	53	58	
AEA	fl oz	9.4	9.3	9.2	9.2	9.2	9.5	9.7	9.5	
Water	gal	34.1	35.3	37.3	37.3	37.3	32.3	28.8	32.3	

Slump	in	8.00		 	 7.00	
Wet Unit Wt	pcf	118.6		 	 120.8	
Batch Temp	⁰ F	85		 1	 86	
Air Content	%	4.5	3.2	 •	 	

7.5.3 10,000 psi HSLC Design Strength

Table 7.8 shows batching results for the 10,000 psi design strength mixes. This mix design was only batched during the field production test (Phase 1) and the laboratory verification (Phase 3). No girders were cast with this mix design; thus only three batches of this mix design were made during the laboratory evaluation phase.

Table 7.8 10,000 psi HSLC Mixes (10F and 10L)

Concrete Components to Produce 1 Cubic Yard								
Component	unit	10F	10L1	10L2	10L3			
1/2-inch LWA	lbs	955	952	952	952			
NW Sand	lbs	1,030	1,027	1,027	1,027			
Class F Fly Ash	lbs	146	146	146	146			
Silica Fume	lbs	49	49	49	49			
Type III Cement	lbs	765	762	764	764			
LRWR	fl oz	58	57	58	58			
HRWR	fl oz	64	88	88	88			
AEA	fl oz	9.6	9.6	9.6	9.6			
Water	gal	29.9	31.8	31.4	31.4			

Slump	in	7.50	3.50	4.25	4.25
Wet Unit Weight	pcf	121.0	122.7	122.4	122.3
Temperature	⁰ F	62	92	91	92
Air Content	%	3.80	3.00	3.00	3.00

7.5.4 12,000 psi HSLC Design Strength

Air Content

%

2.50

Tables 7.9 to 7.11 show batching results for the 12,000 psi objective mix design.

Table 7.9 12,000 psi HSLC Mixes (12F and 12L)

Concr	ete Cor	nponen	ts to Pro	duce 1	Cubic Y	ard		
Component	Unit	12F	12L1	12L2	12L3	12L4	12L5	
1/2-in LWA	Lbs	955	947	947	947	956	955	
NW Sand	Lbs	1,029	1,021	1,021	1,021	1,026	1,024	
Class F Fly Ash	Lbs	150	149	149	149	149	149	
Silica Fume	Lbs	100	99	99	99	100	100	
Type III Cement	Lbs	740	734	734	735	740	740	
LRWR	fl oz	59	59	59	59	59	59	
HRWR	fl oz	131	135	135	135	185	222	
AEA	fl oz	9.9	7.4	7.4	7.4	9.9	9.9	
Water	Gal	27.2	27.2	27.2	28.6	27.7	27.6	
		,		- 4				
Slump	In	4.50	3.50	3.00	3.50	4.00	6.00	
Wet Unit Wt	Pcf	124.0	121.2	121.7	120.9	122.8	123.2	
Batch Temp	⁰ F	86	90	91	89	93	95	

Table 7.10 12,000 psi HSLC Mixes (G2A)

3.50

3.00

3.50

Concrete Components to Produce 1 Cubic Yard									
Component	Unit	G2A1	G2A2	G2A3	G2A4	G2A5			
½-in LWA	lbs	968	949	940	939	945			
NW Sand	lbs	1,039	1,018	1,009	1,007	1,014			
Class F Fly Ash	lbs	151	148	147	147	148			
Silica Fume	lbs	101	99	98	98	98			
Type III Cement	lbs	746	732	725	724	728			
LRWR	fl oz	60	59	58	58	58			
HRWR	fl oz	148	150	146	144	144			
AEA	fl oz	7.5	7.3	7.3	7.3	7.3			
Water	gal	25.8	29.2	30.9	31.1	30.0			
~					T				

Slump	in	5.75		 	
Wet Unit Wt	pcf	120.0		 	
Batch Temp	⁰ F	86		 	
Air Content	%	5.40	3.50	 	

Table 7.11 12,000 psi HSLC Mixes (G2B)

Concrete Components to Produce 1 Cubic Yard								
Component	Unit	G2B1	G2B2	G2B3	G2B4			
½-in LWA	lbs	956	933	933	945			
NW Sand	lbs	1,025	1,001	1,001	1,014			
Class F Fly Ash	lbs	149	146	146	148			
Silica Fume	1bs	100	97	97	98			
Type III Cement	lbs	737	719	719	729			
LRWR	fl oz	59	58	58	59			
HRWR	fl oz	147	145	145	146			
AEA	fl oz	7.4	7.3	7.3	7.3			
Water	gal	28.1	32.1	32.1	31.7			

Slump	in	4.5			
Wet Unit Wt	pcf	114.0			
Batch Temp	⁰ F	86			
Air Content	%	3.00	3.20	3.60	

7.6 Compression Strength Results

Compression strength results are shown according to cylinder size, type of curing, and age of cylinder. The 6 x 12 compression strength results were determined when performing modulus of elasticity tests. A comparison between the 4 x 8 and 6 x 12 results is provided as are the results of a statistical study performed on specimens cast during batch series G2B.

7.6.1 4 x 8 Cylinder Compression Strength Results

The results of compression strength testing for all 4 x 8 cylinders are shown in Table 7.12. For field production and laboratory evaluation, the resulting strengths shown are the average of three compression strength tests. For girder construction batches, the values are the average of all cylinders made from the four or five batches in the batch

series. The number after the "Time of Test" strength is the average specimen age in Days. Figures 7.1, 7.2 and 7.3 graph the strength vs. age of the 8,000, 10,000 and 12,000 psi concretes, respectively. The 1-day strength was not available for the 10L ASTM specimen.

Table 7.12 Results of 4 x 8 Cylinder Compression Strength Testing

	Batch			Mear	Cylinde	r Strength	ı (psi)		
Objective	#				ours, D=				
Strength								Time	
Curing		16H	20H	24H	7D	28D	56D	Of	1Y
								Test	
	8F	7,920	8,470	8,870	9,570	9,830	10,600		10,830
8,000	8L	7,320	7,630	7,730	9,300	9,630	10,430		
Curebox	G1A			7,470	7,810	8,710	9,080	9,418	103D
	G1B			6,320	6,300	7,480	7,750	8,792	110D
	8F			6,760		10,250	11,090		11,802
8,000	8L			6,300		9,830	10,520		
ASTM	GlA			5,740	7,320	8,840	9,350	10,229	103D
	G1B			5,400	5,890	7,600	8,460	9,118	110D
10,000	10F	7,710	9,070	9,750	10,010	10,430	11,170		11,516
Curebox	10L				9,260	9,410	9,920		
10,000	10F			6,200		11,140	11,300		11,675
ASTM	10L			6,950		10,360	11,040		
	12F	10,990	10,500	11,490	11,250	11,460	11,550		12,138
12,000	12L	9,840	9,760	11,101	10,230	10,590	10,860		
Curebox	G2A			9,640	9,460	10,170	10,420	10,965	123D
	G2B			8,260	9,150	9,340	10,250	10,454	144D
	12F			9,330		11,550	11,620		12,278
12,000	12L			6,890		10,600	11,480		
ASTM	G2A			9,290	9,460	10,120	10,820	11,012	123D
	G2B			6,550	8,070	9,810	10,510	10,868	144D




Figure 7.1 Compression Strength vs. Cylinder Age for 8,000 psi Mixes to 56 Days




Figure 7.2 Compression Strength vs. Cylinder Age for 10,000 psi Mixes to 56 Days




Figure 7.3 Compression Strength vs. Cylinder Age for 12,000 psi Mixes to 56 Days

Examination of Table 7.12 and Figures 7.1 through 7.3 show the difference between ASTM cylinder strengths and curebox strengths is significant at early ages and after 100 days. After 103 days, the G1A batch series ASTM specimens had about 800 psi greater strength than the curebox specimens. On average at the time of testing, ASTM specimens had about 4 percent greater strength than curebox specimens compared to 8 percent for the G1A batch series specimens.

Examination of results at the time of testing showed that strength gain continued from 56 days through the time of testing. The strength gain for the 8,000-psi batches was 729 psi on average, a gain of about 8.5 percent. The strength gain for the 12,000-psi batches was 324 psi on average, a gain of about 3 percent.

Examination of results after 365 days for the 8F, 10F and 12F showed that strength gain continued through 365 days. The 8F ASTM specimens had about 9 percent greater strength than the curebox specimens, but that ASTM specimens for the 10F and 12F mixes had less than 1 percent greater strength in comparison to the curebox specimens.

Comparison of the laboratory evaluation mixes with field-production test mixes shows that the field-production mixes had an average strength 3 percent greater than the corresponding laboratory mixes. When making the laboratory mixes, the same type of cement was used as during the field-production batches. The difference could be attributed to mix effort, age of cement, or the slightly different proportioning between the field and laboratory mixes.

The strength of girder mixes made on different days (G1A vs. G1B, G2A vs. G2B) were normally within 7%. In the case of batch series G1A vs. G1B, the difference was about 12 percent. The difference was most likely attributed to the water leak in the concrete mixer.

7.6.2 6 x 12 Cylinder Compression Strength Results

The results of 6 x 12 cylinder compression strength tests are shown in Table 7.13. All strengths are based on an average of three cylinder tests, except the ASTM values for batches G1A, G1B, G2A, and G2B were based on the average of tests of one cylinder from each of the four or five batches in the batch series.

Table 7.13 Results of 6 x 12 Cylinder Compression Strength Testing

Objective	Batch	Mear	Cylinde	r Strength	ı (psi)
Strength	#	(H=Hours	, D=Days	s)
Curing		16H	24H	28D	56D
	8F	7,910	8,460	9,940	10,450
8,000	8L	8,110	8,520		10,330
Curebox	G1A		7,890		9,420
	G1B		6,650		7,480
	8F				10,740
8,000	8L				10,520
ASTM	G1A				9,350
	G1B				8,580
10,000	10F	7,940	9,060	10,410	10,510
Curebox	10L				9,770
10,000	10F				11,720
ASTM	10L				10,150
	12F	10,880	10,870	10,990	11,460
12,000	12L	10,290	10,750		10,550
Curebox	G2A		9,270		10,240
	G2B		9,280		10,710
	12F	- /			11,520
12,000	12L				10,690
ASTM	G2A	l		i	10,660
	G2B				10,840

7.6.3 Comparison of 4 x 8 and 6 x 12 Cylinder Compression Strength Results

In cases where a comparison was possible, 4 x 8 compression strength results were compared to 6 x 12 compression strength results. Table 7.14 provides the percentage differences for the Phases 2, 3 and 4. The percent difference was calculated by subtracting the 6 x 12 value from the 4 x 8 value, dividing the result by the 6 x 12 value, and multiplying by 100. A negative value indicates the 4 x 8 compression strength was less than the 6 x 12 compression strength.

Table 7.14 Comparison of 4 x 8 to 6 x 12 Cylinder Compression Strengths

Objective	Batch	Percent Difference						
Strength	#	(H	=Hours,	D=Days	s)			
Curing		16H	24H	28D	56D			
	8F	0%	5%	-1%	1%			
8,000	8L	-10%	-9%	•	1%			
Curebox	G1A		-10%		-5%			
	G1B		-11%		4%			
	8F				3%			
8,000	8L				0%			
ASTM	G1A				0%			
	GlB				-6%			
10,000	10F	-3%	8%	0%	6%			
Curebox	10L				1%			
10,000	10F				-4%			
ASTM	10L				9%			
	12F	1%	6%	4%	1%			
12,000	12L	-4%	-3%		3%			
Curebox	G2A		6%]	2%			
	G2B		-10%		-4%			
	12F				1%			
12,000	12L				7%			
ASTM	G2A				1%			
	G2B				-6%			

Examination of Table 7.14 shows great variation from one strength group to another. For the 8,000 psi batches, early strength data (16H and 24H) indicate that 6×12 cylinders had greater strength than 4×8 cylinders on average. However, after 56 days, the resulting strengths were about the same on average. For the 10,000 psi batches, there is limited data on which to base a conclusion. For the 12,000 psi batches, results indicate 4×8 and 6×12 early strengths to be about the same on average. After 56 days, 4×8 cylinders had about 1.4% greater strength on average.

7.6.4 Statistical Study

A statistical study was conducted using 30 each 4 x 8 and 30 each 6 x 12 cylinders cast from batch series G2B. Ten each 4 x 8 cylinders and 10 each 6 x 12 cylinders were taken from the three different batches of batch series G2B. The cylinders were allowed to cure under ASTM conditions for 56 days and tested for compression strength.

According to Chapter 5, ACI 318-99,² the testing of 100 or more specimens is desirable. However, based on the inherent uncertainty that like conditions will exist at the time test specimens are created and the time concrete is produced, a sample size of 30 is deemed adequate. The average required compressive strength, f_{cr}', was determined as the minimum of Equations 7.1 and 7.2 (ACI² Equations 5-1 and 5-2, respectively) below where "s" is the standard deviation.

$$f_{cr}' = f_c' + 1.34s \tag{7.1}$$

$$f_{cr}^{'} = f_{c}^{'} + 2.33s - 500 \tag{7.2}$$

Table 7.15 provides the results of the study.

Table 7.15 Results of Statistical Study

·		4 x 8		6 x 12		
Batch #	Mean	n Required Standard Mea		Mean	Required	Standard
		Mean	Deviation		Mean	Deviation
G2B-1	10,717	10,730	528	10,930	10,300	224
G2B-2	10,464	10,740	532	10,349	10,428	319
G2B-3	10,703	10,214	160	10,106	10,557	416
G2B Overall	10,628	10,533	443	10,462	10,635	474

The results in Table 7.15 indicate that the three different batches were not statistically different and that based on 4 x 8 compression strength results the G2B batch series satisfied the requirements for being considered a 10,000 psi design strength mix. Based on 6 x 12 results, the batch series did not satisfy the requirements for being considered a 10,000 psi design strength mix, rather the design strength would be 9,988 psi.

In this research, 4 x 8 cylinders have been used to determine compression strength. Based on this statistical study, an average break strength for the G2 series batches over 10,533 psi indicates the batch series has a 10,000 psi design strength.

7.7 Modulus of Elasticity Results

Modulus of elasticity specimens were cast as specified in Tables 6.1, 7.2 and 7.3. Table 7.16 shows the combined results of all modulus of elasticity testing. Each value represents the average of 3 tests except the ASTM values for batches G1A, G1B, G2A, and G2B that are based on the average of tests on one cylinder from each of the four or five batches in the batch series.

Table 7.16 Modulus of Elasticity Results

Objective Strength Curing	Batch #	# (10 ⁶ psi) (H=Hours, D=Da			
Curing		16H	24H	28D	56D
	8F	3.49	3.67	3.85	3.86
8,000	8L	3.53	3.67		4.02
Curebox	G1A		3.57		3.86
	G1B		3.00		3.28
	8F				4.13
8,000	. 8L				4.39
ASTM	G1A				3.83
	G1B				3.56
10,000	10F	3.48	3.75	4.22	4.08
Curebox	10L				4.08
10,000	10F		7.00		4.26
ASTM	10L				4.33
	12F	3.92	4.12	4.30	4.26
12,000	12L	4.08	4.25		4.24
Curebox	G2A		3.55		3.93
	G2B		3.91		4.10
	12F				4.40
12,000	12L				4.33
ASTM	G2A			,	4.06
	G2B		T-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1		4.05

Examination of Table 7.16 shows that the modulus of elasticity increased with age. In two cases (10F and 12F curebox) the modulus dropped somewhat between 28 and 56 days. In general, it would not appear that significant gain in modulus of elasticity occurs after 28 days.

ASTM specimens produced higher modulus of elasticity results. On average,
ASTM results were 5.6 percent higher for the 8,000 psi design strength batches and 1.9
percent higher for the 12,000 psi design strength batches. Percent difference was

calculated by subtracting the ASTM modulus value from the curebox value, dividing the result by the ASTM modulus value and multiplying the result by 100.

The 56-day results from girder construction tests (G1A, G1B, G2A, G2B) were on average 8.9 percent less than the corresponding field production and laboratory evaluation results. This same trend was evident in Table 7.12 with compression strength results. The suspected cause of the lower results for both strength and modulus was the water leak in the concrete mixer. Despite every effort to control moisture, the water leak allowed more water into the mixes than designed.

The results indicate good consistency between the field production (Phase 2) and laboratory evaluation (Phase 3) modulus of elasticity values.

The results from batch G1B indicate a very low modulus value. The cause of the low results could be poorly compacted cylinders or a higher W/CM ratio than anticipated. Cross-referencing the modulus of elasticity results with strength results in Table 7.12 indicates that a higher W/CM ratio was probably the cause.

Figures 7.4 and 7.5 plot the results of modulus of elasticity vs. equilibrium unit weight and modulus of elasticity vs. compression strength, respectively, from this research and from the data presented in Chapter 2 (Table 2.1). Linear trendlines representing the experimental data and the proposed equation (Equation 3.1) are plotted on each graph. The results from this research are based on 56-day tests; the exact age of data presented in Table 2.1 is unknown. Appendix C lists all modulus of elasticity values. Overall, Equation 3.1 conservatively predicted modulus of elasticity by 4.4 percent with a standard deviation of 6.2 percent.




Figure 7.4 Modulus of Elasticity vs. Equilibrium Unit Weight




Figure 7.5 Modulus of Elasticity vs. Compression Strength

$$E_c = (33,000\sqrt{f_c'} + 4,000,000)(w_c/242)^{0.9}$$
(3.1)

For comparison, the same modulus of elasticity values used previously to evaluate Equation 3.1 were used to evaluate the current equations (Equations 7.3 and 2.1) for modulus of elasticity suggested in ACI 363⁸⁷ and by ACI 318², respectively.

$$E_c = (40,000\sqrt{f_c'} + 1,000,000)(w_c/145)^{1.5}$$
(7.3)

$$E_c = 33w_c^{1.5}\sqrt{f_c'} {2.1}$$

On average, Equation 7.3 conservatively predicted the modulus of slate HSLC by about 9.5 percent with a standard deviation of 5.5 percent. On average, Equation 2.1 predicted the modulus of slate HSLC by about 5.3 percent greater than that found experimentally with a standard deviation of 4.6 percent.

In an attempt to better align the predicted modulus of elasticity values with the experimental values, and to determine a simpler equation than Equation 3.1, a similar investigation was done as detailed in Section 3.3 and shown in Figures 3.4 and 3.5.

The experimental modulus of elasticity values were normalized separately by dividing by $(f_c')^{0.5}$, $(w_c)^{0.5}$, and $(w_c)^{1.5}$. The resulting plot normalized by $(f_c')^{0.5}$ is shown in Figure 7.6.




Figure 7.6 Experimental Modulus of Elasticity Values Normalized by (f_c')^{0.5}

An evaluation of the best-fit relation for "All E_c Values" (all experimental E_c values from this research and other research) showed that a linear trend line was as good or better than other possible curves. The R^2 value for the linear relation was 0.0287 for "All E_c Values." The indication in Figure 7.6 was that the roll of unit weight in determining modulus of elasticity was highly variable resulting in wide scatter and a low R^2 value. In other words, modulus of elasticity for slate HSLC showed little relation to W_c .

The linear trend resulting from Equation 7.3 used to predict modulus of elasticity, normalized by $(f_c')^{0.5}$, is also plotted in Figure 7.6. Equation 7.3 contains the term $w_c^{1.5}$, which emphasizes the effect of unit weight. The resulting linear trend does not compare favorably with the trend indicated by experimental values (all E_c values).

Similar evaluations with other variable forms indicated that $(f_c')^{0.5}$ was the variable that appeared most appropriate in predicting modulus of elasticity.

After examining several equation forms, Equation 7.4 was determined to be the equation that best predicted the modulus of elasticity of slate HSLC.

$$E_c = 44,000\sqrt{f_c' \frac{w_c}{145}} \tag{7.4}$$

Overall, Equation 7.4 provided a better prediction of modulus of elasticity for slate HSLC than the previously suggested Equation 3.1. Equation 7.4 conservatively predicted modulus of elasticity values by 0.2 percent on average with a standard deviation of 5.1 percent. The linear trend resulting from Equation 7.4 used to predict E_c values is also plotted in Figure 7.6. Since Equation 7.4 contains the term $w_c^{0.5}$, which de-emphasizes unit weight, the resulting linear trend compares more favorably with the trend indicated by the experimental values (all E_c values).

Low, mean, and high unit weight values of 111.5 pcf, 118.2 pcf, and 134 pcf, respectively, were determined from the 56-day experimental modulus of elasticity values from this research project and modulus of elasticity values from other research as listed in

Table 2.1. Figure 7.7 shows a plot of the above-mentioned values vs. compression strength and also shows lines plotting the predicted modulus of elasticity using Equation 7.4 based on the low, mean and high unit weight values. Figure 7.7 shows that at a given compressive strength, the variation in modulus of elasticity can be substantial. At a compressive strength of approximately 10,600 psi, the modulus of elasticity varied from approximately 3.65 million psi to 4.45 million psi.

Figures 7.8 and 7.9 show Equation 2.1 and Equation 7.3, respectively, evaluated using the low, mean, and high unit weight values plotted over the same modulus of elasticity values shown in Figure 7.7. Equation 2.1 unconservatively predicted modulus of elasticity for slate HSLC; Equation 7.3 conservatively predicted modulus of elasticity for slate HSLC.




Figure 7.7 Low, Mean, and High Unit Weight Values Plotted Using Equation 7.4




Figure 7.8 Low, Mean, and High Unit Weight Values Plotted Using Equation 2.1




Figure 7.9 Low, Mean, and High Unit Weight Values Plotted Using Equation 7.3

7.8 Modulus of Rupture Results

Modulus of rupture specimens were cast as specified in Tables 6.1, 7.2 and 7.3. Table 7.17 shows the combined results of all modulus of rupture testing. Each value represents the average of 3 tests except the ASTM values for batches G1A, G1B, G2A, and G2B that are based on the average of tests on one specimen from each batch in the batch series. The 56-day normalized modulus of rupture value was calculated by dividing the 56-day modulus of rupture by λ and $(f_c)^{1/2}$.

Table 7.17 Modulus of Rupture (f_r) Results

Objective Strength Curing	Batch Series #	Mean Modulus of Rupture (H=Hours, D=Days) (psi)		$\frac{f_r}{\lambda \sqrt{f_c'}}$	Concrete Compressive Strength (psi)	Mean Normalized Values	
		24H	56D	56D	56D	56D	
	8F	788	1,089	12.43	10,160	12.20	
8,000 Curebox	8L	649	1,077	12.40	10,430		
	G1A		1,042	12.86	9,080		
	G1B		830	11.09	7,750		
	8F						
8,000 ASTM	8L	761	1,030	11.81	10,520	10.84	
	G1A		992	11.21	9,350		
	G1B		743	9.50	8,460		
10,000	10F	641	998	11.10	11,170	12.42	
Curebox	10L	670	1,164	13.74	9,920	12.42	
10,000	10F						
ASTM	10L	678	1,006	11.26	11,040	11.26	
	12F	761	1,014	11.10	11,550	12.10	
12,000 Curebox	12L	645	926	10.45	10,860		
	G2A		1,283	14.79	10,420		
	G2B		1,038	12.06	10,250		
71. 11	12F						
12,000	12L	678	918	10.07	11,480		
ASTM	G2A		1,156	13.07	10,820	10.79	
	G2B		805	9.23	10,510		

The modulus of rupture results shown in Table 7.17 are difficult to interpret.

Based on 56-day strengths, the specimens cured in insulated cureboxes produced higher rupture strengths than ASTM cured specimens. This trend is opposite of that seen for all other specimens where ASTM cured specimens resulted in higher strengths.

In examining specimens cast during field production, the specimens coming from batches with the highest compression strength produced the lowest modulus of rupture values on average for both 24-hour and 56-day data. In examining specimens cast during girder construction, the specimens coming from batches with the highest compression strength produced the highest modulus of rupture values on average.

ACI $318-99^2$ specifies that rupture modulus, f_r , can be predicted using ACI Equation (9-9) shown in Equation 7.5 below.

$$f_r = 7.5\lambda \sqrt{f_c'} \tag{7.5}$$

The normalized values shown in Table 7.17 indicate good consistency between curebox and ASTM values. The average normalized curebox values are consistently higher than the average ASTM values. It would appear these values indicate a consistency of specimen casting and curing throughout all strengths and types of curing.

Other researchers^{11,12,14} have commented on difficulties encountered in using modulus of rupture test results for predicting the cracking strength of concrete beams.

They indicated the test is significantly impacted by the level of moisture during curing and indicated the splitting tension test per ASTM C 496⁸⁸ provided a better indication of

beam cracking strength. Nevertheless, the normalized values indicate that the "7.5" value used in Equation 7.5 is conservative.

7.9 Conclusions

Batching concrete in a mixer having a water leak will most likely produce more widely scattered test results.

For 4 x 8 cylinders cast during girder construction, substantial strength gain occurred between 56 days and the time of testing. For 4 x 8 cylinders cast as part of field production testing (8F, 10F, and 12F) strength gain continued through 365 days. It is likely that internal curing contributed to these gains.

As a general rule, for strength testing after 56 days, 4×8 cylinders provided on average about 1 percent higher strength values than 6×12 cylinders.

ASTM cylinders on average had about 4 percent higher strength than curebox cylinders at 56 days of age or later.

Modulus of elasticity tests on ASTM cylinders produced higher values than corresponding tests on curebox cylinders.

Equation 3.1 conservatively predicted modulus of elasticity results for slate HSLC. Equation 7.4 provided a better overall prediction that was still conservative. Equation 2.1 provided an unconservative prediction of modulus of elasticity. The modulus of elasticity for slate HSLC showed little relation to w_c .

The modulus of rupture test results indicated great variability and that the current ACI equation (Equation 7.5) conservatively predicts f_r .

CHAPTER VIII

DESIGN AND CONSTRUCTION OF HSLC PRETENSIONED BRIDGE GIRDERS

8.1 Introduction

The following objectives were established to serve as guidelines to prioritize and focus the experimental design and procedure.

- 1. To determine the transfer length, l_t, for 0.6-inch diameter prestressing strand used with slate HSLC.
- 2. To determine the development length, l_d, for 0.6-inch diameter prestressing strand used with slate HSLC.
- 3. To verify current code equations for l_t and l_d as appropriate for use with slate HSLC and suggest better equations if necessary.
- To determine the effect of shear reinforcement spacing on strand slip,
 development length, and shear capacity of pretensioned slate HSLC girders.
- 5. To determine the shear strength, V_c, of prestressed slate HSLC.
- 6. To verify current code equations for shear strength of slate HSLC.
- To verify the current code-specified reduction factor, λ, for SLWC as related to concrete tensile strength, and, suggest a more appropriate factor if necessary.

In order to achieve the seven experimental objectives, the following variables were altered in order to observe the results.

Concrete Compressive Strength, f_c'. Concrete design strengths of 8,500 and 10,000 psi were used for girder construction.

Shear Span to Depth Ratio, a/d. The "a" distance was varied from approximately 63 to 100 percent of the current code-specified l_d value.

Yield Strength of Shear Reinforcement Steel, f_y . Only Grade 60 # 4 bar stirrups were used. Values of f_y of 60 ksi (414 MPa) and the actual f_y value were used to determine whether an upper limit was appropriate for use with HSLC.

Spacing of Shear Reinforcement Steel, "s." The "s" distance was varied to determine the impact of A_v/s on l_d , strand slip, and shear strength.

Span Length of Tested Section, L_1 . In order to achieve three tests per girder, the span length was varied to focus on specific sections of the girder for each test.

8.2 Design of Experiment

8.2.1 Type of Girders and Prestressing Strands

AASHTO Type II cross-sections were chosen for testing for several reasons.

First, other recent experimental research on transfer and development length was done at Georgia Tech⁸⁴ and at the University of Texas at Austin⁴⁴ using AASHTO Type II girders. The ability to compare results was desirable. Second, Type II girders were more easily fabricated, transported and handled in the lab and were more economical to produce than larger sections. Third, the section was sufficiently deep to yield the

prestressing strands, which was required to investigate development length. By properly configuring the girder cross-section, it was possible to achieve applicable testing results and data.

The prestressing reinforcement chosen was 0.6-inch diameter, 270-ksi, 7-wire, low relaxation (LOLAX) strand provided by Insteel.

In order to produce the worst-case bond situation, the girders were configured with 8 each 0.6-inch diameter strands in the bottom row. In an AASHTO Type II girder, 8 strands constituted a full layer in the bottom flange. In the event of a severe bond failure, a horizontal crack would be induced across the full layer of prestressed reinforcement. The bottom strands were positioned at a distance 3 inches from the bottom of the girder as per GDOT standards and designed for prestressing to 0.75*f_{pu} or 203 ksi creating the worst-case bond situation.

In addition to the 8 bottom strands, 2 each 0.6-inch strands were placed 2.5 inches from the top of the girder. The purpose of these strands was to control tension stress at the top of the girder at time of strand release, and as a means to space and secure shear reinforcement. The top strands were also stressed to a level of 0.75*f_{pu} or 203 ksi.

8.2.2 Configuration of Girders for Testing

In previous work, 44,84 pretensioned girders were configured such that two tests per girder were possible; one test at each girder-end. In some cases, the center portion of the girder was left predominantly undamaged in the testing process. It was thought that a third test might be possible at the center of the girder with careful planning and proper design. There were two important reasons for wanting to test the center of the girder.

First, since girder cost was a major portion of the research budget, it was thought that by lengthening the girders it would be possible to achieve a third test at relatively little additional cost. Second, and more importantly, by testing the center portion of the girder, it would be possible to insure a fully developed strand and to more clearly focus on the shear characteristics of HSLC. When testing at the girder's ends, the data related to shear could possibly be skewed by less than fully developed pretensioning strands. Each of the six girders in this research project was configured to allow three tests per girder. This reduced the cost per test and provided substantially more data related to the shear strength of HSLC.

8.2.3 Prestressed Girder Design Spreadsheet

In order to facilitate the design of each girder, an EXCEL spreadsheet was developed to perform repetitive calculations related to the design of prestressed slate HSLC girders. The spreadsheet was very comprehensive and allowed the user to input numerous variables related to pretensioned girder design. Calculations within the spreadsheet were based on the 1996 AASHTO⁴⁰ Standard Specification. A complete description of the spreadsheet along with an example of the design of girder test G1C-West is presented in Appendix D.

8.2.4 Composite Girder Cross Section

It was desirable to construct the deck with a width as close to the width of the top flange of the girder as possible for ease of forming and testing. In addition, based on

previous research,^{55,84} it was desirable to achieve a greater depth of composite girder to increase the strain at the level of the bottom strands.


The goal of the testing was to simulate the conditions seen in composite girders found in actual bridges. As such, it was desirable to replicate the moment arm "jd" in testing, as it would be encountered in actual bridge structures. An analysis was conducted assuming AASHTO Type II girders and deck thicknesses as specified by a standard GDOT deck design guide. For girder spacings from 42" to 120", the minimum deck thickness varied from about 6.5 inches to 8.6 inches and jd varied from 31.65 to 34.74 inches with a jd of 33.75 inches for a 7-foot girder spacing

A deck thickness of 11.5 inches and width of 19 inches was selected. This combination produced a predicted internal moment arm of 33.61 inches, which closely matched the desired 7-foot girder spacing. In addition, a deck width of 19 inches meant simplified formwork for deck placement. Thus, by increasing the deck thickness to 11.5 inches, it was possible to increase the depth of the composite girder to increase strain demand on the bottom strands, simplify the formwork for casting of the deck, and closely replicate the moment arm "jd" encountered in standard bridge design.


8.2.5 Composite Girder Design

Having determined the configuration of the composite girder cross-section, it was possible to determine the layout of the girders for testing. In designing three tests per girder, it was important to insure that one test did not overly damage other future test areas on the girder.


8.2.5.1 Concept of Testing Sequence



Test # 1 on Composite Girder



Test # 2 on Composite Girder



Test # 3 on Composite Girder

Figure 8.1 Concept of Girder Testing Sequence

The first test entailed supporting the girder over its entire length and testing one end. The second test involved moving the left support to a point inside any significant damage resulting from the first test, and testing the opposite end of the girder. The third test involved moving the right support to a point inside any significant damage resulting from the second test and testing the center portion of the girder. By using this sequence, it was possible to achieve three tests from one girder.

8.2.5.2 Experimental Objectives vs. Girder Design

The following guidelines were established for girder design to accomplish the objectives set in Section 8.2.

- 1. Install DEMEC gage points on the girder at the ends on both sides of the top flange (from girder-end to a distance of 30 inches) and bottom flange (from girder-end to a distance of 48 inches) to facilitate measurement of concrete surface strains and allow calculation of the transfer length, l_t. This action allowed achievement of research objective 1.
- 2. Install DEMEC gage points on the girder on both sides of the top and bottom flange at midspan over a distance of 24". This action allowed determination of the effective prestressing force at midspan which was essential information for the achievement of all objectives.
- 3. Apply a point load to the composite girder at approximately 70 percent, 85 percent, 95 percent and 100 percent of l_d where l_d was determined by the 1996 AASHTO⁴⁰ Standard Specification. The point at which the failure transitioned from a "shear-type" failure to a "flexural-type" failure was the point at which the

strand was considered fully developed. Shear reinforcement in these tests was in accordance with the 1996 AASHTO⁴⁰ Standard Specification. This action allowed achievement of research objectives 2 and 3 and partial achievement of objective 4.

- 4. Using double the amount of shear reinforcement required according to the 1996 AASHTO⁴⁰ Standard Specification together with applying a point load at approximately 70 percent and 85 percent of l_d allowed achievement of research objective 4, and partial achievement of objectives 5, 6 and 7.
- 5. Using varying amounts of shear reinforcement and loading the girder with varying a/d ratios allowed achievement of research objectives 5, 6 and 7.

8.2.5.3 Composite Girder Design Procedure

Three each Series G1 girders and three each Series G2 girders were designed with concrete design strengths, f_c', of 8,500 psi and 10,000 psi, respectively. Based on previous experiences, it was assumed the girder lengths would be in the range of 35-45 feet. Final design lengths were revised to accommodate the tests as needed. Three tests were planned for each of the six girders indicating 18 total tests. Since two concrete strengths were being investigated, there were 9 different test configurations that were performed on each series of girders. The prestressed girder design spreadsheet was used to iteratively design the tests to fit on the girders. The resulting tests were detailed in Table 8.1. The a/d ratio listed under "Point Load Placement Criteria" is the shear span to depth ratio where "d" is the total height of the composite girder.

Table 8.1 – Girder Test Configurations

Test	Stirrup	Point Load	Shear	Distance	Distance	Distance
Configuration	Density	Placement	Span	L_1 "	"L ₂ "	"L"
		Criteria	"a"			
	. 4		(inches)	(inches)	(inches)	(inches)
1	Single	l _d	90	456	0	456
2	Double	0.70*l _d	61	316	0	456
3	Double	0.85*l _d	75	456	0	456
4	Single	0.95*l _d	85	504	0	504
5	Single	0.70*l _d	61	321	0	456
6	Single	0.85*l _d	75	369	0	504
7	Minimum	a/d=2.28	82	185	140	456
8	Minimum	a/d=2.67	96	210	135	456
9	Minimum	a/d=3.33	120	244	135	504

d = 47.5 inches

The dimension "a" was the shear span. The dimension L_1 was the distance from the left support to the right support. The dimension L_2 was the distance from the left COB to the left support. The COB was the point a distance of 6 inches in from each girder-end that was assumed to be the girder's support point for curing. L_2 was used to signify a cantilever on the left girder-end. The dimension L_2 was the distance from COB to COB. The dimensions "a," L_1 , L_2 and L_3 are shown in Figure 8.1.

Diagrams of the test configurations are depicted in Figures 8.2 through 8.10.

Diagrams of the resulting three girders, configuration "A", "B" and "C", in each series,

G1 and G2, are depicted in Figures 8.11 through 8.13. The testing sequence was alike for each girder with the left end tested first, the right end next, and the center section last.




Figure 8.2 Test Configuration 1




Figure 8.3 Test Configuration 2





Figure 8.4 Test Configuration 3






Figure 8.8 Test Configuration 7




Figure 8.9 Test Configuration 8




Figure 8.10 Test Configuration 9




Figure 8.11 Girder Layout A




Figure 8.12 Girder Layout B




Figure 8.13 Girder Layout C

8.2.5.4 Design Considerations

In designing the test girders, it was necessary to assume a damaged area resulting from each test. In the case of tests 1 through 6, it was assumed that a distance equal to at least "d" away from the point of load application towards the center of the girder would be damaged in addition to the specific area of interest. In the case of girders having double the AASHTO specified amount of shear reinforcing steel, additional area was added for damage as a precaution.

Another consideration in configuring tests 2, 5 and 6 was the fact that a portion of the center of each girder was reinforced with only the minimum-specified 24" steel spacing as seen in Figures 8.8 through 8.10. This 24" spacing area would be used during tests 7 through 9 to specifically examine the shear capacity of the girders. In order to ensure that this area would not undergo significant damage other than minor flexural cracking, girder-bottom stresses were examined for tests 2, 5 and 6 in the area of 24" stirrup spacing. Tests 2, 5 and 6 were critical since the distance between supports would be less allowing a greater point load and thus a greater shear to develop. As long as the resulting bottom stresses were less than $12(f_c')^{1/2}$, it was assumed that resulting damage would not be a significant factor for center-girder tests. In all cases, the bottom stresses were below the critical level.

8.2.5.5 Final Girder Designs

In order to arrive at the final girder designs, tests 1-9 were configured into three girders such that consistent lengths could be achieved to the greatest extent possible. For each series, two each 39-foot girders and one 43-foot girder were configured. Based on

the closeness of the Series 1 and Series 2 concrete design strengths, the shear design varied only slightly. Based on this closeness of design, it was decided to construct both series of girders with the same shear reinforcement spacing.

As part of the final design, additional # 4 stirrups were positioned in the initial d/4 of the girder at both ends to control bursting forces as per AASHTO⁴⁰ Section 9.22.1. Five # 3 "doghouse bars" were spaced at 12 inches on center in the bottom flange at both ends of each girder to enclose the prestressing steel as per AASHTO⁴⁰ Section 9.22.2.

Figures 8.14 through 8.16 provide sketches of girders "A", "B", and "C." The final designs were the same for both series of girders. These final designs were provided to the fabricator for production of the girders.




Figure 8.14 Girder Layout A




Figure 8.15 Girder Layout B




Figure 8.16 Girder Layout C

8.3 Girder Instrumentation

During construction, instrumentation points were installed in each girder to allow measurement of concrete surface strains and deflections. The following sections describe the construction of devices to allow installation of the measurement points.

Concrete surface strain data were obtained using DEMEC gage points. The gage points were cast into each girder by attaching the points to steel strips, which were bolted to the steel girder forms. Figure 8.17 shows a diagram of the DEMEC inserts and the method used for embedding them in the girders. The embedment strips were constructed from steel bar 1½ inches wide by 1/4 inch thick. The DEMEC embedments were installed at a distance of 2 inches on center. The mounting screws were placed at a distance of approximately 10 to 12 inches apart to adequately affix the strips to the girder formwork. Distances greater than 12 inches resulted in the strips bowing away from the formwork. The wing nuts pictured in CUT A were the DEMEC embedments.

Mounting the strips to the formwork was accomplished as pictured in CUT B of Figure 8.17. The strips were placed as shown in Figure 8.18.





Figure 8.17 Diagram of DEMEC Embedment Strip Construction and Installation



- 1. Place embedment strips as close to end of girder as possible.
- 2. Place embedment strips such that embedments are at the same level as the prestressing strands.

Figure 8.18 DEMEC Embedment Strip Placement on Girder




Figure 8.19 Attachment Points for Taut Wire

Deflection at midspan was measured using a piano wire stretched between a mounting post at one end and a pulley at the other as shown in Figure 8.19 A 10-pound weight was attached to the wire to keep it taut. At midspan, a metal ruler and mirror were affixed to the girder with epoxy. (Figure 8.20) The ruler enabled deflection measurement and the mirror prevented error due to parallax.



Figure 8.20 Use of Taut Wire for Deflection Measurement at Midspan

Vibrating wire strain gages (VWSG) with a 6-inch gage length were installed at midspan at the level of the bottom strands. (Figure 8.21)




Figure 8.21 VWSG and Thermocouple Prior to Concrete Placement

Thermocouples were installed in each girder to measure heat of hydration during the curing process. The thermocouples were 6 inches long, ¼ inch in diameter, type K with 1-meter lead wires. The thermocouples were placed in the vicinity of the VWSGs as shown in Figure 8.21.

8.4 Girder Construction

The six girders were constructed at Tindall Corporation precast plant in

Jonesboro, Georgia using plant personnel and standard precast plant procedures. The
author together with Georgia Tech students and faculty installed and measured all
instrumentation and fabricated all material test specimens. The girders were constructed
in three identical sequences. During each sequence, two girders were constructed.

During the first sequence, girders G1A and G1B were constructed. During the second
sequence, girders G2A and G2B were constructed. During the third and final sequence,
girders G1C and G2C were constructed.

8.4.1 DEMEC Gage Embedment and Taut Wire Insert Installation

Installation of the DEMEC gages was accomplished a few days in advance of the actual start of construction. Careful coordination with the concrete plant manager was essential to insure formwork was positioned to allow drilling holes and installation of the DEMEC gage embedment strips. Cordless drills with backup batteries and chargers, a good supply of back-up drill bits, cutting oil, grease pencils and measuring tapes were the keys to success.

Before the strips were attached, a layer of grease was spread across the back of the strip to fill the screw heads of the screws holding the wing nuts (embedments) in place on the strip. The backside of the strip was placed against the formwork. Once in place, any gap between the edge of the strip and the formwork was filled with grease to prevent concrete from getting behind the strip. In addition, the exposed portion of the strip was coated with grease to prevent the strip from sticking to the girder. Grease was kept from the wing nuts because their firm bond to the concrete was essential.

Connection points were also attached to the inside of the formwork to allow installation of connections for the taut wire.

Prior to the formwork being moved into place for girder placement, it was sprayed with form release oil. It was necessary to wipe any excess oil from the wing nuts before the forms were lowered into position.

8.4.2 Strand Tensioning

After the prestressing strands were threaded through the bulkheads, load cells were installed on the passive end to monitor the prestressing force. The load cells were calibrated in advance of tensioning. Results of the calibration can be found in Appendix E. Figure 8.22 shows the load cells in place.




Figure 8.22 Strand Load Cells Installed at Passive End of Girder Line

The load cells were wired to a BLH 1225 Portable 10 Channel Switch and Balance Unit, which was then connected to a BLH 1200B Portable Digital Strain Indicator. The same units used during construction were also used during load cell calibration. Figure 8.22 shows the BLH 1225 and BLH 1200B.




Figure 8.23 Strand Load Cell Monitoring Equipment

With the load cells connected and zeroed, plant personnel tensioned the strands using a Hercules hydraulic jack. Tensioning the 0.6-inch strands to 75 percent of f_{pu} or 203 ksi required a tension force of approximately 44.5 kips. All tensioning and strand elongation data can be found in Appendix H. For purposes of tensioning and tracking strand force, strands were numbered as shown in Figure 8.24. Figure 8.24 also provides the order in which the strands were released.




Figure 8.24 Strand Designation, Tensioning Order, and Release Order

The plant had trouble with their tensioning machine while tensioning the third sequence of girders and had to replace the hydraulic ram. The Hercules tensioning machine was designed for use on 0.5-inch strand and struggled to tension the 0.6-inch strand. In comparing the reported strand tension values with the values recorded using the strand load cells, the strand load cells reported tension values up to 20 percent less than that reported by the hydraulic pump. Appendix F includes determination of prestress force from the strand load cell reported strains and a comparison with plant reported tension values. Load cell data were used for all subsequent analyses. Figures 8.25 and 8.26 show Tindall personnel tensioning the strands.



Figure 8.25 Tindall Personnel Operating Tensioning Machine



Figure 8.26 Jacking of Prestressing Strand

8.4.3 Installation of Shear Reinforcing Steel

Following the tensioning of prestressing strands, the shear reinforcing steel was installed per the sketches shown in Figures 8.14, 8.15 and 8.16. Georgia Tech personnel carefully checked stirrup locations to insure they were in accordance with the plans.






Figure 8.27 Installation of Shear Reinforcing Steel Near Girder End

8.4.4 Installation of VWSG and Thermocouples

The last step taken prior to installing the formwork was to attach the VWSG and thermocouple at midspan. As seen in Figure 8.21, the VWSG was firmly attached to the prestressing strand at the level of the bottom strands. The thermocouple was securely attached in the same vicinity as the VWSG.

8.4.5 Place Formwork

Prior to lifting the formwork into place, the forms were coated with a form release agent (form oil). It was necessary to recheck the DEMEC embedments and wipe any excess oil from the wing nuts prior to form installation. In a few cases, wing nuts had been knocked off the embedment strips and required replacement. Once properly aligned, the forms were locked into place by large threaded rods beneath the formwork and wishbone struts on top. Figures 8.28 and 8.29 show installation of the formwork.




Figure 8.28 Formwork with DEMEC Embedment Strips Being Lifted Into Place




Figure 8.29 Tindall Supervisor Directing Placement of Formwork.

8.4.6 Batch and Place Concrete

Prior to batching the HSLC, moisture tests were conducted on the lightweight aggregate and sand to determine the exact mix design. The moisture tests were started at least two hours prior to placement to allow time to correctly dry the aggregate and configure the mix design.

8.4.6.1 Mix Designs

Table 8.5 provides an overview of the mix design for each girder placement. The mix designs below were based on making 2 cubic yard batches. Each girder required approximately 3.5 cubic yards.

Table 8.2 Mix Designs for Girder Placements (2 cubic yard mix)

Girder #		G1A, G1B	G2A, G2B	G1C	G2C
Date of Placement		9 July 01	12 July 01	17 July	17 July 01
Lightweight Aggregate	(lbs)	1977	1958	1947	1995
Normal Weight Sand	(lbs)	2195	2173	2155	2165
Class F Fly Ash	(lbs)	284	300	284	300
Silica Fume	(lbs)	38	200	38	200
Type III Portland Cement	(lbs)	1570	1480	1570	1480
WRDA 35 (LRWR)	(fl oz)	114	119	114	119
Daravair 1000 (AEA)	(fl oz)	24	20	24	20
ADVA Flow (HRWR)	(fl oz)	95	258	95	258
Water	(gal)	39.5	36.7	44.8	33.1

8.4.6.2 Concrete Mixing

The concrete was mixed in a rotary auger-type mixer located in an elevated mix station approximately 200 feet from the prestressing bed. The mix station did not have a silo for fly ash or silica fume, thus those two components had to be added manually. The concrete components were added in a specific sequence for each batch of concrete. The lightweight and normal weight aggregates were added first with all the low range water reducer (LRWR), air entraining agent (AEA), high range water reducer (HRWR), and approximately half the mix water. Water was held out of the mix because Tindall's mixer had a water leak making exact determination of water added impossible. The initial components were allowed to mix for approximately 1 minute to insure thorough

dispersion of the chemical admixtures. Next, the Type III cement was added. Additional water was added as necessary to allow proper mixing of the cement. Next the Class F fly ash was added with additional water as required. Last, the silica fume was added. Any remaining water up to the specified mix design amount was added and the result observed. If the mix was still stiff, additional HRWR was added to bring the mix to a workable state.

When working with low water cement ratio mixes, water content is crucial.

Noted variations in aggregate moisture content made a relatively large difference in the amount of added mix water required. During the batching process, water beyond the specified mix amount was added based on aggregate observed to be drier than measured during testing. While this may seem imprecise, experience with a particular mix design allows the person supervising the batch process to make adjustments and still achieve excellent results. In each batch process, water was added beyond the specified mix design with resulting strengths being in line with that expected. Without exact moisture control, such changes "on the fly" were unavoidable.

Figure 8.30 shows the elevated mix platform at Tindall Concrete. Concrete transport vehicles (Tuckerbilt) transport the concrete from the base of the platform to the girder line.

8.4.6.3 Material Testing

Upon batching of concrete, it was loaded into the transport vehicle and brought to the quality control station. Tindall personnel performed a slump test according to ASTM C231,⁷⁴ a unit weight test according to ASTM C138,⁷⁵ and recorded the temperature

according to ASTM C1064.⁷⁶ Georgia Tech personnel performed an air content test using a roll-a-meter according to ASTM C173.⁷⁷ To the greatest extent possible, these tests were performed on each batch of concrete.




Figure 8.30 Elevated Mix Platform

A significant number of quality control specimens were cast during each girder placement; many of the specimens were cured in insulated boxes. Based on previous research at Georgia Tech, 84 cylinders cured in insulated boxes more closely matched

actual girder strengths for full-sized girders for the first 7 days. Temperature plots for cylinders cured in insulated boxes compared well to actual girder curing curves during this project.

During the third girder placement, cylinders were cast for a statistical study to determine the actual variation in placing HSLC.

8.4.6.4 Concrete Placement in Girders

After delivering concrete to the quality control station, the remaining concrete was transported to the girder line where it was placed into the forms. The Tindall concrete workers placed the concrete in lifts vibrating each lift with a spud vibrator. One Georgia Tech researcher was present on the girder line at all times during concrete placement to insure the concrete workers did not damage any instrumentation or DEMEC inserts. After all lifts of concrete were in place, the top of the girder was screeded and raked to give it the required 1/4-inch variation for good bond between the deck and girder. The girders were then covered with heavy plastic to protect them from rain and hold in heat during the curing process.

8.4.6.5 Comments on Placement Conditions

The girders in this project were placed during July when the ambient temperature reached well above 90 degrees Fahrenheit at mid-day. During the third concrete placement, events occurred at the plant that forced the placement time to be at about 3:00 pm, the hottest part of the day. The following key conditions existed that created placement problems.

- 1. The formwork had been exposed to direct sunlight throughout the day and was extremely hot to the touch.
- 2. The concrete transport vehicle had been sitting in the sun as well, and the metal hopper was hot.
- 3. The aggregate had been sitting in the silo above the elevated mix platform all day.
 In addition to being warm, the moisture content was probably not as high as that recorded from earlier testing.

The first batch of concrete mixed was for girder G2C. The water to cementitious materials ratio was 0.23. The batch was mixed as previous ones had been mixed. The consistency in the mixer appeared to have a slump of approximately 5-6 inches. When the concrete was released from the mixer into the transport vehicle, a flash set initiated when the concrete touched the hot metal in the hopper. Although not initially noticed, the problem became apparent when concrete was released for quality control checks. The slump was about 3 inches, the air content was about 3 percent and the unit weight was low at 114 pcf. It was decided to use the concrete because it still appeared workable enough to use in the girder. When the delivery vehicle began placing concrete into the girder, it was discovered that better than half the concrete in the vehicle had set in the hopper and could not be discharged into the formwork. In retrospect, the decision to use this initial batch of concrete was an error. At that point, Tindall personnel and volunteers worked quickly to remove the setting concrete from the hopper of the delivery vehicle. After about 30 minutes of effort, all the concrete had been removed.

In the mean time, the small amount of concrete placed in the girder was setting. Before another batch of concrete was mixed, the delivery vehicle was sprayed with cold water to lower the temperature of the hopper and coated with a lubricant to prevent the concrete from becoming bonded to the metal surface. The resulting girder, G2C was acceptable. There was no honeycombing and the cold joint did not appear to be a significant problem. As it turned out during testing, the particular girder end, G2C-West, performed acceptably.

The lessons learned in this event were numerous and related mostly to temperature. The formwork and equipment should have been kept cool prior to the placement. The aggregate should be kept cool to the greatest extent possible.

8.4.7 Concrete Curing

The girders were allowed to cure overnight. Temperature was monitored on each girder using the embedded thermocouple and a printing thermometer. A typical temperature curing curve for girder G1A is shown in Figure 8.31 together with the temperature in the curing box for test cylinders.

Tindall quality control personnel performed compressive strength tests on ASTM cured cylinders approximately 16 hours after casting. For comparison, curebox cylinders were also tested. The curebox cylinders always broke at a much higher strength than the ASTM cylinders. Table 8.3 provides times from concrete placement to form removal and release of prestress. The drop in the ambient temperature at 20 hours resulted from moving the cureboxes from outside into the laboratory.




Figure 8.31 Typical Temperature Curing Curve for Girder G1A

Table 8.3 Concrete Placement Time; Hours Until Form Removal, Release of Prestress

Girder	Time/Date of	Hours Until	Hours Until
	Placement	Form Removal	Prestress Release
G1A	9 July 01, 1800	17.5	21.5
G1B	9 July 01, 1800	17.5	21.5
G1C	17 July 01, 1700	18	22
G2A	12 July 01, 1000	24	29
G2B	12 July 01, 1000	24	29
G2C	17 July 01, 1600	20.5	23

8.4.8 Formwork Removal, Embedment Preparation and Initial Readings

After the metal forms were removed, the DEMEC steel embedment strips were unscrewed and stripped out (Figure 8.32). Once the embedments (wing nuts) were exposed, "initial" DEMEC readings were taken as described in detail in Section 9.6.2.



Figure 8.32 Removal of Screws from DEMEC Embedment Strips

The taut wire was also installed at this time. The mounting hardware as pictured in Figure 8.19 was installed, the wire stretched and the weight hung. The metal ruler was attached using 90-second epoxy at midspan such that two inches was exposed above the wire and 4 inches was exposed below the wire. The mirror was attached also using 90-second epoxy to the side of the ruler following the same spacing guidelines. After two sets of "initial" readings were taken using the DEMEC gage reader and the "initial" deflection was taken, the girder was ready for release of prestress.

8.4.9 Release of Prestress and "Release" Readings

Three Tindall workers using oxy-acetylene welding torches simultaneously flame cut the strands following the pattern identified in Figure 8.24 and shown in Figure 8.33.

After all strands were cut, the "release" concrete surface strain, VWSG, and deflection readings and subsequent readings were recorded as outlined in Section 9.6.2.



Figure 8.33 Flame Cutting of Prestressing Strands with Oxy-Acetylene Welding Torch

8.4.10 Movement From Prestressing Bed to Temporary Storage Location

After prestress release, the girders were moved to a storage area and placed on wooden dunnage located at the centers of bearing (6 inches from each end). While in storage, Georgia Tech researchers took readings as outlined in Chapter 9 to examine

transfer length. Figure 8.34 shows the movement of a girder to the storage location using an overhead crane.




Figure 8.34 Movement of Girder to Storage Location Using Overhead Crane

8.4.11 Movement of Girders to Georgia Tech Structures Lab

After curing for approximately 3-4 weeks at the Tindall Plant, the girders were transported on flatbed trucks to the Georgia Tech Structures Lab. In the lab, the girders were stored as they had been at the concrete plant. One final set of surface strain, VWSG, and deflection readings were taken upon arrival and prior to beginning deck construction. Figure 8.35 shows girder delivery to the Georgia Tech Structures Lab.



Figure 8.35 Delivery of Girders to Georgia Tech Structures Lab

8.5 Composite Deck Construction

Two weeks after the girders were delivered to the Georgia Tech Structures Lab, composite decks were cast on each girder. The concept for deck placement was to cast the entire deck on all six girders in one placement.

8.5.1 Formwork Construction

Figure 8.36 shows a cross section of the formwork used to place the composite decks.




Figure 8.36 Formwork for Composite Deck

By placing the girders close together, it was possible to share formwork between two girders. Based on the selection of 19 inches for the deck width, a 2 x 4 (nominal 1.5 inches by 3.5 inches) was used to form the bottom underneath side of the deck. The side

of the deck was formed with ¾ inch plywood ripped into 13-inch widths and attached to the 2 x 4 boards with screws. The two "L" shaped pieces were then attached with screws to 2 x 4 uprights that ran to the floor for support. The upright lengths were adjusted as necessary to account for camber in the girders. The dead weight of the girders held the formwork in place nicely during deck placement.

Formwork for the outside of edge girders was held in place by ¼-inch threaded rods. Holes were drilled through the formwork through which the threaded rods were run. The rods were then bent around shear stirrups and secured with tie wire. Washers and nuts were installed on the threaded rod on the outside and tightened until the formwork was pulled snugly against the edge of the girder. The upright 2 x 4 boards of the outside edge formwork were held in place by a 2 x 4 that was bolted to the floor cover plates. The plates covered the tie-down locations and were conveniently placed at 4 feet on center. This detail can be seen in Figure 8.38.

8.5.2 Temperature and Shrinkage Steel

Temperature and shrinkage steel reinforcement consisting of two #4 bars was fastened to the shear stirrups at a distance of 3½ inches from the edge of the deck and approximately 2 inches down from the top surface. The bars came in 20-foot lengths and were overlapped by 18 inches as necessary. Figure 8.37 shows the temperature and shrinkage steel in place.




Figure 8.37 Formwork in Place with Temperature and Shrinkage Steel Installed




Figure 8.38 Formwork Ready for Concrete Placement

8.5.3 Concrete Placement

8.5.3.1 Type of Concrete

The type of concrete used for the composite deck was the standard Georgia

Department of Transportation 3,500 psi normal weight bridge deck mix. Thomas

Concrete, of Atlanta, Georgia delivered the concrete to the Structures Lab in readymix trucks.

8.5.3.2 Concrete Placement and Finishing

The readymix trucks were equipped with a concrete conveyor assembly as pictured in Figure 8.39.

Several Georgia Tech researchers assisted in the deck placement. One person operated the spud vibrator to insure good consolidation of the concrete into the forms and around the steel. Two other researchers used a large screed beam to smooth the top surface of the concrete. Two persons insured concrete from the chute was placed into the correct location.

In total, three readymix truckloads were required for completion of the deck. The first truckload was somewhat dry. Water was added on site to increase the slump to 6 inches. The second and third truckloads required no additional water; the measured slump was adequate upon arrival.

After the concrete began to set, the surface was finished with a trowel and then a broom surface was applied. The deck concrete was covered with plastic after initial set was reached. The deck was watered as necessary to keep it moist under the plastic.

After 7 days, the deck was uncovered and formwork removed. The formwork was completely disassembled, cleaned and stored for future use. Girder testing began approximately 52 days after the deck was cast.



Figure 8.39 Readymix Truck with Conveyor Attachment

8.5.3.3 Materials Testing

Both 4 x 8 and 6 x 12 cylinders were cast for compressive strength and modulus of elasticity tests, respectively. The cylinders were cured under ASTM conditions for the first 24 hours then moved to the fog room for curing through the time at which the girders

were tested. The average strength of the deck concrete was 5,385 psi and the modulus of elasticity, E, was 3.37 million psi.

8.6 Direct Pull-Out Test

During girder placement, 24-inch x 36-inch x 24-inch specimen blocks were cast from the G1 and G2 series mixes for the "Mostafa", prestressing strand the direct pull-out test as shown in Figure 8.40.⁹⁰



Figure 8.40 Mostafa Prestressing Strand Direct Pull-out Test

Each block had six, 48-inch segments of strand that were taken from the same reel used for girder construction. The segments were embedded 20 inches into the block with the top 2 inches being encased by PVC pipe as a bond breaker. The total embedded length

was 18 inches. The dimensions of the block were such that each strand had a free radius of at least 8 inches in all directions. Nominal reinforcing and lifting hooks made with #4 bars were placed in the block. Table 8.4 provides an overview of pull-out test results.

The listed value is the load at which the strand underwent initial significant slip. Figures 8.41 and 8.42 provide plots of force vs. strand pull-out.

Table 8.4 Direct Pull-Out Test Results

Strand Test #	G1 Series	G2 Series	
	(kips)	(kips)	
1	47.43	43.82	
2	48.22	49.52	
3	50.75	42.81	
4	51.47	54.36	
Average	49.47	47.63	




Figure 8.41 Direct Pull-Out Results for G1 Series HSLC




Figure 8.42 Direct Pull-Out results for G2 Series HSLC

Measurement of the load was accomplished using a strand load cell connected to the BLH 1200B. The same procedure was used as during girder construction. Load cell # 1 was used for this test. Force was calculated from the strain data using a direct relationship determined during the calibration process. Consult Appendix E for load cell calibration data.

The determination of pull-out capacity was based on the point at which the strand experienced increased slip with little or no increase in load or the point at which the strand underwent a sudden increase in slip and drop in load. This "popping" occurrence was common for all 8 tests performed. In Figures 8.41 and 8.42, the last data point shown was the point at which popping occurred.

Based on Logan's work, the minimum direct pull-out capacity for 0.6-inch diameter strand was 43.2 kips. ⁹⁰ The average pull-out strength for both series exceeded the minimum value. One G2 test was slightly below the 43.2 kip minimum.

8.7 Material Properties

In order to evaluate the flexural performance of the girders, it was necessary to determine various material properties. The following sections provide material properties of the girders at the time of testing. Appendix C provides information on the reinforcing steel used for the shear stirrups and "doghouse" bars. Variations in concrete strength for the composite deck were the result of three different concrete deliveries during deck placement.

8.7.1 Girder Concrete Properties

Specimens were cast at the time of girder placement to allow determination of compressive strength, modulus of elasticity, and modulus of rupture strength at specific times. Table 8.5 lists the results of specimen testing with the range of test values listed.

The initial compressive strength values, f_{ci} , and modulus of elasticity values, E_{ci} , were based solely on curebox cured specimens and were tested at 24 hours, the approximate time of strand release. The compressive strength values, f_c , are based on an average of curebox and ASTM cured specimens tested just prior to girder testing approximately 3-4 months after casting. The moduli of elasticity values, E_c , are based on an estimate using the HSLC modulus equation. When compared with 56-day test values, the estimated values were in agreement. The E_c values listed for the G2C girders are the

-day test values. Suspected inconsistencies in wet unit weight measurement at the time of placement produced predicted values from the HSLC modulus equation that were less than the known 56-day values. The modulus of rupture values, f_r , are based on an average of curebox and ASTM cured specimens tested at 56 days.

Table 8.5 Girder Concrete Properties

Test	f _{ci} '	f _c '	Eci	Ec	f_{r}	
#	24-hour	Time of Test	24-hour	Time	56-day	
"	Curebox	Curebox	Curebox	of Test	Curebox	
	Curebox	& ASTM ⁷⁹	Carobox	Estimated	& ASTM ⁷⁹	
	(psi)	(psi)	(psi)	(psi)	(psi)	
G1A-E	(552)	(P3.)	4-7	(552)	(201)	
G1A-W						
GlA-C		0.500	0.455.06	a so m. o c	1 010	
G1B-E	7,465	9,580	3.47E+06	3.72E+06	1,010	
G1B-W						
G1B-C						
Range	6,753-8,689	8,702-10,640	3.39E+06-3.52E+06	NA	861-1,101	
				·····		
G1C-E						
G1C-W	6,315	8,911	3.00E+06	3.69E+06	796	
G1C-C						
Range	5,444-7,666	8,001-9,450	2.98E+06-3.03E+06	NA	729-908	
G2A-E						
G2A-W						
G2A-C	9,640	10,975	3.55E+06	3.88E+06	1,204	
G2B-E	2,040	10,575	3.331.700	3.00L100	1,204	
G2B-W						
G2B-C						
Range	8,459-10,307	10,499-11,455	3.11E+06-3.79E+06	NA	1,024-1,352	
					·	
G2C-E						
G2C-W	8,261	10,523	3.91E+06	4.08E+06	905	
G2C-C						
Range	7,737-8,738	9,900-11,485	3.87E+06-3.96E+06	NA	744-1,086	

8.7.2 Deck Concrete Properties

Specimens were cast during deck placement to allow determination of compressive strength and modulus of elasticity. Table 8.6 lists the results of testing with the range of test values listed.

Table 8.6 Deck Concrete Properties

Test	f _c '	Ec		
#	Time of Test	Time of Test		
	ASTM ⁷⁹	ASTM ⁷⁹		
	(psi)	(psi)		
G1A-East				
G1A-West				
G1A-Center				
G1B-East				
G1B-West	5,384	3.35E+06		
G1B-Center				
G1C-East				
G1C-West				
G1C-Center				
Range	4,848-5,929	3.24E+06-3.45E+06		
G2A-East				
G2B-East	5278	3.45E+06		
G2C-West				
Range	5,047-5,560	3.28E+06-3.55E+06		
G2A-West				
G2A-Center				
G2B-West	5440	3.36E+06		
G2B-Center) 344 0	J.30E⊤00		
G2C-East				
G2C-Center				
Range	4,975-6,109	3.32E+06-3.42E+06		

Three batches of concrete were delivered to place the deck. The first batch encompassed all G1 series girders. The second batch encompassed all the G2 series

girder sections except G2A-East, G2B-East, and G2C-West, which were covered by the third and final batch delivered. The concrete compressive strength, f_c ', and modulus of elasticity, E_c , values were determined by averaging the test results of specimens from each batch of concrete delivered for the deck. Although the girder tests encompassing a particular batch of deck concrete took place over a range of a few weeks, the strengths and moduli values recorded were in a tight range.

8.7.3 Prestressing Strand Properties

Manufacturer test results were received at the time of girder construction. Table 8.7 lists pertinent properties of the prestressing strand.

Table 8.7 Prestressing Strand Properties

0.6-inch Diameter Grade 270 ksi Low-Relaxation Strand					
Property	Value	Units			
Strand Diameter, db	0.6	inches			
Cross Sectional Area, Aps	0.2183	inches ²			
Modulus of Elasticity, Eps	29,000	ksi			
Yield Strain, ε _γ	0.01	inch/inch			
Yield Stress, f _y	259.6	ksi			
Ultimate Strain, ε _{su}	0.065	inch/inch			
Ultimate Stress, f _{su}	283.2	ksi			

8.8 Effective Prestressing Stress and Losses

It was necessary to determine the strand effective prestressing stress, f_{se} , at the time transfer length was determined and at the time of testing. Two methods were used to determine f_{se} and the results compared. The first method made use of vibrating wire strain gages cast into the girders at midspan at the level of the bottom strands. The second method made use of concrete surface strain (CSS) data. One inherent difference

in these two methods was that the VWSG method read strain internal to the girder and the CSS method read surface strains. A second difference between the two methods was the gage length over which strain was determined. The VWSG had a 6-inch gage length; the CSS measurements were made over a 24-inch distance at midspan. The measurements made over a greater distance should have been more accurate.

Prior to release of prestress, the stress in the strands was known based on load cell readings. Refer to Appendix F for details on the determination of prestressing stress. At release, the known force was transferred to the girders. The elastic shortening of the girder reduced the effective stress in the prestressing strand. At the initial release of prestress, the VWSG and CSS values differed by almost 40 percent. At the time of testing, the measured strains differed by only about 7-9 percent indicating stabilization had occurred across the section.

When the initial prestressing stress was adjusted by the effect of the change in strain in the strand over time, the resulting effective stress values were within about 3 ksi. Force in the strand at a given strain was determined using Figure 8.43. Figure 8.43 was created using a manufacturer provided strand force vs. strand strain test plot.




Figure 8.43 Force-Strain Curve for Prestressing Strand

Based on previous research that used VWSGs successfully, it was decided to use the VWSG indicated strain values to determine the effective prestressing stress. Table 8.8 provides details on the effective prestressing stress and losses determined experimentally and estimated using the AASHTO⁴⁰ procedure.

Although not a specific focus of this research, it is interesting to note the differences between AASHTO⁴⁰ estimated losses and experimentally measured losses. Table 8.9 lists the percent differences between the two values by batch number.

Table 8.8 Effective Prestressing Stress and Losses

Test	Effective	Girder Age	Batch	AASHTO ⁴⁰	Experimentally
#	Prestressing	essing at		Predicted	Determined
ļ	Stress at	Time of Test		Losses	Losses
	Time of Test				
	\mathbf{f}_{se}			(ES,R,CR,SH)	(ES,R,CR,SH)
	(ksi)	(days)		(ksi)	(ksi)
G1A-East	153.7	111	1T1	34.6	25.4
G1A-West	152.3	106	1T1	34.6	26.8
G1A-Center	151.5	113	1T1	34.6	27.5
G1B-East	151.2	94	1T1	34.6	27.8
G1B-West	149.7	99	1T1	34.6	29.3
G1B-Center	149.4	101	1T1	34.6	29.7
G1C-East	149.0	110	1T2	35.7	30.2
G1C-West	147.6	107	1T2	35.7	31.5
G1C-Center	147.7	112	1T2	35.7	31.4
G2A-East	175.8	122	2T1	36.1	15.5
G2A-West	175.7	119	2T1	36.1	15.6
G2A-Center	175.0	124	2T1	36.1	16.3
G2B-East	176.2	131	2T1	36.1	15.1
G2B-West	175.6	126	2T1	36.1	15.8
G2B-Center	175.6	136	2T1	36.1	15.7
G2C-East	159.3	140	2T2	33.3	19.8
G2C-West	158.8	133	2T2	33.3	20.3
G2C-Center	157.7	142	2T2	33.3	21.5

Table 8.9 Comparison of AASHTO⁴⁰ Predicted Losses to Experimental Losses

Batch #	AASHTO	Experimental	Percent	Percent
	Predicted Losses	Losses (Average)	Difference	Difference
	(ksi)	(ksi)	By Batch	By Series
1T1	34.6	27.8	-19.8%	-17.6%
1T2	35.7	31.0	-13.1%	-17.070
2T1	36.4	15.7	-56.6%	-50.5%
2T2	33.3	20.5	-38.3%	-50.576

Batch 1T1 was the G1 series mix made during the "first" G1 series girder placement session. Batch 1T2 was the G1 series mix made during the "second" G1 series

girder placement. The numbering for batches 2T1 and 2T2 follows the same rule.

Although the mix designs were the same for both sessions, exact determination of water content was not possible due to a malfunctioning valve. The batches during both second sessions produced greater losses. The percent difference by series indicates the overall difference for all girders made from a particular mix design. The resulting losses for the G2 series girders differed significantly from the AASHTO⁴⁰ estimated values.

Further details on determination of the effective prestressing stress were included in Appendix F.

8.9 Girder Section Properties

The AASHTO Type II girders had section properties as listed in Table 8.10.

Table 8.10 AASHTO Type II Girder Section Properties (Non-Composite Girder)

Property	Non-Composite Value	Units
Moment of Inertia, Inc	50,979	in ⁴
Cross Sectional Area, Anc	369	in ²
Height, h _{nc}	36	in
Centroid to Girder Top, y _{top-nc}	20.17	in
Centroid to Girder Bottom, ybot-nc	15.83	in
Top of Girder to Top Strands, TCL	2.5	in
Bot of Girder to Bot Strands, BCL	3	in

The resulting girder dimensions deviated slightly from the designed dimensions.

Table 8.11 lists the resulting composite section dimensions and properties for each test.

Table 8.11 Composite Section Properties

Test	Mod.	Girder	Moment	Cross	Centroid	Centroid
#	Ratio	Height	Of	Section	to	to
			Inertia	Area	Top	Bottom
	η	h_c	I_c	A_c	y _{top-c}	y _{bot-c}
		(inches)	(inches)	(inches)	(inches)	(inches)
G1A-East	0.900	48.00	145736	581	10.62	25.38
G1A-West	0.900	47.88	142657	572	10.90	25.10
G1A-Center	0.900	48.00	143768	574	10.82	25.18
G1B-East	0.900	48.00	144954	578	10.70	25.30
G1B-West	0.900	47.50	140492	570	11.04	24.96
G1B-Center	0.900	47.50	139730	567	11.12	24.88
G1C-East	0.907	47.75	143550	577	10.79	25.21
G1C-West	0.907	47.88	144285	578	10.74	25.26
G1C-Center	0.907	48.19	147106	583	10.52	25.48
G2A-East	0.890	47.75	140863	568	11.06	24.94
G2A-West	0.867	47.88	141167	567	11.05	24.95
G2A-Center	0.867	47.88	140391	565	11.13	24.87
G2B-East	0.890	48.00	143464	573	10.85	25.15
G2B-West	0.867	47.75	138916	561	11.25	24.75
G2B-Center	0.867	48.19	143919	572	10.84	25.16
G2C-East	0.824	48.00	137292	553	11.46	25.54
G2C-West	0.846	47.63	135266	551	11.59	24.41
G2C-Center	0.824	48.13	138744	556	11.34	24.66

CHAPTER IX

TRANSFER LENGTH TEST RESULTS AND DISCUSSION

9.1 Introduction

This chapter discusses transfer length in pretensioned girders. Definitions are provided, the importance and use of transfer length is discussed, current code provisions are presented and explained, and the results of the experimental program are presented. Based on experimentally measured transfer length values from this experimental program and others, current code provisions and equations previously suggested for predicting transfer length are evaluated. New equations for predicting transfer length are suggested based on experimental data.

9.2 Definition

Transfer length is the distance required to transfer the effective prestressing force from the strand to the surrounding concrete. Transfer length is developed when the pretensioning strands are released by flame cutting or other method from the restraining abutments. In order for the force transfer to take place, there must be sufficient bond between the pretensioning strand and the concrete. The transfer of force from the strand to the concrete is represented in Figure 9.1.⁴⁰




Figure 9.1 Diagram of fse vs Distance From Girder End

The initial sloped portion of the diagram begins at a stress level of zero where bond begins and is assumed to increase linearly over a distance equal to the transfer length.

The second horizontal portion of the diagram is the region where the strand has fully transferred the effective prestress. The stress in the strand is assumed to remain constant in this region.

9.3 Importance of Transfer Length

While in most cases, transfer length is not the governing design consideration in a pretensioned bridge girder, its importance and implications must be understood. Of greatest importance with regard to transfer length is the design of adequate confinement, transverse steel to enclose the prestressing strands at the ends of the girder where initial stress transfer occurs. The 1996 AASHTO⁴⁰ Standard Specification for Highway Bridges Section 9.22.2 identifies the requirement to detail "nominal reinforcement" in the bottom

flange of the beam to enclose the strands over at least a distance "d" from the beam end.

Without adequate steel present in the transfer region, cracking can occur around

pretensioning strands effectively increasing the transfer length.

The elastic behavior of the beam also is affected by transfer length. As the stress in the strand increases from zero at the free-end of the beam to the level of effective prestress, f_{se} , at a distance equal to the transfer length from the girder end, the flexural stress required to cause cracking on the bottom surface of the beam also increases. Close to the end of the beam, the required cracking moment is less than that at a distance greater than the transfer length from the end of the girder. This change in cracking moment is important not only as a flexural design consideration but also for shear design, which is discussed in Chapter 11. Shear design within the transfer region must consider the reduced effective prestressing force.

9.4 Current Code Provisions

Current code provisions differ on the way transfer length is determined. Both the AASHTO and ACI techniques are conservative and produce similar results; but the two approach the phenomenon differently. AASHTO⁴⁰ Section 9.20.2.4 states the transfer length for prestressing strand shall be taken as 50 diameters (50*d_b) for strand and 100 diameters for single wire. Section R12.9 of the ACI 318² Commentary specifies that transfer length shall be determined using the equation 2.5.

$$l_t = \frac{f_{se}d_b}{3} \tag{2.5}$$

The value f_{se} is the effective stress in the prestressed reinforcement in ksi after allowance for all losses and d_b is the strand diameter in inches. The derivation of the ACI equation was covered in detail in Section 2.8. The current research program examined only 0.6-inch diameter, seven-wire, 270 ksi, low-relaxation pretensioning strand.

9.5 Test Specimens

Six full-scale AASHTO Type II girders were constructed for this research program. The cross section of each girder was identical; each used eight 0.6-inch Grade 270 low-relaxation strands in the bottom flange and two strands in the top flange. Both bottom and top strands were stressed to 75 percent of the strand ultimate strength, f_{pu} . The 28-day concrete design strengths, f_c , were 8,000 psi for the G1 series girders and 10,000 psi for the G2 series girders.

Transfer length data were taken on each girder end producing 12 sets of data. The girders were designated as described in Chapter 8 with a girder number (G1A, G1B, G1C, G2A, G2B and G2C) and end (East or West). Girder numbers were based on concrete design strength, girder length and reinforcement layout. Girder ends were designated based on their orientation in the precast plant at time of construction; i.e. west would indicate the beam end pointed in the westerly direction. For example, transfer length data are reported as G1A-West indicating information about the West end of girder G1A.

9.6 Measurement of Transfer Length Data

Transfer length data for the bottom prestressing strands were measured using the Concrete Surface Strain (CSS) method. As the prestressing strands transferred stress to the concrete, compressive stress and thus strain was induced in the concrete. Based on compatibility, the strain profile in the concrete should mirror the strain in the prestressing strand. Thus, the concrete strain profile should appear the same as the prestressing strand strain profile shown in Figure 9.1. The point at which the concrete strain reaches a maximum value and stabilizes at a constant strain level is the transfer length.

9.6.1 CSS Method

The CSS method of measuring strain in the concrete was accomplished through the use of a detachable mechanical strain gage known as a DEMEC gage. The DEMEC gage measured the distance between two points through the use of two conical points that were inserted into embedments on the surface of the concrete. A DEMEC gage is pictured in Figure 9.2; use of the DEMEC gage is pictured in Figure 9.3.




Figure 9.2 DEMEC Gage



Figure 9.3 DEMEC Gage in Use

The DEMEC gage was used to collect CSS data for determination of the transfer length, development length, and level of prestressing in the strands. A thorough description of construction and installation of the DEMEC gage embedments was covered in Chapter 8.

In order to collect transfer length data on the bottom strands, DEMEC gage embedments were installed at the level of the bottom strands over a 48-inch distance from each girder end on each side of the girder. Spacing on the embedments was set at two inches to produce a well-defined strain profile over the transfer length region. The distance between the conical inserts on the DEMEC gage was approximately 8 inches; this distance varied slightly based on small variations in hole placement on the

embedment strips. On average, the 8-inch gage length coupled with the 0.0001-inch accuracy of the gage produced a sensitivity of 12.5 microstrains in the measurements.

9.6.2 Measurement of Surface Strains and Other Data

It is important to note that the DEMEC gage did not directly measure concrete strains. The readings from the DEMEC gage were distances between the embedments from which the strains could be calculated. The DEMEC gage readings were referred to as "CSS readings" throughout this report; calculations were necessary to determine the strain. The DEMEC gage measured distance over an 8-inch distance. Within that 8-inch distance were located four 2-inch segments. The reading over the 8-inch gage distance inherently averaged the strains over the four included segments.

CSS measurements were made at specified times in the life of each girder. A CSS data-recording sheet shown in Appendix G, Figure G.1 was created to facilitate organized and consistent collection of the thousands of CSS readings and other data. The following readings were taken on each of the six girders prior to strand release, just after strand release and 1, 2, 3, 7, and 14 days after strand release.

- Transfer length CSS readings
- Girder internal temperature and ambient temperature
- Vibrating Wire Strain Gage reading at level of bottom strands at midspan
- CSS readings at midspan used for prestress loss (not used for transfer length calculations)
 - Girder midspan deflection (not used for transfer length calculations)

There were several important rules that were followed when making the CSS and other readings. First, the readings before strand release served as "initial" readings and were the basis for all strain calculations. If the initial readings were in error, all subsequent strain calculations would be flawed. Previous research showed that taking two sets of initial CSS readings and averaging the results provided a good indication of the initial distance between embedments.³⁷ Since some variation in the readings might occur based on operator inconsistency or environmental conditions, two initial readings helped to remove some of the inherent error. On subsequent readings, inconsistencies on data measurement would tend to average out and produce acceptable results.

Second, except for the "initial" and "just after release" readings, the time at which the CSS readings were taken was just prior to sunrise. Based on experience from previous research, it was found that temperature and solar radiation had a tremendous effect on surface strain.³⁷ In order to alleviate these effects to the greatest extent possible, CSS readings were made early in the morning before the girders were exposed to direct sunlight. Also based on previous research, transfer length CSS readings were only taken up through 14 days. After 14 days, the transfer length stabilized. Results in this research indicated stabilization of results occurred as soon as 7 days after release.

Third, when taking the CSS readings, it was essential to use the same DEMEC gage to make the readings each time. It was found that slight differences existed between the two gages that could impact the consistency of the readings. Two DEMEC gages were available; they were labeled #1 and #2. Likewise, the beam sides were labeled with #1 and #2, respectively, to insure the DEMEC gages were used on the same side for each

reading. In addition, two people were required to make the CSS readings. One person took readings while the other person recorded data. To the greatest extent possible, the same people were used to take CSS readings each time. Prior to using a DEMEC gage, it was zeroed to 8 inches between the conical points using a length "standard" bar.

VWSG readings at midspan, temperature readings, and other CSS readings at midspan and at other locations on the beam also were taken. The VWSG and CSS readings at midspan at the level of the bottom strands were used to determine the stress in the prestressing strand. Accurate knowledge of prestressing stress was necessary when evaluating existing transfer length equations and suggesting new ones. Differences occurred between strain readings using the VWSG and CSS methods. Just after release, there were significant differences in the strains that resulted between the two methods. As time progressed, the difference became less, but remained between 5 and 10 percent. Appendix F addresses the determination of prestressing force.

9.6.3 Reduction of Transfer Length Data

Determination of the transfer length was a several step process. An EXCEL spreadsheet was created such that raw transfer length data could be entered with the outcome being a smoothed strain profile for each girder end. The analysis process was broken into steps as listed below. A complete listing of the various worksheets in the spreadsheet to evaluate Girder G1C is provided in Appendix G and referenced below in STEPS 1-8.

STEP 1: Girder data with respect to strand tensioning, temperatures, VWSG readings, midspan deflections and times at which measurements were taken was entered into the "Data" worksheet (Table G.2).

STEP 2: Dimensions describing the location of embedment strips were entered into two worksheets titled "Gages-North" (Table G.3) and "Gages-South" (Table G.4). These dimensions allowed the calculation of exact strain measurement locations with respect to the girder ends. The figures indicate the location of each embedment strip on the particular side of the girder. For transfer length calculations, only data from the embedment strips at the bottom of the girder at each end were used.

STEP 3: CSS readings for each individual embedment strip were entered on the next series of 12 worksheets. Tables G.5 through G.16 show worksheets for each embedment strip on the girder. The location of the embedment strip is indicated by a shaded rectangle in the box below the header line. For example, a reading of -0156 on this sheet would indicate the distance between the measured embedments was 8"- 0.0156" or 7.9844". The "Initial" readings on this series of worksheets were averaged and used to determine the initial gage lengths on "Gages-North" and "Gages-South."

STEP 4: Tables G.17 and G.18 show worksheets "Raw-North" and "Raw-South" which subtracted initial CSS readings from subsequent readings and divided the result by the initial gage length. The resulting values were raw strains for both sides of the girder.

STEP 5: In order to smooth the CSS plots, values were averaged using a 3-point floating average as specified in equation 9.1.

$$\varepsilon_{x} = \frac{\varepsilon_{x-2} + \varepsilon_{x} + \varepsilon_{x+2}}{3} \tag{9.1}$$

The values ε_{x-2} and ε_{x+2} are the strains at 2 inches before and after the strain at "x" inches from the end of the girder. This floating 3-point average smoothed out the peaks and valleys in the CSS data to produce a strain plot that better facilitated determination of the transfer length. Tables G.19 and G.20 show worksheets "Smooth-North" and "Smooth-South." A comparison of the "smooth" and "raw" data demonstrates the smoothing effect. As with the "raw" data, this operation was performed for data from both sides of the girder.

STEP 6: Strains from the left and right sides were averaged and smoothed in Tables G.21 and G.22 respectively.

STEP 7: From the "Average Raw" and "Average Smooth" worksheets were plotted the CSS profiles just after release, and 1, 3, 7 and 14 days after release for both ends of the girder. Figure 9.4 shows a typical "raw" CSS plot for the East end of girder G1C. Figure 9.5 shows a typical "smooth" CSS plot for the same girder end. It was very useful to plot both average raw and average smooth data for error checking.




Figure 9.4 Raw CSS Plot for East End of Girder G1C




Figure 9.5 Smoothed CSS Plot for East End of Girder G1C

STEP 8: Examination of CSS profiles for each of the 12 girder ends and experience from previous research showed that 14-day data provided an excellent prediction of transfer length.³⁷ Based on this observation, two final plots were constructed, one for each end of the girder. Figure 9.4 shows a typical 14-day smooth CSS plot for the East end of girder G1C. The process for determining transfer length from the CSS plot is covered in Section 9.6.4.




Figure 9.6 Transfer Length Determined Using 95 Percent AMS Method for G1C-East

9.6.4 Determination of Transfer Length

Transfer length was determined using the 95% Average Maximum Strain Method (95% AMS). Both Buckner⁴⁶ and Russell⁴⁴ recommended this method as a conservative and objective technique for determining transfer length.

9.6.4.1 95% Average Maximum Strain Line

Recalling Figure 9.1, which provided the idealized profile of stress in the prestressing strand, the second portion of the curve identifying the region of constant strand stress is analogous with the "Constant Strain Plateau." Determination of this region required identifying the point on the 14-day CSS plot where the transition to constant strain occurred. After evaluating the 12 girder-end CSS plots, it was determined that the constant strain plateau began at a point approximately 30 inches from the girder end in each case. The 30-inch distance was chosen for consistency and provided an excellent prediction overall of the strain plateau for all specimens. Referring to Table G.22, there is a column labeled 95%. The values in this column were calculated by taking 95% of the average of the strain values measured at greater than 30 inches from the girder end.

9.6.4.2 Initial Linear Trend Line

The "Initial Linear Trend" line shown in Figure 9.6 was determined in a much more subjective manner. Previous researchers took the intersection of the CSS plot with the constant strain plateau as the defined transfer length.⁴⁴ In many of the CSS plots in this project, the initial sloped portion of the plot was highly non-linear and undependable

for an accurate prediction of transfer length. It was decided to use a technique where a best-fit line was determined by visual inspection for the initial sloped portion of the CSS plot. After determining the approximate location of the line, the CSS data point marking the x-coordinate of the top end of the line was identified. Using the "trend line" option in EXCEL, the best-fit trend line passing through the origin was plotted. The intersection of the initial linear trend line with the 95% AMS line was identified as the transfer length.

9.6.5 CSS Transfer Length Results

Table 9.1 provides transfer length results after 14 days for the 12 girder-ends.

Table 9.1 – CSS Transfer Length Results (inches)

G	1A	G1	В	G1	C	G2	2A	G	2B	G	2C
East	West	East	West	East	West	East	West	East	West	East	West
19.5	18.75	25.00	18.75	28.00	21.50	17.50	13.25	13.00	13.00	19.00	18.00
		FREE		FREE		FREE					

9.6.6 Potential Sources of Error in CSS Transfer Length Results

As presented by Reutlinger³⁷, past work by Buckner and Deatherage pointed out that potential differences existed between transfer lengths of top and bottom strands.

Buckner noted a study at the University of Illinois which reported a 25% decrease in bond strength for strands having 10 inches or more of concrete cast beneath them as compared to strands with only 2 inches of concrete below them. A study conducted by Deatherage on fully pretensioned top strands found that end slip for top strands was 1.5 to 5.2 times that for bottom strands. These results suggest that the transfer length of top

strands may be significantly longer than for bottom strands based on accumulation of excess water and air below the top strands.

Reutlinger³⁷ performed a parametric study to determine the potential effect of differences between the top and bottom strand transfer length on bottom strand transfer length calculations. Assuming that top-strand transfer lengths were between 1 and 5.5 times the bottom-strand transfer lengths, he determined that 95% AMS transfer lengths for the bottom strands could be unconservative by as much as 37%.

Transfer lengths were not determined for top strands in this research project.

However, the concrete used had very little mix water and was dosed heavily with superplasticizers; no excess bleed water was observed at any time. It is very unlikely there was a difference between the top and bottom strand transfer lengths.

9.7 Discussion of Results

9.7.1 Effect of Girder Orientation

Chapter 8 provided details concerning girder construction. The girders were constructed in pairs: G1A and G1B, G2A and G2B and G1C and G2C. The pairs of girders had a combined length in each case at least 35 feet less than the length of the prestressing bed. This 35-foot difference meant there was 35 feet of free prestressing strand between the end of the second girder and the dead end of the prestressing bed. In Table 9.1, girder ends labeled "FREE" were the ends exposed to the excess strand. In each case, the transfer length was substantially longer than similar ends in the girder pairs. Other researchers also have reported this phenomenon.⁴⁴

9.7.2 Effect of Concrete Grade

A single variable statistical analysis produced the results shown in Table 9.2 for the two grades of concrete:

Table 9.2 Statistical Analysis of Transfer Length Data

Girder Series	f _c '	Average fci'	Average	Standard
	Design Strength	Actual Strength	Transfer Length	Deviation
		at 24 Hours	_	
	(psi)	(psi)	(in)	(in)
G1	8,000	7,082	21.92	3.81
G2	10,000	9,180	15.63	2.83

The average transfer length for the G1 series girders was 6.29 inches longer than that of the G2 series girders indicating a clear relation between concrete strength and transfer length. The standard deviation was also significantly less for the G2 series girders compared to the G1 series potentially indicating more consistent transfer lengths overall for higher strength concrete.

In examining the relation between concrete strength and transfer length, it was recognized that concrete strength affected material properties and the amount of change in prestress from release until all losses had occurred. For the purpose of examining transfer length, this study focused on concrete strength and modulus of elasticity. Indirectly, however, the strength of concrete impacted the resulting initial level and effective level of prestress. Initial elastic shortening was determined by the modulus of elasticity of the concrete at release. Creep shortening over the period of time from release until the transfer length was measured was directly related to the concrete grade; a higher strength of concrete, in general, underwent less creep.

9.8 Comparison of Results with Code Provisions and Proposed Equations

This section compares the transfer length results from this research with transfer lengths predicted by code specified provisions and techniques proposed by other researchers. The goal of this comparison was to determine which variables provided the best prediction of transfer length. For comparison purposes, 12 transfer length values from this HSLC research were evaluated along with 8 values from a previous normal weight HPC study by Reutlinger³⁷ to determine what differences if any existed between HSLC and HPC. The transfer length tests in the HPC study were labeled in a manner similar to those in this research project. A transfer length test label of G4A-N indicated "grade 4" concrete, girder reinforcement pattern "A," and the "North" end of the girder. The 8 sets of normal weight HPC data were listed as the last 8 values in the tables. All the transfer length tests used 0.6-in diameter prestressing strand.

9.8.1 Material Properties

To evaluate current equations, a material property listing was composed. Table 9.3 shows concrete strengths at times from release through 56 days. The curing method was either accelerated using a curebox for the first 24 hours or by the ASTM⁷⁹ procedure

Table 9.3 Concrete Strength Data

Test #	lt	f _{ci} '	$\mathbf{f_{ci}}$ '	f _c '	f _c '	f _c '	f _c '
		24-hour	24-hour	28-Day	28-Day	56-Day	56-Day
		Curebox	ASTM	Curebox	ASTM	Curebox	ASTM
	(in)	(psi)	(psi)	(pse)	(psi)	(psi)	(psi)
G1A-E	19.50	7465	5735	8711	8835	9084	9346
G1A-W	18.75	7465	5735	8711	8835	9084	9346
G1B-E	25.00	7465	5735	8711	8835	9084	9346
G1B-W	18.75	7465	5735	8711	8835	9084	9346
G1C-E	28.00	6315	5400	7478	7595	7750	8457
G1C-W	21.50	6315	5400	7478	7595	7750	8457
G2A-E	17.50	9640	9294	10166	10116	10418	10816
G2A-W	13.25	9640	9294	10166	10116	10418	10816
G2B-E	13.00	9640	9294	10166	10116	10418	10816
G2B-W	13.00	9640	9294	10166	10116	10418	10816
G2C-E	19.00	8261	6553	9344	9807	10249	10512
G2C-W	18.00	8261	6553	9344	9807	10249	10512
G2A-S	15.40	14989	10078	16513	17058	16770	18714
G2A-N	17.00	12379	7590	12939	14139	13430	15456
G2B-S	17.90	12379	7590	12939	14139	13430	15456
G2B-N	17.80	11721	7186	12251	13387	12716	14634
G4A-S	16.70	14675	9866	16166	16700	16418	18321
G4A-N	13.80	14395	9678	15858	16382	16105	17972
G4B-S	13.50	14395	9678	15858	16382	16105	17972
G4B-N	13.40	14610	9822	16094	16626	16345	18240

Table 9.4 lists modulus of elasticity values at release (24 hours) and after 56 days Methods of curing were the same as for the concrete strength specimens.

Table 9.4 Modulus of Elasticity Data

Test #	1 _t	Eci	E _c	E _c
		24-hour	56-Day	56-Day
		Curebox	Curebox	ASTM
	(in)	(psi)	(psi)	(psi)
G1A-E	19.50	3.47E+06	3.86E+06	3.83E+06
G1A-W	18.75	3.47E+06	3.86E+06	3.83E+06
G1B-E	25.00	3.47E+06	3.86E+06	3.83E+06
G1B-W	18.75	3.47E+06	3.86E+06	3.83E+06
G1C-E	28.00	3.00E+06	3.28E+06	3.56E+06
G1C-W	21.50	3.00E+06	3.28E+06	3.56E+06
G2A-E	17.50	3.55E+06	3.93E+06	4.06E+06
G2A-W	13.25	3.55E+06	3.93E+06	4.06E+06
G2B-E	13.00	3.55E+06	3.93E+06	4.06E+06
G2B-W	13.00	3.55E+06	3.93E+06	4.06E+06
G2C-E	19.00	3.91E+06	4.10E+06	4.05E+06
G2C-W	18.00	3.91E+06	4.10E+06	4.05E+06
G2A-S	15.40	6.16E+06	5.58E+06	6.12E+06
G2A-N	17.00	5.78E+06	5.71E+06	5.61E+06
G2B-S	17.90	5.78E+06	5.71E+06	5.61E+06
G2B-N	17.80	5.78E+06	5.71E+06	5.61E+06
G4A-S	16.70	6.16E+06	5.58E+06	6.12E+06
G4A-N	13.80	6.16E+06	5.58E+06	6.12E+06
G4B-S	13.50	6.16E+06	5.58E+06	6.12E+06
G4B-N	13.40	6.16E+06	5.58E+06	6.12E+06

9.8.2 Prestressing Strand Stresses

Table 9.5 lists average prestressing strand stresses prior to release (f_{pt}), just after release (f_{si}), and after all losses (f_{se}). The strand tensioning stress, f_{pt} , was determined using strand load cells as described in Chapter 8. Both a CSS technique and VWSG output were used to determine stress in the strands. When strand stresses were required to predict transfer length, values from both techniques were used and the results

compared to measured values. CSS determined prestressing stress values were not determined on the four normal weight HPC girders.

Table 9.5 Prestressing Levels

	4			<u> </u>		<u> </u>
Test #	l_{t}	\mathbf{f}_{pt}	\mathbf{f}_{si}	f_{si}	\mathbf{f}_{se}	f_{se}
		,	VWSG	CSS	VWSG	CSS
	(in)	(ksi)	(ksi)	(ksi)	14-Days	14-Days
					(ksi)	(ksi)
G1A-E	19.50	179.06	161.73	167.40	154.74	152.20
G1A-W	18.75	179.06	161.73	167.40	154.74	152.20
G1B-E	25.00	179.06	160.90	167.94	153.34	153.04
G1B-W	18.75	179.06	160.90	167.94	153.34	153.04
G1C-E	28.00	179.11	162.11	159.52	153.65	146.76
G1C-W	21.50	179.11	162.11	159.52	153.65	149.76
G2A-E	17.50	191.30	178.66	181.52	176.52	171.14
G2A-W	13.25	191.30	178.66	181.52	176.52	171.14
G2B-E	13.00	191.30	178.94	181.28	176.52	169.92
G2B-W	13.00	191.30	178.94	181.28	176.52	169.92
G2C-E	19.00	179.11	164.64	161.87	159.82	161.87
G2C-W	18.00	179.11	164.64	161.87	159.82	156.14
G2A-S	15.40	190.86	178.13		169.75	
G2A-N	17.00	190.86	178.13		169.75	
G2B-S	17.90	190.86	177.24		168.72	
G2B-N	17.80	190.86	177.24		168.72	
G4A-S	16.70	190.86	179.31		170.62	
G4A-N	13.80	190.86	179.31		170.62	
G4B-S	13.50	190.86	179.14		169.90	
G4B-N	13.40	190.86	179.14		169.90	

9.8.3 Code and Suggested Transfer Length Equations

Transfer lengths were predicted using 20 equation variations. Included were code-specified equations and equations suggested by researchers. Table 9.6 provides an

overview of the equations examined. The equation number listed refers to the discussion of the equation in Chapter 2, Background Review.

Table 9.6 Summary of Transfer Length Equations

Source / Author of Equation	Transfer Length, lt	Equation Number
AASHTO ⁴⁰	$50d_b$	2.6
ACI ²	$\frac{f_{se}d_b}{3}$	2.5
Zia and Mostafa ⁴²	$1.5 \frac{f_{si}}{f'_{ci}} d_b - 4.6$	2.8
Martin and Scott ⁴¹	80 <i>d</i> _b	2.7
Deatherage et al. ⁴³	$\frac{f_{si}d_b}{3}$	2.9
Russell ⁴⁴	$\frac{f_{se}d_b}{2}$	2.10
Mitchell et al. ⁴⁵	$0.33 f_{si} d_b \sqrt{\frac{3}{f'_{ci}}}$	2.11
Buckner ⁴⁶	$\frac{1250f_{si}d_b}{E_{ci}}$	2.12
Lane (Mean) ⁴⁷	$4\frac{f_{pt}d_b}{f'_c}-21$	2.13
Lane (95% Confidence) ⁴⁷	$4\frac{f_{pl}d_b}{f'_c} - 5$	2.14

d_b Prestressing strand diameter

ES Prestress losses due to elastic shortening

CR Prestress losses due to creep

lt Transfer length

 f_{pt} Stress in prestressing strand prior to release

 f_{si} Stress in prestressing strand immediately after release (f_{pt} -ES)

 f_{se} Stress in prestressing strand after all losses (f_{pt} -ES-CR-SH)

SH Prestress losses due to shrinkage

f'ci Concrete compressive strength at release

f'c Concrete compressive strength at 28 or 56 days

Eci Concrete modulus of elasticity at release

In order to compare the experimentally measured transfer length values with code and suggested equation results, the following relationship was used to determine the average difference between equation and experimental results:

$$\frac{l_{t(Equation)} - l_{t(Experimental)}}{l_{t(Equation)}}$$
(9.2)

By performing the difference comparison in this manner, the code or suggested equation served as the accepted value.

9.8.4 Results of Comparison

Table 9.7 provides an overview of the results of a comparison of experimentally measured to predicted transfer lengths. The curing method and time of curing specified describe whether an accelerated (curebox) or ASTM curing procedure was used and the age of the specimen. The prestress stress measurement technique describes whether CSS readings or vibrating wire strain gage (VWSG) output was used. The "Max Over" column lists the predicted transfer length value with the largest percentage greater than the experimentally measured value. The "Max Under" column lists the predicted transfer length value with the largest percentage less than the experimentally measured value.

Table 9.7 Overview of Results Sorted by Equation Source

Equation	Equation	Curing	Prestress	Overall Results		
Source	Predicting	Method	Stress	Avg Max		Max
&	l_{t}	&	Msmt.	Diff	Over	Under
Designation		Age	Technique	(%)	(%)	(%)
AASHTO	50d _b	NA	NA	42%	57%	7%
ACI-a	$\frac{f_{se} d_b}{3}$	NA	VWSG	46%	63%	9%
ACI-b	$\frac{f_{se} d_b}{3}$	NA	CSS	40%	62%	5%
Buckner - a	$\frac{1250 f_{si} d_b}{E_{ci}}$	Curebox-24	VWSG	41%	66%	22%
Buckner - b	$\frac{1250 \ f_{si} d_b}{E_{ci}}$	Curebox-24	CSS	49%	66%	30%
Deatherage et al a	$\frac{E_{ci}}{f_{si}d_b}$	NA	VWSG	49%	64%	14%
Deatherage et al b	$\frac{f_{si} d_b}{3}$	NA	CSS	44%	64%	12%
Lane - 95 - a	$4\frac{f_{pt}d_b}{f'_c}-5$	Curebox-28	NA	50%	68%	28%
Lane - 95 - b	$4\frac{f_{pt}d_b}{f'_c}-5$	ASTM-28	NA	48%	68%	26%
Lane - a	$4\frac{f_{pt}d_b}{f'_c}-21$	Curebox-28	NA	-7%	46%	-129%
Lane - b	$4\frac{f_{pi}d_b}{f'_c}-21$	ASTM-28	NA	-20%	47%	-163%
Martin, Scott	80 d _b	NA	NA	63%	73%	42%
Mitchell et al a	$0.33 f_{si} d_b \sqrt{\frac{3}{f'_{cl}}}$	Curebox-24	VWSG	7%	34%	-27%
Mitchell et al b	$0.33 f_{si} d_b \sqrt{\frac{3}{f'_{cl}}}$	ASTM-24	VWSG	19%	35%	-17%
Russell, Burns - a	$\frac{f_{se}d_b}{2}$	NA	VWSG	64%	75%	39%
Russell, Burns - b	$\frac{f_{se}d_b}{2}$	NA	CSS	60%	74%	36%
Zia, Mostafa - a	$1.5 \frac{f_{si}}{f'_{ci}} d_b - 4.6$	Curebox-24	VWSG	-66%	-7%	-161%
Zia, Mostafa - b	$1.5 \frac{f_{si}}{f'_{ci}} d_b - 4.6$	ASTM-24	VWSG	-10%	10%	-42%
Zia, Mostafa - c	$1.5 \frac{f_{si}}{f'_{ci}} d_b - 4.6$	Curebox-24	CSS	-28%	-5%	-60%
Zia, Mostafa - d	$1.5 \frac{f_{si}}{f'_{ci}} d_b - 4.6$	ASTM-24	CSS	-4%	14%	-35%

9.8.4.1 Results of Analysis Based on Average Difference

Analysis of Table 9.7 showed that Mitchell et al.—a produced the best overall estimate of transfer length. The Mitchell et al.-a equation would be considered a "best-fit" equation where a "best-fit" equation was defined as the equation having the lowest average difference between experimental and predicted values.

The use of initial concrete compressive strengths, f'ci, based on curebox data produced better results overall than ASTM strengths. This occurrence was logical. A comparison of heat of hydration curves between girders and curebox specimens showed a close correlation.

The use of prestressing stresses based on CSS data seemed to produce slightly better results than VWSG data. However, the differences were small and results from Buckner's equation showed the opposite trend. Data from Reutlinger's³⁷ tests were based on VWSG data making it desirable to also base this current analysis on VWSG predicted prestress values. Based on the above, VWSG predicted prestress values were used for future analyses.

Although Mitchell et al.-a and Mitchell et al.-b were the best overall equations, there were cases where transfer lengths were underestimated by as much as 27%.

Equations by Buckner, Deatherage, ACI and AASHTO always provided a conservative estimate of transfer length.

9.8.4.2 Results of Analysis Based on Maximum Underestimate

Analysis of Table 9.7 based on maximum underestimate showed equation ACI-b to provide a good overall estimate of transfer length without being overconservative.

ACI-b would be the best choice as a "design equation." A "design" equation was defined as the equation having the lowest positive maximum underestimate value without being overly conservative. Determination of the amount an equation was overconservative was based on the maximum overestimate value. The most favorable combination of these two values indicated the best "design" equation.

Table 9.7 also showed the AASHTO equation and the equation by Deatherage provided good conservative estimates without being overconservative. An interesting note concerning these five equations was that they did not include a term describing the properties of the concrete.

9.8.4.3 Evaluation of Top Five "Best-Fit" and "Design" Equations

In order to determine a strategy for improving current transfer length equations, Table 9.8 was created to show a listing of the top five equations in both the "best-fit" and "design" categories. From this table, it was possible to summarize which factors appeared to be important when predicting transfer length. It was obvious that strand diameter, d_b was a necessary equation variable. It appeared that f_{si} was a better variable for describing the impact of the level of prestress. The variable that appeared to best describe the concrete was f'_{ci} ; Since the Mitchell et al. equations ranked highest with respect to "best-fit," f'_{ci} was considered an important variable. However, based on the use of HSLC and the effect reducing concrete unit weight has on modulus of elasticity, the consideration of E_{ci} was not discarded from further analysis.

Table 9.8 Review of Top Five "Best-Fit" and "Design" Equations

Best-Fit Equations									
Rank	Equation	Equation	Curing	Equation Variables				les	
	Source		Method						
	&		&	d_b	f'ci	Eci	f_{si}	f_{se}	
	Designation		Age				<u> </u>		
1	Mitchell et al a	$0.33 f_{sl} d_b \sqrt{\frac{3}{f'_{al}}}$	Curebox-24	X	X		X		
2	Mitchell et al b	$0.33 f_{sl} d_b \sqrt{\frac{3}{f'_{cl}}}$	ASTM-24	X	X		X		
3	ACI-b	$\frac{f_{se} d_b}{3}$	NA	X				X	
4	Buckner - a	$\frac{1250 \ f_{si} d_b}{E_{ci}}$	Curebox-24	X		X	X		
5	AASHTO	50d _b	NA ·	X					

		Design Equati	ons					
Rank	Equation Source	Equation	Curing Method	Equation Variables				
	& Designation	·	& Age	d _b	f'ci	Eci	\mathbf{f}_{si}	fse
1	ACI-b	$\frac{f_{se} d_b}{3}$	NA	X				X
2	AASHTO	50d _b	NA	X				
3	ACI-a	$\frac{f_{se} d_b}{3}$	NA	X				X
4	Deatherage et al b	$\frac{f_{si}d_b}{3}$	NA	X			X	
5	Deatherage et al a	$\frac{f_{si}d_b}{3}$	NA	X			X	

9.9 Development of an Improved Transfer Length Equation

Table 9.8 helped focus efforts in determining an improved transfer length equation. Using the base equations specified by AASHTO and ACI and the equations suggested by Buckner, Deatherage et al., and Mitchell et al., numerous different equation

configurations were developed and evaluated. In evaluating the equation forms, the following values were used:

f'ci Curebox (accelerated) 24-hour concrete compressive strength

E_{ci} Curebox (accelerated) 24-hour modulus of elasticity

f_{si} Initial prestressing force based on vibrating wire strain gage output

f_{se} Effective prestressing force based on vibrating wire strain gage output

For initial equation development, only the 20 sets of transfer length data (12 HSLC and 8 HPC) were used. For later development, more data from several other researchers was considered.

When determining the percent difference, a different method was used. During the evaluation of existing equations, the "accepted" value was taken as the "equation" value. While developing a new equation, the "accepted" value was the "measured" value. The percent difference was calculated using the following relation:

$$\frac{l_{\iota(Equation)} - l_{\iota(Experimental)}}{l_{\iota(Experimental)}} \tag{9.3}$$

9.9.1 Determination of Equation Variables

The first step taken in developing an improved equation was to identify the variable or variables that would best predict transfer length. Plots were created which singled out one variable and compared it to measured transfer length values. Figures 9.7 through 9.10 show plots involving f'_{ci} and E_{ci} .




Figure 9.7 Transfer Length vs. f'ci




Figure 9.8 Transfer Length vs. $(1/f^2_{ci})^{0.5}$




Figure 9.9 Transfer Length vs. Eci




Figure 9.10 Transfer Length vs. $(1/E_{ci})^{0.5}$

In Figures 9.7 through 9.10, the data points are not separated by lightweight or normal weight concrete. Each point describes one of the 20 tests. In a few cases, two data points are at the same location. A trendline and R² values were plotted in each figure to provide an idea of which variable form might best fit the transfer length data.

The results of Figures 9.7 through 9.10 indicated the variable f_{ci} was most likely a better predictor of transfer length than E_{ci} . The R^2 values for comparison of f_{ci} related variables with transfer length were greater indicating better correlation than those for E_{ci} . As a note, the R^2 value provided an indication of the degree of fit of a series of data points to a line. In comparisons to f_c , a straight line was the best-fit line. In the comparisons involving E_{ci} , other curve forms provided only a very slight improvement in correlation. Overall, the straight line provided a good common basis of comparison.

9.9.2 Determination of Equation Forms

Figures 9.7 through 9.10 showed that f'_{ci} was most likely the material-related variable to predict transfer length. Based on the use of HSLC in this research, it was decided to consider both f'_{ci} and E_{ci} . Using these variables, existing code specified equations and equations seen in Table 9.8, 27 different equation forms were configured and evaluated using the 12 sets of HSLC transfer length data and the 8 sets of normal weight HPC transfer length data from Reutlinger.³⁷ The value f_{ci} was based on 24-hour curebox specimens and prestress levels were based on measurements using VWSG data.

9.9.3 Results of Equation Analysis

The results of the equation analysis showed that the same equation form provided both the "best fit" and "design" equation. The definitions for "best fit" and "design" were defined previously in Sections 9.8.4.1 and 9.8.4.2. The only difference between the two equations was a constant value under the radical. Concrete strength values at release, f_{ci} , are in psi; transfer lengths are in inches.

The equation that provided the best fit was:

$$50 \ d_b \sqrt{\frac{3170}{f'_{ci}}} \tag{9.4}$$

The best equation for design was:

$$50 \ d_b \sqrt{\frac{5500}{f'_{ci}}} \tag{9.5}$$

Equation 9.4 was similar to one suggested by Mitchell for conservatively checking stress in concrete at the time of transfer. Mitchell's equation used 3000 as the constant in lieu of 3170. Mitchell did not recommend using the equation to calculate the transfer length portion of development length.⁴⁵

9.9.4 Equation Verification with Transfer Length Data from other Researchers

To verify the applicability equations 9.4 and 9.5, transfer length data from several other researchers were compiled into a database and evaluated. The data were based only on 0.6-in diameter prestressing strand. In most cases, the tests involved I-shaped girders; however, tests by Mitchell⁴⁵ and Russell⁴⁴ used rectangular cross sections. Table J.1 lists data used in the verification.

Each set of transfer length datum was plotted on a graph with f'ci on the X-axis and transfer length on the Y-axis. Plotting the "best fit" and "design" equations specified in Section 9.9.3 on the overall data plot was successful. However, by slightly increasing the constant values under the radical as seen in equations 9.6 (best fit) and 9.7 (design) below, the predicted plot line better fit the scatter of data points.

$$50 \ d_b \sqrt{\frac{4000}{f'_{ci}}} \tag{9.6}$$

$$50 \ d_b \sqrt{\frac{6000}{f'_{ci}}} \tag{9.7}$$

Figures 9.11 and 9.12 show equations 9.6 and 9.7 plotted respectively against the experimental data points listed in Appendix J.

It is important to comment that the rectangular shapes tested by Russell⁴⁴ were released simultaneously by flame cutting. Specimens by Mitchell⁴⁵ were released gradually which was reported to more closely match transfer lengths recorded under similar conditions in I-shaped girders. When finally configuring the equations, the rectangular shapes from Russell's testing were not included.




Figure 9.11 Proposed Best Fit Equation Plotted on Transfer Length Data




Figure 9.12 Proposed Design Equation Plotted on Transfer Length Data

Evaluation of the proposed equation for both "best fit" and "design" is shown in Table 9.9 where f_{ci} is in psi units. In the "Overall I Shape" category, comparison of both the "Best Fit" and "Design" equations with the current AASHTO equation showed favorable results.

Table 9.9 Results of Evaluation of the Proposed Equations

Basis Of Comparison	AASHTO CODE ⁴⁰	Proposed Design Equation	Proposed Best Fit Equation
	50 d _b	$50 d_b \sqrt{\frac{6000}{f'_{ci}}}$	$50 d_b \sqrt{\frac{4000}{f'_{ci}}}$
Avg Diff (Overall I Shape)	33%	25%	2%
Max Over (Overall I Shape)	131%	82%	49%
Max Under (Overall I Shape)	-42%	-25%	-38%
Avg Diff (LWC I-Shape)	69%	44%	18%
Max Over (LWC I-Shape)	131%	82%	49%
Max Under (LWC I-Shape)	7%	4%	-15%
Avg Diff (NWC I-Shape)	27%	22%	0%
Max Over (NWC I-Shape)	124%	79%	46%
Max Under (NWC I-Shape)	-42%	-25%	-38%
Avg Diff (NWC Rect)	-10%	-1%	-19%
Max Over (NWC Rect)	121%	100%	63%
Max Under (NWC Rect)	-42%	-34%	-46%
Avg Diff (Overall)	21%	18%	-3%
Max Over (Overall)	131%	100%	63%
Max Under (Overall)	-42%	-34%	-46%

The reason the proposed equations provided a better estimate was found in the strength range below 6,000 psi. Examination of the equations shows that the constant term under the radical determines the point at which the equation begins to increase the predicted transfer length above the AASHTO suggested 50d_b. In the case of the "best fit form of the equation, strengths below 4,000 psi underwent an increase in predicted transfer length above 50d_b. Examination of Figure 9.11 demonstrates this condition. In the case of the "design" form of the equation, strengths below 6,000 psi underwent an

increase in predicted transfer length above 50d_b. Examination of Figure 9.12 demonstrates this condition.

In examining the results of 32 different equation forms, it was observed that equation forms based on the AASHTO 50d_b prediction of transfer length in all cases showed better accuracy than the same equation form based on the ACI prediction $f_{se}d_b/3$. For 0.6-inch strand, $50d_b$ is 30 inches. On average, f_{se} is about 165 ksi meaning $f_{se}/3$ would equal about 55. Heuristically speaking, it makes sense to include a term addressing the level of prestress; however, the results of this evaluation did not indicate it produced the most accurate prediction.

Further examination of Table 9.18 showed insignificant difference between transfer length results for HSLC and normal weight HPC. Figures 9.11 and 9.12 show how transfer lengths for HSLC plotted consistently with the normal weight HPC values. To the author's knowledge, there is no other transfer length data available for 0.6-inch prestressing strand used in lightweight concrete in this strength and unit weight range.

9.10 Conclusions

An evaluation of current code provisions using the 12 HSLC transfer lengths in this research and 8 normal weight HPC transfer lengths from Reutlinger³⁷ showed the current AASHTO⁴⁰ and ACI² equations to be conservative. The AASHTO equation overestimated transfer lengths by 42% on average and never underestimated transfer lengths. The ACI equation using VWSG data also overestimated transfer lengths by 46% and never underestimated transfer lengths. Use of either the AASHTO or ACI equations to predict transfer length for slate HSLC was conservative. Based on the concrete

strength range addressed in this research project, modification of the current code specifications for transfer lengths was not necessary for HSLC.

An evaluation of other suggested equations for predicting transfer length showed an equation by Mitchell et al.⁴⁵ to provide the best overall prediction of transfer length. Equations by Buckner⁴⁶ and Deatherage et al.⁴³ also produced good overall predictions. The above equations were applicable to both HSLC and normal weight HPC with good results.

An evaluation of the applicability of initial concrete compressive strength, f_{ci} ', and initial modulus of elasticity, E_{ci} , and 32 possible equation forms showed that d_b and f_{ci} ' were the best parameters for predicting transfer length. New equations for predicting transfer length based on "Best Fit" and "Design" produced more accurate results than current code equations.

There was no indication throughout this analysis that a need existed to differentiate between slate HSLC and normal weight HPC with regard to transfer length. For initial concrete strengths, f_{ci} , over 6,000 psi, the prediction of transfer length was the same for both lightweight and normal weight concrete.

CHAPTER X

GIRDER TEST SET-UP AND PROCEDURE

10.1 Introduction

This chapter provides a description of the set-up and procedure used to test the composite HSLC girders. Detail is provided on the site layout, data acquisition system, and conduct of the test.

10.2 Test Set-up

Figure 10.1 illustrates the overall test set-up. Figure 10.2 shows the test frame with the hydraulic ram attached. Details on pieces of the set-up were included in Figure 10.1.

10.3 Instrumentation

The load cell used to monitor the applied load was a Strainsert 700 kip load cell. The model number was (CLC-FB) Q14928. The voltage rating was 2.00-mv/V (Nom.). The load cell was a full-bridge configuration that required an excitation voltage of 10 volts direct current (DC).

The wire potentiometer used to measure deflection at the point of load application was a Rayelco Position Transducer, model P5-A, 10 volts DC excitation. In addition to the wire pot covered in Section 10.2.3, a dial gage was positioned at the point of load

application to verify wire pot output. The dial gage readings matched wire pot output during each girder test.




Figure 10.1 Experimental Test Set-up




Figure 10.2 Load Frame

The linear variable displacement transducers (LVDT) were manufactured by the Lucas Schaevitz Company. The 3-inch LVDTs were model number HCD 1000. The 6-inch LVDTs were the HCD 2000. The LVDT measuring strain at the top of the girder was a 3-inch LVDT; the gage length was 24 inches. The LVDT measuring strain at the bottom of the girder was a 6-inch LVDT; the gage length was 24 inches. The 0 and 45 degree LVDTs in the rosette were 6-inch LVDTs. The 90 degree LVDT was a 3-inch LVDT. The 0 and 90 degree LVDTs had 10.5-inch gage lengths; the 45 degree LVDT had a 16.25 inch gage length. All LVDTs required a minimum of 12 volts ± up to a maximum of 15 volts ±. This voltage requirement is known as a "bi-polar" voltage. It was required to connect two power supplies in tandem to provide this voltage.




Figure 10.3 LVDTs Configured in Strain Rosette

The devices used to measure strand slip were linear potentiometers having a 2-inch maximum range. The devices had an excitation voltage requirement of 10 volts DC. The devices were calibrated prior to use to verify factory values. Figure 10.4 shows the strand slip indicators attached to the exposed strand segments.

To measure slip between the interface of the deck and the girder, a dial gage was installed halfway between the load point and a support. There was never any indication of slip seen in any of the tests. The only reading on the dial gage was related to the strain gradient between the gage connection points on the girder and the bottom surface of the deck. Figure 10.5 shows the dial gage positioned to record interface slip.




Figure 10.4 Strand Slip Indicators




Figure 10.5 Dial Gage to Measure Interface Slip

10.4 Data Acquisition System

All instrumentation discussed in Section 10.3 was connected to a data acquisition (DAQ) system. A National Instruments DAQ system was used for all tests. Table 10.1 identifies the DAQ system components and uses.

Table 10.1 DAQ System Components and Functions

DAQ	Component	Component	DAQ
Component	Description	Function(s)	Channel
			Assignments
SCXI-1000	4 Slot Chassis	Support DAQ Cards	NA
SCXI-1520	8 Channel Strain Card	Provided 8 Multi-Use	0 – Load Cell
		Channels Which	1 – Top LVDT
		Supported all DAQ	2 – Bottom LVDT
		Requirements	3 – Wire Pot
			4 – 0 Deg LVDT
			5 – 45 Deg LVDT
			6 – 90 Deg LVDT
SCXI-1127	Multiplexer Capable	Multiplexed Output from	7,0 – Strand 1 Slip
	of	8 Strand Slip Indicators	7,1 – Strand 2 Slip
	64 1/4-Bridge Outputs	into Channel 7 of the	7,2 – Strand 3 Slip
	32 ½-Bridge Outputs	SCXI-1520	7,3 – Strand 4 Slip
	16 Full-Bridge Outputs		7,4 – Strand 5 Slip
			7,5 – Strand 6 Slip
			7,6 – Strand 7 Slip
			7,7 – Strand 8 Slip

Figure 10.6 shows a photo of the DAQ system connected to a laptop PC. The power supplies providing the bipolar power for the LVDTs are also pictured. The DAQ system was driven by LABVIEW, the proprietary software of National Instruments. A LABVIEW program was written to support the girder testing.



Figure 10.6 Data Acquisition System with Power Supplies and Laptop Computer

10.5 Conduct of Girder Test

Several steps were involved with the conduct of a girder test. A checklist was created as seen in Figure 10.7, which covered all aspects of test set-up and conduct. The checklist was followed for each test and prevented oversights during tests. Data recording sheets were also created and used to collect CSS readings, deflection measurements and other miscellaneous readings during the test.

Testing Checklist for Girder #		Test Conf	figuration #	Date		
TEST PREPARATION PERIOD			~~·		····	
Position beam on supports – confirm	measurements w	ith testing plan				
Identify all cylinders for breaking and	Identify all cylinders for breaking and modulus testing. Record numbers on this sheet					
Ensure beam is restrained laterally w	Ensure beam is restrained laterally with chain for end tests. Not required for middle test					
Install all instrumentation to include	Install all instrumentation to include slip gage between beam and deck					
Hook-up and test instrumentation						
Confirm volunteers to assist during to	est					
ON DAY OF TESTING						
Test strength and modulus cylinders	and record value	s on this sheet				
Install surge protector at wall for elec	tronics power co	rd, Connect V	WSG reader at n	nidspan		
Set-up camera and check for operabil	ity. Check tape.	Position lights	3.			
Label data sheets, place on clipboard				orrect color		
Check for free travel of linear pots or	•		•			
Zero dial gage under point of load ap	_		rface			
Check for free travel of wire potention	-					
Start EXCEL and bring up strength p		=		oading, M _{cr}		
Start MAX (Never run MAX and L				<i>57</i> , ii		
 Check for operability of 	f all instrumenta	tion and zero al				
o LVDT Top (-0.2), LVI o Close MAX	OT Bot (+0.4), L	VDT 0 (0), LVI	DT 45 (+0.2), L	VDT 90 (+0.2)		
Start LABVIEW and open Beam Tes	ting VI dated 9 (Oct 01 Check	for proper opera	tion then close		
Brief assistants and visitors on safety	_		ioi proper oper	ation then close.		
Take initial DEMEC and VWSG rea					•	
Start LABVIEW and open Beam Tes	=					
o Click on WHITE ARR						
o At SET-UP tab do the	following	•				
	ion rate = 1 read OT upper and lov					
	OFILE to YES	ver revers (0.1	0.2)			
	engths (Top,Bot		2", 45 = 16.97")		
	A H H H A H THEODOM I HUNDEDOM					
	 Null all channels EXCEPT the WIRE POT. Run null on Linear POTs 5 times. 					
	 At SET-UP tab do the following 					
	 Click on START button – this will kick over to the display screens Set deflection limits on Wire POT at first tab of display screens (~2.4", 1") 					
 Set deflection limits on LOAD-DEFLECTION display (~2.4", 1") 						
 Check all screens for initial readings and to ensure lines are plotting correctly Record all initial values in table below. 						
Load Cell Top LVDT Bot LVDT Wire POT 0 LVDT 45 LVDT 90 LVDT						
					···-	
Strand 0 Strand 1 Strand 2	Strand 0 Strand 1 Strand 2 Strand 3 Strand 4 Strand 5 Strand 6 Strand 7					
o Start applying load	L	L	L	L		
At conclusion of test, save data to ha	rd-drive, back-up	data on floppy	disk and record	d any notes.		

Figure 10.7 Girder Testing Checklist

10.5.1 Loading Sequence

Each girder was loaded monotonically until failure at a load of approximately 400 kips. Loading proceeded in increments of approximately 30 kips or in deflection increments of about 0.25 inches. After each load or deflection increment, CSS readings, deflection readings, crack spacings, and VWSG readings were recorded. Readings were also taken at special occurrences such as first flexural or shear crack observation or initial strand slip.

The decision to terminate loading was based on observed failure characteristics. If crushing in the deck was occurring and total strain in the bottom strands was over 2 percent, the failure was judged a flexural failure and loading was terminated. If shear cracking was extensive and indicative of impending failure, loading was sometimes terminated to prevent further extensive damage. If strand slip over 0.1 inches occurred, the girder was watched closely. Strand slip would allow shear cracks to open and sudden violent shear failures to occur. If the test became a potential safety issue, loading was terminated as well. In a few cases, sudden violent failures occurred.

10.5.2 Concrete Surface Strain Readings

Before loading commenced, CSS readings were taken from the DEMEC gage inserts on the girder-end being tested and at midspan. The girder end readings provided an initial value on which to base CSS readings during the test. The midspan readings were useful in verifying the level of effective prestress before load was applied.

After each load increment, CSS readings were taken on the 48-inch strips located on the bottom flange of the girder end being tested. No CSS readings were taken during center span tests because development length was not considered a problem.

10.5.3 Marking Cracks

After each load increment, any newly formed cracks were marked. At the end of the marked crack, the load at which the crack occurred was marked as well. Close examination of the girder surface was necessary to note all the cracks formed. Figure 10.8 shows the marking of cracks.

10.5.4 Visual and Audio Recording of Test

Each girder test was recorded on video in its entirety and photographed with a digital camera. The video footage allowed review of the test to determine the initiation point of failures. In several instances, violent failures were captured on video. Digital photos allowed easy review of important points of the test.

10.5.5 Conclusion of Test

After load was removed, the girder was repositioned for the next test. If all three tests had been conducted on the girder, it was removed from the frame, photographed and placed back in storage.



Figure 10.8 Marking of Cracks During Girder Test

CHAPTER XI

FLEXURAL BEHAVIOR RESULTS AND DISCUSSION

11.1 Introduction

This chapter discusses flexural behavior in HSLC pretensioned girders. Girder material and section properties are provided. Based on experimentally measured values during the 18 girder tests, current code provisions are evaluated.

11.2 Experimental Results

Table 11.1 provides an overview of experimental results listing failure types, ultimate strain values and moments at cracking and ultimate conditions. The failure types were classified using the definitions below:

- FL The girder failed by "BOTH" crushing of the deck and yielding of the strands.
- SH The girder failed purely in shear. It did not meet the criteria for a flexural failure.
- **SH/FL** The girder failed predominantly in shear, but still yielded the strands and crushed the deck. The two failure states occurred almost simultaneously.
- **SH-SL** The girder underwent a shear failure initiated by the strands slipping.
- FL/SH-SL or SH-SL/FL The girder underwent both failure modes with one occurring more predominantly than the other. Both failures would result in yielding of the strands and crushing of the deck.

Table 11.1 Overview of Experimental Results

Test	Failure	Crushing	Cracking	Ultimate	Max	Max
#	Туре	Status	Moment	Moment	Deck	Strand
		of	M_{cr}	M_{ult}	Strain	Strain
	-	Deck			ε _{cu}	$\epsilon_{ m ps}$
			(ft-kips)	(ft-kips)	(in/in)	(in/in)
G1A-E	FL/SH-SL	Crushed	1224	1836	0.0038	0.0158
G1A-W	FL	Crushed	1109	1844	0.0042	0.0168
G1A-C	SH	Not Crushed	1064	1671	0.0029	0.0086
G1B-E	SH-SL	Not Crushed	1133	1578	0.0033	0.0078
G1B-W	FL	Crushed	1109	1840	0.0032	0.0190
G1B-C	SH/FL	Crushed	1188	1774	0.0039	0.0107
G1C-E	SH-SL/FL	Crushed	1155	1796	0.0032	0.0113
G1C-W	FL	Crushed	1145	1828	0.0036	0.0140
G1C-C	FL	Crushed	1142	1898	0.0049	0.0146
G2A-E	FL	Crushed	1220	1855	0.0036	0.0190
G2A-W	FL	Crushed	1176	1855	0.0072	0.0204
G2A-C	SH	Crushed	1124	1657	0.0086	0.0084
G2B-E	FL	Crushed	1110	1799	0.0082	0.0155
G2B-W	FL	Crushed	1124	1840	0.0064	0.0199
G2B-C	SH/FL	Crushed	1210	1869	0.0035	0.0122
G2C-E	FL	Crushed	1079	1870	0.0045	0.0228
G2C-W	FL	Crushed	1094	1793	0.0049	0.0198
G2C-C	FL	Crushed	1219	1885	0.0089	0.0215

G1 Avg	1141	1785	0.0037	0.0132
G2 Avg	1151	1824	0.0062	0.0177

Although there are five failure types listed in Table 11.1, the failures fell into two major categories; flexural failures and shear failures. Sections 11.2.1 and 11.2.2 provide photos of the failures, typical moment-curvature diagrams, and typical load-displacement diagrams for the two main failure categories.

11.2.1 Flexural Failures

Figure 11.1 shows a photo of girder test G1-B West, a typical flexural failure. The vertical lines indicate the location of shear reinforcement. Flexural failures were ductile in nature. A typical flexural failure showed flexural cracks extending from the bottom of the girder up into the deck and evenly spaced shear cracks less than 0.02 inches in width between the support and point of load application.

Spalling of concrete from the top surface was evidence of crushing in the deck.

Figure 11.2 provides a picture of deck crushing from test G1B-West. In Figure 11.2, the loading hardware was removed and the crushed concrete chipped from the deck to show the extent of crushing.

Some flexural failures resulted in longitudinal cracking in the deck as shown in Figure 11.3. Since there was only temperature and shrinkage steel running longitudinally in the deck, the occurrence of this cracking was understandable.




Figure 11.1 Typical Flexural Failure Shown in Girder Test G1B-West




Figure 11.2 Details of Deck Crushing in Girder Test G1B-West




Figure 11.3 Example of Longitudinal Deck Cracking in Girder Test G1A-East

Figure 11.4 provides a typical moment-curvature plot from a flexural failure. This moment-curvature plot from girder test G1B-West shows the theoretical and experimental behavior. The theoretical behavior is slightly offset from the experimental behavior because the girder was assumed to have zero curvature at the initiation of testing. The theoretical curvature value accounted for initial negative curvature due to prestressing where the experimental value did not. Both the theoretical and experimental plots begin at a moment value greater than zero reflecting the initial dead load moment being carried by the girder. The theoretical curve was determined with values at zero applied load, decompression of concrete at the level of the bottom strands, flexural cracking, yielding of the strand, and deck surface strains of 0.001, 0.002 and 0.003. The Construction of the theoretical moment-curvature curve is described in Appendix L.




Figure 11.4 Moment-Curvature Plot from Girder Test G1B-West

Figure 11.5 shows the load-displacement curve from girder test G1B-W, a typical flexural failure. The two points used to describe the predicted curve were based on deflection at cracking and ultimate. A description of the calculation of predicted deflection values is also included in Appendix L.




Figure 11.5 Load-Deflection Plot from Girder Test G1B-West

The load-displacement curves for flexural failures normally returned to within a small deflection from zero reflecting any strand yielding or deck crushing that may have occurred.

Figures 11.6 and 11.7 show a dramatic flexural failure where a large section of the deck and top flange separated from the girder. Note the exposed prestressing strand.




Figure 11.6 Flexural Failure During Girder Test G2B-East.



Figure 11.7 Close-up of Girder-Deck Interface in Girder Test G2B-East Flexural Failure

11.2.2 Shear Failures

Within the category of shear failures were included girder tests that failed purely in shear and those that underwent a shear failure initiated by strand slip. In general, the resulting moment-curvature and load-displacement curves were similar. For explanation purposes, the categories were handled separately. A much more in-depth explanation of shear failures is provided in Chapter 12, Shear Behavior Results and Discussion; this section is provided for better understanding of Table 11.1.

11.2.2.1 Pure Shear Failures




Figure 11.8 Girder Test G2A-Center Showing Pure Shear Failure

Girder test G2A-Center seen in Figure 11.6 involved a center span where the shear reinforcement was spaced at 24 inches. The objective of this test was to examine the shear strength of concrete. The shear crack running from bottom to top occurred very suddenly and violently and was indicative of a pure shear failure. Girders undergoing shear failures precipitated by strand slip showed different failure modes. Figure 11.9 shows a typical moment-curvature diagram for a pure shear failure.




Figure 11.9 Moment-Curvature Plot for Girder Test G2A-Center, a Pure Shear Failure

The sudden shear failure is indicated in Figure 11.9 by the sudden drop on the moment-curvature diagram. Figure 11.10 shows the load-deflection plot for girder test G2A-Center. The same sudden drop in load and increase in deflection is seen.




Figure 11.10 Load-Deflection Plot for Girder Test G2A-Center

11.2.2.2 Shear Failures Initiated by Strand Slip

Girders that underwent excessive strand slip experienced shear failures as well. However, the mode of failure appeared somewhat different. Figure 11.11 shows a photo of girder test G1C-East, a test where excessive strand slip resulted in a predominantly shear-based failure. Although the deck crushed and the strand yielded, the failure was dominated by shear. The shear cracking did not extend from bottom to top as in Figure 11.6, but ended prior to entering the deck. Figure 11.12 shows a photo of shear cracking at the bottom of the girder vicinity the support. The shear cracks were approximately 0.2 inches wide at the widest. Figures 11.13 and 11.14 show moment-curvature and load-deflection curves for girder test G1C-East.




Figure 11.11 Girder Test G1C-East After Strand Slip Induced Shear Failure



Figure 11.12 Girder Test G1C-E Showing 0.2-inch Wide Shear Cracks




Figure 11.13 Moment-Curvature Plot for Girder Test G1C-East




Figure 11.14 Load-Deflection Plot for Girder Test G1C-East

Examination of Figures 11.13 and 11.14 show the different behavior of this type of shear failure compared to the pure shear failure. The shear failure precipitated by strand slip was a gradual shear failure and not the sudden violent failure seen in pure shear failures. Figure 11.13 indicates the girder was unable to reach its predicted curvature value due to strand slip. Figure 11.14 shows that ultimate deflection was close to predicted, however, it was more the result of shear deformation due to strand slip than flexural deformation due to strand yielding as predicted. The girder's response to unloading showed that it experienced some permanent deformation due to strand slip, strand yielding and deck crushing. Its behavior on unloading more resembled a flexural failure and did not resemble a pure shear failure.

11.2.3 Comments on Experimental Results

Specific discussion of experimental results was addressed at the cracking and ultimate conditions in Sections 11.3 and 11.4 respectively. Appendix L provides a complete listing of all moment-curvature and load-deflection diagrams for each test. Photos of girder all end-span tests can be seen in Appendix Q. Photos of all center-span tests can be seen in Appendix M. A spreadsheet encompassing the calculations to evaluate the girders' flexural performance can be seen in Appendix K. All percent difference calculations in the following sections are based on equation 11.1 below.

Percent Difference =
$$\left(\frac{Value_{Exp} - Value_{Pred}}{Value_{Pred}}\right)$$
100 (11.1)

11.3 Results at Cracking

Table 11.2 provides an overview of the predicted and experimental cracking moment for each girder test. Percent difference was calculated using equation 11.1.

Table 11.2 Cracking Moment Results

Test 1	Predicted M _{cr} (ft-kips)	Experimental M _{cr}	Percent Difference
#		M_{cr}	Difference
	(A king)		Difference
	(11-Kips)	(ft-kips)	
G1A-East	1052	1224	16.4%
G1A-West	1005	1109	10.4%
G1A-Center	1065	1064	-0.2%
G1B-East	1019	1133	11.2%
G1B-West	1004	1109	10.4%
G1B-Center	1029	1188	15.5%
G1C-East	999	1155	15.6%
G1C-West	971	1145	17.9%
G1C-Center	1035	1142	10.4%
G2A-East	1165	1220	4.7%
G2A-West	1136	1176	3.5%
G2A-Center	1189	1124	-5.5%
G2B-East	1177	1110	-5.6%
G2B-West	1133	1124	-0.9%
G2B-Center	1200	1210	0.8%
G2C-East	1059	1079	1.9%
G2C-West	1025	1094	6.8%
G2C-Center	1082	1219	12.6%

G1 Average	1020	1141	12.0%
G2 Average	1130	1151	2.0%
G1 Std Dev			5.4%
G2 Std Dev			5.8%

The experimental cracking moment was determined by examining the experimental load vs. deflection plot identifying the point at which a slope change

occurred. In every case, the cracking load indicated on the load vs. deflection plot matched the load recorded where visible flexural cracking first occurred.

Based on the use of equation 11.2, the predicted cracking moment for the G2 series girders was 10.8 percent greater than for G1 girders.

$$f_{cr-\text{Pr}ed} = 7.5\lambda\sqrt{f_c'} \tag{11.2}$$

Since G2 girders had a higher concrete compressive strength than G1 girders, this was logical. Experimentally, the G1 and G2 series average cracking moments were about identical. It is important to note that the predicted cracking moments appeared to become less conservative as compressive strength increased.

Table 11.3 provides an overview of the predicted cracking stress, $f_{cr-Pred}$, based on equation 11.2, the rupture stress, f_r , recorded during testing of beam specimens per ASTM C-78⁸² at an age of 56 days, and the experimental cracking stress, f_{cr-Exp} .

The trend seen in Table 11.3 is the same seen in 11.2 for the cracking moment, except more dramatic. The experimental cracking stress, f_{cr-Exp} , was calculated using equation 11.3 below.

$$f_{cr-Exp} = \frac{M_{cr} - M_{DL}}{S_{bot-c}} + \frac{M_{DL}}{S_{bot-nc}} - \frac{F_{se}}{A_{nc}} + \frac{F_{se}e}{S_{bot-nc}}$$
(11.3)

Table 11.3 Cracking Stress Results

Test	Predicted	ASTM	Experimental	Percent	Percent	Normalized
#		C-78	_	Difference	Difference	Cracking
	f _{cr-Pred}	\mathbf{f}_{r}	f_{cr-Exp}	Exp. Vs.	Exp. vs.	Stress
	(psi)	(psi)	(psi)	Pred.	ASTM	Factor, ξ _{cr}
G1A-East	624	1010	985	57.8%	-2.5%	11.83
G1A-West	624	1010	844	35.3%	-16.4%	10.14
G1A-Center	624	1010	621	-0.5%	-38.6%	7.46
G1B-East	624	1010	863	38.3%	-14.6%	10.37
G1B-West	624	1010	846	35.6%	-16.2%	10.17
G1B-Center	624	1010	964	54.5%	-4.5%	11.59
G1C-East	602	796	930	54.5%	16.8%	11.58
G1C-West	602	796	968	60.8%	21.6%	12.06
G1C-Center	602	796	825	37.1%	3.6%	10.28
G2A-East	668	1204	785	17.5%	-34.8%	8.81
G2A-West	668	1204	752	12.6%	-37.6%	8.44
G2A-Center	668	1204	999	49.6%	-17.0%	11.22
G2B-East	668	1204	528	-20.9%	-56.1%	5.93
G2B-West	668	1204	647	-3.1%	-46.3%	7.27
G2B-Center	668	1204	687	2.9%	-42.9%	7.72
G2C-East	654	905	697	6.6%	-22.9%	8.00
G2C-West	654	905	804	22.9%	-11.2%	9.22
G2C-Center	654	905	946	44.6%	4.5%	10.84
G1 Average	617	939	872	41.5%	-5.6%	10.61
G2 Average	663	1104	761	14.7%	-29.4%	8.61
G1 Std Dev						1.42
G2 Std Dev						1.67

Since all the girders were of approximately the same dimension, the only factors that affected the cracking stress were the experimental cracking moment and the effective prestressing force, F_{se} . In the G2 series girders, the modulus of elasticity was higher at release in comparison to the G1 series girders meaning less initial losses (ES). In addition, the denser matrix of the G2 mix design allowed less time dependent losses (CR and SH). Both factors meant a higher effective prestressing force at time of testing. A

higher prestressing force meant more of the cracking moment was required to overcome the effect of prestress thus the cracking stress was less. On average, the experimental cracking stress values for the G1 and G2 series tests were greater than the predicted values. The trend indicates that predicted cracking strengths become less conservative as the compressive strength increases.

The normalized rupture stress factor, ξ_{cr} , was calculated as below where λ was the lightweight concrete factor equal to 0.85 for SLWC:

$$\xi_{cr} = \frac{f_{cr-Exp}}{\lambda \sqrt{f_c'}} \tag{11.4}$$

As long as the factor ξ_{cr} was greater than 6, the predicted value was conservative. On average, both the G1 and G2 series were conservative. However, girder test G2B-East had a normalized value less than 6. There were no common trends between the girders that explained the lower cracking stress values. Figure 11.15 provides a plot of the normalized cracking stress factor, ξ_{cr} , vs. concrete compressive strength, f_c , showing the downward trend as compressive strength increased. Also plotted on Figure 11.15 for comparison were the normalized values based on modulus of rupture test results again showing the modulus of rupture, f_r , to be a poor predictor of cracking stress.

Comparison of the experimental cracking strengths with modulus of rupture strengths, f_r , determined with the ASTM⁸² beam test showed it to be an unconservative

predictor of cracking strength. This finding also was reported by Dill for high-strength normal weight concrete.⁸⁴




Figure 11.15 Normalized Rupture Strength Factor, ξ_{cr} vs. Compressive Strength, f_c'

Table 11.4 provides an overview of predicted and experimental deflections at cracking. The experimental deflections at cracking were from 16 to 145 percent greater for the G1 series girders and 17 to 96 percent greater for the G2 series girders. Some of this error was due to material properties of the girders. Despite having made numerous specimens, localized variations in the concrete could impact the cracking deflection. In addition, minor errors in identifying the cracking deflection may have occurred. While

exact visual determination of initial flexural cracking was sometimes difficult, close examination of data acquisition system output allowed its identification with good accuracy. Since the gage length of the LVDTs measuring strain at the bottom of the girder spanned 24 inches, initial flexural cracking almost always occurred somewhere in that region. When flexural cracking was first visually noted, the load at which it occurred was noted. In all cases but one, the visually noted cracking load matched the cracking load identified from the test output.

Table 11.4 Deflection Results at Cracking

Test	Predicted	Experimental	Percent
#	Deflection	Deflection	Difference
	$\delta_{ m cr}$	$\delta_{ m cr}$	Predicted vs. Exp.
	(inches)	(inches)	,
G1A-East	0.154	0.270	75.3%
G1A-West	0.267	0.330	23.6%
G1A-Center	0.106	0.260	145.3%
G1B-East	0.208	0.312	50.0%
G1B-West	0.185	0.250	35.1%
G1B-Center	0.123	0.230	87.0%
G1C-East	0.194	0.352	81.4%
G1C-West	0.273	0.441	61.5%
G1C-Center	0.149	0.173	16.1%
G2A-East	0.168	0.303	80.4%
G2A-West	0.294	0.344	17.0%
G2A-Center	0.115	0.220	91.3%
G2B-East	0.170	0.216	27.1%
G2B-West	0.265	0.312	17.7%
G2B-Center	0.134	0.210	56.7%
G2C-East	0.194	0.255	31.4%
G2C-West	0.279	0.357	28.0%
G2C-Center	0.148	0.290	95.9%

G1 Average	1
G2 Average	
G1 Std Dev	
G2 Std Dev	

63.9%
49.5%
39.6%
32.1%

11.4 Results at Ultimate

Table 11.5 provides an overview of the ultimate moment predicted by the AASHTO⁴⁰ technique utilizing the rectangular stress block, the ultimate moment predicted by a cracked section analysis using a Todeschini⁹¹ stress block, and the experimental ultimate moment.

Table 11.5 Moment Results at Ultimate

Test	Predicted	Predicted	Exp.	Percent	Percent
#	$\mathbf{M}_{ ext{ult}}$	$ m M_{ult}$	$M_{\rm ult}$	Difference	Difference
	AASHTO ⁴⁰	Todeschini ⁹¹		Exp. vs.	Exp. vs.
	(ft-kips)	(ft-kips)	(ft-kips)	AASHTO ⁴⁰	Todeschini ⁹¹
G1A-East	1719	1721	1836	6.8%	6.7%
G1A-West	1704 -	1707	1844	8.2%	8.0%
G1A-Center *	1711	1713	1671	-2.3%	-2.5%
G1B-East *	1716	1717	1578	-8.0%	-8.1%
G1B-West	1691	1692	1840	8.9%	8.8%
G1B-Center *	1687	1689	1774	5.2%	5.1%
G1C-East *	1705	1705	1796	5.3%	5.3%
G1C-West	1710	1710	1828	6.9%	6.9%
G1C-Center	1726	1726	1898	10.0%	10.0%
G2A-East	1693	1705	1855	9.6%	8.8%
G2A-West	1711	1717	1855	8.4%	8.0%
G2A-Center *	1707	1714	1657	-3.0%	-3.4%
G2B-East	1707	1718	1799	5.4%	4.7%
G2B-West	1699	1707	1840	8.3%	7.8%
G2B-Center *	1727	1733	1869	8.2%	7.8%
G2C-East	1708	1713	1870	9.5%	9.2%
G2C-West	1679	1688	1793	6.8%	6.2%
G2C-Center	1716	1720	1885	9.8%	9.6%

G1 Average	8.16	8.06
G2 Average	8.25	7.75
G1 Std Dev	1.35	1.37
G2 Std Dev	1.63	1.75

^{*} Failed predominantly in shear. Not included in average or standard deviation.

As noted in Table 11.5, ultimate moment results for girders failing predominantly in shear were not included in the statistical values. On average, the two techniques produced very similar results. The Todeschini⁹¹ stress block provided very slightly closer results. Both techniques produced conservative predictions of ultimate moment.

Table 11.6 provides an overview of deflection at ultimate.

Table 11.6 Deflections at Ultimate

Test	Predicted	Experimental	Percent
#	Deflection	Deflection	Difference
	δ_{ult}	δ_{ult}	Exp. vs.
	(inches)	(inches)	Predicted
G1A-East	1.394	1.245	-10.7%
G1A-West	2.067	2.416	16.9%
G1A-Center	0.900	0.625	-30.6%
G1B-East	1.508	1.350	-10.5%
G1B-West	1.331	1.539	15.6%
G1B-Center	1.067	1.122	5.2%
G1C-East	1.492	1.534	2.8%
G1C-West	2.332	2.270	-2.7%
G1C-Center	1.472	1.550	5.3%
G2A-East	1.262	1.428	13.2%
G2A-West	1.902	2.566	34.9%
G2A-Center	0.821	0.799	-2.7%
G2B-East	1.283	1.205	-6.1%
G2B-West	1.584	2.060	30.1%
G2B-Center	0.954	0.982	2.9%
G2C-East	1.330	1.891	42.2%
G2C-West	2.065	2.208	6.9%
G2C-Center	1.373	2.170	58.0%

G1 Average	
G2 Average	
G1 Std Dev	
G2 Std Dev	

-1.0%
19.9%
14.7%
22.3%

On average, the G1 series girders deflected 1 percent less than predicted. The G2 girders deflected 19.9 percent more than predicted on average. The reason for this variation was how far the girders were pushed during testing. The G1 girders were tested first and were not pushed to as high of strain levels as the G2 girders. As the test program proceeded, there was an increasing effort to push the girders such that the total strain in the prestressing strands approached or exceeded 2 percent. Overall, the ultimate deflection predictions matched experimental values well.

11.5 Conclusions

The current prediction for cracking strength when examined for HSLC showed indications of becoming unconservative as concrete compressive strengths approached 11,000 psi. In some cases, the predicted cracking strengths exceeded the experimental values. The use of a lambda factor of 0.85 for HSLC made with slate aggregate produced conservative results on average for compressive strengths below 11,000 psi. More research is required to examine a potential tension strength ceiling for HSLC and to examine the lambda factor for use with HSLC over 10,000 psi compressive strength.

The modulus of rupture test, ASTM C-78, did not accurately predict cracking strength of HSLC girders.

The current AASHTO procedure for ultimate moment calculation was conservative for HSLC girders with normal weight concrete decks having a compressive strength under 6,000 psi.

CHAPTER XII

SHEAR BEHAVIOR RESULTS AND DISCUSSION

12.1 Introduction

This chapter discusses shear behavior in the HSLC pretensioned girders. Based on experimentally measured values during testing, current code provisions were evaluated.

12.2 AASHTO 1996 Standard Shear Design Approach

The following sections outline the process for calculating the strength of the concrete, V_c , and strength of the steel reinforcement, V_s , based on the 1996 AASHTO Standard Specification for Highway Bridges.⁴⁰

12.2.1 Concrete Strength, V_c

The concrete strength, V_c , is the lesser of the flexure shear strength, V_{ci} , and the web shear strength, V_{cw} . Based on the shear spans and characteristics of the girders in this research, the web shear strength, V_{cw} , was always the governing value. The calculation of both values is explained further in the following sections.

12.2.1.1 Flexure Shear Strength, Vci

The flexure shear strength was calculated using AASHTO⁴⁰ equation (9-27):

$$V_{ci} = 0.6\lambda \frac{\sqrt{f_c'}}{1000}b'd + V_d + \frac{V_i M_{cr}}{M_{max}} \ge 1.7\lambda \frac{\sqrt{f_c'}}{1000}b'd$$
 (12.1)

The value b' was taken as the minimum web thickness of the girder which was 6 inches for an AASHTO Type II. The code specifies that d, the distance from the topmost compression fiber to the centroid of the prestressing strands need not be less than 0.8*h. The value of d normally exceeded the minimum 0.8*h. V_i and M_{max} were the maximum moment and shear at the section in question. The lightweight concrete factor, λ , having a value of 0.85 was included in the equation based on the use of HSLC. The concrete strength f_c ' was listed in psi. Calculation of the cracking moment was accomplished with AASHTO equation (9-28):

$$M_{cr} = \frac{I}{Y_{c}} (6\lambda \frac{\sqrt{f_{c}^{\prime}}}{1000} + f_{pe} - f_{d})$$
 (12.2)

The composite section properties were used in calculating M_{cr} . The concrete strength, f_c , was based on cylinder tests at the time of girder testing.

12.2.1.2 Web Shear Strength, Vcw

The web shear strength was calculated using AASHTO⁴⁰ equation (9-29):

$$V_{cw} = (3.5\lambda \frac{\sqrt{f_c'}}{1000} + 0.3f_{pc})b'd + V_p$$
 (12.3)

In the girders tested, there were no draped strands thus V_p was zero. The value f_{pc} accounted for the effect of prestress and the dead load of the girder alone at the centroid of the composite section. It was calculated as shown in equation 12.4 below:

$$f_{pc} = \frac{F_{se}}{A_{nc}} - \frac{F_{se}e(y_{bot-c} - y_{bot-nc})}{I_{nc}} - \frac{M_{DL}(y_{bot-c} - y_{bot-nc})}{I_{nc}}$$
(12.4)

The effective prestressing force was reduced when the section being examined was inside a distance equal to the transfer length from the end of the girder. The procedure also accounted for the reduced effective prestressing force in calculating f_{pc} . The λ factor equal to 0.85 was included to account for the use of HSLC.

12.2.2 Transverse Steel Shear Strength, Vs

The transverse steel shear strength was calculated using AASHTO⁴⁰ equation (9-30):

$$V_{s} = \frac{A_{v} f_{y} d}{s} \le 8 \frac{\sqrt{f_{c}'}}{1000} b' d \tag{12.5}$$

For the girders tested, the shear area, A_v, was 0.4 in² for double # 4 bar stirrups. The value "s" was the spacing of the stirrups, which was 3.5 inches for the double density stirrups, 7" for single density stirrups and 24" for minimum stirrup spacing. The yield

strength of the stirrups was 62 ksi as determined experimentally. Refer to Appendix C for more information on the material properties of the shear reinforcement.

12.2.3 Nominal Shear Strength, Vn

The nominal shear strength was calculated as:

$$V_n = V_c + V_s \tag{12.6}$$

12.3 ACI Alternate Approach for Calculating V_{cw}

ACI 11.4.2.2 provides an alternate technique for calculating V_{cw} that was investigated in this evaluation.² The ACI Code states that V_{cw} shall be computed as the shear force corresponding to dead load plus live load that results in a principal tension stress of $4\lambda(f_c')^{1/2}$ at the centroidal axis of the member. In composite members, the principal tensile stress is computed using the cross section that resists live load. Lin and Burns⁵⁰ addressed this alternate technique and provided the following equations which come directly from the application of Mohr's circle:

$$V_{cw-Pred} = f_{t-Pred}^{"} \sqrt{1 + \frac{f_{pc}}{f_{t-Pred}^{"}}} bd_{p}$$
 (12.7)

The predicted diagonal tensile strength, f_{t-Pred}" was calculated using equation 12.8:

$$f_{t-\text{Pr}ed}^{"} = 4\lambda\sqrt{f_c^{'}} \tag{12.8}$$

The value of f_{pc} was calculated using equation 12.4 based on conditions at the midpoint of the shear span.

The experimental cracking load, V_{cw-Exp} was recorded when the first shear cracking occurred during the girder test. Based on V_{cw-Exp} , the experimental diagonal tensile strength, $f_{t}^{"}$ -Exp was calculated using equation 12.9.

$$f_{t-Exp}^{"} = \sqrt{\left(\frac{V_{cw-Exp}}{bd_p}\right)^2 + \left(\frac{f_{pc}}{2}\right)^2} - \frac{f_{pc}}{2}$$
(12.9)

The $f_{t-EXP}^{"}$ value was then normalized using equation 12.10.

$$\xi_t = \frac{f_{t-Exp}^*}{\lambda \sqrt{f_c^*}} \tag{12.10}$$

A normalized value, ξ_t , less than 4 was an indication that equation 12.8 provided an unconservative prediction of the tensile stress at which initial web shear cracking occurred.

12.4 1998 AASHTO LRFD Shear Design Approach

The following sections outline the process for calculating the shear strength using the 1998 AASHTO LRFD Specification for Highway Bridges. 92

12.4.1 Concrete Strength, Vc

The LRFD approach for strength calculation is much different than the Standard procedure. The first step was to calculate the effective shear depth, d_v, using equation 12.11.

$$d_{\nu} = d_{p} - \frac{a}{2} \tag{12.11}$$

The value "a" was the depth of the rectangular stress block required to balance the prestress force at the particular section of interest.

The effective web width, b_v , was taken as the web width of the AASHTO Type II girder, 6 inches.

The effective area of prestress, A_{pse} , was calculated by determining the effective number of strands on the flexural tension side of the member. The flexural tension side of the member indicated the bottom half of the composite member. If the distance "x" from the free end of the member to the girder section being evaluated was less than the experimental development length, the total number of bottom strands, 8, was multiplied by x/l_d . If the section being evaluated was greater than l_d from the free end of the member, the effective number of strands was the total number, 8. The effective number

of strands was then multiplied by the area of a prestressing strand, 0.2183 in^2 , to determine A_{pse} .

The shear stress on the concrete was calculated using AASHTO equation (5.8.3.4.2-1):

$$v = \frac{V_u - \phi V_p}{\phi b_v d_v} \tag{12.12}$$

Since there were no draped strands in these girders, V_p was zero. The resistance factor for shear, ϕ , was taken as 1.0 since the nominal stress was desired. The value v/f_c ' was then calculated.

In order to use the modified compression field theory from the AASHTO⁹² LRFD Specification, the angle of inclination of diagonal compressive stress, θ , was required. To determine θ , crack angles were measured at the mid-point of the shear span as listed in Table 12.1.

The strain in the tensile reinforcement on the flexural tension side, ε_x , was then calculated using AASHTO equation (5.8.3.4.2-2):

$$\varepsilon_{x} = \frac{\frac{M_{u}}{d_{v}} + 0.5N_{u} + 0.5V_{u} \cot \theta - A_{ps} f_{po}}{E_{s} A_{s} + E_{p} A_{ps}} \le 0.002$$
 (12.13)

Table 12.1 Measured Crack Angles

Test	Measured Crack Angle
#	(degrees CCW from Horizontal)
G1A-East	31.0
G1A-West	25.0
G1A-Center	25.0
G1B-East	32.0
G1B-West	38.0
G1B-Center	25.0
G1C-East	30.0
G1C-West	30.0
G1C-Center	25.0
G2A-East	38.0
G2A-West	34.0
G2A-Center	33.0
G2B-East	35.0
G2B-West	33.0
G2B-Center	26.0
G2C-East	27.0
G2C-West	30.0
G2C-Center	33.0

Since there was no non-prestressed flexural reinforcement in the test girders and no axial load, equation 12.13 simplified to equation 12.14 as below:

$$\varepsilon_{x} = \frac{\frac{M_{u}}{d_{v}} + 0.5V_{u}\cot\theta - A_{ps}f_{po}}{E_{p}A_{ps}} \le 0.002$$

$$(12.14)$$

The value f_{po} , the stress in the prestressing strand when the stress in the surrounding concrete is zero was conservatively taken as the effective prestress, f_{se} . A correction factor specified by AASHTO equation (5.8.3.4.2-3) was included in the event ε_x was

calculated as a negative number. Since the strain in the strand at effective prestress was 0.005 in/in at a minimum outside the transfer length region, the only point along the strand ε_x could ever approach a value less than 0.002 would be within approximately 12 inches from the free end of the girder.

Using the value v/f_c ' and ϵ_x , a β value was determined from AASHTO Figure 5.8.3.4.2-1. The concrete shear strength, V_c was calculated using AASHTO equation (5.8.3.3-3) below. The equation was modified to reflect the inclusion of the lightweight concrete factor, λ .

$$V_c = 0.0316\lambda\beta\sqrt{f_c'}b_\nu d_\nu \tag{12.15}$$

12.4.2 Transverse Steel Shear Strength, Vs

The strength of the shear reinforcing steel was calculated with AASHTO equation (C5.8.3.3-1):

$$V_s = \frac{A_v f_y d_v \cot \theta}{s} \tag{12.16}$$

The abbreviated version of the equation for V_s was used because the shear stirrups were placed vertically.

12.4.3 Nominal Shear Strength, V_n

The nominal shear strength of the girder was then calculated using AASHTO equations (5.8.3.3-1) and (5.8.3.3-2) combined below:

$$V_n = V_c + V_s \le 0.25 f_c b_v d_v \tag{12.17}$$

12.5 Variable Angle Truss Model

The variable angle truss model (VATM) was used as an analysis tool for two reasons. First, on the girder end tests where strand slip occurred, it was desired to determine the force in the bottom strands near the girder end. Knowing the force in the bottom strands, the bond stress could be estimated and compared to values calculated at transfer, and to values calculated for girders not experiencing strand slip.

The VATM assumes that the girder experiences shear and flexural failure simultaneously. The stirrups resist the entire shear force and are assumed to be at yield. The concrete is assumed to resist zero shear force. The model is addressed in *Prestressed Concrete Structures*, Michael P. Collins and Denis Mitchell.⁴⁸

12.5.1 Shear Force

Vult was equal to the support reaction at the support closest to the applied load.




Figure 12.1 Figure for Calculation of V_{ult}

 V_{ult} was calculated based on Figure 12.1 and equation 12.18.

$$V_{ult} = R_L = R_{L-self wt} + P_{ult} \frac{b}{L_1}$$
 (12.18)

12.5.2 Stirrup Force

The force in the shear stirrups, F_{stirrup}, was calculated using equation 12.19.

$$F_{stirrup} = A_{\nu} f_{y} \tag{12.19}$$

12.5.3 Stirrups Required to Carry Vult

The number of stirrups required, $\#_{\text{stirrups}}$, to carry V_{ult} was calculated with equation 12.18.

$$\#_{Stirrups} = \frac{V_{ult}}{F_{stirrup}} \tag{12.20}$$

The number of stirrups calculated determined the number of compression struts beginning at the applied load and carrying force to the intersection of stirrups with the centroid of the prestressing strands. In addition, the number of stirrups required indirectly determined the angle of the compression field. In general, the more stirrups required to carry V_{ult} , the shallower the compression field angle was to the horizontal. The same number of compression struts initiating at the applied load would also end at the support. The connecting pieces between the compression struts are the shear stirrups.

When configuring the VATM, the maximum angle a strut could make with the horizontal was 70 degrees and the minimum was 25 degrees. This limited the number of struts and stirrups that could carry shear force in the truss. It was possible that insufficient stirrups were available in the angle range from 25 to 70 degrees to carry V_{ult}. In this case, the predicted shear capacity of the girder could be limited by the VATM to a level well below that reached during testing. Girder test G1C-West was an example of this type of test. The VATM predicted a much lower shear capacity than the girder achieved. Figure 12.2 provides a diagram of the VATM for girder test G1C-West. The

critical point on the VATM was at a distance equal to the transfer length, l_t, from the girder free end as labeled in Figure 12.2.




Figure 12.2 Variable Angle Truss Model for Girder Test G1C-West

12.5.4 Internal Moment Arm

The internal moment arm, jd, was calculated using equation 12.21.

$$jd = d_p - \frac{a}{2} (12.21)$$

12.5.5 Force in Strands at Point of Loading

Since the VATM assumes the girder to be at flexural and shear failure simultaneously, the strands must be near failure. The values f_{su}^* and f_{se} were assumed as the stress in the bottom and top strands respectively. The total strand force at the point of loading was be $(f_{su}^* * 8 \text{ strands} + f_{se} * 2 \text{ strands}) * 0.2183 \text{ in}^2$. This strand force was assumed to act at the prestress force centroid labeled in Figure 12.2.

12.5.6 Strand Force Reduction

At each intersection of the strand force centroid with a stirrup, some of the strand force was removed and carried by truss action to the support. Equation 12.22 was used to determine the strand force reduction.

$$F_{\text{Re duction}} = \frac{x}{id} F_{\text{stirrup}} \tag{12.22}$$

The value x indicated the distance the stirrup was from the point of loading. As the distance x increases, the amount of reduction in the strands increases also. Figure 12.3 provides a typical plot of the strand force reduction from the point of loading to the support.




Figure 12.3 VATM Strand Force Reduction Plot for Girder Test G1C-West

12.5.7 Compression Field Crack Angle

The compression field crack angle is labeled in Figure 12.2. In the case of girder test G1C-West, the compression field crack angle was based on the angle of a "carryover strut." A carryover strut is one that neither begins at the point of loading nor ends at the support. If there is no carryover strut, the compression field crack angle will be the angle of the strut originating from the point of loading with smallest angle to the horizontal.

12.5.8 Strand Bond Stress

Strand bond stress was calculated based on the force remaining in the strand, F_{strand} , the length of embedment at the point, l_e , and the nominal circumference, πd_b , of the strand using equation 12.23 below.

$$f_{bond} = \frac{F_{strand}}{l_e \pi d_b} \tag{12.23}$$

A plot of bond stress from the point of loading to the support shows how the bond stress dramatically increases near the support. In the VATM, it was assumed that within one stirrup spacing of the support that only the bottom strands carried the strand force. A plot of bond stress can be seen in Figure 12.4. The bond stress over the transfer length due to the effective prestress was also plotted on the diagram for comparison purposes.

12.5.9 Stress in Compression Strut

Stress in the compression strut, f_{strut} , was calculated with equation 12.24 using V_{ult} .

$$f_{strut} = \frac{V_{ult}}{jd\cos\theta \, b_w \sin\theta} \le 0.85 \, \beta_1 \lambda \, f_c^{\prime} \tag{12.24}$$

The value β_1 was 0.6 based on the use of HSLC with a compressive strength over 6,000 psi. Compliance with this requirement as specified by ACI 318⁹¹ (2002) ensured a level of stress in the strut below which shear crushing would not occur.




Figure 12.4 Bond Stress Plot for Girder Test G1C-West

12.6 Experimental Measurement of Shear Behavior

In order to monitor and measure girder shear behavior, a large strain rosette made with LVDTs was placed on the web of each girder at the mid point of the shear span as pictured in Figure 12.5.




Figure 12.5 Strain Rosette Made with LVDTs on Girder Test G1C-West

The LVDTs oriented in the horizontal and vertical positions had gage lengths of approximately 10.5 inches. The LVDT at a 45-degree angle had a gage length of approximately 16.5 inches. To calculate strains in the three directions, the displacement of the LVDT was divided by its gage length. The gage lengths were carefully measured

for each girder test to ensure proper strain calculation. Having strain information for three distinct directions, and knowledge of the initial prestressing strain along the longitudinal axis of the girder, it was possible to calculate principal strains and directions using a simple strain transformation. Figure 12.6 below shows a typical plot of applied shear vs. principal strains.




Figure 12.6 Plot of Applied Shear vs. Principal Strains for Girder Test G1C-West

The point at which initial shear cracking occurred was where the two principal strain plots separated. This value matched very closely the value at which initial shear cracking was visually and audibly detected during the test. The plot shows initial shear cracking at an applied shear of 134.2 kips. The latter agreed with the applied load of 155 kips at which a shear crack occurred. In order for the LVDTs to measure the onset of shear

cracking, the initial crack had to pass through the rosette. Initial cracking did not pass through the rosette on one girder test.

Another useful aspect of the principal strain information was a plot of how the principal angles varied during the test. Figure 12.7 below provides a typical plot of the second principal strain (compression strain) angle, which indicated the angle of shear cracking through the LVDT rosette.




Figure 12.7 Second Principal Strain Direction (Cracking Angle) for Test G1C-West

The horizontal plateau from the point labeled "initial shear cracking" also was an indication of the applied shear at which cracking occurred. The angle indicated at the end of the plateau was most representative of the actual cracking angle on the girder; protractor measurements of the crack angle normally agreed within \pm 5 degrees with this plateau angle.

Figure 12.7 shows an increase in crack angle with increased applied load. As applied shear increased, the stirrups were required to pick-up more shear increasing the vertical force component and causing the angle of cracking to become greater. This trend was observed during testing. As the applied shear increased, new shear cracks formed at greater angles than those seen at initial cracking. In Figure 12.7, the indicated crack angle appeared to increase from about 32 degrees to 40 degrees as the applied shear increased.

12.7 Experimental Results

Discussion of experimental results was divided into the discussion of the initial shear cracking, ultimate shear capacity, and the variable angle truss model (VATM).

Percent difference was calculated using equation 11.1.

12.7.1 Initial Shear Cracking

Table 12.2 provides an overview of initial shear cracking. The predicted values were calculated at the midpoint of the shear span. The experimental value was the applied shear at which cracking was first recorded visually or electronically.

Examination of Table 12.2 showed that the AASHTO⁴⁰ Standard method of calculating concrete shear strength was conservative overall. In the case of girder tests G1C-Center and G2C-Center, the prediction was less than 3 percent unconservative. The AASHTO⁹² LRFD technique provided predictions of concrete strength that far underestimated their capacity. The ACI² alternate approach provided the closest prediction for V_c where the cracking shear was equated to the shear strength provided by

the concrete. Overall, the predicted V_c values were within about 6 percent of experimental values for both the G1 and G2 girder tests. Girder tests G1C-Center and G2C-Center showed the greatest difference from the ACI alternate predicted values, about 18 percent unconservative overall. Both the tests involved the minimum stirrup spacing of 24 inches.

Table 12.2 Overview of Initial Cracking Shears

Toot	37	37	37	17	Domoont	Domont	Domonut
Test	V _{c-EXP}	V_{cw}	V _{cw}	V _c	Percent	Percent	Percent
#	Exp.	AASHTO	ACI	AASHTO	Diff.	Diff.	Diff.
		Standard	Alternate	LRFD	Exp. vs.	Exp. vs.	Exp. vs.
	(kips)	(kips)	(kips)	(kips)	Standard	ACI Alt	LRFD
G1A-E *	145.0	104.1	124.0	24.7	39.4%	16.9%	488%
G1A-W	120.0	107.1	127.5	26.3	12.1%	-5.9%	356%
G1A-C*	134.0	98.5	118.0	23.5	36.1%	13.6%	470%
G1B-E *	140.0	105.5	125.5	24.7	32.7%	11.6%	466%
G1B-W	141.2	103.9	123.6	24.3	35.9%	14.2%	482%
G1B-C*	136.1	98.9	118.4	25.0	37.6%	14.9%	445%
G1C-E *	123.5	101.5	120.7	23.6	21.7%	2.3%	423%
G1C-W	134.2	104.0	123.3	23.6	29.0%	8.8%	468%
G1C-C	94.0	96.7	115.8	24.6	-2.8%	-18.8%	282%
G2A-E	178.6	114.4	135.7	26.0	56.1%	31.6%	588%
G2A-W	157.3	118.1	139.5	28.8	33.2%	12.8%	447%
G2A-C *	140.0	109.4	130.6	25.0	27.9%	7.2%	460%
G2B-E	163.1	114.6	136.1	25.2	42.3%	19.8%	549%
G2B-W	148.0	117.4	138.7	25.8	26.1%	6.7%	473%
G2B-C *	120.4	110.5	131.9	25.2	9.0%	-8.7%	377%
G2C-E	143.4	112.0	133.0	25.6	28.1%	7.8%	461%
G2C-W	122.4	113.4	134.2	27.1	8.0%	-8.8%	352%
G2C-C	107.0	107.3	128.1	31.3	-0.2%	-16.5%	241%

G1 Avg	129.8	102.2	121.9	24.5	26.8%	6.4%	431%
G2 Avg	142.2	113.0	134.2	26.7	25.6%	5.8%	439%
G1 Std Dev					14.1%	11.9%	68.9%
G2 Std Dev					17.8%	15.2%	104.1%

^{*} Girder failed in shear at ultimate as primary or secondary failure mode

12.7.2 Initial Shear Cracking Considering Stirrup Spacing

Figure 12.8, plots the concrete shear strength, $V_{c\text{-Exp}}$, vs. shear stirrup spacing. The trend lines indicated that $V_{c\text{-Exp}}$ appeared to increase with smaller stirrup spacing. Since the stirrups carried some load prior to concrete cracking, it was understandable that the apparent $V_{c\text{-Exp}}$ value would be higher with closer stirrup spacing. A very interesting aspect of Figure 12.8 was the convergence of the G1 and G2 trendlines at a stirrup spacing of 24 inches. The indication here was that little difference existed between V_c for the G1 and G2 girders. Based on the use of minimum stirrup spacing in these 6 center-span tests, it was likely that these data most truly reflected the V_c value of the girders.




Figure 12.8 Concrete Shear Strength, Vc vs. Stirrup Spacing

The implication of this finding was that an apparent ceiling exists which limits the tension strength of concrete. In order to investigate this possibility, a similar normalization was conducted on the shear results as was done on the cracking strength results at flexural cracking.

12.7.3 Normalized Diagonal Tension Strength Factor, ξ_t

Table 12.3 provides an overview of predicted diagonal tension strengths using the ACI^2 alternate approach, experimental diagonal tension strengths and the normalized diagonal tension factor, ξ_t .

Table 12.3 shows that ξ_t becomes unconservative at 3.70 (less than 4) on average for the G2 series girders with 24-inch stirrup spacing. Figure 12.9 depicts graphically the data from Table 12.3 and shows how the ACI alternate prediction technique for diagonal tensile strength produced some unconservative predictions. Any data points below the 4.0 line were unconservative.

Table 12.3 Normalized Diagonal Tension Strength Factors, $\boldsymbol{\xi_t}$

Test	Stirrup	ACI Alternate	Experimental	Normalized	
#	Spacing	Predicted Diagonal	Diagonal	Diagonal	
Tr	bpacing			Tension Strength	
		(Equation 12.8) f_{t-Exp} "		Factor	
	(inches)	f _{t-Pred} "	(psi)	ξt	
	(11101100)	(psi)	(1921)	21	
G1A-East	3.5	333	415	4.99	
G1A-West	7	333	304	3.66	
G1A-Center	24	333	396	4.76	
G1B-East	7	333	389	4.67	
G1B-West	3.5	333	402	4.83	
G1B-Center	24	333	404	4.85	
G1C-East	7	321	332	4.14	
G1C-West	7	321	363	4.52	
G1C-Center	24	321	238	2.96	
G2A-East	3.5	356	525	5.89	
G2A-West	7	356	424	4.77	
G2A-Center	24	356	393	4.41	
G2B-East	7	356	461	5.18	
G2B-West	3.5	356	392	4.40	
G2B-Center	24	356	312	3.51	
G2C-East	7	349	389	4.46	
G2C-West	7	349	304	3.49	
G2C-Center	24	349	268	3.17	
G1 Average	3.5		409	4.91	
G2 Average	3.5		459	5.15	

Gl Average	3.5
G2 Average	3.5
G1 Average	7
G2 Average	7
G1 Average	24
G2 Average	24

409	4.91
459	5.15
347	4.25
395	4.48
346	4.19
324	3.70




Figure 12.9 Normalized Diagonal Tension Strength Factor, ξ_t , vs. Stirrup Spacing

12.7.4 Ultimate Shear Capacity, Vu

Table 12.4 provides an overview of predicted ultimate shear capacity calculated by the AASHTO Standard method and the AASHTO LRFD method with the strength reduction factor, ϕ_s , of 1 and compares them to the experimental maximum shear values. Using the AASHTO Standard method, the stirrup yield strength was capped at 60 ksi as required by the code, and the results also recorded. Since the value of f_y was 62 ksi, there was an insignificant difference in predicted values.

Table 12.4 lists the results of all tests; Table 12.5 lists only the tests that exhibited a shear, shear-slip or shear-flexure failure. Both tables show the AASHTO⁴⁰ Standard technique produced conservative results overall. Limiting the yield strength to 60 ksi

caused the prediction to be slightly more conservative. The AASHTO⁹² LRFD technique produced more conservative results overall because the girders with 24-inch spacing were predicted to carry much less shear. The AASHTO LRFD penalized those girders with a very low concrete strength relative to the AASHTO Standard procedure.

Table 12.4 Predicted vs. Experimental V_u Values

Test	AASHTO	AASHTO	AASHTO	Exp.	Percent	Percent	Percent
#	Standard	Standard	LRFD		Diff.	Diff.	Diff.
	$f_y = 62 \text{ ksi}$	$f_y = 60 \text{ ksi}$	$f_y = 62 \text{ ksi}$		Exp	Exp	Exp
	$V_{\rm u}$	$V_{\rm u}$	V_u	V_{u}	vs	vs	vs
	(kips)	(kips)	(kips)	(kips)	Std 62	Std 60	LRFD
G1A-East *	379.7	370.8	473.5	362.8	-4.5%	-2.2%	-23.4%
G1A-West *	244.9	240.4	312.8	248.9	1.6%	3.5%	-20.4%
G1A-Center	138.7	137.4	103.8	258.0	86.0%	87.8%	148.5%
G1B-East	243.3	238.9	241.1	312.2	28.3%	30.7%	29.5%
G1B-West *	376.0	367.2	363.5	296.3	-21.2%	-19.3%	-18.5%
G1B-Center	138.6	137.3	104.3	234.1	68.9%	70.5%	124.5%
G1C-East	238.4	234.0	255.5	289.2	21.3%	23.6%	13.2%
G1C-West *	241.4	237.0	255.6	260.3	7.8%	9.8%	1.8%
G1C-Center *	137.1	135.8	105.5	202.2	47.5%	48.9%	91.6%
G2A-East *	388.3	379.4	365.4	366.5	-5.6%	-3.4%	0.3%
G2A-West *	255.4	251.0	223.8	249.7	-2.3%	-0.5%	11.6%
G2A-Center	149.5	148.2	82.3	255.9	71.2%	72.7%	211.0%
G2B-East *	252.5	248.0	215.8	355.4	40.8%	43.3%	64.7%
G2B-West *	391.3	382.4	432.0	296.3	-24.3%	-22.5%	-31.4%
G2B-Center	150.9	149.6	102.7	246.3	63.2%	64.6%	139.9%
G2C-East *	249.8	245.3	268.9	301.0	20.5%	22.7%	11.9%
G2C-West *	249.9	245.5	254.2	255.2	2.1%	4.0%	0.4%
G2C-Center *	147.6	144.1	89.2	200.3	35.7%	39.0%	124.7%

G1	Average
G2	Average

26.2%	28.1%	38.5%
22.4%	24.4%	59.2%

^{*} Tests which exhibited a flexural failure as the primary failure mode

Table 12.5 Predicted vs. Experimental V_u Values for Tests Failing in Shear

Test	AASHTO	AASHTO	AASHTO	Exp.	Percent	Percent	Percent
#	Standard	Standard	LRFD	_	Diff.	Diff.	Diff.
	$f_y = 62 \text{ ksi}$	$f_y = 60 \text{ ksi}$	$f_y = 62 \text{ ksi}$		Exp	Exp	Exp
	$V_{\rm u}$	$V_{\rm u}$	$V_{\rm u}$	V_{u}	vs	vs	vs
	(kips)	(kips)	(kips)	(kips)	Std 62	Std 60	LRFD
G1A-Center	138.7	137.4	103.8	258.0	86.0%	87.8%	148.5%
G1B-East	243.3	238.9	241.1	312.2	28.3%	30.7%	29.5%
G1B-Center	138.6	137.3	104.3	234.1	68.9%	70.5%	124.5%
G1C-East	238.4	234.0	255.5	289.2	21.3%	23.6%	13.2%
G2A-Center	149.5	148.2	82.3	255.9	71.2%	72.7%	211.0%
G2B-Center	150.9	149.6	102.7	246.3	63.2%	64.6%	139.9%

G1 Average		
G2 Average		
G1 Std Dev		
G2 Std Dev		

51.1%	53.2%	78.9%
67.2%	68.7%	175.5%
31.3%	31.0%	67.5%
5.7%	5.7%	50.3%

Figure 12.10 provides a plot of the data from Table 12.6 normalized by dividing the ultimate shear capacity, V_u , by the lightweight concrete factor, λ , and the square root of the compressive strength. Trendlines are depicted in Figure 12.9 for the AASHTO Standard⁴⁰ and LRFD⁹² Specifications. The figure shows how the AASHTO⁹² LRFD Specification becomes overly conservative at larger stirrup spacings where the contribution of V_s is low. At closer stirrup spacings, the figure shows how the results from the Standard and LRFD specifications provide very similar results.




Figure 12.10 Normalized Ultimate Shear Capacity, Vu, vs. Stirrup Spacing

12.7.5 Variable Angle Truss Model

The variable angle truss model was considered as a technique for estimating the shear capacity of HSLC girders. Table 12.6 provides an overview of the results for girders failing in shear. On average for all G1 and G2 girders failing in shear, the VATM under predicted shear capacity by a significant amount. Discounting the girders having 24-inch stirrup spacing, the predictions were about 35 percent conservative on average for the G1 girders. The girders with 24-inch stirrup spacing were penalized because the VATM does not consider concrete strength in determining shear capacity.

Table 12.6 Variable Angle Truss Model Results

Test	VATM	Experimental	Percent
#	V_n	V_n	Difference
			Experimental
	(kips)	(kips)	vs. VATM
G1A-Center	49.6	258.0	420.1%
G1B-East	223.2	312.2	39.9%
G1B-Center	49.6	234.1	372.0%
G1C-East	223.2	289.2	29.6%
G2A-Center	49.6	255.9	416.0%
G2B-Center	49.6	246.3	396.6%

G1	Average
G2	Average

215.4%
406.3%

12.7.6 Interface Shear

There was no recorded interface shear slip during any test.

12.8 Conclusions

The current AASHTO Standard specification provides a conservative prediction of concrete and ultimate shear capacity when shear steel capacity is capped at a yield strength of 60 ksi. The alternate design procedure listed in ACI-318 Section 11.4.2.2 for predicting shear strength produced some unconservative predictions for concrete compressive strengths over 10,000 psi. The method for predicting interface shear strength is conservative for HSLC.

The current AASHTO LRFD specification provides a conservative prediction of ultimate strength.

The VATM provides an overconservative prediction of shear capacity in HSLC girders.

CHAPTER XIII

DEVELOPMENT LENGTH RESULTS AND DISCUSSION

13.1 Introduction

This chapter presents the results of the development length tests, discusses the findings and compares the behavior to predicted values and that observed by others.

Based on experimentally measured transfer length values from this experimental program and others, current code provisions and equations previously suggested for predicting development length are evaluated. New equations for predicting development length are suggested based on these findings.

13.2 Definition

The development length is the sum of the "transfer length" and the "flexural bond length." The flexural bond length is the additional length of pretensioning strand beyond the transfer length over which bond is developed to allow the strand to reach the stress level f_{ps} at the nominal flexural strength of the member. Development length can also be defined as the minimum distance from the end of the member beyond which the application of a point load will result in a flexural failure. The transfer of force from the strand to the concrete that occurs along the development length is represented in Figure 13.1.




Figure 13.1 Diagram of Components of Development Length, $l_d^{\,2}$

The initial sloped portion of the diagram begins at a stress level of zero where bond begins and is assumed to increase linearly over a distance equal to the transfer length. The dashed line indicates the effective stress level due to prestressing only (f_{se}). The sloped portion of the diagram beyond the transfer length where the stress level increases gradually to the level f_{ps} is the flexural bond length. The shape of this diagram is codified in the AASHTO⁴⁰ and ACI² design specifications. For the purpose of this research, embedment length was defined as the distance from the girder end to the point load.

13.3 Importance of Development Length

Similar to transfer length, development length will not likely be the governing design criteria on a pretensioned bridge girder. However, the development length extends three to four times farther than transfer length from the end of the member and thus impacts the girder design over a longer region. At a distance less than the development length from the end of the member, the required cracking moment is less than that at a distance greater than the development length. This change in cracking moment is important not only as a flexural design consideration, but for shear capacity as well. Shear design within the development length region must consider the variation of prestressing force.

13.4 Current Code Provisions

Current code provisions for determining development length are similar in form.

AASHTO⁴⁰ Section 9.28.1 specifies the development length shall be determined using the Equation 13.1.

$$l_d = (f_{su}^* - \frac{2}{3} f_{se})D \tag{13.1}$$

where f_{su}^* is the average stress in the prestressing steel at ultimate load in ksi, f_{se} is the effective steel prestress after losses in ksi, and D is the nominal diameter of the prestressing steel in inches. Section 12.9.1 of the ACI 318 Code² specifies the development length shall be determined using the Equation 13.2.

$$l_d = (f_{ps} - \frac{2}{3} f_{se}) d_b \tag{13.2}$$

where f_{ps} is the stress in the prestressed reinforcement at nominal strength in ksi, f_{se} is the effective stress in the prestressed reinforcement after allowance for all prestress losses in ksi, and d_b is the strand diameter in inches. Both equations produce the same prediction for development length.

13.5 Measurement of Development Length

Each girder end of the six Type II girders was tested for development length producing 12 sets of data. Girder end designations were the same as used in transfer length testing. In order to determine development length, the position of the point load must be varied from girder to girder. The precise development length would be where the point load resulted in concurrent flexural, shear and bond failure. If the failure mode is purely flexural, the tested embedment length is greater than the development length. If the failure mode is shear and bond failure, the tested embedment length is less than the development length. Load positioning in several locations is necessary to bracket the actual development length.

For this research, the girder ends were designed to allow the application of point loads at embedment lengths calculated as varying percentages of the current code-specified development length. The original girder design assumed f_{ps} and f_{su}^* to be 270 ksi. The values of f_{se} were calculated using the standard AASHTO⁴⁰ technique as 165.02 ksi and 165.65 ksi for the G1 and G2 girders, respectively. Using these values and a strand diameter of 0.6 inches, the predicted development lengths were 96 inches and 95.7

inches for the G1 and G2 girders respectively. Table 13.1 shows the embedment lengths tested as a percentage of the estimated development length values and also shows the embedment lengths tested as a percentage of the development length calculated based on experimentally determined values of f_{ps} , f_{su}^* , and f_{se} , which are listed for each girder.

Table 13.1 Embedment Lengths Tested as Percentages of AASHTO⁴⁰ Predicted Values

Girder#	Stirrup	Embed.	Percent of	Experi	mental	l_d	Percent of ld
	Density	Length	l _d based on	Values		based	based on
	1X		estimated	f_{ps}, f_{su}^*	f_{se}	on	experimental
1	2X		values of			exp.	values of f _{ps} ,
Ì			$f_{ps}, f_{su}^*,$			values	f_{su} and f_{se}
		(in)	and f _{se}	(ksi)	(ksi)	(in)	
G1A-E	2X	67	70 %	265.1	153.7	97.6	69 %
G1A-W	1X	96	100 %	265.4	152.3	105.9	91 %
G1B-E	1X	67	70 %	227.6	151.2	106.3	63 %
G1B-W	2X	81	84 %	266.3	149.8	106.9	76 %
G1C-E	1X	81	84 %	263.0	149.0	107.2	76 %
G1C-W	1X	91	95 %	264.4	147.6	107.8	84 %
G2A-E	2X	67	70 %	266.3	175.8	96.5	70 %
G2A-W	1X	96	100 %	266.8	175.7	96.5	100 %
G2B-E	1X	67	70 %	265.0	176.2	96.3	70 %
G2B-W	2X	81	85 %	266.6	175.6	96.6	84 %
G2C-E	1X	81	85 %	267.7	159.3	103.1	79 %
G2C-W	1X	91	95 %	266.6	158.8	103.3	88 %

The value listed in the "Stirrups" column of Table 13.1 describes the amount of shear stirrups used in the girder end. A "1X" indicates the AASHTO specified stirrup spacing was used. A "2X" indicates that one half the AASHTO specified stirrup spacing was used or stated otherwise, twice the amount of stirrups. The amount of stirrups is referred to as the stirrup density. The AASHTO specified stirrup spacing is "Single"

Density." One half the AASHTO specified spacing is "Double Density." As explained in Chapter 8, varying the stirrup density was designed to determine its effect on strand slip.

By determining the type of failure on each of the girder end tests, the actual development length can be bracketed into a tight range of values.

13.6 Development Length Test Results

One failure criteria for development length testing focused on end slip of the prestressing strands. Slip for each of the eight bottom strands was measured continually throughout girder loading as described in Chapter 10. For each data acquisition reading, an average of the eight values was calculated. If the average value exceeded 0.01 inches during the test, this was assumed to be a "bond" or "slip" type of failure. Russell⁴⁴ and Dill⁸² also used this 0.01-inch slip to define a slip condition. This type of failure was often termed "shear-slip" because it was believed that the formation of a shear crack was the trigger for strand slip to begin. As discussed in Chapter 12, shear failure was always associated with slip at the girder ends. If the value did not exceed 0.01 inches, and girder end failed in flexure. For a failure to be considered a flexural failure, yielding of the prestressing strands and crushing of the deck had to occur.

CSS data were also collected after each load step. The CSS data were used to track the level of stress in the cross section and the location of cracks occurring in the first 48 inches of the girder. Perfect bond between the strand and concrete was assumed so that the concrete surface strains were equated to added strain in the strands. Table 13.2 provides the results of development length testing.

Table 13.2 Development Length Test Results

Test #	Stirrup	Strand	Average	Maximum	Maximum	Failure Mode
E=East	Density	Embedment	Strand	Strand	Deck	FL-Flexure
W=West	1X		Slip	Strain	Strain	SH-Shear
·	2X		at P _{max}	$\epsilon_{ m ps}$	Ecu	SL-Strand Slip
		(inches)	(inches)	(in/in)	(in/in)	
G1A-E	2X	67	0.0102	0.0158	0.0038	FL/SH-SL
G1A-W	1X	96	0.0000	0.0168	0.0042	FL
G1B-E	1X	67	0.7350	0.0078	0.0030	SH-SL
G1B-W	2X	81	0.0007	0.0190	0.0032	FL
G1C-E	1X	81	0.1988	0.0113	0.0032	SH-SL/FL
G1C-W	1X	91	0.0000	0.0140	0.0036	FL
G2A-E	2X	67	0.0033	0.0190	0.0036	FL
G2A-W	1X	96	0.0000	0.0204	0.0072	FL
G2B-E	1X	67	0.0065	0.0155	0.0045	FL
G2B-W	2X	81	0.0000	0.0199	0.0064	FL
G2C-E	1X	81	0.0041	0.0228	0.0045	FL
G2C-W	1X	91	0.0000	0.0198	0.0049	FL

13.6.1 Notes on Development Length Test Results

In girder tests G1A-East, G2A-East and G2B-East the flexural failure was accompanied by the deck splitting longitudinally down the middle as shown in Figure 13.2. The failure mode of Girder G1A-E is listed as FL/SH-SL. This indicates that the girder exhibited both flexural and shear-slip modes with the flexural mode occurring most predominantly. The failure mode of Girder G1C-E is listed as SH-SL/FL. This also indicates the girder exhibited both flexural and shear-slip modes, but the shear-slip mode was predominant. Girders listing just FL exhibited only flexural failure characteristics. Shear cracking occurred in all tests.



Figure 13.2 Longitudinal Cracking in Deck of Girder G1A-East

13.6.2 Development Length for G1 Girders

In order to evaluate the development length test results, strand end slip was graphed against embedment length. Since only selected embedment lengths were tested, it was not possible to exactly pinpoint the development length. It was possible, however, to identify points at which the failure transitioned from flexure to shear-slip. Figure 13.3 shows a bar graph for all G1 girders. The G1 1X bar graphs for the 67 and 81-inch

embedment length strand slip results were limited to 0.02 inches to better show the 2X bar graph results. The table below the bar graph shows the actual strand slip values.




Figure 13.3 G1 Series Girder Average Strand End Slip vs Embedment Length Values

Figure 13.3 shows the development length for G1 series girders with single density stirrups to be greater than 81 inches, but less than 91 inches. Since at an embedment length of 81 inches, the level of average end slip exceeds the 0.01-inch limit, the actual development length must be greater than 81 inches. At an embedment length of 91 inches, the level of average slip is less than 0.01 inches; thus the actual development length must be less than 91 inches. Without test data to fill the void between 81 and 91 inches, the conservative conclusion is that the development length for G1 series girders with single density stirrups was 91 inches.

A similar analysis for G1 series girders with double density stirrups indicates a development length greater than 67 inches but less than 81 inches. Again, without other data, a conservative conclusion is that the development length was 81 inches.

13.6.3 Development Length for G2 Girders

Figure 13.4 shows a bar graph for all G2 girder tests that compares average strand end slip with embedment length.




Figure 13.4 G2 Series Girder Average Strand End Slip vs Embedment Length Values

No G2 series girder test exceeded the end slip limit of 0.01 inches. Again, without additional test data to provide conclusive results for embedment lengths less than 67 inches, the conservative conclusion is that the development length for G2 series girders was 67 inches for both single and double density stirrups.

Table 13.3 provides a consolidated listing of development lengths.

Table 13.3 Experimentally Determined Development Lengths (inches)

Girder Series	Single Stirrup Density (1X)	Double Stirrup Density (2X)
G1	91	81
G2	67	67

13.7 Discussion of Results

13.7.1 Strand Stress Plots

This section addresses the level of strand stress determined based on CSS data. Each strand stress plot provides a depiction of the effective level of prestress over the entire embedment length, a plot of the strand stress over the first 48 inches of the girder when the strand was at its yield stress at the point of loading, and a plot of strand stress over the first 48 inches of the girder when the strand was at its maximum stress at the point of loading. A complete listing of photographs and strand stress graphs for each development length test is found in Appendix Q.

13.7.1.1 Strand Stress Plots When End Slip Occurred

If significant strand end slip over occurred during the test, it was impossible to accurately estimate what the level of stress was at a point along the strand based on CSS data. Strand end slip indicates there is a lack of adequate bond between the strand and concrete; near perfect bond is necessary for CSS to be a meaningful predictor of an increase in strand stress. A telling depiction of the effect of strand end slip can be seen in Figure 13.5 for test G1B-East, which shows the stress level in the strand to be 260 ksi

near the end of the girder and only 227 ksi at the point of load application. Extensive shear cracking in the transfer length region during test G1B-East initiated a strand slip failure resulting in strand end slip of 0.75 inches. The slip allowed the shear cracks to expand causing CSS values in that region to become extremely large. When used to predict strand strain, the values were found to be erroneous.




Figure 13.5 G1B-East Strand Stress vs. Distance from Girder end

13.7.1.2 Strand Stress Plots Where End Slip Was Less Than 0.01 Inches

In tests where strand slip was less than 0.01 inches, the CSS data appeared consistent and was used to determine the strain and the stress in the prestressing strand. Two trends became evident in examining these plots. First, in every case where strand slip was under 0.01 inches, there was an observed increase in strand stress in the transfer length region above the level of effective prestress. The effect was far more pronounced

with shorter embedment lengths. Second, in some cases, the length over which the largest amount of prestressing force was transferred appeared to be a distance somewhat less than the original transfer length discussed in Chapter 9. Figure 13.6 shows test G1A-East as an example of the strand stress increase in the transfer length region as well as the apparent reduction in transfer length. The embedment length on this test was only 67 inches. The "lone" triangle plots the maximum stress in the strand at the point of loading at the girder's ultimate load. This actual plot of strand stress differs significantly from the theoretical diagram shown in Figure 13.1.




Figure 13.6 G1A-East Strand Stress vs. Distance from Girder End

The variable angle truss model concept discussed in Chapter 12, Shear Behavior Results and Discussion, required a high strand force at the end of the girders with low shear span-to-depth ratios or low values of embedment length. The high stress values

developed in the transfer length zone for the girders with embedment lengths of 67 and 81 inches correspond to the compression strut requirement.

Figure 13.7 shows test G2C-West, which resulted in a much less pronounced example of stress increase in the transfer length region. In this example, the embedment length was 91 inches. The strand stress increased above the level of effective prestress, but not to the extent seen in Figure 13.6. The apparent transfer length remained about the same. The dip in the stress plot in Figure 13.7 was based on a lack of cracking in the region of the girder between 12 and 40 inches from the girder end. Cracking across the DEMEC embedment line caused large increases in the CSS values read.




Figure 13.7 G2C-West Strand Stress vs. Distance from Girder End

13.7.2 Strand Slip vs. Shear Cracking

A comparison was made between the onset of shear cracking and strand slip. The comparison was accomplished by examining the plot of applied shear vs. average end slip to determine the applied shear at which slip initiated and comparing that shear value to cracks on the girder. This comparison was made for all tests where the initiation of end slip could be determined. Figure 13.8 shows an applied shear vs. average strand end slip for test G1A-East; diagram has a well-defined slip initiation point. Several tests produced slip diagrams as in Figure 13.9 where it was not possible to determine an end slip initiation point. Based on this level of scatter in the data, any average slip value less than 0.0006 inches was considered zero slip. Figure 13.8 also shows an increase in strand end slip as the girder was unloaded. This phenomenon was seen in several tests and appeared to relate to a clamping effect on the prestressing strand. With the ultimate load on the girder, the end reactions were at a maximum and tended to clamp the strand. As the girder was unloaded, this clamping action was reduced. As the reaction decreased, additional slip occurred. This phenomenon only occurred in tests where slip was greater than 0.0006 inches. This unloading end slip was not included in the average maximum slip values recorded. Appendix R presents all applied shear vs. average strand slip diagrams.




Figure 13.8 Applied Shear vs. Strand Slip (G1A-East) Showing Slip Initiation Point





Figure 13.9 Applied Shear vs. Strand End Slip (G2C-West) Showing NO Slip Initiation

Figure 13.10 shows typical CSS data corresponding with applied shear levels, the location of shear cracks crossing the bottom strands, and the transfer length region. CSS data was plotted because it provided a measure of crack growth and allowed identification of the cracks that were increasing most significantly in size. Comparing crack locations with the resulting end slip allowed determination of the region where shear cracking most significantly impacted strand slip. Based on crack location, a comparison was made between strand slip in girders with single and double density shear reinforcement. Similar graphs for each girder test are listed in Appendix R.



Shear Crack Data										
Distance From End (Inches)	5.0	7.0	12.5	20.5	23.5	26.5	34.0	42.0	44.0	47.5
Applied Shear at Cracking (Kips)	169	315	242	339	315	355	339	339	291	355

Figure 13.10 G1A-East CSS and Shear Cracking vs. Distance from Girder End

13.7.2.1 Results for Single Stirrup Density (1X)

Table 13.4 Applied Shear vs. Strand Slip Results for Single Stirrup Density

Test #	Strand	Applied Shear	Shear Crack	Average Strand
	Embedment	At Crack	Distance From	Slip at Applied Shear
	l_e	Formation	Girder End	(Maximum Average
	(l_t)	(Max Applied Shear)		Slip Recorded)
	(Inches)	(Kips)	(Inches)	(Inches)
		156	8	No Slip
		191	10.75	0.0006
	67	208	12.5	0.0009
G1B-East		277	42	0.0138
	(25)	295	15, 19, 26, 34	0.0441
		(302)		0.2133
				(0.7350)
		147	9	No Slip
	81	243	17	0.0034
G1C-East	01	261	14, 20, 30	0.0126
GIC-East	(28)	277	39	0.0431
	(28)	(282)		0.0944
				(0.1988)
		177	4	No Slip
		225	10	0.0008
	67	299	37, 43.5	0.0020
G2B-East		322	13.5	0.0034
]	(13)	344	30	0.0053
		(349)		0.0060
				(0.0065)
		143	7	No Slip
	81	215	15	No Slip
G2C-East		281	27.5, 34, 42	No Slip
	(19)	(294)		0.0022
				(0.0041)

Table 13.4 shows the results of examining the onset of strand slip in the development length tests with single stirrup density. The "Applied Shear at Crack Formation" column specifies the level of applied shear at which a specific crack formed across the bottom layer of strands. In the same column is also listed the maximum

applied shear reached during the test. The "Shear Crack Distance From Girder End" column specifies the distance the crack across the lower strands is from the end of the girder. The "Average Strand Slip at Applied Shear" column lists the strand end slip at the listed applied shear value. Also listed in the column is the value of the maximum average strand slip recorded.

Table 13.4 shows that in every case, a shear crack passing through the level of the bottom strands within the transfer length region initiated or dramatically increased strand end slip. When examining the result of a crack, one must look to the resulting end slip on the following line. For example, during test G1B-East, the recorded slip at an applied shear of 208 kips was 0.0009 inches. The next recorded slip value was 0.0138 inches at an applied shear of 277 kips. This was a fifteen-fold increase in end slip initiated by the formation of the crack at 12.5 inches from the girder end. Similar results were evident when cracks formed at 15, 19, 26, and 34 inches from the girder end at an applied shear of 295 kips. The resulting slip of 0.2133 measured at the maximum applied shear of 302 kips showed a five-fold increase in end slip. Test G1C-East showed a four-fold increase in end slip after the formation of a crack at 17 inches from the girder end, and a three-fold increase after the formation of cracks at 14, 20 and 30 inches from the girder end. Tests G2B-East and G2C-East also showed similar increases in end slip after cracking occurred in or near the transfer length region. Although neither test resulted in a shear-slip failure, the impact of transfer length region cracking is evident.

13.7.2.2 Results for Double Stirrup Density (2X)

Table 13.5 Applied Shear vs. Strand Slip Results for Double Stirrup Density

Test #	Strand	Applied Shear	Shear Crack	Average Strand
	Embedment	At Crack	Distance From	Slip at Applied Shear
	l_e	Formation	Girder End	(Maximum Average
	(1_t)	(Max Applied Shear)		Slip Recorded)
	(Inches)	(Kips)	(Inches)	(Inches)
		169	5	No Slip
		242	12.5	$0.001\hat{0}$
	67	291	44	0.0018
G1A-East	67	315	7, 23.5	0.0025
GIA-East	(10.5)	339	20.5, 34, 42	0.0039
	(19.5)	355	26.5, 47.5	0.0072
}		(357)		0.0082
				(0.0102)
		243	5	No Slip
	81	266	7.5, 12	No Slip
G1B-West		286	29, 39.5, 42.5	No Slip
	(18.75)	(289)		No Slip
				(No Slip)
		245	7.5	No Slip
	67	318	34, 39.5	No Slip
G2A-East	07	343	14.5, 23	0.0007
0211 2001	(17.5)	355	11, 46	0.0017
	(17.6)	(361)		0.0030
				(0.0033)
		201	6	No Slip
GOD III	81	226	8	No Slip
G2B-West	44.5	251	10, 14, 45	No Slip
	(13)	279	18.5, 32, 41.5	No Slip
		(286)		(No Slip)

Table 13.5 provides the results for girder ends having double stirrup density. The order of listing in Table 13.5 compares directly with the order in Table 13.4: the concrete grade and embedment lengths match. Direct comparison shows that the resulting slips were much less than the single density stirrups. The only double density stirrup test that

underwent a shear-slip greater than 0.01 inches was G1A-East with a slip of 0.0134 inches. For the G1 series girders, doubling the stirrup density dramatically reduced end slip values. For the G2 series girders, the effect was much less pronounced; however, the increased density did reduce end slip.

13.7.2.3 Results for Other Single Stirrup Density Tests

It was not possible to perform an analysis of shear cracking vs. strand slip for girder tests G1A-West, G1C-West, G2A-West and G2C-West since no strand slip occurred.

13.7.3 Shear Crack Location

Shear cracking across the bottom strands within the transfer length region initiated large increases in strand end slip. Other researchers have reported this phenomenon. Despite several shear cracks in the transfer length region, tests G1B-West and G2B-West showed no slip because of the double stirrup density. Tests G1A-East and G2A-East showed slip, but at very small or almost acceptable levels. Russell reported that additional bond stresses can be developed beyond initial strand slip and that small slips are not always followed by complete anchorage failure. Russell also reported that closely spaced cracks were an indication of good bond and wide crack spacing indicated poor bond. Both of Russell's observations were confirmed in the present tests.

13.7.4 Effect of Concrete Grade

Concrete grade also played a significant role in determining development length. Table 13.3 clearly demonstrates a reduction in development length based on concrete grade alone. The G1 series girders had compressive strengths on average approximately 1500 psi less than the G2 series girders. The water cement ratios were approximately 0.29 for the G1 series girders and 0.23 for the G2 series girders. A significant difference between the two mix designs was the amount of silica fume. The G1 series girders had 2 percent silica fume by weight of the total cementitious materials, and the G2 series girders had 10 percent. Past researchers have stated that the addition of silica fume will significantly improve the tensile strength and bond of lightweight concrete to prestressing strand. 21,94,95 The results of the present research confirm this observation.

13.7.5 Bond Stress Examined with the Variable Angle Truss Model

The VATM was discussed in Chapter 12 as a technique for predicting girder shear capacity. Another use for the VATM was the evaluation of bond stress at the girder end, the calculation of which was addressed in Section 12.5.8. Figure 13.11 shows a typical plot of bond stress from girder test G1C-East, a shear failure. Table 13.6 provides an overview of bond stress predictions using the VATM for all girder end tests and compares them to strand slip that occurred during development length testing. The "Bond Stress at Ultimate-VATM" value was taken as the maximum bond stress value within the transfer length region as labeled in Figure 13.11. Appendix N provides strand force and bond stress plots for girder tests G1A-East, G1B-East, and G1C-East, those tests that resulted in development length failures due to excessive strand slip.




Figure 13.11 Bond Stress Plot Using VATM for Girder G1C-East

Only data from the girder-end tests was provided since strand slip and bond stress were not a problem in center-span tests. Table 13.6 shows that the VATM predicted higher bond stresses for those girder ends that underwent strand slip failures. Examining average VATM bond stress values, it was evident that the model was predicting higher bond stress values for the girder ends undergoing strand slip failures. For the G1 girders, the average bond stress from all tests was 2.55 ksi; the average bond stress for G1 girders not undergoing strand slip was 1.88 ksi. For the G2 girders, there was a wide scatter of bond stress predictions. Since no G2 girder failed due to strand slip, it was not possible to determine a bond stress above which slip would occur. It appeared the VATM was useful for verifying trends, but not for making predictions.

Table 13.6 VATM Bond Stress Prediction vs. Strand Slip Results

				· · · · · · · · · · · · · · · · · · ·
	Bond Stress	Bond Stress	Average	Status of
Test	At Transfer	At Ultimate	Maximum	Development
#		VATM	Strand Slip	Length
	(ksi)	(ksi)	(inches)	Test
G1A-East *	0.91	1.98	0.0102	FAIL
G1A-West	0.94	1.77	0.0000	PASS
G1B-East	0.70	3.92	0.7350	FAIL
G1B-West *	0.92	0.77	0.0007	PASS
G1C-East	0.62	2.84	0.1988	FAIL
G1C-West	0.80	2.10	0.0000	PASS
G2A-East *	1.16	2.02	0.0033	PASS
G2A-West	1.54	1.89	0.0000	PASS
G2B-East	1.57	4.02	0.0065	PASS
G2B-West *	1.56	0.92	0.0000	PASS
G2C-East	0.97	2.89	0.0041	PASS
G2C-West	1.02	2.28	0.0000	PASS

G1 Average All Tests	0.82	2.23
G2 Average All Tests	1.30	2.34
G1 Average Passing Tests		1.55
G2 Average Passing Tests		2.34

^{*} Indicates Double Stirrup Density

13.8 Comparison of Results with Code Provisions and Proposed Equations

This section compares the development length results from this research with development lengths predicted by code specified provisions and with predictive equations proposed by other researchers. The goal of these comparisons was to determine if the code equations were adequate for design of slate HSLC girders and which variables provided the best prediction of development length. For comparison purposes, the twelve

development length values found from this HSLC research were evaluated along with eight values from a previous normal weight HPC study by Dill⁸⁴ to determine what differences, if any, existed between HSLC and HPC. All development length tests used 0.6-inch diameter prestressing strand.

13.8.1 Material Properties and Prestressing Strand Stresses

Table 13.7 lists material properties and prestressing strand stresses for the twenty development length tests. Included are concrete strengths at release, f_{ci} , and at time of testing, f_{c} ; strand stress values at time of prestressing, f_{pt} , just after strand release, f_{si} , just prior to girder testing, f_{se} , and at ultimate load, f_{ps} . Accelerated cure strengths were used for f_{ci} ' (24-hour) and for f_{c} ' (time of testing). Based on the evaluation of transfer length data, the accelerated cure strengths provided more consistent data. Strand load cells were used to measure strand stresses at the time of tensioning. Strand strain measurements after release and prior to testing were done with a VWSG. Strand strain at ultimate load was determined by measuring CSS with an LVDT, adding that strain to the strain due to effective prestress, and converting the total strand strain to a stress using the strand's stress-strain curve. Again, based on the evaluation of transfer length data, it was found that VWSG data provided a good estimate of strand stress values. Work by Reutlinger³⁷ used VWSG data for strand stress calculation; the use of VWSG data from this research helped maintain consistency for this evaluation.

Table 13.7 Concrete Strengths and Prestressing Levels

Girder	Develop-	f _{ci}	f _c '	f_{pt}	f_{si}	f_{se}	f_{ps}
#	ment	-01	Prior	Before	After	Prior	at
	Length		to	Release	Release	To Testing	Ultimate
	J		Testing		VWSG	vwsg	Load
							CSS
	(Inches)	(psi)	(psi)	(ksi)	(ksi)	(ksi)	(ksi)
G1A-E	81	7465	9580	179	162	154	266
G1A-W	91	7465	9580	179	162	152	266
G1B-E	91	7465	9580	179	161	151	266
G1B-W	81	7465	9580	179	161	150	266
G1C-E	91	6315	8911	179	162	149	266
G1C-W	91	6315	8911	179	162	148	266
G2A-E	67	9640	10975	191	179	176	266
G2A-W	67	9640	10975	191	179	176	266
G2B-E	67	9640	10975	191	179	176	266
G2B-W	67	9640	10975	191	179	176	266
G2C-E	67	8261	10523	179	165	159	266
G2C-W	67	8261	10523	179	165	159	266
G2A-S*	80	14989	16770	191	178	170	275
G2A-N*	80	12379	13430	191	178	170	275
G2B-S*	80	12379	13430	191	177	169	275
G2B-N*	80	11721	12716	191	177	169	275
G4A-S*	80	14675	16418	191	179	171	275
G4A-N*	80	14395	16105	191	179	171	275
G4B-S*	80	14395	16105	191	179	170	275
G4B-N*	80	14610	16345	191	179	170	275

^{*} Tests done by Reutlinger³⁷

13.8.2 Code and Suggested Development Length Equations

Development lengths were predicted using 12 different techniques. Table 13.8 provides an overview of the equations examined. The equation number listed refers to the discussion of the equation in Chapter 2, Background Review.

Table 13.8 Summary of Development Length Equations

Source / Author of Equation	Development Length, l _d	Equation Number
AASHTO ⁴⁰ / ACI ²	$(f_{ps} - \frac{2}{3}f_{se})d_b$	2.16
Barnes, Burns and Kreger ⁵⁵	$1.25 \left(\frac{f_{pl}}{\sqrt{f'_{cl}}} + (f_{ps} - f_{pe}) \right) d_b$	2.27
Buckner ⁴⁶	$f_{si}\frac{d_b}{3} + \lambda \left(f_{su} - f_{se}\right)d_b$	2.23
Deatherage et al. 43	$f_{si} \frac{d_b}{3} + 1.5(f_{su} - f_{se}) d_b$	2.20
Lane 95% ⁴⁷	$\left(\frac{4f_{pt}d_b}{f_c'} - 5\right) + \left(\frac{6.4(f_{su} - f_{se})d_b}{f_c'} + 15\right)$	2.26
Lane 95% ⁴⁷ (10 ksi limit on f _c ')	$\left[\frac{4f_{pt}d_b}{f_c} - 5 + \frac{6.4(f_{su} - f_{se})d_b}{f_c} + 15 \right]$	2.26
Lane Mean ⁴⁷	$\left \left(\frac{4f_{pt}d_b}{f_c'} - 21 \right) + \left(\frac{6.4(f_{su} - f_{se})d_b}{f_c'} + 26 \right) \right $	2.25
Lane Mean ⁴⁷ (10 ksi limit on f _c ')	$\left \left(\frac{4f_{pt}d_b}{f_c'} - 21 \right) + \left(\frac{6.4(f_{su} - f_{se})d_b}{f_c'} + 26 \right) \right $	2.25
Martin and Scott ⁴¹	$(f_{ps} - \frac{135}{d_b^{1/6}}) \frac{d_b}{0.39}$	2.18
Mitchell et al. ⁴⁵	$0.33 f_{si} d_b \sqrt{\frac{3}{f'_{ci}}} + (f_{su} - f_{se}) d_b \sqrt{\frac{4.5}{f'_{c}}}$	2.22
Zia and Mostafa ⁴²	$(1.5\frac{f_{si}}{f_{ci}}d_b - 4.6) + 1.25(f_{su} - f_{se})d_b$	2.19

- d_b Prestressing strand diameter
- f_{pt} Stress in prestressing strand prior to release
- f_{si} Stress in prestressing strand immediately after release (f_{pt} -ES)
- f_{se} Stress in prestressing strand after all losses (f_{pt} -ES-CR-SH)
- f_{pe} Same as f_{se}
- f_{ps} Stress in prestressing strand at member nominal strength
- f_{su} Ultimate stress of prestressing strand

ES Prestress losses due to elastic shortening

CR Prestress losses due to creep

SH Prestress losses due to shrinkage

f_{ci} Concrete compressive strength at release

f_c' Concrete compressive strength at time of testing

M_n Nominal moment capacity of a member

M_{cr} Cracking moment capacity of a member

I_t Transformed moment of inertia of a member

 λ 1.0 \leq [λ = (0.6+40 ϵ_{ps})] \leq 2.0

In order to compare the experimentally measured development length values with code and suggested equation results, the following relationship was used to determine the average difference between equation and experimental results:

Average Difference =
$$\frac{l_{d(Equation)} - l_{d(Experimental)}}{l_{d(Equation)}}$$
(13.3)

By performing the difference comparison in this manner, the code or suggested equation served as the accepted value. If the experimental development length is less than that predicted, the ratio is positive, indicating a conservative prediction.

13.8.3 Results of Experimental and Predicted Results

Table 13.9 compares predicted and experimental development lengths.

Table 13.9 Overview of Development Length Prediction Results for HSLC

		Overall Results				
Equation	Equation	Avg	Max	Max		
Source	Equation	Diff	Over	Under		
		(%)	(%)	(%)		
AASHTO ⁴⁰ /ACI ²	$(f_{ps}-\tfrac{2}{3}f_{se})d_b$	19%	30%	8%		
Barnes, Burns, Kreger ⁵⁵	$1.25 \left(\frac{f_{pt}}{\sqrt{f_{ci}'}} + (f_{ps} - f_{pe}) \right) d_b$	37%	47%	31%		
Buckner ⁴⁶	$f_{si}\frac{d_b}{3} + \lambda \left(f_{su} - f_{se}\right)d_b$	42%	54%	18%		
Deatherage et al. ⁴³	$f_{si} \frac{d_b}{3} + 1.5(f_{su} - f_{se}) d_b$	44%	54%	39%		
Lane 95% ⁴⁷	$\left(\frac{4f_{pt}d_b}{f_c'} - 5\right) + \left(\frac{6.4(f_{su} - f_{se})d_b}{f_c'} + 15\right)$	7%	30%	-28%		
Lane 95% ⁴⁷ (10 ksi limit on f _c ')	$\left(\frac{4f_{pt}d_b}{f_c'} - 5\right) + \left(\frac{6.4(f_{su} - f_{se})d_b}{f_c'} + 15\right)$	17%	32%	1%		
Lane Mean ⁴⁷	$\left(\frac{4f_{pt}d_b}{f_c'} - 21\right) + \left(\frac{6.4(f_{su} - f_{se})d_b}{f_c'} + 26\right)$	1%	27%	-39%		
Lane Mean ⁴⁷ (10 ksi limit on f _c ')	$\left[\left(\frac{4 f_{pt} d_b}{f_c'} - 21 \right) + \left(\frac{6.4 (f_{su} - f_{se}) d_b}{f_c'} + 26 \right) \right]$	12%	28%	-5%		
Martin and Scott ⁴¹	$(f_{ps} - \frac{135}{d_b^{1/6}}) \frac{d_b}{0.39}$	58%	63%	50%		
Mitchell et al. ⁴⁵	$0.33 f_{si} d_b \sqrt{\frac{3}{f'_{ci}}} + (f_{su} - f_{se}) d_b \sqrt{\frac{4.5}{f'_c}}$	- 27%	2%	-60%		
Zia and Mostafa ⁴²	$(1.5\frac{f_{si}}{f_{ci}^{'}}d_b - 4.6) + 1.25(f_{su} - f_{se})d_b$	6%	24%	-3%		

The average difference was calculated using equation 13.3 for the twelve lightweight girder tests and the eight normal weight HPC girder tests and is listed in the "Avg Diff" column. The "Max Over" column lists greatest positive percent difference between the

predicted and experimental value. The "Max Under" column lists the greatest negative percent difference between the predicted and experimental value.

13.8.3.1 Results of Analysis Based on Average Difference

Analysis of Table 13.9 showed that the equation by Zia and Mostafa produced the best overall prediction of development length. The Zia and Mostafa equation would be considered a "best-fit" equation where a "best-fit" equation was defined as the equation having the lowest average difference between experimental and predicted values as well as not having excessive overestimates or underestimates. Lane's Mean equation was within 1 percent on average, but had a maximum underestimate of –39 percent. Lane's 95 percent confidence equation was within 7 percent on average, but had a maximum underestimate of –28 percent. The AASHTO/ACI equation and equations by Lane (95 percent confidence with 10 ksi cap on f_c'), Barnes, Burns and Kreger, Buckner, Deatherage et al., and Martin and Scott did not provide as accurate a prediction, but always provided a conservative estimate of development length. Martin and Scott's equation as well as the equation by Deatherage et al. were overly conservative.

13.8.3.2 Results of Analysis Based on Maximum Underestimate

Analysis of Table 13.9 based on maximum underestimate showed that Lane's 95 percent confidence equation having a 10 ksi cap on f_c' to provide a good overall estimate of development length without being overconservative. This equation would be the best choice as a "design" equation. A "design" equation was defined as the equation having the lowest positive maximum underestimate value without being overly conservative.

The most favorable combination of these two values indicated the best "design" equation. Lane's 95 percent confidence equation having a 10 ksi cap on f_c' had a maximum underestimate value of 1 percent, which indicates the equation did not under predict any value, and had an average difference of 17 percent. The AASHTO/ACI equation produced a maximum underestimate of 8 percent again indicating the equation did not under predict any value, and had an average difference of 19 percent. The equation by Zia and Mostafa produced a maximum underestimate of –3 percent and had an average difference of 6 percent. Equations by Barnes, Burns and Kreger, Buckner, Martin and Scott, and Deatherage et al. never underestimated development lengths, but all had average differences in excess of 35 percent.

13.8.3.3 Evaluation of Top Five "Best-Fit" and "Design" Equations

Tables 13.10 and 13.11 show a listing of the top five equations in both the "best-fit" and "design" categories. From these tables it was possible to identify which variables used in the flexural bond portion of the equations were the best predictors. The variables d_b , f_{se} , f_{ps} , f_{su} and f_c appeared to be the most important in predicting development length.

Table 13.10 Review of Top Five "Best-Fit" Equations

	Best-Fit Equations					
Rank	Equation Source	Equation	Equation Variables			
			\mathbf{d}_{b}	f_{se}	f_{su}	f _c '
1	Zia and Mostafa ⁴²	$(1.5\frac{f_{si}}{f_{ci}}d_b - 4.6) + 1.25(f_{su} - f_{se})d_b$	X	X	X	
2	Lane Mean ⁴⁷ (10 ksi limit on f _c ')	$\left(\frac{4f_{pl}d_{b}}{f_{c}^{\prime}}-21\right)+\left(\frac{64(f_{su}-f_{se})d_{b}}{f_{c}^{\prime}}+26\right)$	X	X	X	Х
3	Lane Mean ⁴⁷	$\left(\frac{4f_{pt}d_b}{f_c'} - 21\right) + \left(\frac{6.4(f_{su} - f_{se})d_b}{f_c'} + 26\right)$	X	X	X	X
4	Lane 95% ⁴⁷	$\left(\frac{4f_{pt}d_{b}}{f_{c}'} - 5\right) + \left(\frac{6.4(f_{su} - f_{se})d_{b}}{f_{c}'} + 15\right)$	X	X	X	X
5	Lane 95% ⁴⁷ (10 ksi limit on f _c ')	$\left(\frac{4f_{pt}d_b}{f_c'} - 5\right) + \left(\frac{6.4(f_{su} - f_{se})d_b}{f_c'} + 15\right)$	X	X	X	X

Table 13.11 Review of Top Five "Design" Equations

p-2-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-		Design Equations					
Rank	Equation Source	Equation	Equation Variables				
			d _b	f _{se}	f_{ps}	f_{su}	fc'
1	Lane 95% ⁴⁷ (10 ksi limit on f _c ')	$\left(\frac{4f_{pl}d_{b}}{f_{c}^{\prime}}-5\right)+\left(\frac{64(f_{su}-f_{se})d_{b}}{f_{c}^{\prime}}+15\right)$	x	x		X	X
2	Zia and Mostafa ⁴²	$(1.5\frac{f_{si}}{f_{ci}}d_b - 4.6) + 1.25(f_{su} - f_{se})d_b$	X	X		X	
3	Lane Mean ⁴⁷ (10 ksi limit on f _c ')	$\left(\frac{4f_{pl}d_b}{f_c^{'}}-21\right) + \left(\frac{64(f_{su}-f_{se})d_b}{f_c^{'}}+26\right)$	X	X		X	X
4	AASHTO ⁴⁰ /ACI ²	$(f_{ps}-\tfrac{2}{3}f_{se})d_b$	X	X	X		
5	Barnes, Burns, Kreger ⁵⁵	$1.25 \left(\frac{f_{pl}}{\sqrt{f_{ci}'}} + (f_{ps} - f_{pe}) \right) d_b$	X	х	X		

13.9 Development of an Improved Development Length Equation

13.9.1 Determination of Equation Forms

Two equations were presented in Chapter 9 for predicting transfer length. One goal in determining a new development length equation was to incorporate the suggested transfer length relations. The two transfer length equations suggested were:

Best Fit Equation:

$$l_t = 50 d_b \sqrt{\frac{4000}{f_{ci}}} \tag{9.6}$$

Design Equation:

$$l_t = 50 d_b \sqrt{\frac{6000}{f_{ci}'}} \tag{9.7}$$

Based on equations suggested by other researchers in Tables 13.10 and 13.11, the following equation characteristics were thought to show promise:

- Equations including d_b
- Equations incorporating (f_{su}-f_{se})
- Equations incorporating (f_{ps}-f_{se})
- Equations incorporating f_c'
- Equations based on current ACI or AASHTO forms
- Equations incorporating the transfer length equation suggested in this research

Using these guidelines, numerous equation forms were evaluated using data from the 20 development length tests from this research and that by Dill.⁸⁴ Percent difference was calculated using the following expression as articulated in Chapter 9.

Average Difference =
$$\frac{l_{d(Equation)} - l_{d(Experimental)}}{l_{d(Experimental)}}$$
(9.3)

13.9.2 Results of Equation Analysis

Sixteen equation forms were investigated which incorporated the basic form of the suggested transfer length equations. Current code equation forms were modified to provide more accurate results. Concrete compressive strengths were based on accelerated curing during the first 24 hours. All strand stress values were based on VWSG data. Two equation forms emerged from the process that met the "best fit" and "design" equation criteria. The most promising "best fit" equation was:

$$\left(50\sqrt{\frac{2500}{f_{ci}^{'}}} + f_{ps} - f_{se}\right)d_b \tag{13.3}$$

The most promising "design" equation was:

$$\left(50\sqrt{\frac{5000}{f_{ci}'}} + f_{ps} - f_{se}\right)d_b \tag{13.4}$$

The "best-fit" equation has the smallest average difference and the most promising "design" equation has the smallest positive maximum under length prediction. The initial term of each equation is very similar to the equations for transfer length. Close comparison and evaluation indicates that the transfer length portion of the equation is apparently reduced in the development length equation. This further indicates the trends seen in the strand stress plots in Appendix Q and discussed in Section 13.7.1.2. As the girder was loaded, the strands tended to transfer more force in a region somewhat shorter than the specified transfer length. Tables 13.12 and 13.13 provide a comparison of the above equations with the top ranked "best fit" and "design" equations and current code equations. The comparison shows that the proposed equations provide better predictions of development, especially the design equation.

Table 13.12 Comparison of Proposed Best Fit Equation With Other Equations

Equation	Best Fit Equation	Overa	ıll Resu	ılts
Source		Avg Diff (%)	Max Over (%)	Max Under (%)
Proposed Equation	$\left(50\sqrt{\frac{2500}{f_{ci}^{'}}} + f_{ps} - f_{se}\right)d_b$	1%	21%	-6%
Zia and Mostafa ⁴²	$(1.5\frac{f_{si}}{f_{ci}}d_b - 4.6) + 1.25(f_{su} - f_{se})d_b$	6%	24%	-3%
AASHTO ⁴⁰ / ACI ²	$(f_{ps} - \frac{2}{3}f_{se})d_b$	19%	30%	8%

Table 13.13 Comparison of Proposed Design Equation With Other Equations

Equation	Design Equation	Overa	ıll Resu	lts
Source		Avg	Max	Max
	*	Diff	Over	Under
		(%)	(%)	(%)
Proposed Equation	$\left(50\sqrt{\frac{5000}{f_{ci}'}} + f_{ps} - f_{se}\right)d_b$	9%	31%	0%
Lane 95% ⁴⁷ (10 ksi limit on f _c ')	$\left(\frac{4f_{pt}d_b}{f_c'} - 5\right) + \left(\frac{6.4(f_{su} - f_{se})d_b}{f_c'} + 15\right)$	17%	32%	1%
AASHTO ⁴⁰ / ACI ²	$(f_{ps} - \frac{2}{3}f_{se})d_b$	19%	30%	8%

13.9.3 Proposed Equation Evaluation for use on HSLC

Table 13.14 provides a comparison of results for the proposed equation for HSLC and high strength normal weight concrete.

Table 13.14 Proposed Equation Evaluation for use on HSLC

	AASHTO ⁴⁰	Proposed Equation	Proposed Equation
	ACI ²	For	For
Basis of	Code	Design	Best Fit
Comparison	$(f_{ps}-\tfrac{2}{3}f_{se})d_b$	$\left(50\sqrt{\frac{5000}{f_{ci}'}} + f_{ps} - f_{se}\right) d_b$	$\left(50\sqrt{\frac{2500}{f_{ci}'}} + f_{ps} - f_{se}\right) d_b$
Avg Diff (HSLC)	19%	13%	4%
Max Over (HSLC)	30%	31%	21%
Max Under (HSLC)	8%	2%	-6%
Avg Diff (NWC)	18%	2%	-5%
Max Over (NWC)	18%	4%	-3%
Max Under (NWC)	17%	0%	-6%
Avg Diff (Overall)	19%	9%	1%
Max Over (Overall)	30%	31%	21%
Max Under (Overall)	8%	0%	-6%

Table 13.14 showed the AASHTO/ACI equation gave consistent and conservative values for both HSLC and NWC. There appears to be more scatter in the values for HSLC than for NWC. The proposed equation for design produced more conservative results for HSLC than for NWC. Since the proposed equation incorporates a term addressing initial concrete compressive strength, this could indicate the equation becomes less conservative as initial compressive strength increases. The initial compressive strengths for the NWC were about 5,000 psi higher than the HSLC strengths on average. Similar trends are seen for the proposed best-fit equation. Figure 13.12 provides a plot of the results in Table 13.14.




Figure 13.12 Comparison of Design and Best-Fit Equations to AASHTO Equation

To further verify the proposed equations, data from other researchers on HSLC would be useful. Yet no other development length data has been published for 0.6-inch prestressing strand used in lightweight concrete. Evaluation using data from other NWC and sand lightweight concrete tests would prove useful for comparison and further verification.

13.10 Conclusions

An evaluation of current code provisions using the twelve slate HSLC girder development length tests in this study and eight normal weight HPC girder tests from Dill⁸² showed the current AASHTO⁴⁰ and ACI² provisions to be conservative. The code equations overestimated development lengths by 19 percent for both slate HSLC and normal weight HPC and never underestimated them. Use of the current code provisions for design of development length for slate HSLC and 0.6-inch diameter strand was conservative. Based on the concrete strength range addressed in this research project, modification of the current code specifications for development length was not necessary for HSLC or for 0.6-inch diameter strands.

An evaluation of other suggested equations for predicting development length showed an equation by Zia and Mostafa⁴² to provide the best overall prediction of development length. Equations by Lane as identified in Table 13.10 also produced good overall predictions. The above equations were applicable to both slate HSLC and normal weight HPC with good results.

Based on an evaluation of 16 different equation forms, two new equations were suggested. The new equations for predicting development length based on "best-fit" and

"design" produced more accurate results than current code specifications and showed slight improvements over other suggested equation forms.

Test results showed conclusively that shear cracking in the transfer length region across the bottom strands did not induce significant strand slip if stirrup density was doubled over the current AASHTO⁴⁰ specified density in the region.

The addition of silica fume into the mix design at a 10% replacement rate by weight of cementitious materials substantially reduced development length. Although the silica fume increased compressive strength and early strength, the apparent major impact was the creation a much better bond between the prestressing strand and the concrete matrix.

There was no indication throughout this analysis that need existed to differentiate between slate HSLC and normal weight HPC. With regard to development length, for concrete compressive strengths over 8,000 psi, the prediction of development length was the same for both lightweight and normal weight concrete.

CHAPTER XIV

CONCLUSIONS AND RECOMMENDATIONS

14.1 Conclusions

Conclusions are presented in the following sections by topic.

14.1.1 Analytical Investigation

The use of HSLC has the potential to increase the length of simple span AASHTO Type IV and V sections up to four percent and Bulb-Tee sections up to three percent. However, AASHTO Type II and III sections do not benefit appreciably from the use of HSLC. The Modified Bulb-Tee section extended the length of a Standard Bulb-Tee by 10 feet using 8, 10 and 12 ksi HSLC or high-strength NWC. Bulb-Tee (Standard or Modified) sections provided longer spans at less weight for girders over 105 feet in length when compared to AASHTO sections. For spans between 125 feet and 155 feet, the use of HSLC can reduce the gross vehicle weight to less than 150 kips so that a superload permit is not required for transport of long span girders.

14.1.2 HSLC Mixes and Properties

HSLC mixes were developed in the laboratory for 8,000 psi and 10,000 psi using slate lightweight ½-in coarse aggregate and normal weight, natural sand. The dry unit weight of the concretes was approximately 117 and 119 pcf, respectively. A 12,000 psi

design strength mix could not be developed. The strengths of mixes using lightweight fine aggregate could not be controlled, therefore no recommended mix used lightweight fines.

The laboratory mixes were verified during field production. The field mixes yielded slightly higher strengths than found in the laboratory. Close monitoring of LWA moisture was required.

The HSLC, both 8,000 psi and 10,000 psi design strength continued to gain strength over the 100-day test period. Accelerated cured cylinders, which matched curing conditions of precast beams showed about 25 percent higher one-day strength than ASTM cured cylinders; at 56 days, the ASTM cured cylinders were about 4% stronger than the accelerated cured cylinders. Equation 7.4 was developed and provides a better estimate of the modulus of elasticity for slate HSLC than previous relations for normal strength concretes.

14.1.3 Transfer Length

An evaluation of current code provisions using the 12 HSLC transfer lengths in this research and 8 normal weight HPC transfer lengths from Reutlinger⁸⁴ showed the current AASHTO⁴⁰ and ACI² equations to be conservative. The AASHTO equation overestimated transfer lengths by 42% on average and never underestimated transfer lengths. The ACI equation using VWSG data to determine prestressing strand stress also overestimated transfer lengths by 46% and never underestimated transfer lengths. Use of either the AASHTO or ACI equations to predict transfer length for slate HSLC was conservative. Based on the concrete strength range addressed in this research project,

modification of the current code specifications for transfer lengths was not necessary for slate HSLC.

An evaluation of other suggested equations for predicting transfer length showed an equation by Mitchell et al. 45 to provide the best overall prediction of transfer length. Equations by Buckner 46 and Deatherage et al. 43 also produced good overall predictions. The above equations were applicable to both slate HSLC and normal weight HPC with good results.

An evaluation of the applicability of initial concrete compressive strength, f_{ci} , and initial modulus of elasticity, E_{ci} , and 32 possible equation forms showed that d_b and f_{ci} were the best parameters for predicting transfer length.

There was no indication throughout this analysis that a need existed to differentiate between slate HSLC and normal weight HPC with regard to transfer length. For initial concrete strengths, f_{ci}', over 6,000 psi, the prediction of transfer length was the same for both slate lightweight and normal weight concrete.

14.1.4 Flexural Behavior

The current prediction of cracking stress and cracking moment, when examined for slate HSLC, showed indications of becoming unconservative as concrete compressive strengths approached 11,000 psi. In some cases, the predicted cracking moments exceeded the experimental values. The use of a lambda factor (λ) of 0.85 for HSLC made with slate LWA produced conservative results on average for compressive strengths below 11,000 psi. More research is required to examine a potential tension

strength ceiling for HSLC and adjustments to lambda for concrete compressive strengths over 10,000 psi.

The modulus of rupture test, ASTM C 78⁸², did not accurately predict the cracking stress of HSLC girders.

The current AASHTO procedure for ultimate moment calculation was conservative for slate HSLC girders with normal weight concrete decks having a compressive strength under 6,000 psi.

14.1.5 Shear Behavior

The current AASHTO⁴⁰ Standard specification provided a conservative prediction of concrete and ultimate shear capacity when shear steel capacity was capped at a yield strength of 60 ksi. The alternate design procedure listed in ACI-318² Section 11.4.2.2 for predicting shear strength produced some unconservative predictions for concrete compression strengths over 10,000 psi. The method for predicting interface shear strength was conservative for slate HSLC.

The current AASHTO LRFD⁹² specification provided a conservative prediction of ultimate shear strength for slate HSLC.

The variable angle truss model provided an overconservative prediction of shear capacity in HSLC girders.

14.1.6 Development Length

An evaluation of current code provisions using the twelve HSLC girder development length tests in this study and eight normal weight HPC girder tests from

Dill⁸⁴ showed the current AASHTO⁴⁰ and ACI² provisions to be conservative. The code equations overestimated development lengths by 19 percent for both HSLC and normal weight HPC and never underestimated them. Use of the current code provisions for design of development length for slate HSLC and 0.6-inch diameter strand was conservative. Based on the concrete strength range addressed in this research project, modification of the current code specifications for development length was not necessary for HSLC or for 0.6-inch diameter strands.

An evaluation of other suggested equations for predicting development length showed an equation by Zia and Mostafa⁴² to provide the best overall prediction of development length. Equations by Lane⁴⁷ as identified in Table 13.10 also produced good overall predictions. The above equations were applicable to both slate HSLC and normal weight HPC with good results.

Test results showed conclusively that shear cracking in the transfer length region across the bottom strands did not induce significant strand slip if stirrup density was doubled over the current AASHTO⁴⁰ specified density in the region.

The addition of silica fume into the mix design at a 10% replacement rate by weight of cementitious materials gave indications of reducing development length.

There was no indication throughout this analysis that need existed to differentiate between slate HSLC and normal weight HPC. With regard to development length, for concrete compressive strengths over 8,000 psi, the prediction of development length was the same for both slate lightweight and normal weight concrete.

14.2 Recommendations

Recommendations are presented in the following sections by topic.

14.2.1 Analytical Investigation

When designing girders in excess of 105 feet, use Bulb-Tee sections (Standard or Modified). Use the Modified Bulb-Tee (one additional layer of strands in a 2-in deeper bottom flange) to gain an additional 10 feet in span length instead of designing for the next larger size Bulb-Tee section. Use slate HSLC to reduce both girder and gross vehicle weight.

14.2.2 HSLC Mixes and Properties

Accurately control the absorbed water in the LWA. Determine the percentage of absorbed moisture above which mix water will not be absorbed during concrete batching. Apply water by sprinkling or other method to the LWA stockpile for a sufficient length of time prior to batching such that the absorbed moisture is in excess of the minimum required amount. Test the LWA as often as is necessary during batching to insure that moisture contents are within the tolerance of the given mix design.

Use match curing of cylinders to predict initial strength of the concrete for precast prestressed concrete girder production. For later age testing (28-days and after) ASTM cured specimens are adequate. The 4 x 8 cylinders provide a reliable measure of compressive strength and may be used in place of 6 x 12 cylinders.

Use Equation 7.4 to predict the modulus of elasticity for slate HSLC.

$$E_c = 44,000 \sqrt{f_c' \frac{w_c}{145}} \tag{7.4}$$

14.2.3 Transfer Length

Use the current AASHTO⁴⁰ and ACI² equations to conservatively predict transfer length in pretensioned girders constructed with slate HSLC and 0.6-in pretensioning strands. For a more accurate prediction that is still conservative, use equation 9.7.

$$50 \ d_b \sqrt{\frac{6000}{f'_{ci}}} \tag{9.7}$$

14.2.4 Flexural Behavior

Do not use the modulus of rupture test, ASTM C 78,⁸² for determining the cracking stress and cracking moment for pretensioned slate HSLC girders.

More research is required to examine a potential tension strength ceiling for HSLC, as related to flexural cracking, and adjustments to lambda for concrete compressive strengths over 10,000 psi.

Use the current AASHTO procedure for ultimate moment calculation for slate HSLC girders with normal weight concrete decks having a compressive strength under 6,000 psi.

14.2.5 Shear Behavior

Use the current AASHTO Standard specification to provide a conservative prediction of concrete and ultimate shear capacity in slate HSLC pretensioned girders when shear steel capacity is capped at a yield strength of 60 ksi.

More research is required to examine a potential tension strength ceiling for HSLC, as related to diagonal tension cracking, and adjustments to lambda for concrete compressive strengths over 10,000 psi. Examination of the alternate design procedure listed in ACI-318 Section 11.4.2.2 for predicting shear strength, V_c, is necessary for concrete compressive strengths over 10,000 psi.

The AASHTO Standard Specification can be used to conservatively predict interface shear strength between slate HSLC and normal weight concrete.

The AASHTO LRFD Specification can be used to conservatively predict ultimate shear strength in slate HSLC pretensioned girders.

14.2.6 Development Length

The current AASHTO⁴⁰ and ACI² provisions can be used to conservatively predict development length in pretensioned girders constructed with slate HSLC and 0.6-in diameter pretensioning strands. For a more accurate prediction that is still conservative, use equation 13.4.

$$\left(50\sqrt{\frac{5000}{f_{ci}^{'}}} + f_{ps} - f_{se}\right)d_b \tag{13.4}$$

In the transfer length region, use two times the stirrup density currently specified by the AASHTO⁴⁰ Standard Specification to limit strand slip in the event of shear cracking.

Use silica fume at up to a 10% replacement rate by weight of cementitious materials to reduce development length.

14.2.7 Future Research

As a result of this research project, some areas requiring additional research became apparent.

First, the tension strength ceiling of HSLC and its effect on diagonal tension cracking strength and flexural cracking strength is unknown. The overall relation between concrete strength and the LWC reduction factor, λ , requires examination, especially for concrete compressive strengths over 10,000 psi.

Second, a spectrum of testing using the same concrete strengths with varying amounts of silica fume is required to determine its exact impact on development length.

Third, based on the tremendous property variation between different types of LWA, there is a need to thoroughly investigate the use of various light weight aggregates in like test configurations to determine material specific factors for each category of design.

REFERENCES

- 1. Murillo, J. A., Thoman S., Smith, D., "Lightweight Concrete for a Segmental Bridge," *Civil Engineering*, Vol. 64, No. 5, May 1994, pp. 68-70.
- 2. Building Code Requirements for Reinforced Concrete, ACI 318-99, and Commentary, ACI 318R-99, American Concrete Institute, Detroit, 1999.
- 3. Harmon, K., "Physical Characteristics of Rotary Kiln Expanded Slate Lightweight Aggregate," *Proceedings, Second International Symposium on Structural Lightweight Aggregate Concrete*, Kristiansand, Norway, June 2000, 11 pp.
- 4. Raithby, K. D., Lydon, F. D., "Lightweight Concrete in Highway Bridges," *The International Journal of Cement Composites and Lightweight Concrete*, Vol. 2, No. 3, May 1981, pp. 133-146.
- 5. Bender, B. F., "Economics and Use of Lightweight Concrete in Prestressed Structures," *PCI Journal*, Vol. 35, No. 6, November-December 1980, pp. 62-67.
- 6. Brown, W. R., Davis, C. R., A Load Response Investigation of Long Term Performance of a Prestressed Lightweight Concrete Bridge at Fanning Springs, Florida, Final Report, No. FL/DOT/SMO-93-401, Florida Department of Transportation, April 1993, 66 pp.
- 7. Hansen, H. H., "Shelby Creek Bridge," Portland Cement Association Engineered Concrete Structures, Vol. 5, No. 2, August 1992, p. 3.
- 8. Roberts, J. E., "Lightweight Concrete Bridges for California Highway System," *ACI SP 136*, American Concrete Institute, Detroit, 1992, pp. 254-271.
- 9. Expanded Shale, Clay and Slate Institute, "Back-up Statistics to Building Bridges," Information Sheet # 470.4, Salt Lake City, June 1994, 15 pp.
- 10. Melby, K., Jordet, E. A., Hansvold, C., "Long-span Bridges in Norway Constructed in High-Strength LWA Concrete," *Engineering Structures*, Vol. 18, No. 11, November 1996, pp. 845-849.

- 11. Holm, T. A., Bremner, T. W., State-of-the-Art Report on High-Strength, High-Durability Structural Low-Density Concrete for Applications in Severe Marine Environments, U. S. Army Corps of Engineers Engineer Research and Development Center No. ERDC/SL TR-00-3, August 2000, 103 pp.
- 12. Shideler, J. J., "Lightweight-Aggregate Concrete for Structural Use," *Journal of the American Concrete Institute*, Vol. 54, No. 10, October 1957, pp. 299-328.
- 13. Wang, P. T., Shah, S. P., Naaman A. E., "Stress-Strain Curves of Normal and Lightweight Concrete in Compression," *ACI Journal*, Vol. 75, No. 11, November 1978, pp. 603-611.
- 14. Hanson, J. A., "Tensile Strength and Diagonal Tension Resistance of Structural Lightweight Concrete," *Journal of the American Concrete Institute*, Vol. 58, No. 1, July 1961, pp. 1-37.
- 15. ASTM C 127, Standard Test Method for Specific Gravity and Absorption of Coarse Aggregate, American Society for Testing and Materials, West Conshohocken, PA, 1993, 5 pp.
- 16. ASTM C 128, Standard Test Method for Specific Gravity and Absorption of Fine Aggregate, American Society for Testing and Materials, West Conshohocken, PA, 1997, 5 pp.
- 17. Bremner, T. W., Newman, "Microstructure of Low Density Concrete Aggregate," Proceedings of the Ninth Congress of the Federation Internationale de la Precontrainte, Volume 3, Commission Reports, Stockholm, June 1982.
- 18. ACI Manual of Concrete Practice, "Standard Practice for Selecting Proportions for Structural Lightweight Concrete (ACI 211.2-91), American Concrete Institute, Detroit, 1996.
- 19. Pfeiffer, D. W., "Sand Replacement in Structural Lightweight Concrete," *ACI Journal*, Vol. 64, No. 7, July 1967, pp. 384-392.
- 20. Fujji, K., Kakizaki, M., Edahiro, H., Unisuga, Y., Yamamoto, Y., "Properties of High-Strength and High-Fluidity Lightweight Concrete," *ACI SP 179*, American Concrete Institute, Detroit, pp. 254-271.
- 21. Leming, M. L., Properties of High Strength Concrete An Investigation of High Strength Concrete Characteristics using Materials in North Carolina, Final Report, No. 23241-86-3, North Carolina Department of Transportation, July 1988 186 pp.

- 22. Mor, A., "Steel-Concrete Bond in High Strength Lightweight Concrete," *ACI Materials Journal*, Vol. 89, No. 1, January-February 1992, pp. 76-82.
- 23. Smeplass, S., "Moisture in Light Weight Aggregates Practical Consequences for the Production Properties of Light Weight Aggregate Concrete", *Proceedings, Second International Symposium on Structural Lightweight Aggregate Concrete*, Kristiansand, Norway, June, 2000.
- 24. Holm, T. A., Valsangkar, A. J., "Lightweight Aggregate Soil Mechanics: Properties and Applications," Transportation Research Record 1422; Soils, Geology, and Foundations; Lightweight Artificial and Waste Materials for Embankments Over Soft Soils, Transportation Research Board, January 1993, pp. 7-13.
- 25. Valum, R., Nilsskog, J. E., "Production and Quality Control of High Performance Lightweight Concrete for the Raftsundet Bridge," Proceedings of the Fifth International Symposium on Utilization of High Strength / High Performance Concrete, Sandefjord, Norway, June 2000, pp. 909-918.
- 26. Hoff, G. C., "High Strength Lightweight Aggregate Concrete for Arctic Applications," *ACI SP 136*, American Concrete Institute, Detroit, 1992, pp. 1-65.
- 27. Morales, J., Short-Term Mechanical Properties of High Strength Lightweight Concrete, Report 82-9 on NSF Grant No. ENG78-05124, Ithaca, August 1982.
- 28. Leming, M. L., *Creep and Shrinkage of Lightweight Concrete*, North Carolina State University Publication, 1990, 4 pp.
- 29. FIP Committee, "Chapter 7, Design of Prestressed Lightweight Concrete Structures," Federation Internationale de la Precontrainte Manual of Lightweight Aggregate Concrete, 2nd Edition, 1983, pp. 168-206.
- 30. Bilodeau, A., Chevrier, R., Malhotra, M., Hoff, G. C., "Mechanical Properties, Durability and Fire Resistance of High-Strength Lightweight Concrete," *Proceedings of the International Symposium on Structural Lightweight Aggregate Concrete*, Sandefjord, Norway, June 1995, pp. 432-443.
- 31. Holm, T. A., Bremner, T. W., "Chapter 10, High Strength Lightweight Aggregate Concrete," *High Performance Concretes and Applications*, S. P. Shah and S. H. Ahmad, ed., Edward Arnold, London, pp. 341-374.
- 32. Carolina Stalite, Information from Carolina Stalite Company, Salisbury, NC, 2000, 6 pp.

- 33. Holm, T. A., Bremner, T. W., "70 Year Performance record for High-Strength Structural Lightweight Concrete," *Proceedings of the First Materials Engineering Congress, Serviceability & Durability of Construction Materials*, Denver, August 2000, pp. 884-893.
- 34. Bremner, T. W., Holm, T. A., "Elastic Compatibility and the Behavior of Concrete," *ACI Journal*, Vol. 83, No. 2, March-April 1986, pp. 244-250.
- 35. Kohno, K., Okamoto, T., Isikawa, Y., Sibata, T., Mori, H., "Effects of Artificial Lightweight Aggregate on Autogenous Shrinkage of Concrete," *Cement and Concrete Research*, Vol. 29, 1999, pp. 611-614.
- 36. Bremner, T. W., Holm, T. A., Ries, J. P., "Enhanced Hydration and Properties of Specified Density Concrete," Expanded Shale, Clay and Slate Institute Information Sheet 4284.1, February 2001, 8 pp.
- 37. Reutlinger, C., "Direct Pull-Out Capacity and transfer Length of 0.6-inch Diameter Prestressing Strand in High-Performance Concrete," Masters Thesis, Georgia Institute of Technology, Atlanta, GA, May 1999, 352 pp.
- 38. Janney, J. R., "Nature of Bond in Pre-Tensioned Prestressed Concrete," *Journal of the American Concrete Institute*, Vol. 50, No. 9, May 1954, pp. 717-736.
- 39. Hanson, N. W., Karr, P. H., "Flexural Bond Tests of Pretensioned Prestressed Beams," *Journal of the American Concrete Institute*, Vol. 55, No. 7, January 1959, pp. 783-802.
- 40. Standard Specifications for Highway Bridges, 16th ed., American Association of State Highway and Transportation Officials, Washington, D. C., 1996.
- 41. Martin, L. D., Scott, N. L., "Development of Prestressing Strand in Pretensioned Members," *ACI Journal*, Vol. 73, No. 8, August 1976, pp. 453-456.
- 42. Zia, P., Mostafa, T., "Development Length of Prestressing Strands," *PCI Journal*, Vol. 22, No. 5, September/October 1977, pp. 54-65.
- 43. Deatherage, J. H., Burdette, E. G., and Chew, C. K., "Development Length and Lateral Spacing Requirements of Prestressing Strand for Prestressed Concrete Bridge Girders," *PCI Journal*, Vol. 39, No. 1, January/February 1994, pp. 70-83.
- 44. Russell, B. W., "Design Guidelines for Transfer, Development and Debonding of Large Diameter Seven Wire Strands in Pretensioned Concrete Girders," Doctoral Thesis, The University of Texas at Austin, 1992, 464 pp.

- 45. Mitchell, D., Cook, W. D., Khan, A. A., Tham, T., "Influence of High Strength Concrete on Transfer and Development Length of Pretensioning Strand," *PCI Journal*, Vol. 38, No. 3, May/June 1993, pp. 52-56.
- 46. Buckner, C. D., "A Review of Strand Development Length for Pretensioned Concrete Members," *PCI Journal*, Vol. 40, No. 2, March/April 1995, pp. 84-105.
- 47. Lane, S. N., A New Development Length Equation for Pretensioned Strands in Bridge Beams and Piles, Final Report, No. FHWA-RD-98-116, Federal Highway Administration, December 1998, 131 pp.
- 48. Collins, M. P., Mitchell, D., *Prestressed Concrete Structures*, Prentice Hall, Englewood Cliffs, New Jersey, 1991.
- 49. Nawy, E. G., *Prestressed Concrete A Fundamental Approach*, Third Edition, Prentice Hall, Upper Saddle River, New Jersey, 2000,
- 50. Lin, T. Y., Burns, N. H., Design of Prestressed Concrete Structures, Third Edition, John Wiley and Sons, New York, New York, 1981.
- 51. Holm, T. A., Personal telephone conversation on March 25, 2002 concerning the origination of the lightweight concrete factor, λ .
- 52. Johnson, M. K., Ramirez, J. A., "Minimum Shear Reinforcement in Beams with Higher Strength Concrete," *ACI Structural Journal*, Vol. 86, No. 4, July-August 1989, pp. 376-382.
- 53. Building Code Requirements for Reinforced Concrete, ACI 318-89, and Commentary, ACI 318R-89, American Concrete Institute, Detroit, 1989.
- 54. Shahawy, M. A., Batchelor, B., "Shear Behavior of Full-Scale Prestressed Concrete Girders: Comparison Between AASHTO Specifications and LRFD Code," *PCI Journal*, Vol. 41, No. 3, May-June 1996, pp. 48-62.
- 55. Barnes, R. W., Burns, N. H., Kreger, M. E., "Development Length of 0.6-inch Prestressing Strand in Standard I-Shaped Pretensioned Concrete Beams," Research Report 1388-1, Center for Transportation Research, Bureau of Engineering Research, The University of Texas at Austin, December 1999, 318 pp.
- 56. Ma, J., Tadros, M. H., Baishya, M, "Shear Behavior of Pretensioned High-Strength Concrete Bridge I-Girders," *ACI Structural Journal*, Vol. 97, No. 1, January-February 2000, pp. 185-192.

- 57. Ramirez, J., Olek, J., Rolle, E., Malone, B., "Performance of Bridge Decks and Girders with Lightweight Aggregate Concrete, Final Report," Report FHWA/IN/JTRP-98/17, Purdue University, October 2000, 616 pp.
- 58. Guide for Structural Lightweight Aggregate Concrete, ACI 213, (Draft Copy for Voting by Committee 213), American Concrete Institute, Detroit, 2002.
- 59. Peterman, R. J., Ramirez, J. A., Olek, J., "Design of Semi-lightweight Bridge girders, Development Length Considerations," Transportation Research Board Record 1696, Paper No. 5B0063, Transportation Research Board, 2000.
- 60. Peterman, R. J., Ramirez, J. A., Olek, J., "Evaluation of Strand Transfer and Development Lengths in Pretensioned Girders with Semi-Lightweight Concrete," Final Report," Report FHWA/IN/JTRP-99/3, Purdue University, July 1999, 89 pp.
- 61. Kolozs, R. T., "Transfer and Development Lengths of Fully Bonded 1/2-Inch Prestressing Strand in Standard AASHTO Type I Pretensioned High Performance Lightweight Concrete (HPLC) Beams," Masters Thesis, The University of Texas at Austin, May 2000, 155 pp.
- 62. Bond of Reinforcement in Concrete, International Federation for Structural Concrete (fib) State-of-Art Report, Bulletin 10, Lausanne, Switzerland, 2000, 427 pp.
- 63. den Uijl, J. A., "Bond Modeling of Prestressing Strand," *ACI SP 180*, ed. Roberto Leon, American Concrete Institute, Farmington Hills, pp. 145-169.
- 64. Kahn, L. F., Saber, A., "Analysis and Structural Benefits of High Performance Concrete for Pretensioned Bridge Girders," *PCI Journal*, Vol. 45, No. 4, July/August 2000, pp. 100-107.
- 65. Meyer, K. F., Kahn, L. F., "Annotated Bibliography for High-Strength, Lightweight Prestressed Concrete Bridge Girders," Task 1 Report, Georgia Department of Transportation Project No. 2004, Georgia Institute of Technology, January 2001, 14 pp.
- 66. Shams, M., "Time-Dependent Behavior of High-Performance Concrete," Doctoral Thesis, Georgia Institute of Technology, May 2000, 572 pp.
- 67. ASTM C 330, Standard Specification for Lightweight Aggregates for Structural Concrete, American Society for Testing and Materials, West Conshohocken, PA, 1999, 4 pp.

- 68. ASTM C 33, Standard Specification for Concrete Aggregates, American Society for Testing and Materials, West Conshohocken, PA, 1999, 8 pp.
- 69. Mehta, P. K., Monteiro, P. J. M., Concrete Microstructure, Properties, and Materials, Second Edition, McGraw Hill, New York, New York, 1993.
- 70. ASTM C 150, Standard Specification for Portland Cement, American Society for Testing and Materials, West Conshohocken, PA, 2000.
- 71. ASTM C 618, Standard Specification for Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use as a Mineral Admixture in Concrete, American Society for Testing and Materials, West Conshohocken, PA, 1999, 4pp.
- 72. ASTM C 494, Standard Specification for Chemical Admixtures for Concrete, American Society for Testing and Materials, West Conshohocken, PA, 1999, 9 pp.
- 73. ASTM C 260, Standard Specification for Air Entraining Admixtures for Concrete American Society for Testing and Materials, West Conshohocken, PA, 2000, 3 pp.
- 74. ASTM C 143, Standard Test Method for Slump of Hydraulic-Cement Concrete, American Society for Testing and Materials, West Conshohocken, PA, 1998, 3 pp.
- 75. ASTM C 138, Standard Test Method for Unit Weight, Yield, and air Content (Gravimetric) of Concrete, American Society for Testing and Materials, West Conshohocken, PA, 2000, 3 pp.
- 76. ASTM C 1064, Standard Test Method for Temperature of Freshly Mixed Portland Cement Concrete, American Society for Testing and Materials, West Conshohocken, PA, 1999, 2 pp.
- 77. ASTM C 173, Standard Test Method for Air Content of Freshly Mixed Concrete by the Volumetric Method, American Society for Testing and Materials, West Conshohocken, PA, 1994, 3 pp.
- 78. ASTM C 231, Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method, American Society for Testing and Materials, West Conshohocken, PA, 1994, 3 pp.
- 79. ASTM C 31, Standard Practice for Making and Curing Concrete Test Specimens in the Field, American Society for Testing and Materials, West Conshohocken, PA, 1998, 5 pp.

- 80. ASTM C 39, Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens, American Society for Testing and Materials, West Conshohocken, PA, 1999, 5 pp.
- 81. ASTM C 469, Standard Test Method for Static Modulus of Elasticity and Poisson's Ratio of Concrete in Compression, American Society for Testing and Materials, West Conshohocken, PA, 1994, 4 pp.
- 82. ASTM C 78, Standard Test Method for Flexural Strength of Concrete (Using Simple Beam with Third-Point Loading), American Society for Testing and Materials, West Conshohocken, PA, 1994, 3 pp.
- 83. ASTM C 512, Standard Test Method for Creep of Concrete in Compression, American Society for Testing and Materials, West Conshohocken, PA, 1992, 4 pp.
- 84. Dill, J. C., "Development Length of 0.6-inch Diameter Prestressing Strand in High-Performance Concrete," Masters Thesis, Georgia Institute of Technology, May 2000, 322 pp.
- 85. ASTM C 1231, Standard Practice for Use of Unbonded Caps in Determination of Compressive Strength of Hardened Concrete Cylinders, American Society for Testing and Materials, West Conshohocken, PA, 2000, 4 pp.
- 86. Buchberg, B. S., "Investigation of Mix Design and Properties of High-Strength/High-Performance Lightweight Concrete," Masters Thesis, Georgia Institute of Technology, January 2002, 453 pp.
- 87. Guide for High-Strength Concrete, ACI 363, American Concrete Institute, Detroit, 2000.
- 88. ASTM C 496, Standard Test Method for Splitting Tensile Strength of Cylindrical Concrete Specimens, American Society for Testing and Materials, West Conshohocken, PA, 1996, 4 pp.
- 89. Sikes, G. H., Strougal, E. J., Meisner, J. L., "Computer Manual for Service Load Design of Concrete Bridge Slabs," Georgia Department of Transportation, January 1999, 18 pp.
- Logan, D. R., "Acceptance Criteria for Bond Quality of Strand for Pretensioned Prestressed Concrete Applications," PCI Journal, Vol. 42, No. 2, March/April 1997. pp. 52-90.

- 91. MacGregor, J. G., *Reinforced Concrete*, Second Edition, Prentice Hall, Englewood Cliffs, New Jersey, 1992, 848 pp.
- 92. LRFD Specifications for Highway Bridges, American Association of State Highway and Transportation Officials, Washington, D. C., 1998.
- 93. Cagley, J. R., "Changing from ACI 318-99 to ACI 318-02, What's New?," Concrete International, Vol. 23, No. 6, June 2001, pp. 69-182.
- 94. Vaysburg, A., "Durability of Lightweight Concrete Bridges in Severe Environments," *Concrete International*, Vol. 18, No. 7, July 1996, pp. 33-38.
- 95. Yeginobali, A., Sobolev, K. G., Soboleva, S. V., Tokyay, M., "High Strength Natural Lightweight Aggregate Concrete with Silica Fume," *ACI SP 178*, American Concrete Institute, Detroit, May 1998, pp. 739-758.



School of Civil and Environmental Engineering

Structural Engineering, Mechanics and Materials Research Report No. 02-5

Appendices for Transfer and Development Length of High Strength Lightweight Concrete Precast Prestressed Bridge Girders

Task 5 Report

Prepared for

Office of Materials and Research Georgia Department of Transportation

GDOT Research Project No. 2004

by

Karl F. Meyer, Lawrence F. Kahn James S. Lai, and Kimberly E. Kurtis

June 2002

APPENDIX A

INPUT FILE CREATOR FOR GDOT COMPUTER PROGRAM

This Appendix contains an example of the spreadsheet used to create input files for use with the Georgia Department of Transportation prestressed girder design program

The worksheet shown in Table A.1 shows the input variables. Most of the variables were held constant; the shaded variables were changed for the parametric study.

The worksheet shown in Table A.2 lists values calculated based on the variables entered in Table A.1. For determination of diaphragm locations, it was assumed that diaphragm spacing would be at a maximum of 35 feet.

The worksheet shown in Table A.3 provides the values to be entered for rows 1 through 8 in the program input file. The shaded values were entered as listed except for the decimal points that are shown for clarity. The initial row of the input file providing information is not listed in Table A.3.

Table A.1 Input Values for Girder Design

INPUT VALUES FC	OR G	DOT PR	ESTRES	FOR GDOT PRESTRESSED GIRDER PROGRAM IN DESIGN MODE	GN M	ODE	
DECK VARIAB	ABLES			GIRDER VARIABLES			
MINIMUM DECK THICKNESS	t _d	7.000	INCHES	GIRDER TYPE (AASHTO,BT)		· BT72	1-6,BT
AVERAGE COPING DEPTH		3.00	INCHES	NUMBER OF GIRDERS		13	EACH
FUTURE PAVING ALLOWANCE		0.015	KSF	GIRDER SPACING	s	84.00	INCHES
LIGHTWEIGHT CONCRETE		NO	YES/NO	GIRDER LENGTH	Γ	166.00	FEET
CONCRETE STRENGTH	f_c	3500	PSI	LIGHTWEIGHT CONCRETE		, TES	YES/NO
CONCRETE WEIGHT	Wc	145	PCF	LIGHTWEIGHT CONCRETE REDUCTION FACTOR	~	92.0	NO UNITS
ALLOWANCE FOR GRINDING		0.00	INCHES	CONCRETE STRENGTH	ţ	100001	PSI
WEIGHT OF SIDEWALK		0.00	K/FT	% CONCRETE STRENGTH AT RELEASE		%06	PERCENT
DISTANCE FROM DECK TO GIRDER	DF	00.0	INCHES	CONCRETE WEIGHT (WHOLE NUMBERS ONLY)	Wc	118	PCF
DECK PANELS USED		ON	YES/NO	STRAND DIAMETER	Ω	9.0	INCHES
MISCELLANEOUS VARIABLES THAT ARE NORMALLY CONSTANT VALUES	NORMA	LLY CONST	ANT VALUES	TOP STRAND C/S AREA	Ast	0.217	INCH~2
WEIGHT OF BARRIERS		820	LB/FT	BOTTOM STRAND C/S AREA	A _{sb}	0.217	INCH^2
DISTRIBUTION FOR DEFLECTION	DFD	1.000	NO UNITS	STRAND ULTIMATE STRENGTH	f_{pq}	270	KSI
WEIGHT OF FORMWORK		16	PSF	STIRRUP SIZE		5	#
FACTOR INITIAL BM TOP STRESS	SIT	-3.0	NO UNITS	STIRRUP ULTIMATE STRENGTH	fu	09	KSI
FACTOR FINAL BM BOTTOM STRESS	SFB	-6.0	NO UNITS	DISTANCE END TO SUPPORT	XDIST	8.00	INCHES
ALLOW FINAL BEAM END TOP STRESS	SFT	-200	PSF	BOTTOM STRAND REDUCTION FACTOR	RBFPU	0.75	NO UNITS
AASHTO CODE VERSION		1996		TOP STRAND REDUCTION FACTOR	RTFPU	0.75	NO UNITS
CONCRETE WEIGHT FOR DIAPHRAGMS		150	PCF	LOLAX STRANDS USED	TT	YES	YES/NO
THICKNESS OF DIAPHRAGMS		10	INCHES	DRAPED STRANDS		YES	YES/NO
TOP OF BEAM TO TOP STRANDS	TCL	2.50	INCHES	NUMBER OF DIAPHRAMS ON GIRDER	NPL	4	EACH
BOTTOM OF BEAM TO BOTTOM STRANDS	BCL	3.00	INCHES		֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֡֓֓֓֡֓֓֓		
STRAND SPACING	SPAC	2.00	INCHES	USER INPUT VALUES		OPEN	
NUMBER OF TOP STRANDS	NST	2	EACH				
MAXIMUM DRAPED STRANDS PER ROW		2	NO UNITS	USER INPUT VALUES	ت	TMP LOCK	
				USER INPUT VALUES (CONSTANTS)>			

Table A.2 Calculated Values

NON-COMPOSITE DEAD LOAD	EAD LO	AD (A)	
WEIGHT OF SLAB		0.592	KIP/FT
WEIGHT OF COPINGS		0.127	KIP/FT
WEIGHT OF FORMWORK		0.056	KIP/FT
TOTAL NON-COMPOSITE DEAD LOAD	WDL_{nc}	0.775	KIP/FT
COMPOSITE DEAD LOAD	DIOAD		
FUTURE WEARING SURFACE		0.105	KIP/FT
BARRIERS		0.063	KIP/FT
TOTAL COMPOSITE DEAD LOAD	$\mathrm{MDL}_{\mathrm{c}}$	0.168	KIP/FT
MISCELLANEOUS CALCI	CALCULATED	VALUES	
WIDTH OF GIRDER TOP FLANGE		42	INCHES
GIRDER MODULUS OF ELASTICITY	E	3.82	ISG 931
GIRDER MODULUS AT RELEASE	E_{ci}	3.74	ISG 931
DISTRIBUTION FOR MOMENT	DFM	1.273	SLIND ON
DISTRIBUTION FOR SHEAR (INT)	DFV	1.571	SLIND ON
APPROXIMATE GIRDER WEIGHT		104.33	KIPS
DECK MODULUS OF ELASTICITY	E	3.41	1E6 PSI
DIAPHRAGM WEIGHT PER FOOT		0.667	KIPS
POINT LOADS ON	GIRDER	~	
POINT LOAD # 1	^	4.001	KIPS
LOCATION # 1 FROM END		33.200	FEET
POINT LOAD # 2	^-	4.001	KIPS
LOCATION # 2 FROM END		66.400	FEET
POINT LOAD # 3	^	4.001	KIPS
LOCATION #3 FROM END		99.600	FEET
POINT LOAD # 4	^	4.001	KIPS
LOCATION # 4 FROM END		132.800	FEET
POINT LOAD # 5			KIPS
LOCATION:# 5 FROM END			FEET
PROGRAM CALCULATED VALUES	^		

Table A.3 Input File for GDOT Prestressed Girder Computer Program

XXXXX 04 2.285 FX00 2.00 5.6 5.	11 12 13 14 15 16 17 18 19 11 12 13 14 15 16 17 18 19 ASB AST DIAM TCL BCL SPAC 20 20 20 20 20 20 20 20 20 20 20 20 20 2	X = SPACE		1 1 12 13 14 15 16 17 18 19 19 19 19 19 19 19 19 19 19 19 19 19	
Color Colo	ROW TYPE NST XDIST ANXIMUM NUMBER OF STRANDS PER ROW ANXIMUM NUMBER	ROW RBFPU BIPU IBLOSS FBLOSS RIFPU IFPU ITLOSS FTLOSS WTC LOLAX ITLG FTLG DLG	ROW DBOND ROW	ROW DRAPE RS HT HOLD MAXIMUM DRAPED STRANDS PER ROW MAXIMUM DRAPED STRANDS PER ROW 6 7 8 9 10 11 12 14 15 16 17 18 19 ROW (CONTINUED) ROW (CONTINUED)	ROW XPI PI XP2 P2 XP3 P3 XP4 P4 XP5 P5 P5 P8 P8 P8 P9 P4 XP5 P5 P8
ROW ROW	ROW ROW ROW	362	ROW	ROW ROW	ROW

APPENDIX B

MIX DESIGN SPREADSHEET

This Appendix contains an example of the LWC Mix Design Spreadsheet. Table B.1 shows the spreadsheet with an example mix design.

The user does the following:

- 1. Enter values for SG (Specific Gravity) and Cost for each component to set the material parameters. Enter the desired air content and batch size.
- 2. Enters the weight of each particular component per cubic yard at SSD, except chemical admixtures, in the "Theoretical Mix Design at SSD" Section.
- 3. Enter the dose of chemical admixtures in fl oz / 100 weight of cementitious materials.
- 4. Adjust the components until the W/CM ratio is as desired. The percent cement paste and ratio of coarse to fine aggregate are listed at the bottom of the page.
- 5. While batching, if additional chemical admixtures or water are added, enter the values in the spreadsheet in ml for chemical admixtures and pounds for water.
- 6. The final mix design reflecting added amounts during batching, if any, is reflected in the "Final Mix Design at SSD" section. If nothing additional was added, this will be the same as the "Theoretical Mix Design at SSD."

Table B.1 Mix Design Spreadsheet

LIGHT	LIGHTWEIGHT CONC		RETE MIX DESIGN	m	# 1	X	XXXX	-	f.' 1	×	ksi		Date		
W.	Material Data	Mois	Moisture Data	T	eoretical	Mix Des	Theoretical Mix Design at SSD		1,0 Adj	H;O Adjusted Batch	9	Final Mix Design at SSD	Design	at SSD	1
Description	SG Cost Per	% SSD SGF	% As Is %	% Free Pe	Per Cubic Yard	/ard	Per Batch		EDV(cf)	Amount	٦	Pel	Per Cubic Yard	Yard	
3/4" - NWA		${\mathbb H}$	H	井	0	0.00	0.00		0.00	0.00	Γ	0		- \$	П
3/8" - NWA	dl 0500 \$ 0.0048 lb	0.60 2.681	0.00	0.00	ا <u>ء</u>	000	80.0	ا ا	0.00	0.00	q	0	 	5	Т
NW Sand	2.608 \$ 0.0054	+	+	<u> </u>		7.43	45.00		1	44.58		1205		\$ 6.48	8
3/4" - LWA	1.415 \$ 0.0276	6.00 1.500	0.00	0.00	0.0	0.00	0.00		00.0	0.00		٥		S	1
1/2" - LWA	_	Н	Н	1.60 945	11, 9.77	77	35.00		0.37	35.55	2	937	يا	\$ 25.86	98
3/8" - LWA LW Fines	1.570 \$ 0.0300 1.710 \$ 0.0275	5.00 1.664	5.00	0.00	_	00.00	0.00	Щ	0.00	0.00	<u> </u>	0 0	5	S	
			Tot Aggregate >	e> 2160	Ĭ₽	17.20 cf	11-		╢	80.30		2141.7	٩	\$ 32.34	12
		% by Wt						{	1		1				1
FA - Class C	2.250 \$ 0.0300	0.0	⊢	0	Ö	00.0	00.0	Ľ	00.0	0.00	Ī	6		٠	Γ
FA - Class F		19.4	W/CIM 0.5	0.338	=	1.07	5.56		0.04	256		149	<u>.</u>	\$ 4.46	9
GGBFS		0.0	S/CV 75	0 27 48	<u>0</u>	00.0		1 P	0.00	0.00	Q.	0	ءِ	8	Γ
Metakaolin	2.500 \$ 0.0500	0.0	-	느	Ö	0.00	0.00		0.00	0.00		٥	.	S	Т
SF - (F 10,000)	2.200 \$ 0.0500	7.1	1 D/P:73 11	110 2 55	0'	0.40	2.04		0.01	*204		55	L	\$ 2.73	73
Type III Cement	3.150 \$ 0.0440 lb	73.5	_	570	lb 2.	2.90 cf	21.11) او	0.11	31.10	q	595	lb	\$ 24.87	37
			Tot Cementitious >	277 < Su	lb 4.37	37 cf	28.70	9	0.16	28.70	٩	768.4	q.	\$ 32.06	9
		fl oz / 100 wt									1				1
WRDA 35	\$ 0.0500	+	Ц	10 54.3	0.0		2.01			10000		П	fluid oz	\$ 3.14	4
A DIVA Flour	1.139 \$ 0.0300	3 - 9 0.00		T) 		Т	0	- 1	0.00	Ē	Т	per 100	2	٦
Daravair 1000	\$ 0.0500	1/4 - 3 0.00	mixing	0.0		0.000 cf	0.00	_	0.007	1000		0.00	¥	2 7.90	2
Total additi	Total additional volume added >	0.0085 cf	Tot Admixtures >	s> 116.3	<u> </u>	0.121 cf	4.31		0.004	0.31		9.40		\$ 11.04	14
]	1	K	gal		1	L	1
Water	1.000 \$ 0.0013 gal	Pounds water added =>	Н	0.50 264.2	lb	4.23 cf	9.78	1b 0.	0.152	_	g	275.3	qı	\$ 0.04	4
Design Air =>	4.00 %					1.08 cf			0.04	cĮ		3.97	%	Air	
Design Slump =>	· 3-5 Inches	Batch Size =>	1.00	GC P	Percent Cement Paste >	ment Pas	П	36	Coar	se / Fine	Aggre	Coarse / Fine Aggregate Ratio		1.31	
Dire	Direct any questions about this s	s spreadsheet to L	preadsheet to LTC Fred Meyer, Georgia Institute of Technology, Atlanta, GA (404) 385-1429 -	Georgia Inst	titute of I	Pechnolog	rv. Atlanta.	GA (4	04) 385		Versio	Version 4. 7 Feb 2001	2001		I
				D			666								7

The following calculations verify the values listed in Table B.1.

Assumed Values

Brown Brothers Sand (NW Sand): Theoretical Mix Design at SSD = 1215 pcy

Specific gravity (SG) = 2.608

SSD moisture = 0.5% As-Is moisture = 0%

1/2" Stalite LWA (1/2" - LWA): Theoretical Mix Design = 945 pcy

SG = 1.44

SSD moisture = 7.67% As-is moisture = 9.27%

Class "F" flyash (FA - Class F): Theoretical Mix Design = 150 pcy

SG = 2.25

Silica Fume (SF - F 10,000): Theoretical Mix Design = 55 pcv

SG = 2.2

Type III Cmt (Type III Cement): Theoretical Mix Design = 570 pcy

SG = 3.15

Water Reducer (WRDA 35): Theoretical Mix Design = 7 oz/100 weight

of cementitious material

SG = 1.199

Superplasticizer (ADVA Flow): Theoretical Mix Design = 8 oz/100 weight

of cementitious material

SG = 1.043

AEA (Daravair 1000): Theoretical Mix Design = 1 oz/100 weight

of cementitious material

SG = 1.0

Air - 4%

During batching the following were added: WRDA 35 = 10 ml = .00003531 cf

ADVA Flow = 5 ml = .00001766 cf

water = 0.5 lbs = .008013 cf

Batch Size = 1 cubic foot

Calculated Values

NW Sand: Specific gravity factor (SGF) = $(2.608) \times (1+0.005) = 2.621$ percent free moisture = 0% - 0.05% = -0.5%volume of material per cy = $(1215 \text{ pcy}) \times (1 / ((62.4 \text{pcf}) \times (2.621)) = 7.428 \text{ cf}$ weight of material per cf of batch = (1215 pcy) / (27 cf/cy) = 45 lbsWater adjusted weight of material per cf of batch = $(45 \text{ lbs}) \times (1/(1+(.5/100))) \times (1+0.0/100) = 44.776 \text{ lbs}$ Water adjusted volume of material per cf of batch = ((45 lb) / ((2.621) x (62.4 pcf)))+((44.776 lbs) - (45 lbs)) / 62.4 pcf = 0.2716 cf1/2" - LWA: Specific gravity factor (SGF) = $(1.44) \times (1+0.0767) = 1.550$ percent free moisture = 9.27 % - 7.67 % = 1.60 %volume of material per cy = $(945 \text{ pcy}) \times (1 / ((62.4 \text{pcf}) \times (1.55)) = 9.77 \text{ cf}$ weight of material per cf of batch = (945 pcy) / (27 cf/cy) = 35 lbsWater adjusted weight of material per cf of batch = $(35 \text{ lbs}) \times (1 / (1+(7.67 / 100))) \times (1+9.27 / 100) = 35.52 \text{ lbs}$ Water adjusted volume of material per cf of batch = ((35 lb) / ((1.55) x (62.4 pcf)))+((35.52 lbs) - (35 lbs)) / 62.4 pcf = 0.3702 cf**Total Aggregate:** weight = 1215 lbs (NW Sand) + 945 lbs (1/2" - LWA) = 2,160 lbs

weight = 1215 lbs (NW Sand) + 945 lbs
$$(1/2" - LWA) = 2.160$$
 lbs volume = 7.43 cf (NW Sand) + 9.77 $(1/2" - LWA) = 17.20$ cf

FA - Class F:

volume per cy =
$$(150 \text{ lbs}) / ((2.25) \text{ x} (62.4 \text{ pcf})) = \underline{1.0683} \text{ cf}$$

weight = $(150 \text{ pcy})) / (27 \text{cuf/cuy}) \text{ x} (1 \text{ cf/batch}) = \underline{5.555} \text{ lbs/batch}$
volume = $(5.555 \text{ lbs/batch}) / ((2.25) \text{ x} (62.4 \text{ pcf})) = \underline{0.0395} \text{ cf/batch}$

SF - F 10,000:

volume per cy =
$$(55 \text{ lbs}) / ((2.2) \text{ x } (62.4 \text{ pcf})) = \underline{0.4006} \text{ cf}$$

weight = $(55 \text{ pcy})) / (27\text{cf/cy}) \text{ x } (1 \text{ cf/batch}) = \underline{2.037} \text{ lbs/batch}$
volume = $(2.037 \text{ lbs/batch}) / ((2.5) \text{ x } (62.4 \text{ pcf})) = \underline{0.01484} \text{ cf/batch}$

Type III Cement:

volume =
$$(570 \text{ lbs/cy}) / ((3.15) \text{ x} (62.4 \text{ pcf})) = \underline{2.8998} \text{ cf/cy}$$

weight = $(570 \text{ pcy})) / (27 \text{cuf/cuy}) \text{ x} (1 \text{ cf/batch}) = \underline{21.11} \text{ lbs/batch}$
volume = $(21.11 \text{ lbs/batch}) / ((3.15) \text{ x} (62.4 \text{ pcf})) = \underline{0.1074} \text{ cf/batch}$

Total Cementitious:

weight = 150 lbs (FA -Class F) + 55 lbs (SF - F 10,000) + 570 lbs (Type III Cement) =
$$\underline{775}$$
 lbs

volume =
$$1.0683$$
 cf (FA - Class F) + 0.4006 cf (SF - F $10,000$) + 2.8998 cf (Type III Cement) = 4.37 cf

WRDA 35:

volume = (7 fl oz/100 wt) x ((775 / 100) 100 wt/cy) =
$$\underline{54.25}$$
 fl oz/cy
volume = (54.25 fl oz/cy) x (1 cf/batch) / (27 cf/cy) = $\underline{2.009}$ fl oz/batch
volume = (54.25 fl oz/cy) / (957.5065 fl oz/cf) = $\underline{0.05666}$ cf/cy
volume = (.05666 cf/cy) x (1 cf/batch) / (27 cf/cy) = $\underline{0.00210}$ cf/batch
volume = (.00210 cf/batch) x (28316.8466 ml/cf) = $\underline{59.42}$ ml/batch

ADVA Flow:

volume = (8 fl oz/100 wt) x ((775 / 100) 100 wt/cy) =
$$\underline{62}$$
 fl oz/cy
volume = (62 fl oz/cy) x (1 cf/batch) / (27 cf/cy) = $\underline{2.296}$ fl oz/batch
volume = (62 fl oz/cy) / (957.5065 fl oz/cf) = $\underline{0.06475}$ cf/cy
volume = (.06475 cf/cy) x (1 cf/batch) / (27 cf/cy) = $\underline{0.00239}$ cf/batch
volume = (.00239 cf/batch) x (28316.8466 ml/cf) = $\underline{67.909}$ ml/batch

Total Admixtures: By using the milliliters of admixtures and the specific gravities, a weight of equivalent water can be found.

equivalent water mass = 59.42 ml (WRDA 35) x (1.199) =
$$71.2446$$
 g
equivalent water mass = 67.909 ml (ADVA Flow) x (1.043) = 70.8291 g
total equivalent water mass = 71.2466 g (WRDA 35) + 70.8291 g (ADVA Flow) = 142.0757 g
weight = (142.0757 g) x (1 oz / 28.3498 g) x (1 lb / 16 oz) = 0.3132 lb
volume = .05666 cf (WRDA 35) + .06475 cf (ADVA Flow) = 0.121 cf

Water:

volume of water per cy = 27 cf - vol_{aggregate} - vol_{cement} - vol_{admixture} - vol_{air}
volume of air (4 %) = (.04) x (27 cf/cy) = 1.08 cf/cy
volume of water = 27 cf - 17.20 cf - 4.37 cf - 0.121 cf - 1.08 cf =
$$4.233$$
 cf/cy
volume of water = 1.0 cf - 0.64 cf - 0.16 cf - 0.004 cf - 0.04 = 0.152 cf/batch
weight = (4.233 cf/cy) x (62.4 pcf) = 264.1392 pcy
weight = (264.1392 pcy) x (1 cf/batch) x (1 cy / 27 cf) = 9.783 lbs/batch

Final Mix Design: The additions of WRDA 35, ADVA Flow and water need to be accounted for when reporting the final mix design

Final FA - Class F weight =
$$(150 \text{ lbs}) / (1.008066) = \underline{148.80} \text{ lbs}$$

Final SF - F 10,000 weight =
$$(55 \text{ lbs}) / (1.008066) = \underline{54.55} \text{ lbs}$$

Final Type III Cement weight =
$$(570 \text{ lbs}) / (1.008066) = \underline{565.44} \text{ lbs}$$

Final WRDA 35 volume =
$$(7 \text{ fl oz}/100 \text{ wt}) + (10 \text{ ml/cf}) \times (27 \text{ cf/cy}) \times (1 \text{ fl oz}/29.5735 \text{ ml}) \times (1 \text{ cy}/775 \text{ lb}) \times (100 \text{ lb}/\text{per }100 \text{ wt}) = \frac{8.178}{100} \text{ fl oz}/100 \text{ wt}$$

Final WRDA 35 volume =
$$(8 \text{ fl oz/100 wt}) + (5 \text{ ml/cf}) \times (27 \text{ cf/cy}) \times (1 \text{ fl oz/} 29.5735 \text{ ml}) \times (1 \text{ cy/} 775 \text{ lb}) \times (100 \text{ lb/per } 100 \text{ wt}) = 8.589 \text{ fl oz/100 wt}$$

Final admixture water equivalent weight =
$$(8.178 \text{ fl oz}) \times (1.199) + (8.589 \text{ fl oz}) \times (1.043) = 18.76719 \text{ fl oz of water}$$

Final admixture weight = $(18.76719 \text{ fl oz}) \times (768 \text{ lbs} / 100 \text{ lbs}) \times (29.5735 \text{ ml/fl})$ oz) $\times (.002205 \text{ lb/ml}) = 9.397 \text{ lbs}$

Final Water weight =
$$((267.1 \text{ lbs}) + (.5 \text{ lb}) \times (1 / 1\text{cf}) \times (27 \text{ cf/cy})) \times (1 / (1 + .0085) = 275.3 \text{ lbs}$$

Final Air Content = $4 \% \times (1 / (1 + .0085)) = 3.97 \%$

Cost:

NW Sand	$= (1205.28 \text{ lbs}) \times (\$0.0054/\text{lbs})$	= 9	6.48
1/2" - LWA	$= (937.44 \text{ lbs}) \times (\$0.0276/\text{lbs})$	= \$	\$ 25.86
FA - Class F	= (148.80 lbs) x (\$0.03/lbs)	= \$	4.46
SF - F 10,000	$= (54.55 \text{ lbs}) \times (\$0.05/\text{lbs})$	= \$	2.73
Type III Cement	$= (565.44 \text{ lbs}) \times (\$0.044/\text{lbs})$	= \$	\$ 24.87
WRDA 35	= $(8.18 \text{ fl oz}/100 \text{ wt}) \times (7.6879**) \times (\$0.05)$	= \$	3.14
ADVA Flow	= $(8.59 \text{ fl oz}/100 \text{ wt}) \times (7.6879**) \times (\$0.1197/\text{fl oz})$) = \$	7.90
Water	$= (275.3 \text{ lb}) \times (\$0.0013/\text{gal}) / (8.34 \text{ lbs/gal})$	= 9	0.04
Total		\$	75.48

Water/Cementitious Ratio = $(275.3 \text{ lbs}) / (768.79) = \underline{0.358}$

Unit Weight = (aggregate wt + cement wt + admixture wt + water wt)/ 27
=
$$((2142.7 \text{ lbs}) + (768.4 \text{ lbs}) + (9.40 \text{ lbs}) + (275.3 \text{ lbs})) / 27 = 3195.8$$

= 118.3 lbs/cf

^{**} The number of 100 weight of cement in the cubic yard

APPENDIX C

MATERIAL PROPERTIES

This Appendix contains material property data in the sections listed below.

- C.1 HSLC material properties used in evaluating modulus of elasticity equations in Chapter 7.
- C.2 Tension test results of #4 bar reinforcing steel used for all shear stirrups.
- C.3 Tension test results of #3 bar reinforcing steel used for "doghouse" bars in the transfer region.

C.1 Material Properties for Modulus of Elasticity Specimens

Table C.1 16-Hour Curebox Cured Specimens

Specimen	Wet Unit	As-Tested	Compression	Modulus of
Identification	Weight	Unit Weight	Strength (4 x 8)	Elasticity
	(pcf)	(pcf)	(psi)	(psi)
8F-1	118.6	117.9	7,920	3,407,479
8F-2	118.6	117.9	7,920	3,530,161
8F-3	118.6	117.9	7,920	3,515,616
10F-1	121.0	120.3	7,710	3,427,358
10F-2	121.0	120.3	7,710	3,430,741
10F-3	121.0	120.3	7,710	3,572,510
12F-1	124.0	123.3	10,990	3,998,394
12F-2	124.0	123.3	10,990	3,592,513
12F-3	124.0	123.3	10,990	4,161,776
8L-1	122.0	121.3	7,320	3,458,627
8L-2	122.0	121.3	7,320	3,658,242
8L-3	122.0	121.3	7,320	3,467,933
12L-1	122.8	122.1	9,840	4,058,913
12L-2	122.8	122.1	9,840	4,019,955
12L-3	122.8	122.1	9,840	4,167,468

Table C.2 24-Hour Curebox Cured Specimens

Specimen	Wet Unit	As-Tested	Compression	Modulus of
Identification	Weight	Unit Weight	Strength (4 x 8)	Elasticity
	(pcf)	(pcf)	(psi)	(psi)
G1A-1-24	118.7	117.7	7,093	3,386,729
G1A-2-24	118.7	117.7	7,093	3,524,518
G1A-3-24	118.7	117.7	7,093	3,508,675
G1B-1-24	119.8	118.8	5,915	2,975,988
G1B-2-24	119.8	118.8	5,915	3,005,111
G1B-3-24	119.8	118.8	5,915	3,032,753
G2A-1-24	120.0	119.0	9,807	3,789,901
G2A-2-24	120.0	119.0	9,807	3,745,692
G2A-3-24	120.0	119.0	9,807	3,109,247
G2B-1-24	114.0	113.0	8,313	3,963,880
G2B-2-24	114.0	113.0	8,313	3,865,080
G2B-3-24	114.0	113.0	8,313	3,888,308
8F-4	118.6	117.6	8,870	3,577,737
8F-5	118.6	117.6	8,870	3,673,648
8F-6	118.6	117.6	8,870	3,747,778
10F-4	121.0	120.0	9,750	3,744,977
10F-5	121.0	120.0	9,750	3,686,261
10F-6	121.0	120.0	9,750	3,801,950
12F-4	124.0	123.0	11,490	4,139,841
12F-5	124.0	123.0	11,490	4,188,613
12F-6	124.0	123.0	11,490	4,031,863
8L-4	122.0	121.0	7,730	3,748,723
8L-5	122.0	121.0	7,730	3,688,108
8L-6	122.0	121.0	7,730	3,558,556
12L-4	122.8	121.8	11,101	4,224,670
12L-5	122.8	121.8	11,101	4,262,995
12L-6	122.8	121.8	11,101	4,262,688

Table C.3 28-Day Curebox Cured Specimens

Specimen	Wet Unit	As-Tested	Compression	Modulus of
Identification	Weight	Unit Weight	Strength (4 x 8)	Elasticity
	(pcf)	(pcf)	(psi)	(psi)
8F-7	118.6	116.6	9,830	3,890,477
8F-8	118.6	116.6	9,830	3,849,350
8F-9	118.6	116.6	9,830	3,806,191
10F-7	121.0	119.0	10,430	4,016,648
10F-8	121.0	119.0	10,430	4,684,482
10F-9	121.0	119.0	10,430	4,043,618
10F-10	121.0	119.0	10,430	4,120,260
12F-7	124.0	122.0	11,460	4,361,462
12F-8	124.0	122.0	11,460	4,331,051
12F-9	124.0	122.0	11,460	4,207,477

Table C.4 56-Day Curebox Cured Specimens

Specimen	Wet Unit	As-Tested	Compression	Modulus of
Identification	Weight	Unit Weight	Strength (4 x 8)	Elasticity
	(pcf)	(pcf)	(psi)	(psi)
G1A-1-56	118.7	116.2	9,084	3,814,994
G1A-2-56	118.7	116.2	9,084	3,901,364
G1A-3-56	118.7	116.2	9,084	3,877,308
G1B-1-56	119.8	117.3	7,750	3,302,301
G1B-2-56	119.8	117.3	7,750	3,247,403
G1B-3-56	119.8	117.3	7,750	3,295,650
G2A-1-56	120.0	117.5	10,418	4,036,274
G2A-2-56	120.0	117.5	10,418	3,874,421
G2A-3-56	120.0	117.5	10,418	3,891,948
G2B-1-56	114.0	111.5	10,249	4,076,345
G2B-2-56	114.0	111.5	10,249	4,184,515
G2B-3-56	114.0	111.5	10,249	4,029,685
8F-10	118.6	116.1	10,600	3,875,411
8F-11	118.6	116.1	10,600	3,671,790
8F-12	118.6	116.1	10,600	4,016,215
10F-11	121.0	118.5	11,170	4,195,290
10F-12	121.0	118.5	11,170	4,176,745
10F-13	121.0	118.5	11,170	3,861,762
12F-10	124.0	121.5	11,550	4,209,773
12F-11	124.0	121.5	11,550	4,276,240
12F-12	124.0	121.5	11,550	4,295,494
8L-7	119.4	116.9	10,430	4,034,355
8L-8	119.4	116.9	10,430	4,040,931
8L-9	119.4	116.9	10,430	3,990,007
10L-1	122.4	119.9	9,920	4,104,663
10L-2	122.4	119.9	9,920	4,067,865
10L-3	122.4	119.9	9,920	4,075,294
12L-7	121.7	119.2	10,860	4,207,700
12L-8	121.7	119.2	10,860	4,207,945
12L-9	121.7	119.2	10,860	4,304,298

Table C.5 56-Day ASTM Cured Specimens

Specimen	Wet Unit	As-Tested	Compression	Modulus of
Identification	Weight	Unit Weight	Strength (4 x 8)	Elasticity
	(pcf)	(pcf)	(psi)	(psi)
G1A-1-ASTM-56	118.7	116.2	9,352	3,875,746
G1A-2-ASTM-56	118.7	116.2	9,575	3,774,216
G1A-3-ASTM-56	118.7	116.2	9,834	4,096,713
G1A-4-ASTM-56	118.7	116.2	8,715	3,593,701
G1A-5-ASTM-56	118.7	116.2	9,252	3,816,347
G1B-1-ASTM-56	119.8	117.3	8,063	3,623,900
G1B-2-ASTM-56	119.8	117.3	8,252	3,328,719
G1B-3-ASTM-56	119.8	117.3	9,056	3,740,114
G2A-1-ASTM-56	120.0	117.5	10,377	3,984,773
G2A-2-ASTM-56	120.0	117.5	11,377	3,927,559
G2A-3-ASTM-56	120.0	117.5	11,369	4,297,258
G2A-4-ASTM-56	120.0	117.5	10,555	4,131,074
G2A-5-ASTM-56	120.0	117.5	10,405	3,979,495
G2B-1-ASTM-56	114.0	111.5	10,244	4,283,444
G2B-2-ASTM-56	114.0	111.5	10,826	3,912,993
G2B-3-ASTM-56	114.0	111.5	10,523	3,964,648
8F-13	118.6	116.1	11,090	4,059,005
8F-14	118.6	116.1	11,090	4,272,725
8F-15	118.6	116.1	11,090	4,051,198
10F-14	121.0	118.5	11,300	4,273,372
10F-15	121.0	118.5	11,300	4,353,486
10F-16	121.0	118.5	11,300	4,163,007
12F-13	124.0	121.5	11,620	4,344,719
12F-14	124.0	121.5	11,620	4,535,964
12F-15	124.0	121.5	11,620	4,313,065
8L-10	119.4	116.9	10,520	4,382,289
8L-11	119.4	116.9	10,520	4,461,557
8L-12	119.4	116.9	10,520	4,318,485
10L-4	122.4	119.9	11,040	4,406,935
10L-5	122.4	119.9	11,040	4,285,072
10L-6	122.4	119.9	11,040	4,283,424
12L-10	121.7	119.2	11,480	4,429,366
12L-11	121.7	119.2	11,480	4,304,119
12L-12	121.7	119.2	11,480	4,262,217

C.2 Tension Test Results of Steel Used for Shear Stirrups




Figure C.1 Stress vs. Strain Plot for Shear Reinforcement Steel

C.3 Tension Test Results of Steel Used for "Doghouse Bars"




Figure C.2 Stress vs. Strain Plot for "Doghouse Bar" Reinforcement Steel

APPENDIX D

GIRDER DESIGN SPREADSHEET

Appendix D contains the individual pages from the Girder Design Spreadsheet.

The entire set of worksheet pages is provided from the design of girder test G1C-West.

The pages are listed in the order the calculations occur. All calculations are based on the 1996 AASHTO⁴⁰ Standard Specification for Highway Bridges. A similar series of worksheets was prepared for each girder test to determine girder test design characteristics. Listed below are the individual worksheets within the overall spreadsheet and a brief description of the worksheet's function. The Tables are all placed at the end of this Appendix.

Table D.1 - Section and Material Properties for Girder Design

Table D.2 – Support Conditions, Calculation of M_f and P_u – Worksheet used to specify support conditions and determine predicted ultimate load.

Table D.3 – Predicted Loss

Table D.4 – Non-Composite Girder Stress Calculations

Table D.5 - Composite Girder Stress Calculations

Tables D.6 and D.7 - Shear Design Calculations

Table D.8 - Deck / Girder Interface Shear Calculations

Below is a description of each page of the spreadsheet. The general concept of the spreadsheet was to determine the flexural capacity based on the selected girder and strand pattern, then design the shear reinforcement to allow reaching the flexural capacity. Interface shear was checked as a precaution to insure no problems would occur during testing.

D.1 Assumptions for Using Spreadsheet

This spreadsheet assumed the prestressed girder had straight prestressing strand.

The strand could be set at any height, but was assumed to be straight. It was not possible to drape the strands within this spreadsheet. A possible modification to provide better flexibility in the spreadsheet would be to include this option.

D.2 Worksheet 1 - Section and Material Properties for Girder Design

Worksheet 1 seen in Table D.1 allowed the user to enter variable data describing the girder's section and material properties. Following user-entered variables, the spreadsheet calculated values as follows.

The modulus of elasticity was based on the entered unit weight value. A unit weight greater than 135 pcf triggered the use of equation 3.1. A unit weight less than or equal to 135 pcf triggered the use of equation 3.3.

The modular ratio, η , was calculated using equation D.1.

$$\eta = \frac{E_{c-Deck}}{E_{c-Girder}} \tag{D.1}$$

The non-composite girder properties (girder only) were hard-wired into the spreadsheet and triggered by user entry of the AASHTO or PCI Bulb Tee Type. The weight per foot of the girder was calculated based on the girder cross sectional area times the estimated equilibrium weight of the concrete. An allowance was incorporated into the worksheet where the user could enter a value for the added weight of steel (prestressed and non-prestressed) per cubic foot of concrete. This value was assumed to be 3 pcf for each girder design.

Composite girder properties were calculated as follows assuming full composite action between the girder and deck. The composite moment of inertia, I_c , was calculated using equations D.2 and D.3.

$$I_c = I_{nc} + A_{nc}(y_{bot-c} - y_{bot-nc})^2 + \frac{1}{12}\eta W_f t_d^3 + (\eta W_f t_d)(\frac{t_d}{2} + h_{g-nc} - y_{bot-c})^2$$
 (D.2)

$$y_{bol-c} = \frac{A_{g-nc}y_{bol-nc} + \eta W_f t_d (h_{g-nc} + \frac{t_d}{2})}{A_{g-nc} + \eta W_f t_d}$$
(D.3)

The remaining composite girder properties were calculated using equations D.4 through D.8.

$$y_{top-c} = h_{g-nc} - y_{bot-c} \tag{D.4}$$

$$S_{bot-c} = \frac{I_c}{y_{bot-c}} \tag{D.5}$$

$$A_{g-c} = A_{g-nc} + \eta W_f t_d \tag{D.6}$$

$$Q_{d} = (\eta W_{f} t_{d}) (\frac{t_{d}}{2} + y_{top-c})$$
 (D.7)

$$h_{g-c} = h_{g-nc} + t_d \tag{D.8}$$

The composite girder weight per foot was the combined weight of the noncomposite girder, the deck and the specified steel allowance.

The depth to prestressing steel, d_p , was calculated using equations D.9 and D.10.

$$d_{p} = MAX(h_{g-nc} + t_{d} - (y_{bot-nc} + e), 0.8h_{g-c})$$
(D.9)

$$e = \frac{\sum F_{ps} d}{\sum F_{ps}} - y_{bol-nc} \tag{D.10}$$

The variable "e" described the location of the centroid of the prestressing force in reference to the non-composite girder centroid. A negative value of "e" indicated the prestressing force centroid was below the non-composite centroid.

The predicted strand development length, l_d , was calculated using AASHTO⁴⁰ equation (9-32) shown in equation D.11 below.

$$l_d = (f_{ps} - \frac{2}{3} f_{se}) d_b \tag{D.11}$$

The predicted strand transfer length, l_t , was calculated using the AASHTO⁴⁰ specified $50*d_b$.

D.3 Worksheet 2 - Supports, Applied Load and Moment Furnished

Worksheet 2 shown in Table D.2 provided the user a visual image of the girder with support locations and location of point load application. This page allowed the user to input values describing the location of the left and right support and the location at which the point load was applied. Based on this input, the spreadsheet adjusted the support locations, determined the moment furnished at all points along the girder based on the number of prestressing strands developed, then determined the maximum point load, based on flexural capacity, that could be applied at the location specified. The spreadsheet accounted for the self-weight of the girder and deck in determining the maximum point load and also calculated the support reactions.

At the lower right portion of the page were values required to calculate the maximum furnished moment. This section of Worksheet 2 determined, based on user input on the girder and deck characteristics, whether the girder was "under" or "over" reinforced and whether "a" was within the deck. The spreadsheet provided calculations

for all combinations except "over" reinforced and "a" being greater than the deck thickness. The desired condition for this research was to be under-reinforced and to have "a" within the deck. Equations D.12 through D.18 were used to determine the moment furnished.

$$f_{ps} = f_{pu} \left(1 - \frac{\gamma_p \rho_p f_{pu}}{\beta_1 f_c'} \right) \tag{D.12}$$

$$\gamma_p = 0.55 \ for \frac{f_{py}}{f_{pu}} \ge 0.80, 0.40 \ for \frac{f_{py}}{f_{pu}} \ge 0.85, 0.28 \ for \frac{f_{py}}{f_{pu}} \ge 0.90$$
 (D.13)

$$\rho_{p} = \frac{A_{ps}}{bd_{p}} \tag{D.14}$$

$$\beta_1 = 0.85 - (f_c' - 4,000)0.05 \ge 0.65$$
 (D.15)

$$\varpi_p = \frac{\rho_p f_{ps}}{f_{c-Dec^k}'} \tag{D.16}$$

If ω_p was less than $0.36\beta_1$, the girder was considered under-reinforced. The rectangular stress block depth, "a" was determined based on the composite girder characteristics. If "a" was less than the deck thickness, the girder was considered a rectangular section and the moment furnished (nominal moment) was calculated using equation D.17.

$$M_n = A_{ps} f_{ps} (d_p - \frac{a}{2})$$
 (D.17)

If "a" was greater than the deck thickness, the moment furnished (nominal moment) was calculated using equation D.18.

$$M_n = 0.85 f'_{c-Dk} t_d W_f (d_p - \frac{a}{2}) + 0.85 f'_{c-Girder} \left(W_{f-Girder} (a - t_d) \left(d_p - t_d - \frac{(a - t_d)}{2} \right) \right)$$
 (D.18)

D.4 Worksheet 3 – Loss Calculations

Worksheet 3 as shown in Table D.3 provided loss calculations based on procedures specified in the 1996 AASHTO⁴⁰ Specification. The losses were divided into three groups. The first group included elastic shortening (ES) and initial steel relaxation (R) losses experienced at the time prestressing strands were released. The second group included creep (CR), shrinkage (S) and additional steel relaxation (R) experienced from the time of strand release until the time of deck placement. The third and final group included additional steel relaxation (R) and creep (CR) that occurred in the time between deck placement and testing. The user had only limited input on this page. It was necessary for the user to input an assumption for the percent of losses due to elastic shortening (ES) which occurred at the time the prestressing strand was cut. It was necessary for the user to iterate this guess until the assumed amount and the actual amount were within 0.1 percent of each other. A good initial assumption was around six

percent. It was also necessary for the user to input percentages of steel relaxation that occurred during the different stages. If the user-entered percentages did not total 100, the spreadsheet automatically indicated an error was made. At the bottom of the sheet, a consolidated listing was provided showing the effective levels of prestress at the different stages of the girder's construction sequence. Losses were calculated using equations D.19 through D.22.

$$ES = \frac{E_{ps}}{E_{ci-g}} \left(\frac{P_i}{A_{g-nc}} \left(1 + \frac{e^2}{r_{nc}^2} \right) - \frac{M_D e}{I_{nc}} \right)$$
 (D.19)

$$CR = 12 \left(\frac{P_i}{A_{g-nc}} \left(1 + \frac{e^2}{r_{nc}^2} \right) - \frac{M_D e}{I_{nc}} \right) + 7 f_{cds}$$
 (D.20)

In the case of the test girders, f_{cds} , the stress at the centroid of the prestressing strand was zero at the time of deck placement. At testing, f_{cds} was no longer zero based on the addition of the deck. An additional creep component, although small, was added at that stage.

$$SH = (17,000 - 150RH)$$
 (D.21)

$$R = 5000 - 0.10ES - 0.05(SH + CR)$$
 (D.22)

Steel relaxation losses were broken into three pieces including "initial", "at deck placement" and "at testing." Percentages were assigned to each particular component as deemed appropriate.

D.5 Worksheet 4 - Non-Composite Stress Calculations (Stages 1 and 2)

Worksheet 4 as shown in Table D.4 provided stresses at the TOP and BOTTOM of the girder at the 20th points at stages 1 (Strand Release) and 2 (Deck Placement). Shown on the girder were the values of girder self-weight and deck self-weight. Included in the self-weight values was a small component due to the weight of the reinforcing and prestressing steel. This value was entered on Worksheet 1 as the Steel Weight Allowance per Cubic Foot. The stresses were broken down by axial component, strand eccentricity (F*e) component, and dead load (DL) component. The stress level used at stage 1 was the effective prestress after elastic shortening (ES) and initial strand relaxation (R) losses occurred. The stress level used at stage 2 was the effective prestress after all losses occurred except final strand relaxation and final creep losses. The stress levels at the various stages can be seen on Worksheet 3, Table D.3 at the bottom left corner. In order to calculate the stress level at a given 20th point, the spreadsheet calculated the transfer length on Worksheet 1 then determined the number of strands developed. Throughout the sheet, negative (-) values indicate compression stress and positive (+) values indicate tension stress. Equations D.23 and D.24 were used to calculate stresses at the top and bottom of the non-composite girder at stages 1 and 2.

$$f_{top} = -\frac{F_{se}}{A_{g-nc}} - \frac{F_{se}e}{S_{top-nc}} - \frac{M_{DL}}{S_{top-nc}}$$
 (D.23)

$$f_{bot} = -\frac{F_{se}}{A_{g-nc}} + \frac{F_{se}e}{S_{bot-nc}} + \frac{M_{DL}}{S_{bot-nc}}$$
 (D.24)

The values of F_{se} and M_{DL} were different between the two stages. Fse became less over time. M_{DL} was the weight of the girder only for stage 1. For stage 2, it was the weight of the girder and the deck.

D.6 Worksheet 5 - Composite Stress Calculations (Stage 3)

Worksheet 5 shown in Table D.5 provided calculations of composite stresses at the top and bottom of the girder and slab at time of testing. The stresses were broken down by axial component, strand eccentricity (F*e) component, dead load (DL) component, and live load (LL) component. The stress level used at stage 3 was the effective prestress after all losses occurred. The live load component reflected stresses resulting from the point load application. Determination of the number of strands developed was based on the strand development length specified in Worksheet 1.

Moment values shown were listed in ft-kips. The support condition number indicated the position of the supports. A support condition number "1" indicated the supports were located at the ends of the girder offset by the X-DIST. A support condition "2" indicated the right-side support was moved in from the end forming a cantilever. A support condition "3" indicated both the left and right side supports were moved in from their

respective ends forming a double-cantilevered girder. The spreadsheet referred to these support condition numbers when determining the dead load moment values. As a note, these support condition numbers were not shown on the non-composite stress calculations page since at stages 1 and 2 the girder was supported at its centers of bearing (COB). Only during testing would the supports be moved to other than the end center of bearing locations. Equations D.25 and D.26 were used to calculate stresses at top and bottom of the girder at stage 3.

$$f_{top} = -\frac{F_{se}}{A_{g-nc}} - \frac{F_{se}e}{S_{top-nc}} - \frac{M_{DL}}{S_{top-nc}} - \frac{M_{LL}}{S_{top-c}}$$
(D.25)

$$f_{bot} = -\frac{F_{se}}{A_{g-nc}} + \frac{F_{se}e}{S_{bot-nc}} + \frac{M_{DL}}{S_{bot-nc}} + \frac{M_{LL}}{S_{bot-c}}$$
(D.26)

The stresses at the top and bottom of the deck were calculated based on the live load moment only using equations D.27 and D.28.

$$f_{top} = -\frac{M_{LL}(y_{top-c} + t_d)}{I_c}$$
 (D.27)

$$f_{bot-Deck} = -\frac{M_{LL} y_{top-c}}{I_c} \tag{D.28}$$

D.7 Worksheet 6 - Girder Shear Design (Left of Load)

Worksheet 6 shown in Table D.6 performed shear design calculations for the section of the girder at 10^{th} points from the left support to the point load based on the 1996 AASHTO⁴⁰ Specification. The distance from the left support to the point load was "a." Values of M_u and V_u were calculated at each point based on all dead and live loads. The value of M_u at the point load location was the same as the maximum furnished moment if all strands were developed at that point. V_{ci} (flexure shear strength) and V_{cw} (web shear strength) were calculated to determine the concrete strength component V_c using equations D.29 through D.32. V_c was the minimum of the V_{ci} and V_{cw} values.

$$V_{ci} = 0.6\lambda \frac{\sqrt{f_c'}}{1000}bd_p + V_d + \frac{V_i M_{cr}}{M_{max}} \ge 1.7\lambda \frac{\sqrt{f_c'}}{1000}bd_p$$
 (D.29)

$$M_{cr} = \frac{I}{Y_t} (6\lambda \frac{\sqrt{f_c'}}{1000} + f_{pe} - f_d)$$
 (D.30)

$$V_{cw} = (3.5\lambda \frac{\sqrt{f_c}}{1000} + 0.3f_{pc})bd_p + V_p$$
 (D.31)

$$f_{pc} = \frac{F_{se}}{A_{nc}} - \frac{F_{se}e(y_{bot-c} - y_{bot-nc})}{I_{nc}} - \frac{M_{DL}(y_{bot-c} - y_{bot-nc})}{I_{nc}}$$
(D.32)

Based on the required shear, V_u , the spreadsheet determined the shear to be carried by shear stirrups, V_s , using equation D.33.

$$V_s = \frac{V_u - V_c}{\phi_s} \tag{D.33}$$

The required minimum stirrup spacing, s, was calculated based on several criteria as specified in equations D.34 through D.35. If $V_s > 8$ (f_c ')^{1/2} bd_p , web crushing was considered a potential a problem. The girder section was not adequate to handle the shear force. If $V_s > 4$ (f_c ')^{1/2} bd_p , the value from D.34 was divided by 2. The resulting minimum stirrup spacing was the minimum of equations D.34 and D.35.

$$s_{\text{max}} = MAX(0.75h_{g-c}, 24 \text{ inches})$$
 (D.34)

$$s = \frac{A_{\nu} f_{\nu} d_{p}}{V_{s}} \tag{D.35}$$

D.8 Worksheet 7 - Girder Shear Design (Right of Load)

Worksheet 7 shown in Table D.7 performed the same calculations as Worksheet 6 at 10th points from the load to the right support. The distance from the load to the right support was "b."

D.9 Worksheet 8 – Interface Shear Check

Worksheet 8 shown in Table D.8 performed calculations to insure adequate capacity existed at the interface between the girder and deck. The basic interface shear capacity, V_{nh} , was determined based on the condition of the surface of the girder and the contact area using equation D.36.

$$V_{nh} = v_{nh} A_c \tag{D.36}$$

$$A_{v-\min} = \frac{50bs}{f_v} \frac{1}{s}$$
 (D.37)

Based on the cleanliness and roughness of the contact surface and the inclusion of minimum shear reinforcement steel per linear inch of girder according to equation D.37, the spreadsheet listed the basic interface shear stress, v_{nh} , the maximum value being 350 psi. The contact area, A_c , was determined as the interface shear contact width (width of the top of girder in this case) multiplied by the contact length, d, which was the distance from the point load to the closest support or one tenth of the span length, L_1 , whichever was less. For this research, the length "d" was typically taken as one tenth of the span. The basic interface shear capacity was compared with the shear at the left support (worst case based on the configuration of this spreadsheet). If the basic capacity exceeded the worst-case shear, no further steel was required. If the basic capacity was inadequate, the added capacity of the shear steel was calculated.

The added capacity was calculated based on the amount of steel beyond the codespecified minimum in equation D.37. For every one percent of steel provided beyond the minimum, the interface shear capacity increased by an amount calculated in equation D.38.

Additional
$$V_{nh}$$
 per one % steel = $\left(\frac{160 f_y}{40,000}\right) bd$ (D.38)

In most cases, as was true in this research, the steel provided by minimum shear reinforcement more than satisfied the requirement. No additional steel was required to meet interface shear requirements.

On the right-hand side of worksheet 8 are calculations for tensile stress at the shear interface. These calculations were provided to check the resulting tensile stress under maximum live load for comparison with acceptable levels. Acceptable levels were defined as $7.5*\lambda*(f_c')^{1/2}$. For slab concrete which was assumed to be normal weight concrete, $\lambda=1$. For the girder which was constructed with HSLC, $\lambda=0.85$. Using a Mohr's circle calculation to determine tensile stress at the interface, the result was compared with the acceptable levels for both the slab and girder. If the tensile stress was less than both levels, the indicator window indicated, "Tensile Stress at Interface is OK."

Table D.1 Section and Material Properties for Girder Design

GIGWest			Section	Section and Material Properties for Pretensioned Girder Design	for P	retensi	oned	Gird	er Des	ign		
Deck Variables	sa			Elasticity Modulus Values	alues				Strand Data (No Drape)	ata (No	Drape)	
Deck Thickness	٦	JH.5%	Z	Deck Modulus	Ecd	3.41E+06	PSI	Ref. I	Dist. Nbr % fpu	nd y %	$\mathbf{F}_{\mathbf{p}s}$	$\mathbf{F}_{\mathbf{p}}\mathbf{d}$
Deck Width	Wr	· 6P	Z	Girder Modulus	Ecg	3.59E+06	PSI	#	# Z	%	KIP	KIP-IN
Concrete Strength	ټې	3500	PSI	Modular Ratio (E _{cd} /E _{cb})	և	0.950	None	TOP	33.5	1.75	87.89	2944.1
Concrete Weight	W	145	PCF	Non-Composite Girder Properties	ropertie	Ş		18	D.	500	0.00	0.0
Girder Cross Section Variables	Variable	•		Moment of Inertia	Inc	50979	Ľ.	17	j.	000	0.00	0.0
Girder Type		Jane Dave	1-5,BT	Distance from Centroid to Top of Beam	Үюр-вс	20.17	Z	16	.0	00.0	0.00	0.0
Girder Top Flange Width		* 77	Z	Distance from Centroid to Bot. of Beam	$Y_{\text{bot-nc}}$	15.83	Z	15	31.0	3	0.00	0.0
Concrete Design Strength	ړي.	8000	PSI	Section Modulus (Top)	S _{top-nc}	2527.47	EZ.	14	29.0	900	0.00	0.0
Concrete Equilibrium Weight	W	1160	PCF	Section Modulus (Bot)	S _{bot-пс}	3220.40	IN	13	27.0 0.72	000	0.00	0.0
% Concrete Strength at Release		*75%"	%	Cross Sectional Area	Ag-nc	369	$1N^2$	12	25.0 mg	000	0.00	0.0
LWC Reduction Factor	~	0.85	None	Weight per Foot (Concrete & Steel)	Wg-nc	0.305	K/FT	11	23.0	200	0.00	0.0
Strand Diameter	ę	*9.0	Z	Web Thickness	р	9	Z	10	21.0	900	0.00	0.0
Strand C/S Area	A	0,217.	N ₂	Height of Girder	h _{g-nc}	36	Z	6	19.0	000	0.00	0.0
Strand Ultimate Strength	¹	~270	KSI	Composite Girder Properties	perties			8	17.0	000	0.00	0.0
Strand Yield as % of Ultimate		0.0	None	Moment of Inertia	I.	142547.25	Z	7	15.0 0.51	8	0.00	0.0
Strand Modulus of Elasticity	퍤	28500	KSI	Distance from Centroid to Top of Beam	Ytop-c	10.84	Z	9	13.0 *10*	8	0.00	0.0
Stirrup Size		Cr4 Cr	#	Distance from Centroid to Bot. of Beam	Y _{bot-c}	25.16	Z	5	11.0	000	0.00	0.0
Stirrup Yield Strength	ť		KSI	Section Modulus (Bot)	Sbot-c	5664.62	ĘZ	4	9.0	S C	0.0	0.0
Distance from End to COB	XDIST	6.00	Z	Cross Sectional Area	Age	576.68	2	3	7.0	ğ	0.00	0.0
Percent Strand Ultimate at Jacking		.75%	%	Weight per Foot (Concrete & Steel)	Wg-c	0.5295	K/FT	7	5.0 CC	300	0.00	0.0
Top of Beam to Top Strands	TCL	2.50	Z	First Moment of Deck About Centroid	Õ	3444.42	ĘZ	-	3.0 .8	9	351.54	1054.6
Bottom of Beam to Bottom Strands	BCL	3.00	Z	Overall Depth of Composite Girder	h_{g-c}	47.5	Z	Ä	Eccentricity from NC Centroid	from N	C Centr	pid
Strand Spacing	SPAC	2.00	Z	Miscellaneous Properties	rties				Distance		-6.73	Z
Miscellaneous Variables Normally		Constant		Stirrup Area	A	0.4	IN^2	0 2	Strand Development Length	elopme	nt Lengi	h
Steel Weight Allowance / Cubic Ft		3.0	PCF	Depth to Prestressing Steel	đ,	38.4	Z	AASI	AASHTO-STD (96)	(96)	96.14	Z
Prestress stress for la calculation	t _y	270+	KSI	Ratio of Prestressed Reinforcement	ρ	0.0030	None	Dist.	Dist. from Bearing	ing	90.14	Z
Shear Strength Reduction Factor	ě	1.00	None	Strand Yield to Ultimate Factor	γ _p	0.28	None		Strand Transfer Length	ransfer	Length	
Flexural Strength Reduction Factor	φ ^r	1.00	None	Ratio of a/c (Based on Deck Concrete)	βι	0.85	None	AASI	AASHTO-STD (96)	(96)	38.04	Z

Table D.2 Support Conditions, Calculation of Moment Furnished and Predicted Ultimate Load

BRNG 0.000 0	G1C-West Support Conditions, Applied Load (KIP) and Moment Furnished (FT-KIP)	3 0.05L 0.10L 0.15L 0.20L 0.25L 0.30L 0.35L 0.40L 0.45L 0.50L 0.55L 0.60L 0.65L 0.70L 0.75L 0.80L 0.85L 0.90L 0.95L BRNG	2.10 4.20 6.30 8.40 10.50 12.60 14.70 16.80	25.20 50.40 75.60 100.80 126.00 151.20 176.40 201.60 226.80 252.00 277.20 302.40 327.60 352.80 378.00 403.20 428.40 453.60 478.80 504.00	Number of Strands Developed Assuming I _a	0.65 1.17 1.70 2.00 2.00 2.00 2.00 2.00 2.00 2.00 2.00 2.00 2.00 2.00 2.00 2.00 2.00 2.00 2.00 1.70 1.17 0.65 0.12	2.60 4.69 6.79 8.00 8.00 8.00 8.00 8.00 8.00 8.00 8.0	492.3 889.9 1287.5 1516.9	233	->	DECK		BEAM			upport R Support a Distance from left support to point load SSCO IN 7.08 FT M _r (Max) Calculations	action Reaction L, Distance from left support to right support 50400 IN 42.00 FT d, 38.40 IN	(KIPS) L ₂ Distance from left COB to left support 0.000 IN 0.00 FT	11.38 L Overall Length of Beam (COB-COB) 504.00 IN 42.00 FT	39.25 b Distance from point load to right support 419.0 IN 34.92 FT	A.85 50.63 L ₃ Distance from right support to right COB 0.0 IN 0.00 FT Beam is Under-reinforced	a/d Ratio of shear distance to depth 2.36 NA a < Deck Thickness	
G1C- BRNG 0. 0.00 2 0.00 2 0.00 2 94.7 49 PRACTION REACTION (KIPS) 11.38 193.46 204.85	-West	05L 0.10L	Н	\vdash		H	Н	_								-							
	G1C-	BRNG 0.0	Н	Н			Н	_						·	٥	L. Support	Reaction	(KIPS)	11.38	193.46	204.85		The second second

Table D.3 Loss Calculations

G1C-West				Prestressed Girder Loss Calculations	d Gir	der Los	S Calc	ulations			
Beam Values				ES-Elastic Shortening (Release)	ortening	(Release)		CR-Creep (Deck Placement)	Placen	ient)	
Girder Length (COB-COB)	L	42.00	FT	Radius of Gyration	$\Gamma_{\rm rc}^2$	138.2	IN ₂	Modular Ratio (Eps/Ecb)	η	7.95	None
Girder Cross Sectional Area	Ag-nc	369	IN^2	Initial Jacking Force	P _j	439.4	KIPS	Stress at Steel Centroid	f _{cir}	-1.385	KSI
NC Moment of Inertia	Inc	62605	ľ.	Est. Jacking Force Loss	OK	-5.7%	%	Addl. DL Since Release	W _{SD}	0000	K/FT
Top)	Stop-nc	2527.47	E E	Final Jacking Force	P_{i}	414.4	KIPS	Moment due to W _{SD}	M _{SD}	0.0	N-KIP
NC Section Modulus (Bot)	Sbot-nc	3220.40	EZ.	MAX Dead Load Moment	M _D	6.908	IN-KIPS	Stress at Steel Centroid	f _{esd}	0.000	KSI
Strand Eccentricity from NC Centroid	v	-6.73	Z	Stress at Steel Centroid	f _{cir}	-1.385	KSI	LWC Factor		1.0	None
NC Girder Weight / Foot (Concrete & Steel)	σM	0.305	K/FT	Modular Ratio (E _{ps} /E _{cig})	η	8.30	None	Creep Factor	K_{CR}	1.0	None
Deck Weight / Foot (Concrete & Steel)	WsD	0.225	K/FT	ES Losses (KSI - %)	Apes	-11.49	-5.7%	CR Losses (KSI - %)	$\Delta_{ m pCR}$	-16.62	-8.2%
				R-Steel Stress Relax (Release)	s Relax (Release)		CR-Creep (Testing)	[esting]		
				% Relax at Release		48°60E3	%	Modular Ratio (Eps/Ecb)	h	7.95	None
Steel Values				Time (Jack to Release)	trel	24	HRS	Stress at Steel Centroid	f_{cir}	-1.385	KSI
Area of Prestressing Steel	Aps	2.17	IN^2	R Losses (KSI - %)	Δ_{f_PR}	-0.81	-0.4%	Addl. DL Since Release	Wsp	0.725	K/FT
Strand Ultimate Strength	Ť.	270	KSI	R-Steel Stress Relax (Deck Placement)	lax (Dec	k Placement		Moment due to W _{SD}	M_{SD}	594.2	N-KIP
Strand Yield Strength	f_{py}	243	KSI	% Relax at Release		%00°	%	Stress at Steel Centroid	fcsd	0.078	KSI
Strand Modulus of Elasticity	Eps	28500	KSI	Time (Release to Slab)	tslab	30	DAYS	LWC Factor		1.0	None
Percent Strand Ultimate at Jacking	%	0.75	None	R Losses (KSI - %)	$\Delta_{ m fpR}$	-1.62	~8.0-	Creep Factor	Kcr	·0:1-	None
Strand Jacking Stress	f_{si}	202.5	KSI	R-Steel Stress Relax (Testing)	s Relax (Testing)		CR Losses (KSI - %)	$\Delta_{\rm fpCR}$	-0.55	-0.3%
				% Relax at Release	7	~~ 40*~	%	SH-Shrinkage (Deck Placement)	ck Plac	ement)	
				Time (Release to Test)	test	··· 09:=	DAYS	Shrinkage Factor	K_{SH}	-0-4	None
				R Losses (KSI - %)	$\Delta_{\rm fpR}$	-0.27	-0.1%	Relative Humidity	RH	~ 70 ~	%
Concrete Values				Steel Stress Relaxation Percentages-OK	ation Pe	rcentages-	ОК	SH Losses (KSI - %)	∆рѕн	-6.50	-3.2%
Girder Concrete Design Strength	f°,	0008	PSI			Consolid	ited Loss	Consolidated Loss Calculations			
Girder Design Modulus	Ecg	3.59E+06	PSI	Stage	Total	Total KSI Loss	% Loss	Remaining Prestress (KSI)		Losses	
% Girder Concrete Strength at Release		75%	%	1. At Release		-12.30	%9-	190.20	fps	ES & R	R
Girder Concrete Strength at Release	f_{ci}	0009	PSI	2. At Deck Placement		-37.03	-18%	165.47	f_{sc}	CR, SH & R	& R
Girder Modulus at Release	$\mathbf{E}_{\mathrm{cig}}$	3.43E+06	PSI	3. At Testing		-37.85	-19%	164.65	f_{se}	CR & R	8

Table D.4 Non-Composite Stress Calculations

est 0.10L 0.15L 4.20 6.30 50.40 75.60 2.00 8.00 8.00 8.00 8.00 8.00 8.00 1.099 0.099 0.099 0.099 0.099 0.0157 0.056 0.057 0.050 0.050 0.057 0.050 0.057 0.050 0.05	Non-Composite Girder Stresses at Stages 1 and 2 of Construction	0.55L 0.60L 0.65L 0.70L 0.75L 0.80L 0.85L 0.90L 0.95L BRNG	23.10 25.20 27.30 29.40 31.50 33.60 35.70 37.80 39.90 42.00	100.80 126.00 151.20 176.40 201.60 226.80 252.00 277.20 302.40 327.60 352.80 378.00 403.20 428.40 453.60 478.80 504.00	ed Assuming I,	2.00 2.00 2.00 2.00 2.00 2.00 2.00 2.00 1.64 0.32	8.00 8.00 8.00 8.00 8.00 8.00 8.00 8.00	K/FT	K/FT			te Beam due to Effective Prestress & Beam DL (At Release) After Initial Losses Have Occurred (ES & R) Assuming I, (KSI)	1.119 -1.119 -1.119 -1.119 -1.119 -1.119 -1.119 -1.119 -1.119 -1.119 -1.119	1.099 1.099 1.099 1.099 1.099 1.099 1.099 1.099 0.901 0.173	-0.863 -0.863 -0.863 -0.863	-0.316 -0.306 -0.291 -0.268 -0.239 -0.204 -0.163 -0.115 -0.061 0.000	-0.326 -0.310 -0.288 -0.259 -0.224 -0.182 -0.134 -0.077	-1.733 -1.741 -1.753 -1.771 -1.793 -1.821 -1.853 -1.891 -1.577 -0.312	posite Beam due to Effective Prestress & All Permanent DL after Slab Placement (ES, R, CR & SH) Assuming I, (KSI)	0.973 0.973 0.973 0.973 0.973 0.973 0.973 0.973 0.153	0.956 0.784	-0.750 -0.750 -0.750 -0.750 -0.750 -0.750 -0.750 -0.750 -0.615 -0.118	-0.504 -0.466 -0.416	0.431 0.418 0.396 0.365 0.326 0.278 0.222 0.157 0.083 0.000	-0.549 -0.521 -0.483 -0.433 -0.372	-1.293 -1.306 -1.328 -1.358 -1.397 -1.445 -1.502 -1.567 -1.331 -0.272
		0.10L 0.15L 0.20L 0.25L	2.10 4.20 6.30 8.40 10.50 12.60 14.70	25.20 50.40 75.60	Numbe	1.64 2.00 2.00 2.00 2.00 2.00 2.00	6.56 8.00 8.00 8.00 8.00 8.00 8.00	DIG	BEAN	V	∇		-0.917 -1.119 -1.119 -1.119 -1.119 -1.119	0.901 1.099 1.099 1.099 1.099 1.099	-0.707 -0.863 -0.863 -0.863 -0.863 -0.863 -0.863	0.048 0.090 0.128 0.160 0.188 0.210 0.228	-0.077 -0.134 -0.182 -0.224 -0.259 -0.288 -0.310	-1.577 -1.891 -1.853 -1.821 -1.793 -1.771 -1.753	Stresses in Non-Composite Beam due to Effective Prest	-0.798 -0.973 -0.973 -0.973 -0.973 -0.973 -0.973	0.784 0.956 0.956 0.956 0.956 0.956 0.956	-0.615 -0.750 -0.750 -0.750 -0.750 -0.750 -0.750	-0.105 -0.200 -0.283 -0.355 -0.416 -0.466 -0.504	0.083 0.157 0.222 0.278 0.326 0.365 0.396	-0.119 -0.217 -0.300 -0.372 -0.433	-1.331 -1.567 -1.502 -1.445 -1.397

Table D.5 Composite Stress Calculations

	EI	G1C-West	est				ت		site 1	Beam	Stres	Composite Beam Stresses at Stage 3 of Construction (Testing)	Stage	e 3 of	Cons	truct	ion (Testin	ng)		
REF	BRNG	BRNG 0.05L 0.10L	0.10L	0.15L	0.20L	0.25L		0.351	0.40	0.451	0.501	0.30L 0.35L 0.40L 0.45L 0.50L 0.55L 0.60L 0.65L 0.70L 0.75L 0.80L 0.85L 0.90L 0.95L BRNG	0.60L	0.65L	0.70L	0.75L	0.80L	0.85L	0.90L	0.95L	BRNG
FT	0.00	2.10	4.20	6.30	8.40	10.50	12.60	14.70	08.91	18.90	0 21.00	23.10	25.20	27.30	29.40	31.50	33.60	35.70 37.80		39.90	42.00
									Numbe	r of Stra	inds Dev	Number of Strands Developed Assuming Id	suming	٩							
# Top	0.12	0.65	1.17	1.70	2.00	2.00	2.00	2.00	0.00	2.00	0.00	2.00	2.00	2.00	2.00	2.00	2.00	1.70	1.17	9.65	0.12
# Bot	0.50	2.60	4.69	6.79	8.00	8.00	8.00	8.00	8.00	8.00	8.00	8.00	8.00	8.00	8.00	8.00	8.00	6.79	4.69	2.60	0.50
Max				233																	
Load				->																	
CIIDT									DECK		0 2246	L/ET									
100																					
-									BEAM		0.3049	K/FT									
	Ø																				þ
Mpr	0.0	22.2	42.0	59.5	74.7	87.6	98.1	106.2	2 112.1	115.6	6 116.8	115.6	112.1	106.2	98.1	9.78	74.7	59.5	42.0	22.2	0.0
MLL	0.0	406.3	812.5	1218.8	1318.7	1236.3	1153.9	9 1071.4	4 989.0	9.906 (824.2	741.8	659.3	576.9	494.5	412.1	329.7	247.3	164.8	82.4	0.0
3		Str	Stresses in Composite	Compos	site Bea	m due t	o Prestr	essing,	Permane	ent DL a	nd Point	Beam due to Prestressing, Permanent DL and Point Load with Above Support Conditions (All Losses) Assuming I4 (KSI)	h Above	Suppor	t Condit	ions (All	Losses)	Assumi	ing la (KS	J.	
Axial	-0.060	_	-0.314 -0.568 -0.822	-0.822	896:0-	96:0-	-0.96	3 -0.96	8 -0.96	8 -0.96	8 -0.968	896.0- 896.0- 896.0- 896.0- 896.0- 896.0- 896.0-	-0.968	-0.968	896.0- 896.0- 896.0-	-0.968	-0.968 -0.822 -0.568 -0.314	-0.822	-0.568		-0.060
Fe (T)	0.059	0.309	0.558	0.808	0.951	0.951	0.951	0.951	1 0.951	1 0.951	1 0.951	0.951	0.951	0.951	0.951	0.951	0.951	0.808	0.558	0.309	0.059
(a)	0.047	747.0-	_	-0.03±	į				-11		-11		_,	0.747	7.77	0.747	7.7.	-0.034		11	0.047
DL-T	0.000	-0.105	-0.200	-0.283	-0.355		-0.466		4 -0.532	_	\Box		-0.532	-0.504	-0.466	-0.416	-0.355	-0.283	-0.200	-0.105	0.000
DL-B	0.000	0.083	0.157	0.222	0.278	0.326	0.365	0.396	5 0.418	3 0.431	0.435	0.431	0.418	0.396	0.365	0.326	0.278	0.222	0.157	0.083	0.000
LL-T	0.000	-0.371	-0.741	-1.112	-1.203	-1.128	-1.053	3 -0.977		2 -0.827	7 -0.752	-0.677	-0.601	-0.526	-0.451	-0.376	-0.301	-0.226	-0.150	-0.075	0.000
LL-B	0.000	0.861	1.721	2.582	2.794	2.619	2.444	2.270	2.095	1.921	1 1.746	1.571	1.397	1.222	1.048	0.873	869.0	0.524	0.349	0.175	0.000
Grd-T	-0.001	-0.481	-0.951	-1.409	-1.575	-1.560	-1.535	5 -1.499	9 -1.451	1 -1.393	3 -1.323	-1.242	-1.150	-1.048	-0.934	-0.809	-0.672	-0.523	-0.360	-0.186	-0.001
Grd-B	-0.107	0.387	0.872	1.348	1.357	1.230	1.095	0.951	0.798	3 0.636	5 0.466	0.287	0.099	-0.097	-0.302	-0.516	-0.738	-0.710	-0.500	-0.299	-0.107
Deck-T	Deck-T 0.000	-0.764	-0.764 -1.528	-2.292	-2	-2.325	-2.170	-2.01	5 -1.86	0 -1.70	5 -1.550	479 -2.325 -2.170 -2.015 -1.860 -1.705 -1.550 -1.395 -1.240 -1.085 -0.930 -0.775 -0.620 -0.465 -0.310 -0.155	-1.240	-1.085	-0.930	-0.775	-0.620	-0.465	-0.310	-0.155	0.000
Deck-B	Deck-B 0.000	-0.371	-0.741	-1.112	-1	-1.128	-1.05	1 -0.97	7 -0.90;	2 -0.82	7 -0.752	203 -1.128 -1.053 -0.977 -0.902 -0.827 -0.572 -0.677 -0.601 -0.526 -0.451 -0.376 -0.301	-0.601	-0.526	-0.451	-0.376	-0.301	-0.226 -0.150	-0.150	-0.075	0.000

Table D.6 Girder Shear Design Calculations (Left of Load)

G1C-West				Ği	Girder Shear Design (Left of Load	ear De	sign (L	eft of L	oad)			
District 1 & S. 1 2	, a	L-SUPT	0.1 a	0.2 a	0.3 a	0.4 a	0.5 a	0.6 a	0.7 a	0.8 a	0.9 a	P-LOAD
Distance from Left Support (inches)	N	0.00	8.50	17.00	25.50	34.00	42.50	51.00	59.50	68.00	76.50	85.00
Ultimate Moment Furnished	FT-KIP	94.67	228.79	362.91	497.02	631.14	765.26	86.668	1033.49	1167.61	1301.73	1435.85
Transferred Strands Factor		0.16	0.38	09.0	0.83	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Transferred # Top Strands	#	0.32	0.76	1.21	1.66	2.00	2.00	2.00	2.00	2.00	2.00	2.00
Transferred # Bottom Strands	#	1.26	3.05	4.84	6.62	8.00	8.00	8.00	8.00	8.00	8.00	8.00
Developed Strands Factor		90.0	0.15	0.24	0.33	0.42	0.50	65.0	89'0	0.77	98.0	0.95
Developed # Top Strands	#	0.12	0.30	0.48	99'0	0.83	1.01	1.19	1.36	1.54	1.72	1.89
Developed # Bottom Strands	#	0.50	1.21	1.91	2.62	3.33	4.04	4.74	5.45	6.16	6.87	7.57
Non-composite DL Moment (BM+SL)	FT-KIP	00.0	7.74	15.22	22.43	29.38	36.06	42.48	48.63	54.51	60.13	65.48
Total DL Shear (BM+SL)	KIP	11.38	11.01	10.63	10.26	9.88	9.51	9.13	8.76	8.38	8.01	7.63
Available Moment Capacity	FT-KIP	94.67	221.04	347.68	474.59	601.76	729.20	856.90	984.87	1113.10	1241.60	1370.36
Ultimate Moment, M _u	FT-KIP	0.00	144.78	289.29	433.54	577.53	721.24	864.70	1007.88	1150.80	1293.46	1435.85
Ultimate Shear, Vu	KIP	204.85	204.47	204.10	203.72	203.35	202.97	202.60	202.22	201.85	201.47	201.10
$f_{ m d}$	KSI	0.000	0.029	0.057	0.084	0.109	0.134	0.158	0.181	0.203	0.224	0.244
SFPF (Based on I _d)	KIPS	22.30	53.89	85.48	117.07	148.66	180.25	211.84	243.43	275.01	306.60	338.19
fpe Tpe	KSI	-0.107	-0.259	-0.410	-0.562	-0.714	-0.865	-1.017	-1.168	-1.320	-1.472	-1.623
M_{CR}	FT-KIP	265.85	323.81	382.23	441.12	500.47	560.30	620.59	681.34	742.57	804.26	866.42
· V _{ei} (Flexure Shear)	KIPS	29.78	478.83	290.81	228.05	196.61	177.70	165.05	155.97	149.14	143.79	139.49
FPF (Based on I _c)	KIPS	56.35	136.19	216.03	295.86	357.29	357.29	357.29	357.29	357.29	357.29	357.29
fpc	KSI	-0.083	-0.218	-0.353	-0.486	-0.593	-0.607	-0.621	-0.635	-0.648	-0.660	-0.672
V _{cw} (Web Shear)	KIPS	90'.29	76.39	85.68	94.93	102.26	103.28	104.25	105.19	106.08	106.93	107.75
Vc	KIPS	29.78	76.39	85.68	94.93	102.26	103.28	104.25	105.19	106.08	106.93	107.75
φ/^Λ	KIPS	204.85	204.47	204.10	203.72	203.35	202.97	202.60	202.22	201.85	201.47	201.10
Shear Steel Beyond Minimum Required	Y/N	YES	YES	YES	YES	YES	YES	YES	YES	YES	YES	YES
Web Crushing		CRUSH	OK	OK	OK	OK	OK	ΟĶ	OK	OK	OK	OK
Required Strength of Steel, Vs	KIPS	175.07	128.08	118.41	108.79	101.08	69.66	98.34	97.04	95.77	94.54	93.35
Required Stirrup Spacing, s	Z	6.58	8.99	9.73	10.59	11.40	11.56	11.71	11.87	12.00	12.00	12.00

Table D.7 Girder Shear Design Calculations (Right of Load)

G1C-West				Gir	Girder She	Shear Design	ign (Ri	(Right of Load	(paor			
Distance from I of Summer (Jacker)	14	P-LOAD	0.1 b	0.2 b	0.3 b	0.4 b	0.5 b	9.0	0.7 b	0.8 b	0.9 b	R-SUPT
Cistance from test Support (menes)	IIV	85.00	126.90	168.80	210.70	252.60	294.50	336.40	378.30	420.20	462.10	504.00
Ultimate Moment Furnished	FT-KIP	1435.85	1516.94	1516.94	1516.94	1516.94	1516.94	1516.94	1516.94	1416.91	755.79	94.67
Transferred Strands Factor		1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.16
Transferred # Top Strands	#	2.00	2.00	2.00	2.00	2.00	2.00	2.00	2.00	2.00	2.00	0.32
Transferred # Bottom Strands	#	8.00	8.00	8.00	8.00	8.00	8.00	8.00	8.00	8.00	8.00	1.26
Developed Strands Factor		0.95	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.93	0.50	90.0
Developed # Top Strands	#	1.89	2.00	2.00	2.00	2.00	2.00	2.00	2.00	1.87	1.00	0.12
Developed # Bottom Strands	#	7.57	8.00	8.00	8.00	8.00	8.00	8.00	8.00	7.47	3.99	0.50
Non-composite DL Moment (BM+SL)	FT-KIP	65.48	84.78	104.03	113.62	116.76	113.44	103.66	87.43	64.74	35.60	00.0
Total DL Shear (BM+SL)	KIP	7.63	5.78	3.94	2.09	0.24	-1.61	-3.46	-5.31	-7.16	-9.01	-10.85
Available Moment Capacity	FT-KIP	1370.36	1428.95	1412.91	1403.32	1400.18	1403.50	1413.28	1429.51	1352.17	720.19	94.67
Ultimate Moment, Mu	FT-KIP	1435.85	1321.31	1200.32	1072.88	938.97	798.62	651.81	498.54	338.81	172.63	0.00
Ultimate Shear, V.	KIP	31 61	33.46	35.31	37.16	39.01	40.86	42.71	44 56	46.40	48.25	50.10
							2010					2000
f _d	KSI	0.244	0.328	0.388	0.423	0.435	0.423	0.386	0.326	0.241	0.133	0.000
SFPF (Based on l _d)	KIPS	338.19	357.29	357.29	357.29	357.29	357.29	357.29	357.29	333.73	178.02	22.30
tpe	KSI	-1.623	-1.715	-1.715	-1.715	-1.715	-1.715	-1.715	-1.715	-1.602	-0.854	-0.107
M _{CR}	FT-KIP	866.42	870.12	841.89	825.02	819.50	825.34	842.54	871.09	857.62	556.06	265.85
V c (Flexure Shear)	KIPS	37.22	38.33	39.21	41.17	44.79	51.12	62.25	83.05	120.81	156.93	#########
FPF (Based on 1,)	KIPS	357.29	357.29	357.29	357.29	357.29	357.29	357.29	357.29	357.29	357.29	56.35
fpc	KSI	-0.672	-0.721	-0.757	-0.778	-0.785	-0.777	-0.756	-0.720	-0.670	-0.606	-0.083
V _{cw} (Web Shear)	KIPS	107.75	111.16	113.60	115.06	115.53	115.03	113.55	111.08	107.63	103.21	90.79
V _c	KIPS	37.22	38.33	39.21	41.17	44.79	51.12	62.25	83.05	107.63	103.21	67.06
φ/^Λ	KIPS	31.61	33.46	35.31	37.16	39.01	40.86	42.71	44.56	46.40	48.25	50.10
Shear Steel Beyond Minimum Required	Υ/N	NO	NO	ON	ON	NO	NO	ON	NO	ON	NO	ON
Web Crushing		OK	OK	OK	OK	OK	OK	OK	OK	OK	OK	OK
Required Strength of Steel, Vs	KIPS	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Required Stirrup Spacing, s	Z	24.00	24.00	24.00	24.00	24.00	24.00	24.00	24.00	24.00	24.00	24.00

Table D.8 Deck / Girder Interface Shear Calculations

5	อว	3500 PSI	443.71 PSI	8000 PSI	570.20 PSI	412.48 PSI	338.19 KIPS	369 IN ²	-6.73 IN	20.17 IN	10.84 IN	50979 IN⁴	142547 IN ⁴	65.48 FT-KIP	1370.36 FT-KIP	-1576.88 PSI	101.381 PSI	\$ OK	
lations	at Interfac	\mathbf{f}_{c}^{\prime}		j3		Vh	굓	Anc	ə	Уюр-ис	Y _{top-c}	JI.	ľ	⁷⁰ W	$M_{\mathrm{\Gamma}\Gamma}$	f_{ca}	$\mathbf{f}_{\mathbf{t}}$	nterface is	
Deck / Girder Interface Shear Calculations	Tensile Stress at Interface	Deck Concrete Design Strength	Maximum Allowable Deck Tensile Stress	Girder Concrete Design Strength	Maximum Allowable Beam Tensile Stress	Maximum Interface Shear Stress (VQ/Ib)	Effective Prestress Force	Girder Cross Sectional Area	Strand Eccentricity from NC Centroid	Distance from NC Centroid to Beam Top	Distance from C Centroid to Beam Top	Non-Composite Moment of Inertia	Composite Moment of Inertia	Dead Load Moment	Live Load Moment	Maximum Compressive Stress at Interface	Maximum Tensile Stress at Interface	Tensile Stress at Interface is OK	
Deck/		None	None	KIPS	E _Z	Z	Z	Z	N ₂	KSI	$ m N^2$			YES/NO	YES/NO	YES/NO	PSI	KIPS	
	nes	0.85	1.00	204.85	3444.42	142547	12	50.40	604.8	75	0.4			SHA!!	' VES	YES	350	211.68	conate
	r Calculation Values	_	φ	₀	SÒ		þ	Span/10	Ą	ť	Ą		ondition					\ In	Canacity Ade
G1C-West	Interface Shear Ca	Lightweight Concrete Reduction Factor	Shear Strength Reduction Factor	Maximum Unfactored Shear	First Moment of Deck About Centroid	Composite Moment of Inertia	Interface Shear Contact Width	Contact Length, d (a+XDIST<=SPAN/10)	Contact Area (b,*Contact Length)	Yield Strength of Tie Reinforcement	Stirrup Area		Interface Condition	Contact Surface Clean	Contact Surface Roughened 1/4"	Minimum Ties Provided	Maximum Basic Interface Stress	Maximum Basic Interface Force	Basic Interface Shear Canacity Adequate

Additional Interface Capacity Provided by Shear Reinforcement	ided by She	ar Reinforcemei	ıt
Additional Interface Capacity Required		0.00	KIPS
Worst Case Stirrup Spacing over "a"	s	12.00	N
Minimum Tie Area per Inch of Beam		0800'0	IN^2/IN
Additional V _{nh} Capacity per Percent		181.4	KIPS
Additional Percent Required		0.00	%
Additional Required Tie Area		0.000000	IN ² /IN
Total Tie Area Required		0.008000	IN^2/IIN
Min. Tie Area Provided by V Reinforcement		0.033333	M^2/IN
Resulting Contact Area Stress		338.70	ISd
Interface Shear Capacity Adequate	acity Adequ	ate	

APPENDIX E

LOAD CELL CALIBRATION

This Appendix contains the calibration curves for strand load cells used to monitor the force in the prestressing strands from initial tensioning through the time of strand release. Figures E.1 through E.10 show the calibration curves determined for each strand load cell. The following procedure was used in determining the calibration curves.

- 1. All load cells were connected to the BLH 1225 Portable 10 Channel Switch and Balance Unit, which was connected to a BLH 1200B Portable Digital Strain Indicator. The load cells were a "full-bridge" configuration. The same units used for this calibration were used during girder construction.
- 2. The load cells were placed individually in an 800 kip SATEK compression testing machine. After being properly positioned, load was applied to the cells slowly through a load of 45 kips, the maximum anticipated load during strand tensioning. At the 10, 20, 30, 40, and 45 kip readings indicated on the SATEK machine, corresponding strain readings were taken from the digital strain indicator.
- 3. After testing, all load and strain data was entered into an EXCEL spreadsheet and plotted. The slope of each stress vs. strain plot was determined using the linear trendline option in EXCEL. The slope values are listed in the bottom right of each calibration plot.




Figure E.1 Calibration Curve for Strand Load Cell # 1




Figure E.2 Calibration Curve for Strand Load Cell # 2




Figure E.3 Calibration Curve for Strand Load Cell #3




Figure E.4 Calibration Curve for Strand Load Cell #4




Figure E.5 Calibration Curve for Strand Load Cell # 5




Figure E.6 Calibration Curve for Strand Load Cell #6




Figure E.7 Calibration Curve for Strand Load Cell #7




Figure E.8 Calibration Curve for Strand Load Cell #8




Figure E.9 Calibration Curve for Strand Load Cell #9




Figure E.10 Calibration Curve for Strand Load Cell # 10

APPENDIX F

PRESTRESSING STRESS CALCULATION

This Appendix contains the procedures used to determine the stress in the prestressing strands at initial tensioning of strands, just prior to release of strands, and as necessary at other times during testing.

At the time of strand tensioning and just prior to strand release, strand load cell values were used. Table F.1 shows a spreadsheet listing the calibration constants reported in Appendix E and the load cell strain readings for each series of girders. The resulting stress just prior to release, f_{pt} , is listed for each series of girders. The f_{pt} values were used in the transfer length analysis and are reported in Table 9.5.

After release of the strands, the level of prestress was determined with vibrating wire strain gages (VWSG) cast into the girders at midspan at the level of the bottom strands (Figure 8.21). Output from the gages was measured using the device pictured in Figure F.1. The device sent a small excitation voltage to the VWSG causing the wire within to vibrate. The frequency at which the wire in the gage vibrated was based on the amount of tension or compression the gage was experiencing. The values recorded at each measurement were an internal gage resistance used to determine a temperature correction factor and the frequency at which the wire was vibrating. A spreadsheet was created as shown in Table F.2 to determine the strain values.

Table F.1 Prestressing Strand Stress Values at Time of Tensioning and Just Prior to Release

		Strano	Strand Load Ce	ell Strain	Ill Strain Conversion Factors From Graph Trendlines and PT Forces	on Factor	rs From (Graph Tr	endlines	and PT F	orces	
			Load Cell 1	Load Cell 2	Load Cell 3	Load Cell 4	Load Cell 5	Load Cell 6	Load Cell 7	Load Cell 8	Load Cell 9	Load Cell 10
_	Kips / µ-strain	train	0.007219	0.006958	0.007456	0.008018	0.007579	0.007454	0.007451	0.007690	0.007555	0.007492
	Strand Area	0 2403	Strand 1	Strand 2	Strand 3	Strand 4	Strand 5	Strand 6	Strand 7	Strand 8	Strand 9	Strand 10
	(in²)	0.4163	Bottom L							Bottom R	Top L	Top R
							Girders (Girders G1A / G1B				
_	At Stressing	µ-strains	4533	5275	5430	4975	5352	5286	5206	5340	5430	5532
	392.09	Kips	32.72	36.70	40.49	39.89	40.56	39.40	38.79	41.06	41.02	41.45
	Before Release	L-strains	4513	5270	5438	4960	5313	5270	5150	5357	5448	5479
Ь	390.89	Kips	32.58	36.67	40.55	39.77	40.27	39.28	38.37	41.20	41.16	41.05
4(Bottom / Top Totals	Totals				308.68	.68				82	82.21
<u> </u>	f _{pt} (ksi)	179.06										
ı					4		Girders (Girders G2A / G2B				
	At Stressing	L-strains	6013	5107	5193	4742	5516	5432	5296	5452	5587	5824
لــا	405.21	Kips	43.41	35.53	38.72	38.02	41.81	40.49	39.46	41.93	42.21	43.63
	Before Release	µ-strains	6140	5310	5351	4891	5727	5572	5426	5612	5781	6011
	417.62	Kips	44.32	36.95	39.90	39.22	43.40	41.53	40.43	43.16	43.68	45.03
لـــا	Bottom / Top Totals	Totals				328.91	16:				88	88.71
	f _{pt} (ksi)	191.30	2000	1000000		The state of the s						
I							Girders (Girders G1C / G2C				
	At Stressing	L-strains	5163	5218	5640	5549	5484	5456	5126	5115	5489	5601
	403.31	Kips	37.27	36.31	42.05	44.49	41.56	40.67	38.19	39.33	41.47	41.96
	Before Release	µ-strains	4989	5023	5387	5406	5279	5309	2000	4970	2387	5443
	391.01	Kips	36.02	34.95	40.17	43.35	40.01	39.57	37.26	38.22	40.70	40.78
	Bottom / Top Totals	Totals				309.53	.53				18	81.48
ш	f _{pt} (ksi)	179.12										
ı												




Figure F.1 Vibrating Wire Strain Gage Reader

To convert the frequency readings (Hz) to strains, Equation F.1 was used where $\epsilon_{Apparent}$ was the uncorrected strain value, GF was the gage factor provided by the manufacturer (0.9996), and HZ was the wire vibration frequency read by the gage reader.

$$\varepsilon_{Apparent} = 0.003304 GF (Hz)^2 \tag{F.1}$$

To calculate temperature from the gage resistance reading (Ω WG), Equation F.2 was used where T_t was the temperature and Ω WG was the gage resistance in ohms.

$$T_{t} = \frac{1}{(0.0014051 + 0.0002369 \ln(\Omega WG) + 0.0000001019 \ln(\Omega WG)^{3})} - 273.2 \qquad (F.2)$$

To correct the strain reading for temperature effects, Equation F.3 was used where $\epsilon_{Initial}$ was the strain reading taken just prior to strand release, $T_{Initial}$ was the temperature of the gage when the first strain reading was taken, and the CTE values are the coefficients of thermal expansion for steel and concrete, 12.2 and 10.2 $\mu\epsilon$ /°C, respectively.

$$\varepsilon_{Corrected} = (\varepsilon_{Apparent} - \varepsilon_{Initial})GF + (T_t - T_{Initial})(CTE_{Steel} - CTE_{Concrete})$$
 (F.3)

The temperature correction was based on changes from the temperature at which the first VWSG reading was taken. In general, a drop in temperature meant a lower strain value; an increase in temperature meant a higher strain.

The force in the prestressing strand at any time after strand release was determined using the three equations shown in Figure F.2. The appropriate equation was determined depending on whether $\varepsilon_{\text{Corrected}}$ was in the elastic (0 - 0.7135 percent strain), transition (0.7135 – 1.25 percent strain), or plastic (> 1.25 percent strain) portion of the force vs. strain curve. Once the force was determined, the stress was calculated by dividing the strand force by the area of the strand, 0.2183 in². The shape of the curve in Figure F.2 was determined using the actual force vs. strain curve from the strand manufacturer.

Table F.2 Calcultion of Prestressing Strand Stress Values for Girder Test G1C-West

		Deter	mination	of Initial	Determination of Initial Strand Strain Due to Prestressing	train Du	e to Presi	tressing			
				Prestressing V	Prestressing Values Reported by Tindall QC	d by Tindall Q	C				
Strand #	1	2	3	4	5	9	L	8	6	10	TOTAL
Elongation (In)	10.625	9.875	9.75	9.875	9.875	10.125	9.875	10.25	10.125	10.25	(Kips)
Tensioning Load (Kip)	45	45	45	45	45	45	45	45	45	45	450.00
			Prestress	ing Values Rea	Prestressing Values Read From Strain Boxes Using Load Cells	n Boxes Using	Load Cells				
kips/μ-strain	0.007219	0.006958	0.007456	0.008018	0.007579	0.007454	0.007451	0.007690	0.007555	0.007492	TOTAL
μ-strains at Tensioning	5163	5218	5640	5549	5484	5456	5126	5115	5489	5601	(Kips)
Tensioning Load (Kip)	37.27	36.31	42.05	44.49	41.56	40.67	38.19	39.33	41.47	41.96	403.31
μ-strains at Release	4989	5023	5387	5406	5279	5309	2000	4970	5387	5443	(Kips)
Release Load (Kip)	36.02	34.95	40.17	43.35	40.01	39.57	37.26	38.22	40.70	40.78	391.01
	Values Used to		Strain in Stra	nd at Prestress	Calculate Strain in Strand at Prestressing and Just Before Release (Enter Tindall or Load Cell)	Sefore Release	(Enter Tindal	lor Load Cell)			Load Cell
				Initial Stran	Initial Strand Strain Values	Se					Average
% Strain at Release	95.0	0.55	0.63	89.0	69:0	0.62	0.58	09:0	0.64	0.64	0.61
Strand Ult Stress, fpu	283.20	KSI	Strand /	Strand Area, As	0.2183	$ m IN^2$	I	evel of Prestre	Level of Prestressing as % of f _{pu}	2	63.25%
	Vibrat	ing	7ire Strai	n Gage R	Wire Strain Gage Readings and Strand Strain/Force Values	nd Stran	d Strain	Force Va	lues		
Vibrating Wi	Vibrating Wire Strain Gage Fact	e Factor - Ente	er Value from	Strain Gage Co	or - Enter Value from Strain Gage Certification Sheet	eet	9666.0	CTE Steel	12.2	CTE Conc	10.2
	Λ	Vibrating Wire	ng Wire Strain Gage Values	alues				Prestressing St	Prestressing Strand Strain / Force / Stress	Force / Stress	
Time of Reading	4Н	MMG	Temp	Apparent E	Temp Corr	Corrected 8	$f_{pt} = Be$	fore Release, f	fpt = Before Release, fat = fpt - ES, fse = fpt - ES - CR - SH	$= f_{pt} - ES - CR$	-SH
Sumo of the anning	711	(Ohms)	(deg C)	(μ-strains)	(µ-strains)	(μ-strains)	µ-strains	% Strain	Force (K)	Stress (ksi)	Value
Before Release (0)	902.66	1308	44.99	1697	NA	1697	6131	19:0	39.10	179.11	fpt
Just After Release	799.65	1387	43.49	2112	£-	5109	5550	0.55	35.39	162.11	f_{si}
1 Day	791.59	2407	30.04	2070	-30	2040	5480	0.55	34.95	160.09	
7 Days	762.00	2868	25.97	1918	-38	1880	5320	0.53	33.93	155.42	
14 Days	749.82	2863	26.01	1857	-38	1819	5260	0.53	33.54	153.65	f,e
Just Before Testing	708.37	3360	22.38	1657	-45	1612	5053	0.51	32.22	147.61	ftest




Figure F.2 Strand Force vs. Strain Curve for Prestressing Strand

APPENDIX G

TRANSFER LENGTH CALCULATION SPREADSHEET

Appendix G contains the individual pages from the Transfer Length Calculation Spreadsheet. The entire set of worksheet pages is provided for Girder G1C. The pages are listed in the order the calculations occur. A similar series of worksheets was prepared for each girder to determine transfer lengths. Listed below are the individual worksheets within the overall spreadsheet and a brief description of the worksheet's function.

Table G.1 - Data Taking Sheet – Used to record CSS readings taken with DEMEC gages.

Table G.2 – Data Worksheet – Worksheet used to enter background data information on girder readings to include times, temperatures, strain readings and jacking forces.

Tables G.3-G.4 – Gage Locations, North & South – Worksheets used to enter distances to ends of embedment strips. Initial gage lengths calculated.

Tables G.5-G.16 - CSS Reading Sheets – Data entry worksheets for each embedment strip (12 total). Readings entered from **Data Taking Sheets**.

Tables G.17-G.18 - Raw CSS Data Sheets, North & South — Worksheets listing raw strain data calculated from CSS readings and initial gage lengths.

Tables G.19-G.20 – Smoothed CSS Data Sheets, North & South – Worksheets listing smoothed strain data determined by a three-point floating average.

Table G.21 - Average Raw Transfer Length Plot Data — Worksheets averaging North and South raw data.

Figures G.1-G.2 - Raw Plots East and West - Raw CSS plots for East and West ends.

Table G.22 - Average Smoothed Plot Data - Worksheets averaging North and South smoothed data.

Figures G.3-G.4 - Smoothed Plots East and West - Smoothed CSS plots for East and West ends.

Figures G.5-G.6 - Transfer Length Plots East and West – 14-day transfer length calculation plots based on the 95% AMS Method.

NOTE ON DATA COLLECTION: Prior to girder construction, it was decided that CSS data collection and recording would be made more consistent and "foolproof" by establishing a basic rule. The rule was that all CSS readings would be taken from LEFT to RIGHT as the data taker looked at the embedment strip. The CSS data form (Table G.1) was configured such that the table provided areas for data entry that matched the location of the embedment strips on the girder. The LEFT to RIGHT rule applied to both sides of the girder. This was done to help alleviate errors from occurring in the field.

Table G.1 Transfer Length Data Taking Sheet

on Each Plate		Notes					ing 4 Reading 5																
Take Readings From Left to Right on Each Plate	Readings	WWG					Reading 3 Reading 4	30 Inch Top Right						48 Inch Bottom Right									
Readings Fro	efore Taking	103Hz2					Reading 2	30 I						48 In									
Take	ge on Bar B	Hz					Reading 1																
	er - Zero Ga	TCI					Reading 5																
	Gage Read	TCA					Reading 4	enter						Center									
Beam Side	mes and Notes for Readings - Gage Length is 8" on DEMEC Gage Reader - Zero Gage on Bar Before Taking Readings	Deflection					Reading 2 Reading 3 Reading 4 Reading 5	26 Inch Top Center						26 Inch Bottom Center									
	ngs - Gage L	Time					Reading 1																
	es for Readi	II					Reading 5																
	imes and Not	Date					Reading 4 Reading 5							n Left									
ber	Dates, Ti						Reading 3	30 Inch Top I						48 Inch Bottom				\downarrow					
Beam Number		Reading #	1	2	3	5	Reading 1 Reading 2 Reading 3	3						48			-		-				
		Rea					Reading 1																

Table G.2 Data Worksheet for Girder G1C

B	Beam #	GIC	Raw Data	Raw Data for Transfer and Development Length	fer and De	evelopme	ent Leng	th	
Reading	Date	Time	Midspan	Ambient	Internal	Vibrating	Vibrating Wire Strain Gage Data	Gage Data	Notes
#	(DD/MM/YY)		Deflection (Inches)	Temperature (Degrees F)	Temperature (Degrees F)	ZH	$10^3 \mathrm{HZ}^2$	9w w	
Initial 1	07/18/2001	12:10	2.031	85.0	117.4	902.66	814.85	1308	Initial Reading 1 Sunny
Initial 2	07/18/2001	12:10	2.031	85.0	117.4	902.66	814.85	1308	Initial Reading 2, Sunny
Release	07/18/2001	15:15	2.453	87.8	108.5	799.65	639.55	1387	After Cutting Strand, Cloudy
1-Day	07/19/2001	7:08	2.469	74.2	84.6	791.59	626.65	2407	1-Day, At Sunrise, Dry and Clear
2-Day	07/20/2001	6:53	2.484	73.6	83.5	784.09	614.80	2514	2-Day, At Sunrise, Dry and Clear
3-Day	07/21/2001	6:50	2.500	72.5	79.0	780.30	608.70	2829	3-Day, At Sunrise, Overcast
7-Day	07/25/2001	7:10	2.531	73.8	78.7	762.00	580.60	2868	7-Day, At Sunrise, Overcast
14-Day	08/01/2001	6:30	2.555	72.0	78.1	749.82	563.00	2863	14-Day, At Sunrise, Mostly Clear
%56									
Slope									
				Load C	Load Cell and Jacking Data	king Da	ta	3	
,					,				
Load	lime	Frior		Strand	Strand	Strand	Date/Iime	Temp	Notes
Cell	Jo	ę		* ±	Jacking	Elongation		(Deg F)	
(Strand)	Stressing (me)	Release (me)			Force (Pounds)	(Inches)			
					,				
1	5163	4989		1	45000	9.875			
2	5218	5023		7	45500	9.750			
3	5640	5387		3	46000	9.750			
4	5549	5406		*	46000	9.875			
5	5484	5279		2	46000	9.875	17 11 01	312	
9	5456	5309		9	46000	9.875	10 mc / 1	۲,	
7	5126	2000		7	45000	10.000			
8	5115	4970		8	45000	10.000			
6	5489	5387		6	46000	9.750			
10	5601	5443		10	46000	9.750			

Table G.3 North Side Gage Locations

	1.25	33.63	=	Position	20	2.938	1.5	Γ	Lgth	8.01	8.01	8.02	8.01	8.01	8.01	7.98	7.97	7.95	7.96	8.01	8.01	8.04	8.03	8.00	8.01	8.01	8.02	8.03	207	
	Î	السال	<u>-</u>	Pc			1	<u>it-R</u>	Init	104	148	190	96	146	601	-219	-255	-530	420	69	127	361	257	12	99	142	208	283	710	49.04
			Top - R		2			48" Bot - R	Posn	43.53	41.53	39.52	37.52	35.52	33.51	31.52	29.52	27.54	25.55	23.55	21.54	19.53	17.53	15.53	13.53	11.52	9.52	7.51	70	
		33.63	-		Bot - R				Elev	2.99	2.99	2.99	2.99		-	2.98	2.98	2.97	2.97	2.97	2.96	2.96	2.96	2.96	2.95	2.95	2.95	2.95	2.94	Lengtn =>
								Γ	Lgth	8.08	8.07	8.09	8.09	8.08	8.07	8.06	8.07	8.05	8.06	8.04	ZI									
		ge (IN)			-	3		op - R	Init	762	743	865	922	753	969	909	740	549	639	409	28.25				FT	N				
		< Elevation of End Gage (IN)>				Î		30" Top - R	Posn	25.46	23.44	21.42	19.40	17.38	15.36	13.35	11.33	9.31	7.30	5.29	(µ =>				43.00	8.00				
		ion of I				Elevation (IN)>			Elev	33.63	33.63	33.63	33.63	33.63	33.63	33.63	33.63	33.63	33.63	33.63	Length =>					tp:				
		. Elevat				Elevati			Lgth	8.13	8.12	8.09	8.10	8.10	8.10	8.16	8.13	8.11	N						Length	DEMEC Gage Length				
	3	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \				V	(A)	3-10	Init	1258	1166	606	1022	286	1019	1620	1310	1117	24.35						Beam Length	MEC G				
اج	t Gage	33.75	6		6	3.063	t Gage	26" Bot - C	Posn	249.9	251.9	253.9	256.0	258.0	260.0	262.1	264.1	266.1	Length =>							DE				
Gages - North	nd to 1s		ပ	Z	၂		nd to 1s	L	Elev	3.01	3.02	3.02	3.03	3.03	3.04	3.04	3.05	3.05	Leng											
ges -	3eam E		Top - C	G1C - N	Bot - C		3eam E	#	Lgth	7.94 1	7.94 2	7.97	7.98 4	7.99 5	7.97 6	7.97	7.97	7.95	10	111	12	13	14	15	16	17	18	19	70	
3	Distance from Beam End to 1st Gage (IN)	33.75	1	Ļ	_	3	Distance from Beam End to 1st Gage (IN)	၁	Init L	-574 7	Н	-339 7	-180 7	-146 7	-299 7.	Н	Н	H	23.88											
	Distance	33	Ш		Ш)istance	26" Top - C	Posn	_		254.0	256.0 -1	258.0 -]	_		264.0	_												
		(IN)		4				26	Elev P	-	_	33.75 25	_	33.75 25		33.75 26		33.75 26	Length =>											
		< Elevation of End Gage (IN)>				Elevation (IN)		┝	Lgth E	8.01 33	_		7.98 33	8.00 33	8.05 33	8.07 33	-	8.03 33	Н	8.00	8.02	8.00	8.01	7.99	7.97	8.00	8.02	8	5 5	
		of Enc				ă		1	nit L	Н	\vdash	-	207 7.	3 8	526 8	_	8 681	⊢	Н	.28 8.	Н	50 8.		_	┡	L	Ш	358 8.	4	
		levation				(E)		48" Bot	Posn 1		6.63	Ľ	10.62 -2	12.62	14.63 5		7	<u> </u>		Ŀ	26.68 2	28.68	30.68	32.68	34.67 -3	36.67	38.67	-	7	
		< E			20			4	Elev P	Н	Н		-	3.00 12	3.00	3.00	-	┢┈	Н	-	3.00 26	┝╌┥	3.00 30	3.00 32	3.00	3.00 36	3.00 38	-	3.00	Length =>
		33.75						ŀ	Lgth E	8.14 3		8.12	Н	8.08	8.09 3	8.08	_	8.10 3	_		IN 3	3.	33	8	εĭ	εį	Ε,	m	1	
		33			Bot - I			+	Init L	1420 8.	1212 8.	1221 8	1208 8.	843 8.	874 8.	809 8	Н	8 686	1072 8.	1144 8.	28.40 I									
			Top - L					Top -	Posn L	5.07	7.10 12	9.13	11.16 12	13.18 8	15.20 8	17.23 8	Н	21.27	23.30 10	25.33 11										
		33.63	1	Position	-	3	0.625	30	Elev P	L	L	Н	33.67	33.68 13	33.69 15	33.70 17	-	33.71 21	33.72 23	33.73 25	Length =>									
	<u> </u>] <u></u>		Pc			9	L			11		3.	3	3.	3,	3.	m	33	κí										

Table G.4 South Side Gage Locations

Beam Gage Locations - South	- Distance from Beam End to 1st Gage (IN)	- Elevation of End Gage (IN)> 33.75	Top-C 9 1 Top-R 11	GIC - S	Bot-C 9 1 Bot-R 20	3.125 < Elevation (IN)> 3.375 3.125	Distance from Beam End to 1st Gage (IN)	# 26" Bot - C 30" Top - R 48" Bot - R	Lgth Elev Posn Init Lgth Elev Posn Init Lgth Elev Posn Init Lgth	1 3.13 249.9 911 8.09 33.75 25.03 686 8.07 3.35 43.25 1065 8.11	2 3.13 252.0 827 8.08 33.75 23.01 677 8.07 3.34 41.24 463 8.05	3 3.13 254.0 692 8.07 33.75 20.99 802 8.08 3.33 39.23 338 8.03	4 3.13 256.0 626 8.06 33.75 18.97 786 8.08 3.32 37.22 228 8.02	5 3.13 258.0 755 8.08 33.75 16.95 798 8.08 3.31 35.21 267 8.03	6 3.13 260.0 574 8.06 33.75 14.93 779 8.08 3.30 33.21 88 8.01	8.07 7 3.13 262.0 715 8.07 33.75 12.91 776 8.08 3.29 31.21 -18 8.00	8.07 33.75 10.90 678 8.07 3.28 29.22 1.77	33.75 8.88 623 8.06 3.27 27.22 -289	6.86 670 8.07 3.26 25.23 -376	33.75 4.85 691 8.07 3.24 23.24 -370	12 Length => 28.25 IN 3.23 21.26 -505 7.95	19.28 -774	17.29 -709	3.20 15.31 -703 7.93	16 Beam Length 43.00 FT 3.19 13.33 -703 7.93	17 DEMEC Gage Length 8.00 IN 3.18 11.34 423 7.96	3.17 9.35 -511 7.95	3.16 7.36	3.15 5.37 -247 7.98	Length => 45.99 IN
Beam Gag	Distance from	of End Gage (IN)	1] < Elevation (IN)> 3.125	Distance from	Bot - L 26" Top - C	Init Lgth Elev	-500 7.95 33.67 249.9 1162	-192 7.98 33.69 251.9 686	-192 7.98 33.71 254.0 854	48 8.00 33.73 256.0 736	170 8.02 33.75 258.0 641	-18 8.00 33.77 260.0 770	-5	-56 7.99	-313 7.97 33.83 266.1 879	-75 7.99 Length => 24.27		-252 7.97	253	-37	-155 7.98	101-	-580 7.94	469 7.95	-178	-107	45.89 IN
		33.75 < Elevation	11	······	Bot - L 20	3.063		L 48" Bot	t Lgth Elev	3.12 4.73	8.06 3.12 6.72	8.08 3.11 8.72	8.05 3.11 10.72	6 8.06 3.11 12.72	8.07 3.11 14.72	8.06 3.10 16.72	3.10 18.72	8.08 3.10	80.8	Ĥ	3 IN 3.09 26.70		-	3.08 32.70	3.08 34.70	3.08 36.68	3.07 38.67	3.07 40.67	3.07 42.67	Length =>
	0.875	33.88	1 Top-L	Position	1 B	3.125	0.75	30" Top - 1	Elev Posn Init	33.86 4.90 576	33.85 6.92 614	33.84 8.94 758	33.83 10.95 501	33.82 12.96 566	33.81 14.98 669	33.80 17.00 619	33.79 19.02 925	33.79 21.04 847	L	33.77 25.08 761	Length => 28.23									

Table G.5 CSS Reading Sheet for 30-inch Top Left Embedment Strip on North Side

	Beam Number	GIC	Beam Side	Side	North		30 Inch Top Left	Cop Left	
Not the set of the set									
Initial 1	Initial 2	Release	1-Day	2-Day	3-Day	7-Day	14-Day	95%	Slope
1418	1422	1422	1409	1398	1402	1398	1402		
1209	1215	1211	1198	1191	1191	1186	1191		
1221	1220	1217	1205	1192	1198	1190	1611		
1204	1211	1206	1194	1187	1189	1811	1192		
0844	0842	0836	0824	0816	0817	9805	0819		
0875	0873	9980	0849	0843	0845	9836	0844		
2080	0810	0800	0784	0782	0784	0774	6220		
0963	0954	6260	0940	0932	0933	0914	0932		
0660	2860	9860	0971	0964	0963	0965	5960		
1071	1072	1066	1049	1042	1046	1038	1042		
1143	1145	1138	1119	6111	1119	1111	1117		

Table G.6 CSS Reading Sheet for 48-inch Bottom Left Embedment Strip on North Side

Beam Number	umber	G1C	Веап	Beam Side	North		48 Inch Bottom Left	ttom Left	
DIEST ST. C. ST.									
Initial 1	Initial 2	Release	1-Day	2-Day	3-Day	7-Day	14-Day	%56	Slope
0110	0109	0101	9800	0081	0081	0072	1800		
-0046	-0044	-0057	-0070	-0074	-0070	-0083	-0077		
-0160	-0160	-0172	-0185	-0203	-0205	-0209	9610-		
-0196	-0218	-0234	-0258	-0256	-0252	-0256	-0243		
0003	0003	-0021	-0032	-0035	-0038	-0044	-0040		
0523	0529	0503	0492	0481	0481	0475	0482		
9990	0664	0630	0615	0190	8090	6090	2090		
0483	0494	0463	0439	0446	0429	0428	0438		
0338	0338	0297	0281	0275	0273	0264	0266		
0049	9900	0014	-0013	-0019	-0013	-0028	-0017		
-0031	-0024	-0070	-0085	6800-	9800-	9600-	-0095		
0244	0237	0194	9910	0163	0161	0152	0154		
-0049	-0051	8600-	-0115	-0127	-0124	-0135	-0136		
6800	0094	0033	-0005	0007	-0017	-0015	0012		
-0091	-0091	-0143	-0164	-0179	-0184	-0192	-0194		
-0303	-0300	-0345	-0365	-0375	-0375	-0383	-0380		
0023	0026	-0017	-0039	-0045	1500-	-0058	-0057		
0178	0179	0132	0113	0109	0102	9000	0101		
0358	0357	0321	0289	0277	0283	0273	0268		
0389	0382	0339	0316	0314	0303	0292	0303		

Table G.7 CSS Reading Sheet for 26-inch Top Center Embedment Strip on North Side

		П								_	
		Slope									
p Center		95%									
26 Inch Top Center		14-Day	-0624	-0653	-0386	-0228	-0186	-0341	-0339	-0321	-0595
		7-Day	-0628	-0658	-0392	-0229	-0209	-0352	-0353	-0334	6090-
North	seculing Bucketing Fires	3-Day	-0619	-0647	-0380	-0221	-0179	-0335	-0339	-0325	-0586
Beam Side	i a en esta esta esta esta fieldes portuges de la composition della composition dell	2-Day	-0610	-0652	-0383	-0223	-0196	-0341	-0345	-0326	-0587
Beam		1-Day	6090-	-0641	-0372	-0215	-0199	-0340	-0342	-0326	-0589
GIC		Release	-0587	-0614	-0353	-0200	-0170	-0315	-0313	-0305	-0557
umber		Initial 2	-0577	-0598	-0341	-0181	-0147	-0301	-0301	-0285	-0540
Beam Number		Initial 1	-0570	-0596	-0336	-0179	-0145	-0297	-0302	-0281	-0533

Table G.8 CSS Reading Sheet for 26-inch Bottom Center Embedment Strip on North Side

		Slope									
om Center		95%									
26 Inch Bottom Center		14-Day	1158	1072	0822	0915	0920	7560	1541	1228	1032
		7-Day	1165	1073	0813	6060	0917	0942	1534	1225	1013
North	THE STEEL WAS PROPERTIES	3-Day	1180	1081	0824	0919	0921	0954	1546	1230	1031
Side	NA CENTRAL CONTRACTOR	2-Day	1181	1078	0832	0935	0922	6560	1547	1243	1037
Beam Side		1-Day	1192	1087	0839	0948	0924	0964	1549	1235	1044
G1C		Release	1272	1110	0842	0971	0943	9260	1567	1253	1060
umber		Initial 2	1262	1164	2060	1021	8860	1017	1617	1307	1117
Beam Number		Initial 1	1254	1167	0911	1023	9860	1020	1623	1312	1117

Table G.9 CSS Reading Sheet for 30-inch Top Right Embedment Strip on North Side

	20 (C)	Slope											
	September 1	Slc											
op Right		95%											
30 Inch Top Right		14-Day	0729	6040	0832	9895	0720	0662	0578	0693	0520	9190	0387
		7-Day	0721	0702	0820	0882	0714	0658	0573	9890	0514	0604	0379
North		3-Day	0727	0710	0829	0891	0723	0663	0280	6890	0521	0611	0387
Beam Side		2-Day	0730	0200	0830	2880	0719	0661	0575	6890	0516	1190	0384
Веаш		1-Day	0730	0712	0833	0893	0722	2990	0579	0693	0522	0614	0388
GIC		Release	0270	0732	0852	0902	0738	0685	9650	0714	0538	0628	0405
Beam Number		Initial 2	0920	0744	9802	0918	0753	9690	2090	0740	0550	0639	0409
Beam N		Initial 1	0763	0742	980	9260	0752	2690	9090	0740	0548	0639	0409

Table G.10 CSS Reading Sheet for 48-inch Bottom Right Embedment Strip on North Side

ŗ		F	П																				_
			Slope																				
	tom Right	And the second s	%56																				
	48 Inch Bottom Right		14-Day	0010	0054	0114	0010	9900	0053	-0304	-0341	-0631	-0501	9000	0051	0500	0198	-0028	0022	9600	0159	0230	0204
			7-Day	9000	0052	0103	2000	9500	8700	-0315	-0351	-0643	-0518	-0011	0047	0283	6810	-0052	2000	0082	0149	0211	0181
	North		3-Day	0016	0062	0109	0016	6500	0038	90£0-	-0339	-0635	-0504	-000	0053	0298	0197	-0052	-0003	6003	0161	0224	0187
	Beam Side		2-Day	0016	6500	0115	0014	0063	0040	-0301	-0336	-0617	-0502	0000	5500	9670	0201	-0033	0000	0092	0168	0243	0191
	Веаш		1-Day	0026	0057	0123	0021	8900	0049	-0297	-0327	-0610	-0513	0003	6500	0302	0204	-0017	0022	0094	0168	0225	0100
	G1C		Release	0041	0600	0137	0042	1600	0057	-0278	-0308	-0588	-0507	0025	0078	0316	0218	-0015	0031	0111	0189	0258	0208
	umber		Initial 2	0105	0149	0191	0093	0148	0110	-0219	-0256	-0536	-0423	0000	0126	0365	0256	6000	0048	0141	0213	0276	0223
	Beam Number		Initial 1	0103	0147	0188	8600	0144	0107	-0219	-0254	-0524	-0416	8900	0128	0357	0258	0014	0064	0143	0203	0289	020

Table G.11 CSS Reading Sheet for 30-inch Top Left Embedment Strip on South Side

Beam Number	G1C	Bean	Beam Side	South		30 Inch Top Left	Fop Left	
Initial 2	2 Release	1-Day	2-Day	3-Day	7-Day	14-Day	95%	Slope
0578	920	0553	0554	0565	0552	0554		
0613	9090	0594	0592	9650	0587	0593		
0762	0749	0733	0733	0741	0733	0735		
0503	0478	0473	0472	0476	0471	0467		
0563	0563	0550	0567	0576	0568	0571		
9990	90661	0647	0617	0652	0640	0647		
0611	5090	0591	0650	0596	0587	0690		
0928	0603	0894	8880	0904	6680	0904		
8838	9080	0783	0620	0802	0813	0814		
L8 L0	0775	0763	0759	0759	0754	0757		
0761	0752	0735	0730	0739	0729	0728		

Table G.12 CSS Reading Sheet for 48-inch Bottom Left Embedment Strip on South Side

Beam	Beam Number	GIC	Bean	Beam Side	South		48 Inch Bottom Left	ttom Left	
San Personal State Based Spreed	endere de la companya de la company								
Initial 1	Initial 2	Release	1-Day	2-Day	3-Day	7-Day	14-Day	%56	Slope
-0500	-0500	-0533	-0546	-0545	-0542	-0551	-0545		
-0192	-0192	-0234	-0244	-0250	-0250	-0252	-0248		
-0192	-0192	-0222	-0233	-0233	-0233	-0243	-0228		
0040	9500	2000	-0005	6000-	-0011	-0010	-0014		
0170	0170	0140	0135	0129	0126	0115	0124		
-0010	-0025	8900-	-0085	9200-	9800-	8200-	-0094		
-0026	-0019	8900-	9800-	6800-	-0082	-0087	6800-		
-0055	-0056	-0107	-0123	-0128	-0123	-0138	-0132		
-0313	-0313	-0353	-0367	-0374	-0370	-0373	-0369		
-0077	-0073	-0134	-0150	-0157	-0154	-0165	-0160		
-0095	-0095	-0150	-0171	-0176	-0168	-0182	-0171		
-0266	-0237	-0329	-0343	-0353	-0348	-0353	-0352		
0253	0253	0192	0175	0167	0182	5910	9910		
-0038	-0035	-0130	-0141	-0146	-0145	-0154	-0155		
-0154	-0155	-0203	-0194	-0211	-0210	-0216	-0210		
-0101	-0100	-0167	-0175	-0184	-0179	-0191	-0188		
-0580	-0580	-0620	-0636	-0638	-0637	-0647	-0644		
-0467	-0470	-0500	-0505	-0516	-0512	-0528	-0522		
-0178	-0178	-0263	-0220	-0276	-0278	-0294	-0283		
-0108	-0106	-0151	-0159	-0163	0910-	-0174	-0170		

Table G.13 CSS Reading Sheet for 26-inch Top Center Embedment Strip on South Side

Beam Number	GIC	Bean	Beam Side	South		26 Inch T	26 Inch Top Center	
			MACHINE OF PRINCIPAL STRUCTURES	om denda Dreger, dri made kier yrodo				
П	Release	1-Day	2-Day	3-Day	7-Day	14-Day	95%	Slope
	1147	1122	1124	1124	1115	1118		
	0633	0617	0614	0621	6090	0613		
	0838	0815	0824	0828	0817	0821		
0732	0726	0710	0200	0720	0713	0720		
0639	0637	0638	0621	0617	9090	0613		
0770	0748	0754	0739	0741	0729	0734		
0721	0705	0690	9892	8890	2290	0682		
6693	0647	6590	0990	0661	0652	0654		
222	9980	0845	0864	0862	0852	0829		

Table G.14 CSS Reading Sheet for 26-inch Bottom Center Embedment Strip on South Side

		Slope									
om Center		95%									
26 Inch Bottom Center		14-Day	0819	0736	0619	0547	0673	0508	0636	0642	0681
		7-Day	0824	0737	0616	0549	2290	0496	0619	0633	6290
South	essus exemples	3-Day	0834	0755	0625	0559	0890	0565	0633	0640	0681
Side	e de la company de la constante	2-Day	0834	0753	0630	0563	8890	0498	0624	0646	0687
Beam Side		I-Day	0840	0756	0631	0565	2690	0209	0644	0646	0692
GIC		Release	0851	6920	0646	0546	0702	0512	0643	199 0	0703
umber		Initial 2	8060	0824	0692	0616	0752	0572	0713	6690	0753
Beam Number		Initial 1	0913	0829	0692	0635	0758	0575	0716	0207	09/0

Table G.15 CSS Reading Sheet for 30-inch Top Right Embedment Strip on North Side

	Hanselman superconnected police	Slope											
30 Inch Top Right		%56											
30 Inch 7		14-Day	0647	0638	0771	0742	09/0	0742	0741	0649	0592	0650	0671
		7-Day	0642	0636	89/0	0741	0764	0740	0738	0643	0590	0647	0664
South		3-Day	0653	0645	9220	0746	0759	0748	0745	0648	0594	0652	6990
Beam Side		2-Day	0654	0636	020	0747	0762	0742	0740	0646	0593	0645	2990
Bean		1-Day	0649	0639	0771	0746	0763	0743	0742	0647	0591	0648	0670
GIC		Release	0/90	0990	6/10	0761	0780	0758	0761	9990	0610	0662	0684
Beam Number		Initial 2	8290	0890	9080	0785	2620	7770	6220	8290	0621	0290	9890
Beam N		Initial 1	0694	0673	0797	9820	6620	0781	0772	0678	0625	0290	9690

Table G.16 CSS Reading Sheet for 48-inch Bottom Right Embedment Strip on South Side

ſ		B. All Bridge	0)																				
		Section of the section of	Slope																				
	tom Right	VOS DE COMPUTATION CONTRACTOR DE COMPUTATION DE L'ARGENT PROPERTIES	95%																				
	48 Inch Bottom Right	_	14-Day	0935	0370	0246	0120	0174	8000-	-0107	-0271	-0373	-0449	-0454	-0580	-0837	-0758	-0746	-0742	-0476	-0527	-0348	-0217
			7-Day	0935	0371	0245	0115	0174	0000	-0106	-0273	-0388	-0455	-0454	-0582	-0851	-0765	-0752	-0755	-0484	-0540	-0355	-0222
	South		3-Day	0943	0381	0255	0127	0185	0010	-0095	-0259	-0387	-0439	-0443	-0572	-0837	-0758	-0746	-0740	-0466	-0532	-0351	-0220
	Beam Side		2-Day	0949	0377	0253	0133	0182	0013	9600-	-0260	-0388	-0450	-0445	-0575	-0831	-0758	-0749	-0746	-0460	-0522	-0347	-0212
	Веап		1-Day	0952	0381	0261	0131	0188	0017	0600-	-0249	-0378	-0426	-0436	-0568	-0816	6520-	-0746	-0740	-0459	-0529	-0347	-0215
	G1C		Release	1005	0402	0281	0149	0208	0034	-0073	-0237	-0366	-0411	-0419	-0550	-0792	-0734	-0721	-0724	-0449	-0514	-0330	-0187
	umber		Initial 2	1065	0457	0338	0230	0263	0091	-0016	-0175	-0288	-0373	-0370	-0504	-0775	-0706	1690-	6690-	-0419	-0511	-0322	-0249
	Beam Number		Initial 1	1065	0469	0337	0225	0270	9800	-0019	-0178	-0289	-0378	-0369	-0505	-0773	-0712	-0714	9020-	-0426	-0511	-0325	-0244

Table G.17 Raw Concrete Surface Strains for North Side of Girder G1C

Raw Transfer Length Data - North Side of Girder G1C

	Slope																			
	%\$6																			
	14-Day	1173	1173	942	1067	866	693	1065	1078	1271	1024	787	948	884	735	464	425	286	611	654
CSS - Microstrains	7-Day	1236	1198	6201	1105	1135	1005	1203	1204	1422	1238	666	866	1/6	847	794	612	749	736	891
CSS - Mi	3-Day	6601	1073	1004	993	1086	088	1090	1053	1321	1062	887	924	784	748	794	737	611	286	67.
	2-Day	1099	1110	626	1018	1036	855	1028	9101	\$601	1037	862	668	608	869	955	200	624	499	492
	1-Day	<i>51</i> 6	1135	829	930	973	743	8/6	903	1007	1175	824	849	734	099	356	425	599	466	716
	Release	981	724	655	899	989	643	740	999	730	1100	550	612	260	486	331	312	387	237	305
Rot-R	Gage #	1	. 7	3	4	5	9	7	∞	6	10	Ξ	12	13	14	15	16	17	18	19
	Slope																			
	%56			Γ								Г						Г		
П	9																			1
	14-Day 9	356	400	451	451	537	546	713	627	968	898	844	1078	1076	993	1289	586	1018	196	1114
rostrains	14-Day	468 356	475 400	614 451	614 451	587 537	633 546	762 713	H	921 896	1006 868	857 844	1103 1078	1063 1076	1330 663	1264 1289	1023 985	1031 1018	1041 967	1052 1114
CSS - Microstrains	ay 7-Day 14-Day	468	475	614	614	587	633	762	752	921	9001	857	1103	1063	5 1330	1264		1031	L	1052
	ay 7-Day 14-Day	356 468	313 475	564 614	564 614	512 587	559 633	700 762	739 752	809 921	818 1006	732 857	991 1103	1063	5 1330	1264	1023	943 1031	954 1041	1052
	3-Day 7-Day 14-Day	356 468	363 313 475	539 564 614	614 564 614	512 587	559 559 633	676 700 762	528 739 752	809 921	893 818 1006	769 732 857	966 991 1103	926 1063	1117 1355 1330	1101 1164 1264	922 1023	868 943 1031	867 954 1041	927 1052
	2-Day 3-Day 7-Day 14-Day	293 356 356 468	363 313 475	313 539 564 614	639 614 564 614	475 512 587	422 559 559 633	614 676 700 762	615 528 739 752	710 784 809 921	818 893 818 1006	719 769 732 857	928 966 991 1103	813 963 926 1063	1205 1117 1355 1330	914 1101 1164 1264	922 922 1023	794 868 943 1031	817 867 954 1041	1002 927 1052

Table G.18 Raw Concrete Surface Strains for South Side of Girder G1C

_			_			_	_			_											_
	Slope																				
	%56																				
	14-Day	1604	1156	1139	1340	1152	1199	1119	1184	1060	923	1901	950	795	618	549	498	672	201	307	370
rostrains	7-Day	1604	1143	1151	1402	1152	1099	1106	1209	1248	866	1061	975	972	902	624	999	773	365	395	307
CSS - Min	3-Day	1505	1019	1027	1253	1015	974	696	1034	1236	797	923	846	795	618	549	473	547	264	345	332
	2-Day	1431	1069	1052	1178	1053	936	186	1046	1248	936	948	887	719	819	286	549	471	138	295	433
	1-Day	1394	1019	952	1203	8/6	887	906	806	1123	634	835	799	530	631	549	473	459	226	295	395
	Release	740	758	703	8/6	729	674	694	758	972	446	622	572	227	315	233	271	333	38	82	746
Bot-R	Gage #	1	7	3	7	5	9	7	8	6	10	11	12	13	14	15	16	11	18	19	20
	Slope																				
	%56																				
	14-Day	995	702	451	277	574	926	831	957	703	1063	156	1260	1084	1482	\$69	1095	908	673	1315	789
crostrains	7-Day	642	752	639	725	989	756	908	1032	753	1126	1089	1273	1097	1469	170	1133	844	748	1453	839
CSS - Mi	3-Day	828	727	514	737	549	856	744	844	715	886	914	1210	885	1357	569	982	218	247	1253	663
	2-Day	995	727	514	712	511	731	831	206	765	1026	1014	1273	1072	1369	208	1045	730	265	1228	701
	1-Day	615	652	514	662	437	844	794	844	8/9	938	951	1147	972	1307	495	932	705	459	1153	651
	Release	415	526	376	512	374	631	695	644 44	502	738	889	972	760	1169	209	832	504	396	1065	551
Bot-L	Gage #						و			6	10		12	13	14	15	16	17	18	19	6
	- Microstrains	Bot-R CSS - Microstrains Bot-R CSS - Microstrains Bot-R CSS - Microstrains CSS	Release 1-Day 2-Day 7-Day 14-Day 95% Slope Release 1-Day 2-Day 7-Day 14-Day 95% 415 579 566 528 642 566 1 740 1394 1431 1505 1604 1604 1604	CSS - Microstrains Release 1-Day 2-Day 7-Day 14-Day 95% Slope Release 1-Day 2-Day 7-Day 14-Day 95% 415 579 566 528 642 566 1 740 1394 1431 1505 1604 1604 526 652 727 727 752 702 2 758 1019 1069 1143 1156	CSS - Microstrains Release 1-Day 2-Day 7-Day 14-Day 95% Slope Gage# Release 1-Day 2-Day 7-Day 14-Day 95% 415 579 566 528 642 566 1 740 1394 1431 1505 1604 1604 1604 526 652 727 727 752 702 2 758 1019 1069 1019 1143 1156 376 514 514 514 639 451 3 703 952 1052 1057 1151 1139	CSS - Microstrains Release 1-Day 2-Day 7-Day 14-Day 95% Slope Release 1-Day 2-Day 7-Day 14-Day 95% 415 579 566 528 642 566 164 1604 1604 1604 526 557 727 727 727 727 727 164 169 1019 1069 1019 1143 1156 376 514 514 514 639 451 3 703 952 1027 1151 1139 512 662 712 725 775	Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope Release 1-Day 2-Day 3-Day 14-Day 95% 415 579 566 528 642 566 2 56 1604 1604 1604 526 577 727 752 702 2 758 1019 1069 1019 1156 1156 376 514 514 514 639 451 3 703 952 1052 1027 1151 1139 512 662 712 725 775 4 978 1203 1178 1253 1402 1340 512 662 712 737 725 775 4 978 1203 1178 152 1152 1152	CSS - Microstrains Release 1-Day 2-Day 3-Day 14-Day 95% Slope Release 1-Day 2-Day 3-Day 14-Day 95% 415 579 566 528 642 566 10 1394 1431 1505 1604 14-Day 95% 526 579 570 727 727 727 727 727 161 1069 1019 1069 1019 1156 1157 1157 1152 1152 1152 1152 1152 1159 1159 1159 1159 1159 1159 1159 1159 1159 1159 1159 1159 1159 1159 1159 1159 1159 1159<	Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% 415 579 566 528 642 566 102 109 1394 1431 1503 1604	Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% 415 579 566 528 642 566 1 740 1394 1431 1505 1604 1604 1604 526 552 727 727 752 702 2 758 1019 1069 1019 1143 1156 376 514 514 514 639 451 3 703 952 1052 1027 1151 1139 512 514 514 514 517 775 775 4 978 1203 1178 1139 1152 51 540 586 574 84 978 1053 978 1162 1162 1162 563 754 844 731 844 907 978 978 978 1069	Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% 415 579 566 528 642 566 102 109 1394 1431 1505 1604 1604 1604 526 528 642 566 702 702 2 758 1019 1069 1019 1143 1156 510 514 514 514 514 639 451 3 703 952 1052 1151 1139 512 514 514 514 517 775 775 4 978 1203 1178 1139 1152 1152 1160 1169	Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope Gage # Release 1-Day 2-Day 7-Day 14-Day 95% Slope Gage # Release 1-Day 2-Day 7-Day 14-Day 95% 14-Day 95% 14-Day 95% 14-Day 95% 14-Day 150 1604	Release 1-Day 2-Day 7-Day 14-Day 95% Slope Gage # Release 1-Day 2-Day 7-Day 14-Day 95% Slope Gage # Release 1-Day 2-Day 7-Day 14-Day 95% Slope 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope 1-Day 2-Day 3-Day 7-Day 14-Day 95% 14-Day 95% 14-Day 1504 1604 1	Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope Gage # Release 1-Day 2-Day 7-Day 14-Day 95% 14-Day 95% 14-Day 95% 14-Day 95% 14-Day 3-Day 7-Day 14-Day 1504 14-Day 14-Day 95% 14-Day 1504 16	Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% 415 579 566 528 642 566 510 1 740 1394 1431 1503 1604	Release 1.Day 2.Day 3.Day T.Day 14-Day 55% Slope Release 1.Day 2.Day 7.Day 14-Day 95% Slope I 740 1394 1431 1505 1604 1604 95% 415 579 566 528 642 566 102 1604 <	Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope Cage# Release 1-Day 2-Day 7-Day 14-Day 95% Slope Cage# Release 1-Day 2-Day 7-Day 14-Day 95% Slope 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope 1-Day 2-Day 3-Day 7-Day 14-Day 95% 14-Day 3-Day 7-Day 14-Day 95% 14-Day 95% 14-Day 95% 14-Day 95% 14-Day 95% 14-Day 14-Day 95% 14-Day 95% 14-Day 14-Day 95% 15%	Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% 415 579 566 528 642 566 578 Slope Cage H Release 1-Day 2-Day 7-Day 14-Day 95% 415 579 566 528 642 566 528 642 566 102 1019 1019 1019 1143 1505 1604 604 95% 526 652 727 727 725 702 2 78 1019 1069 1143 1150 1160 <t< th=""><th>Release 1-Day 2-Day 3-Day 7-Day 14-Day 55% Slope Cage# Release 1-Day 2-Day 7-Day 14-Day 95% Slope Cage# Release 1-Day 2-Day 7-Day 14-Day 95% Slope 1 740 1394 1431 1505 1604 <t< th=""><th>Role Release LOSS - Microstrains Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope Release 1-Day 2-Day 7-Day 1-Day 1</th><th>Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope CSS - Microstrains Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope Cage# Release 1-Day 3-Day 7-Day 14-Day 95% 415 579 566 528 642 566 528 642 566 11 7-Day 14-Day 95% 526 652 727 727 725 702 2 758 1019 1049 1143 1156 512 662 712 737 725 775 4 978 1203 1178 1156 1156 512 662 712 737 725 956 6 674 887 1905 1189 973 1199 1189 972 1199 1189 972 1199 1189 972 1189 972 1189 972 1189 972 <td< th=""></td<></th></t<></th></t<>	Release 1-Day 2-Day 3-Day 7-Day 14-Day 55% Slope Cage# Release 1-Day 2-Day 7-Day 14-Day 95% Slope Cage# Release 1-Day 2-Day 7-Day 14-Day 95% Slope 1 740 1394 1431 1505 1604 <t< th=""><th>Role Release LOSS - Microstrains Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope Release 1-Day 2-Day 7-Day 1-Day 1</th><th>Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope CSS - Microstrains Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope Cage# Release 1-Day 3-Day 7-Day 14-Day 95% 415 579 566 528 642 566 528 642 566 11 7-Day 14-Day 95% 526 652 727 727 725 702 2 758 1019 1049 1143 1156 512 662 712 737 725 775 4 978 1203 1178 1156 1156 512 662 712 737 725 956 6 674 887 1905 1189 973 1199 1189 972 1199 1189 972 1199 1189 972 1189 972 1189 972 1189 972 <td< th=""></td<></th></t<>	Role Release LOSS - Microstrains Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope Release 1-Day 2-Day 7-Day 1-Day 1	Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope CSS - Microstrains Release 1-Day 2-Day 3-Day 7-Day 14-Day 95% Slope Cage# Release 1-Day 3-Day 7-Day 14-Day 95% 415 579 566 528 642 566 528 642 566 11 7-Day 14-Day 95% 526 652 727 727 725 702 2 758 1019 1049 1143 1156 512 662 712 737 725 775 4 978 1203 1178 1156 1156 512 662 712 737 725 956 6 674 887 1905 1189 973 1199 1189 972 1199 1189 972 1199 1189 972 1189 972 1189 972 1189 972 <td< th=""></td<>

Table G.19 Smoothed Concrete Surface Strains for North Side of Girder G1C

					Smoo	thed Tra	ınsfer L	Smoothed Transfer Length Data - North Side of Girder G1C	ta - Nor	th Side o	f Girder	GIC					
Bot-L					Microstrains				Bot-R				CSS - Mic	CSS - Microstrains			
Gage#	Release	1-Day	2-Day	-Day	7-Day	14-Day	%56	Slope	Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day	%56	Slope
1									_								
2	135	306	419	411	519	402			2	722	626	1046	1058	1171	1096		
3	213	422	505	480	995	434			3	682	965	1019	1023	1127	1901		
4	263	463	543	547	509	480			4	0/9	911	994	1027	1106	1002		
5	308	200	549	545	219	512			5	999	882	696	986	1082	616		
9	338	491	270	591	199	665			9	069	868	973	1019	1115	616		
7	343	550	587	999	716	679			7	682	874	996	1008	1137	946		
8	418	646	663	750	812	745			∞	711	962	1046	1155	1276	1138		
6	436	714	735	789	893	161			6	831	1028	1049	1145	1288	1124		
10	508	749	815	786	876	698			10	793	1002	866	1090	1220	1027		
11	531	822	928	847	886	930			11	754	949	932	957	1078	920		
12	270	820	668	883	1008	666			12	574	802	856	865	686	873		
13	637	982	1015	1090	1165	1049			13	552	748	802	818	939	958		
14	661	226	1901	1148	1219	1119			14	459	584	889	775	871	704		
15	642	972	1047	1147	1205	1089			15	376	480	159	759	751	551		
16	572	835	964	1010	1106	1097			16	343	460	627	714	718	502		
17	548	802	988	940	1032	066			17	312	507	607	645	669	541		
18	518	821	912	942	1041	1033			18	310	605	538	642	792	617		
19	538	845	616	696	1085	1036			19	214	513	434	559	889	471		
20									70								

Table G.20 Smoothed Concrete Surface Strains for South Side of Girder G1C

					Smoo	othed Tra	ınsfer L	Smoothed Transfer Length Data - South Side of Girder G1C	ta - Sou	th Side o	f Girder	GIC					
Bot-L				CSS - Mic	Microstrains				Bot-R				CSS - Microstrains	rostrains			
Gage#	Release	1-Day	2-Day	3-Day	7-Day	14-Day	%56	Slope	Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day	%56	Slope
1																	
2	439	581	602	590	<i>LL</i> 9	573			7	734	1122	1184	1184	1299	1299		
3	471	609	651	629	705	642			3	813	1058	1100	1100	1232	1212		
4	421	537	579	009	683	009			4	804	1044	1094	1098	1235	1210		
5	909	648	652	714	722	892			S	794	1022	1056	1801	1218	1230		
9	525	169	169	716	750	187			9	669	924	066	986	1119	1157		
7	615	827	823	815	865	915			7	709	006	886	992	1138	1167		
8	572	21.1	835	768	864	830			∞	808	626	1092	6201	1188	1121		
6	628	820	668	849	026	806			6	725	888	1077	1022	1152	1056		
10	643	856	935	872	686	906			92	089	864	1044	985	1103	1015		
11	466	1012	1104	1037	1163	1092			11	547	756	924	857	1011	876		
12	208	1023	6111	1003	1153	8601			12	474	721	851	856	1003	935		
13	296	1142	1238	1511	1280	1275			13	372	653	741	754	884	788		
14	846	924	1050	626	1112	1087			14	259	570	<u>\$</u>	654	191	654		
15	870	116	1041	1011	1124	1601			15	273	551	584	546	664	555		
16	648	111	828	266	916	865			16	279	493	535	523	989	573		
17	577	669	167	749	806	858			17	214	386	386	428	009	457		
18	655	772	852	839	1015	931			18	151	327	302	385	511	394		
61	671	754	842	821	1013	976			19	288	305	289	314	356	293		
70									20								

Table G.21 Averaged Raw Concrete Surface Strains for Girder G1C (North Reference)

		Slope																					
		%56																					
	Order)	14-Day	0	358	8/9	531	089	499	725	783	920	826	925	886	1266	1081	1274	694	1047	937	807	1244	186
	s (Reverse	7-Day	0	539	821	289	737	649	775	827	1001	928	1063	1163	1347	1150	1336	888	1134	974	913	1326	1037
rence)	CSS - microstrains (Reverse Order	3-Day	0	445	728	550	674	643	825	746	814	819	938	886	1266	696	1224	- 88 <i>L</i>	1034	855	775	1163	881
rth Refe	CSS - n	2-Day	0	439	609	909	899	605	644	765	828	832	944	1025	1184	1044	6611	181	1040	874	292	1169	006
1C - (No		1-Day	0	451	684	909	631	431	009	727	682	292	881	1063	1077	637	1142	619	653	818	644	1144	812
irder G		Release	0	257	416	306	450	343	481	527	602	257	644	894	851	712	954	625	159	286	525	894	699
ata for C	Bot-R	Posn	0	5.12	7.12	9.12	11.12	13.12	15.12	17.12	19.13	21.13	23.13	25.13	27.12	29.12	31.11	33.11	35.11	37.10	39.10	41.10	43.10
h Plot D		Slope																					
er Leng		%56																					
v Transf	Order)	14-Day	0	363	354	326	295	218	547	999	711	923	596	884	1069	1130	1056	1244	1069	1179	1053	1135	1315
Averaged Raw Transfer Length Plot Data for Girder G1C - (North Reference)	ostrains (Normal Order)	7-Day	0	88£	435	489	663	625	679	734	862	948	1033	927	1176	1136	1218	1181	1088	1217	1096	1097	1383
🖫	ŀĒ	-Day	0	344	6	4	.2	13	4.	6	.7	829	71	764	.13	980	162	690	696	8601	166	973	1266
Ave		Q-E)	7E	37	17	555	67	554	59) <i>L</i>	28	.8	7	Ξ	6	1	1					L
Ave	CSS - microstr	2-Day 3-D	0	H			543 55	512 49	573 55	647 65	Н			852 7	Н			_	_				1 100 1
Ave		3	0 0	H	329		543	512	573		624	836	921	852	6 1107	1005	1049	1019	284	1023	626	1035	_
Ave		2-Day		394	329	270 338	549 543	455 512	573	622 647	573 624	754 836	827 921	677 852	1026 1107	861 1005	1056 1049	900 1019	887 987	998 1023	885 959	936 1035	1160




Figure G.1 Raw CSS Data for East End of Girder G1C




Figure G.2 Raw CSS Data for West End of Girder G1C

Table G.22 Averaged Smoothed Concrete Surface Strains for Girder G1C (North Reference)

	-	_		-	_	_	_		_		_	_		_	_	_	_	_	_			-
		Slope	0	522	630	570	635	699	810	843	890	913	1059									
		%56	975	975	975	975	975	975	975	975	975	975	975	975	975	975	975	975	975	975	975	
	Order)	14-Day	0	522	630	570	635	699	810	843	068	913	1059	1111	1207	1016	1005	892	930	966	1011	
	(Reverse	7-Day	0	682	748	169	720	750	898	106	086	1034	1611	1220	1278	1125	6111	666	1001	1071	1092	
ference)	CSS - microstrains (Reverse Order)	3-Day	0	574	159	622	714	738	795	793	857	915	1064	1074	1153	993	1015	892	888	931	940	
orth Re	CSS - mi	2-Day	0	518	595	593	639	671	755	818	878	934	1051	1084	1142	1008	1007	668	892	935	944	
G1C - (N		1-Day	0	547	209	522	554	989	902	09/	811	903	1007	1026	1052	668	505	962	805	698	298	
aged Smoothed Transfer Length Plot Data for Girder G1C - (North Reference)		Release	0	327	391	366	425	451	537	562	109	869	962	819	839	764	780	259	623	899	969	
Data for	Bot-R	Gage#	0	7.12	9.12	11.12	13.12	15.12	17.12	19.13	21.13	23.13	25.13	27.12	29.12	31.11	33.11	35.11	37.10	39.10	41.10	43.10
gth Plot		Slope	0	348	414	469	542	577	641	191	998	924	972									
ısfer Ler		%56	1137	1137	1137	1137	1137	1137	1137	1137	1137	1137	1137	1137	1137	1137	1137	1137	1137	1137	1137	
hed Tran	Order)	14-Day	0	348	414	469	542	577	641	191	998	924	972	1027	1085	1143	1123	1164	1100	1122	1168	
d Smootl	trains (Normal Order)	7-Day	0	437	539	603	649	663	742	848	948	970	1045	0801	1177	1179	1162	1162	1134	1137	1192	
Average	icrostrain	3-Day	0	362	433	487	534	995	099	752	822	821	916	625	1085	1070	1067	1045	6101	1021	9201	
	CSS - micros	2-Day	0	354	403	464	542	577	614	702	793	698	096	886	1054	1024	1019	1010	066	1006	1052	
	1 1								0	0	8	752	843	854	186	939	948	626	923	940	983	
		1-Day	0	306	374	425	497	521	999	920	718	7	∞	∞	6	6	6	6	5	֓֓֓֓֓֓֓֓֓֓֓֓֟֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓		
		Release 1-Day	0 0	212 306	182 374	238 425	294 497	306 52	301 56		Н	527		648 8		685 6	671 9	683 6	929	599	636	




Figure G.3 Smoothed CSS Data for East End of Girder G1C




Figure G.4 Smoothed CSS Data for West End of Girder G1C




Figure G.5 Transfer Length Determined Using 95% AMS Method for East End of Girder G1C




Figure G.6 Transfer Length Determined Using 95% AMS Method for West End of Girder G1C

APPENDIX H

CONCRETE SURFACE STRAIN AND OTHER DATA

This Appendix contains raw data for each girder. The following data items were recorded before strand release (initial), just after release, and 1, 2, 3, 7 and 14-days after strand release. The data taken through 14 days were used to determine transfer length.

Date and time

Midspan deflection

Ambient temperature

Internal girder temperature

Reading in hertz from the vibrating wire strain gage at midspan

Resistance reading from the thermistor in the vibrating wire strain gage

CSS readings from each embedment strip

The following values were also recorded for each girder at the time of strand tensioning.

Strain reading from strand load cell

Strand jacking force

Strand elongation

Date and time

Ambient temperature

Strand load cell readings were also recorded immediately prior to strand release for comparison with initial load cell readings. The sections correspond with the individual girders as follows:

Section H.1 - Girder G1A

Section H.2 - Girder G1B

Section H.3 - Girder G1C

Section H.4 – Girder G2A

Section H.5 - Girder G2B

Section H.6 – Girder G2C

The directions North and South refer to girder sides based on orientation at time of construction. East and West refer to girder ends. The gage positions on embedment strips are always referenced from left to right as shown in Figures G.3 and G.4. Gage locations are numbered from 1 to 20 meaning there are 20 CSS readings taken on each bottom embedment strip. The embedment strips are located at the ends of the girders on both sides at the level of the bottom row of prestressing strands. Positive CSS values indicate a compressive strain.

H.1 Girder G1A

Table H.1 G1A Girder Data

Gir	der#	G1A	Raw Da	ta for Transfer	and Develo	pment Le	ngth
Reading	Date	Time	Midspan	Ambient	Internal	VWS	G Data
#	(m/dd/yy)	(24 hr)	Deflection (inches)	Temp (Deg F)	Temp (Deg F)	Hz	ΩWG
Initial 1	7/10/01	11:30	1.703	80.0		924.84	2128
Initial 2	7/10/01	12:10	1.703	80.0		924.84	2128
Release	7/10/01	15:07	2.063	90.0		822.05	2128
1-Day	7/11/01	7:40	2.078	75.0			
2-Day	7/12/01	7:45	2.094	75.0	73.8	809.31	2470
3-Day	7/13/01	7:05	2.094	74.7	72.2	802.80	2515
7-Day	7/17/01	6:30	2.109	72.4	67.0	790.57	2884
14-Day	7/24/01	6:55	2.125	74.5	68.4	778.42	2568

	Strand	Jacking D	ata from Load	Cells and Tensi	oning Machine	
	Load			hine Readings	Date and Time	Ambient
	Read	ings			Of	Temp
Load	At	Prior	Strand	Strand	Tensioning	_
Cell	Time of	То	Jacking	Elongation		
(Strand)	Stressing	Release	Force		(m/dd/yy)	1
#	(με)	(με)	(lbs)	(inches)	(24 hr)	(Deg F)
1	4533	4513	45000	10.250		
2	5275	5270	45000	9.875		
3	5430	5438	45000	10.125		
4	4975	4960	45000	9.875		
5	5352	5313	45000	9.875	9 Jul 01	00
6	5286	5270	45000	9.750	11:30	90
7	5206	5150	45500	9.875		
8	5340	5357	45000	10.625		
9	5430	5448	45000	10.250		
10	5532	5479	45000	. 10.125		

Table H.2 Raw Concrete Surface Strain Data for Girder G1A-North

East		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	157	244	307	269	420	457
2	250	350	463	375	550	600
3	237	350	412	375	525	637
4	243	380	405	380	480	517
5	450	512	587	525	774	837
6	344	432	407	382	545	632
7	419	557	632	594	695	720
8	344	444	557	507	895	682
9	456	780	905	818	955	1030
10	482	657	757	707	932	1007
11	499	674	699	737	861	886
12	468	643	693	705	942	980
13	356	494	544	556	744	606
14	531	681	644	631	794	869
15	451	488	576	589	902	764
16	513	738	851	876	964	1101
17	457	569	632	644	845	1082
18	449	674	736	736	936	1010
19	475	674	737	724	1086	1149
20	431	281	807	757	857	957

West		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	401	526	514	526	764	7 77
2	450	801	901	813	1063	1088
3	632	944	1019	957	1182	1294
4	588	639	751	676	964	1014
5	514	564	740	765	1003	1053
6	358	421	484	409	861	987
7	88	615	615	615	640	678
8	407	707	745	795	907	982
9	501	739	939	814	1052	1127
10	592	879	941	792	555	1203
11	639	551	639	701	1139	1152
12	263	313	489	489	890	1065
13	382	495	557	570	795	708
14	413	125	276	363	651	614
15	318	517	580	580	704	754
16	589	288	175	63	100	251
17	407	307	319	357	369	457
18	281	432	444	469	557	544
19	19	144	19	6	169	257
20	162	37	287	249	336	448

Table H.3 Raw Concrete Surface Strain Data for Girder G1A-South

East		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	411	722	760	772	872	897
2	618	693	843	830	930	955
3	468	805	855	855	967	992
4	588	763	825	800	900	925
5	474	699	736	724	611	649
6	530	629	729	754	854	854
7	455	679	804	791	854	916
8	610	722	834	809	909	984
9	978	916	1190	1265	1277	1240
10	529	754	.754	816	754	828
11	473	771	821	809	846	833
12	416	714	702	640	665	677
13	497	634	721	671	696	671
14	542	879	941	904	1003	1041
15	306	892	917	892	980	830
16	256	693	768	756	831	843
17	256	493	430	493	468	443
18	330	542	492	504	529	156
19	100	338	563	438	701	688
20	94	357	408	395	508	508

West		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	75	300	325	275	613	526
2	232	545	557	307	820	770
3	224	511	499	499	499	524
4	312	561	598	524	661	686
5	319	731	706	406	643	818
6	437	762	787	824	837	824
7	507	745	845	883	1033	1083
8	530	830	880	892	980	992
9	527	765	1003	1078	1191	1179
10	502	765	803	803	891	916
11	784	1034	934	1047	884	884
12	510	863	876	914	939	989
13	532	757	770	845	882	607
14	532	832	857	895	983	970
15	381	731	744	756	719	669
16	548	810	847	872	959	959
17	486	910	997	1096	1184	1258
18	491	802	827	1286	988	827
19	690	1150	1200	1225	1324	1312
20	584	870	895	920	1045	1007

H.2 Girder G1B

Table H.4 G1B Girder Data

Gir	der#	G1B	Raw Da	ta for Transfer	and Develo	opment Le	ength
Reading	Date	Time	Midspan	Ambient	Internal	VWS	G Data
#	(m/dd/yy)	(24 hr)	Deflection (inches)	Temp (Deg F)	Temp (Deg F)	Hz	WG
Initial 1	7/10/01	11:30	1.938	80.0		929.61	2009
Initial 2	7/10/01	12:10	1.938	80.0		929.61	2009
Release	7/10/01	15:25	2.250	90.0		822.64	2009
1-Day	7/11/01	7:55	2.266	75.0			
2-Day	7/12/01	7:50	2.297	75.0	85.3	808.81	2448
3-Day	7/13/01	7:45	2.297	77.2	82.6	802.40	2534
7-Day	7/17/01	7:30	2.320	70.0	78.5	788.66	2905
14-Day	7/24/01	7:00	2.328	75.6	83.0	775.01	2499

	Strand	Jacking D	ata from Load	Cells and Tensi	oning Machine	
	Load	Cell	Tension Mac	hine Readings	Date and Time	Ambient
	Read	ings			Of	Temp
Load	At	Prior	Strand	Strand	Tensioning	
Cell	Time of	To	Jacking	Elongation		
(Strand)	Stressing	Release	Force		(m/dd/yy)	
#	(με)	(με)	(lbs)	(inches)	(24 hr)	(Deg F)
1	4533	4513	45000	10.250		
2	5275	5270	45000	9.875		
3	5430	5438	45000	10.125		
4	4975	4960	45000	9.875		
5	5352	5313	45000	9.875	9 Jul 01	90
6	5286	5270	45000	9.750	11:30	30
7	5206	5150	45500	9.875		
8	5340	5357	45000	10.625		
9	5430	5448	45000	10.250		
10	5532	5479	45000	10.125		

Table H.5 Raw Concrete Surface Strain Data for Girder G1B-North

East		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	37	174	224	199	422	497
2	6	156	193	193	380	430
3	337	175	912	212	237	62
4	256	169	219	169	156	219
5	75	38	126	113	414	477
6	87	500	512	500	612	700
7	424	649	711	836	998	973
8	238	450	500	488	663	801
9	243	593	456	418	655	805
10	350	350	413	388	588	725
11	419	618	743	743	806	906
12	535	573	797	834	759	909
13	478	763	813	850	999	1073
14	224	385	509	559	832	584
15	453	552	639	614	925	1011
16	494	569	656	669	844	881
17	539	627	727	702	928	966
18	533	445	771	720	1121	1422
19	444	657	732	720	895	932
20	537	599	724	674	1011	1024

West		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	381	618	705	705	930	955
2	312	599	661	661	811	874
3	343	580	580	605	855	892
4	462	487	549	574	874	824
5	357	532	607	644	832	882
6	368	630	667	692	867	904
7	383	458	558	608	822	834
8	301	690	652	527	928	941
9	478	578	692	754	918	993
10	126	604	579	717	805	918
11	343	618	705	705	1005	1217
12	381	644	744	656	982	1032
13	392	702	802	1001	963	1001
14	137	337	411	349	623	773
15	300	512	612	587	849	887
16	50	237	200	225	437	575
17	150	287	400	412	562	612
18	181	355	418	430	530	630
19	62	312	374	361	374	399
20	106	44	181	156	243	243

Table H.6 Raw Concrete Surface Strain Data for Girder G1B-South

East		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	553	452	515	917	666	766
2	723	911	999	987	1163	1213
3	545	859	946	972	1072	1034
4	490	842	968	930	1069	1081
5	661	837	1039	1089	1177	1328
6	763	1078	1216	1166	1191	1254
7	391	858	1022	1073	1148	1249
8	581	961	1024	1011	1138	1188
9	541	906	1007	981	1095	1120
10	490	653	741	402	502	578
11	509	760	860	747	835	873
12	383	483	508	445	571	596
13	408	633	872	784	922	959
14	519	795	895	857	995	958
15	507	569	682	607	594	532
16	274	449	6043	473	473	473
17	193	442	492	417	542	529
18	361	274	460	361	448	410
19	56	43	155	192	354	329
20	346	136	333	197	148	309

West		Ra	w CSS - 1	nicrostra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	38	163	250	225	463	338
2	13	138	413	188	263	238
3	131	344	319	294	406	344
4	287	449	424	499	687	612
5	281	582	544	544	582	544
6	263	501	538	538	714	601
7	457	820	832	870	958	882
8	532	857	882	920	970	970
9	476	839	889	1001	1026	1014
10	394	732	757	732	844	807
11	470	846	871	883	984	1009
12	389	703	741	766	879	879
13	439	777	827	802	927	902
14	726	801	852	826	952	889
15	451	889	977	1002	1140	1140
16	450	775	813	813	938	888
17	558	846	947	909	1085	1147
18	666	1005	1419	1608	1633	1620
19	438	676	714	726	827	827
20	495	746	821	821	1272	1147

H.3 Girder G1C

Table H.7 G1C Girder Data

Gir	der#	G1C	Raw Da	ta for Transfer	and Develo	opment Le	ngth
Reading	Date	Time	Midspan	Ambient	Internal	VWS	G Data
#	(m/dd/yy)	(24 hr)	Deflection (inches)	Temp (Deg F)	Temp (Deg F)	Hz	WG
Initial 1	7/18/01	12:10	2.031	85.0	117.4	902.66	1308
Initial 2	7/18/01	12:10	2.031	85.0	117.4	902.66	1308
Release	7/18/01	15:15	2.453	87.8	108.5	799.65	1387
1-Day	7/19/01	7:08	2.469	74.2	84.6	791.59	2407
2-Day	7/20/01	6:53	2.484	73.6	83.5	784.09	2514
3-Day	7/21/01	6:50	2.500	72.5	79.0	780.30	2829
7-Day	7/25/01	7:10	2.531	73.8	78.7	762.00	2868
14-Day	8/1/01	6:30	2.555	72.0	78.1	749.82	2863

	Strand	Jacking D	ata from Load	Cells and Tensi	oning Machine	
	Load		Tension Mac	hine Readings	Date and Time	Ambient
	Read	ings			Of	Temp
Load	At	Prior	Strand Strand		Tensioning	
Cell	Time of	To	Jacking	Elongation		
(Strand)	Stressing	Release	Force		(m/dd/yy)	
#	(με)	(με)	(lbs)	(inches)	(24 hr)	(Deg F)
1	5163	4989	45000	9.875		
2	5218	5023	45500	9.750		
3	5640	5387	46000	9.750		
4	5549	5406	46000	9.875	17 1-101	
5	5484	5279	46000	9.875	17 Jul 01	75
6	5456	5309	46000	9.875	9:40	75
7	5126	5000	45000	10.000		
8	5115	4970	45000	10.000		
9	5489	5387	46000	9.750		
10	5601	5443	46000	9.750		

Table H.8 Raw Concrete Surface Strain Data for Girder G1C-North

East		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	106	293	356	356	468	356
2	150	313	363	313	475	400
3	150	313	539	564	614	451
4	338	639	614	564	614	451
5	300	437	475	512	587	537
6	286	422	559	559	633	546
7	428	614	676	700	762	713
8	317	615	528	739	752	627
9	510	710	784	809	921	896
10	481	818	893	818	1006	868
11	531	719	769	732	857	844
12	580	928	966	991	1103	1078
13	600	813	963	926	1063	1076
14	730	1205	1117	1355	1330	993
15	651	914	1101	1164	1264	1289
16	546	797	922	922	1023	985
17	519	794	868	943	1031	1018
18	580	817	867	954	1041	967
19	454	852	1002	927	1052	1114
20	578	865	889	1026	1163	1026

West		Ra	w CSS - 1	nicrostra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	786	974	1099	1099	1236	1173
2	724	1135	1110	1073	1198	1173
3	655	829	929	1004	1079	942
4	668	930	1018	993	1105	1067
5	686	973	1036	1086	1135	998
6	643	743	855	880	1005	693
7	740	978	1028	1090	1203	1065
8	665	903	1016	1053	1204	1078
9	730	1007	1095	1321	1422	1271
10	1100	1175	1037	1062	1238	1024
11	550	824	862	887	999	787
12	612	849	899	924	998	948
13	560	734	809	784	971	884
14	486	660	698	748	847	735
15	331	356	556	794	794	494
16	312	425	700	737	612	425
17	387	599	624	611	749	586
18	237	499	499	586	736	611
19	305	716	492	729	891	654
20	100	324	312	362	436	150

Table H.9 Raw Concrete Surface Strain Data for Girder G1C-South

East		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	740	1394	1431	1505	1604	1604
2	758	1019	1069	1019	1143	1156
3	703	952	1052	1027	1151	1139
4	978	1203	1178	1253	1402	1340
5	729	978	1053	1015	1152	1152
6	674	887	936	974	1099	1199
7	694	906	981	969	1106	1119
8	758	908	1046	1034	1209	1184
9	972	1123	1248	1236	1248	1060
10	446	634	936	797	998	923
11 -	622	835	948	923	1061	1061
12	572	799	887	849	975	950
13	227	530	719	795	972	795
14	315	631	618	618	706	618
15	233	549	586	549	624	549
16	271	473	549	473	662	498
17	333	459	471	547	773	672
18	38	226	138	264	365	201
19	82	295	295	345	395	307
20	746	395	433	332	307	370

West		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	415	579	566	528	642	566
2	526	652	727	727	752	702
3	376	514	514	514	639	451
4	512	662	712	737	725	775
5	374	437	511	549	686	574
6	631	844	731	856	756	956
7	569	794	831	744	806	831
8	644	844	907	844	1032	957
9	502	678	765	715	753	703
10	738	938	1026	988	1126	1063
11	688	951	1014	914	1089	951
12	972	1147	1273	1210	1273	1260
13	760	972	1072	885	1097	1084
14	1169	1307	1369	1357	1469	1482
15	607	495	708	695	770	695
16	832	932	1045	982	1133	1095
17	504	705	730	718	844	806
18	396	459	597	547	748	673
19	1065	1153	1228	1253	1453	1315
20	551	651	701	663	839	789

H.4 Girder G2A

Table H.10 G2A Girder Data

Gir	der#	G2A	Raw Da	ta for Transfer	and Develo	opment Le	ength
Reading	Date	Time	Midspan	Ambient	Internal	VWS	G Data
#	(m/dd/yy)	(24 hr)	Deflection (inches)	Temp (Deg F)	Temp (Deg F)	Hz	WG
Initial 1	7/13/01	10:15	2.047	82.8	112.0	920.40	1377
Initial 2	7/13/01	10:15	2.047	82.8	112.0	920.40	1377
Release	7/13/01	15:30	2.359	98.8	106.4	846.40	1410
1-Day	7/14/01	7:25	2.313	73.6	81.0	844.75	2771
2-Day							
3-Day	7/16/01	6:40	2.320	75.3	80.5	843.64	2813
7-Day	7/20/01	7:55	2.344	74.2	82.3	838.23	2556
14-Day	7/27/01	6:55	2.344	73.1	78.7	839.09	2759

	Strand	Jacking Da	ata from Load	Cells and Tensi	oning Machine	
	Load	Cell	Tension Mac	hine Readings	Date and Time	Ambient
	Read	ings			Of	Temp
Load	At	Prior	Strand Strand		Tensioning	
Cell	Time of	То	Jacking	Elongation		
(Strand)	Stressing	Release	Force		(m/dd/yy)	
#	(με)	(με)	(lbs)	(inches)	(24 hr)	(Deg F)
1	6013	6140	45000	10.500		
2	5107	5310	45500	9.875		Ì
3	5193	5351	45500	10.000		
4	4742	4891	45000	10.000		
5	5516	5727	45000	9.750	12 Jul 01	05
6	5432	5572	45000	9.750	11:30	95
7	5296	5426	45000	9.875		
8	5452	5612	45000	10.000		
9	5587	5781	45500	10.500		
10	5824	6011	45500	10.375		

Table H.11 Raw Concrete Surface Strain Data for Girder G2A-North

East		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	205	441		541	553	665
2	479	653		727	653	715
3	318	518		555	568	555
4	375	525		338	350	300
5	351	627		715	690	777
6	437	687		825	837	862
7	200	474		723	624	723
8	718	1343		1318	1381	1531
9	281	505		455	318	405
10	582	819		894	894	1044
11	800	963		1038	1026	1213
12	454	728		778	703	790
13	584	733		819	844	1018
14	452	614		564	490	614
15	459	645		632	620	694
16	487	761		936	923	1023
17	795	1095		1158	1158	1233
18	494	782		857	845	945
19	375	663		726	726	763
20	399	624		611	636	711

West		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	474	924		1048	1036	1136
2	443	855		855	818	905
3	462	774		761	774	848
4	543	668		705	705	880
5	606	831		918	931	981
6	537	800		837	812	887
7	332	759		759	796	846
8	407	658		720	670	733
9	521	823		923	898	973
10	308	659		709	684	785
11	1456	1244		1156	1206	1131
12	719	906		969	981	1069
13	467	790		828	815	877
14	518	767		817	829	904
15	431	843		905	918	1005
16	319	644		706	656	706
17	331	543		543	531	581
18	268	455		480	. 443	493
19	318	567		505	517	630
20	380	355		430	380	442

Table H.12 Raw Concrete Surface Strain Data for Girder G2A-South

East		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	339	740		916	991	891
2	232	508		1022	1060	822
3	207	570		695	833	620
4	577	1080		1230	716	1193
5	283	674		674	1177	699
6	359	801		901	990	788
7	411	790		853	878	828
8	398	727		968	1081	1006
9	283	586		674	774	724
10	246	497		573	636	548
1.1	333	696		797	885	809
12	376	714		840	1015	902
13	332	1210		1310	1285	1298
14	262	600		762	825	787
15	188	551		576	639	651
16	230	479		529	542	616
17	118	629		753	716	790
18	56	292		367	379	317
19	6	217		254	378	353
20	49	234		296	308	247

West		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	100	150		363	163	138
2	213	413		575	638	651
3	0	13		225	213	325
4	237	449		537	424	337
5	200	475		650	700	587
6	382	733		858	870	1008
7	288	738		926	1026	1013
8	351	438		576	739	613
9	395	758		1022	1084	1034
10	332	607		882	920	807
11	201	590		728	803	728
12	263	564		715	727	589
13	282	582		595	708	595
14	300	526		663	638	538
15	219	443		606	618	518
16	225	514		651	702	601
17	207	470		582	595	507
18	232	496		672	722	621
19	188	464		539	539	501
20	257	495		633	633	558

H.5 Girder G2B

Table H.13 G2B Girder Data

Gir	der#	G2B	Raw Da	ta for Transfer	and Develo	opment Le	ength
Reading	Date	Time	Midspan	Ambient	Internal	VWS	G Data
#	(m/dd/yy)	(24 hr)	Deflection (inches)	Temp (Deg F)	Temp (Deg F)	Hz	WG
Initial 1	7/13/01	10:50	1.875	82.8	112.0	900.40	1363
Initial 2	7/13/01	10:50	1.875	82.8	112.0	900.40	1363
Release	7/13/01	15:50	2.172	98.8	107.1	826.40	1396
1-Day	7/14/01	7:46	2.094	73.6	82.6	823.30	2653
2-Day							
3-Day	7/16/01	6:40	2.117	75.8	80.6	822.40	2789
7-Day	7/20/01	7:57	2.148	75.4	81.5	818.38	2614
14-Day	7/27/01	7:02	2.164	73.1	78.5	817.30	2797

	Strand	Jacking D	ata from Load	Cells and Tensi	oning Machine	· · · · · · · · · · · · · · · · · · ·
	Load	Cell	Tension Mac	hine Readings	Date and Time	Ambient
	Read	ings			Of	Temp
Load	At	Prior	Strand Strand		Tensioning	
Cell	Time of	To	Jacking	Elongation		
(Strand)	Stressing	Release	Force		(m/dd/yy)	
#	(με)	(με)	(lbs)	(inches)	(24 hr)	(Deg F)
1	6013	6140	45000	10.500		
2	5107	5310	45500	9.875		
3	5193	5351	45500	10.000		
4	4742	4891	45000	10.000		
5	5516	5727	45000	9.750	12 Jul 01	05
6	5432	5572	45000	9.750	11:30	95
7	5296	5426	45000	9.875		
8	5452	5612	45000	10.000		
9	5587	5781	45500	10.500		,
10	5824	6011	45500	10.375		1

Table H.14 Raw Concrete Surface Strain Data for Girder G2B-North

East		Raw CSS - microstrains							
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day			
1	269	282		394	232	407			
2	218	368		456	418	493			
3	188	538		613	575	588			
4	362	562		487	512	562			
5	306	643		718	718	755			
6	307	846		896	896	921			
7	357	745		833	858	870			
8	482	670		745	732	845			
9	426	764		751	802	802			
10	387	562		624	761	699			
11	443	643		717	680	705			
12	412	750		775	800	787			
13	425	575		675	712	725			
14	526	751		776	801	801			
15	495	608		758	821	808			
16	387	600		637	687	675			
17	431	731		831	881	881			
18	443	693		768	793	793			
19	411	648		686	711	711			
20	469	770		895	907	995			

West		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	577	903		916	903	966
2	469	932		770	745	982
3	294	620		632	620	645
4	269	694		756	794	781
5	432	807		969	982	1007
6	345	697		860	848	948
7	470	808		871	908	996
8	414	927		815	1053	1028
9	426	751		751	751	776
10	156	730		630	755	780
11	457	909		909	1021	1084
12	457	733		771	821	796
13	464	639		765	790	740
14	370	683		770	846	921
15	337	511		499	598	548
16	31	570		570	608	608
17	131	407		457	469	544
18	150	250		462	575	837
19	125	501		551	614	614
20	137	436		535	510	660

Table H.15 Raw Concrete Surface Strain Data for Girder G2B-South

East		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	486	786		698	748	673
2	274	474		548	524	548
3	306	656		793	780	705
4	262	637		749	861	811
5	212	623		511	561	387
6	262	674		712	762	737
7	424	523		573	561	573
8	299	585		623	685	623
9	243	841		865	828	940
10	317	678		703	753	753
11	311	646		658	671	646
12	298	634		621	845	659
13	261	573		623	747	685
14	224	623		623	760	660
15	244	582		569	607	569
16	300	550		625	737	687
17	641	928		803	878	803
18	44	342		330	280	243
19	25	375		450	537	462
20	38	388		401	489	401

West		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	38	263		389	363	38
2	131	281		269	306	31
3	19	393		455	417	368
4	243	1028		1028	1003	941
5	187	674		724	612	749
6	294	606		606	556	444
7	163	539		639	601	639
8	256	656	ļ	631	618	568
9	376	689		777	752	765
10	351	740		715	690	652
11	219	621		596	771	583
12	321	736		736	799	723
13	256	569		557	607	507
14	545	1108		1146	1196	1171
15	237	587		550	562	537
16	293	681		730	743	730
17	305	417		455	505	480
18	329	652		615	665	652
19	292	728		790	865	740
20	242	640		677	776	665

H.6 Girder G2C

Table H.16 G2C Girder Data

Gir	der#	G2C	Raw Da	ta for Transfer	and Develo	opment Le	ength
Reading	Date	Time	Midspan	Ambient	Internal	VWS	G Data
#	(m/dd/yy)	(24 hr)	Deflection (inches)	Temp (Deg F)	Temp (Deg F)	Hz	WG
Initial 1	7/18/01	12:40	2.047	85.0	125.5	913.36	1427
Initial 2	7/18/01	12:40	2.047	85.0	125.5	913.36	1427
Release	7/18/01	15:00	2.469	87.8	108.9	827.12	1428
1-Day	7/19/01	6:55	2.438	74.2	86.0	817.71	2353
2-Day	7/20/01	6:55	2.469	73.6	84.6	814.71	2469
3-Day	7/21/01	6:50	2.453	72.5	78.8	813.58	2807
7-Day	7/25/01	7:10	2.469	73.8	78.0	806.60	2886
14-Day	8/1/01	6:30	2.477	72.0	78.5	802.68	2850

	Strand Jacking Data from Load Cells and Tensioning Machine									
	Load	Cell	Tension Mac	hine Readings	Date and Time	Ambient				
	Read	ings			Of	Temp				
Load	At	Prior	Strand Strand		Tensioning					
Cell	Time of	To	Jacking	Elongation						
(Strand)	Stressing	Release	Force		(m/dd/yy)	ŀ				
#	(με)	(με)	(lbs)	(inches)	(24 hr)	(Deg F)				
1	5163	4989	45000	9.875						
2	5218	5023	45500	9.750						
3	5640	5387	46000	9.750						
4	5549	5406	46000	9.875						
5	5484	5279	46000	9.875	17 Jul 01	75				
6	5456	5309	46000	9.875	9:40	13				
7	5126	5000	45000	10.000						
8	5115	4970	45000	10.000						
9	5489	5387	46000	9.750		{				
10	5601	5443	46000	9.750						

Table H.17 Raw Concrete Surface Strain Data for Girder G2C-North

East		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	100	251	276	238	226	138
2	200	437	499	537	562	387
3	44	469	582	506	619	256
4	281	505	443	568	555	418
5	431	668	743	781	756	643
6	445	632	632	658	670	582
7	494	1220	782	807	794	569
8	513	789	852	952	952	801
9	519	706	831	819	844	719
10	543	756	818	831	856	731
11	649	899	899	924	936	861
12	512	662	699	737	749	587
13	506	706	718	743	731	643
14	532	669	794	845	870	719
15	457	682	670	670	720	545
16	444	619	694	719	694	656
17	500	700	800	825	825	738
18	468	668	693	755	780	693
19	369	693	731	781	818	668
20	494	757	769	769	832	669

West		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	370	633	684	633	734	408
2	395	595	620	570	570	369
3	307	632	657	670	695	532
4	444	607	732	657	657	444
5	445	670	746	758	758	696
6	433	659	671	671	696	533
7	419	620	532	532	557	394
8	463	776	739	638	689	488
9	469	681	669	656	694	569
10	604	779	779	804	804	629
11	539	765	802	840	903	752
12	771	846	771	796	921	407
13	558	758	796	896	846	683
14	388	551	589	639	664	501
15	386	586	536	549	573	474
16	113	138	476	513	476	13
17	338	489	439	489	464	188
18	344	494	469	507	507	382
19	169	332	419	382	394	194
20	93	429	728	641	740	292

Table H.18 Raw Concrete Surface Strain Data for Girder G2C-South

East		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	673	798	760	873	873	661
2	573	773	835	860	823	723
3	687	850	887	925	962	875
4	506	681	730	743	768	693
5	531	731	881	918	1055	818
6	593	780	767	917	867	730
7	574	686	711	736	748	711
8	747	846	846	871	871	859
9	591	740	1014	765	765	728
10	629	803	828	853	903	928
11	547	671	759	846	821	746
12	640	776	751	963	925	813
13	560	734	784	871	883	833
14	137	200	462	499	524	424
15	512	624	787	799	961	861
16	269	331	469	569	669	506
17	112	224	312	474	424	436
18	137	261	485	386	435	249
19	0	163	250	288	275	288
20	44	169	282	357	407	294

West		Ra	w CSS - 1	microstra	ins	
Gage #	Release	1-Day	2-Day	3-Day	7-Day	14-Day
1	6	220	270	270	408	245
2	62	262	337	337	425	375
3	81	106	5254	243	280	168
4	144	406	431	369	494	469
5	368	455	543	555	618	580
6	357	482	545	545	632	482
7	350	475	538	551	638	576
8	462	612	649	674	749	699
9	376	476	527	564	664	501
10	514	577	665	614	677	702
11	508	571	709	684	709	696
12	887	510	787	1001	711	1001
13	719	669	706	706	844	832
14	550	676	738	776	813	713
15	550	512	662	675	762	675
16	462	75	562	662	699	412
17	405	467	604	617	692	480
18	447	423	534	559	646	534
19	559	622	584	647	709	572
20	379	553	553	602	714	577

APPENDIX I

SMOOTHED CONCRETE SURFACE STRAIN PROFILES AND DETERMINATION OF TRANSFER LENGTH

This Appendix contains smoothed CSS profiles for each girder end as well as plots showing the determination of transfer length based on 14-day CSS data.

I.1 Girder G1A-East




Figure I.1 Concrete Surface Strains for G1A-East




Figure I.2 14-Day Transfer Length Determined for G1A-East

I.2 Girder G1A-West




Figure I.3 Concrete Surface Strains for G1A-West




Figure I.4 14-Day Transfer Length Determined for G1A-West

I.3 Girder G1B-East




Figure I.5 Concrete Surface Strains for G1B-East




Figure I.6 14-Day Transfer Length Determined for G1B-East

I.4 Girder G1B-West




Figure I.7 Concrete Surface Strains for G1B-West




Figure I.8 14-Day Transfer Length Determined for G1B-West

I.5 Girder G1C-East




Figure I.9 Concrete Surface Strains for G1C-East




Figure I.10 14-Day Transfer Length Determined for G1C-East

I.6 Girder G1C-West




Figure I.11 Concrete Surface Strains for G1C-West




Figure I.12 14-Day Transfer Length Determined for G1C-West

I.7 Girder G2A-East




Figure I.13 Concrete Surface Strains for G2A-East




Figure I.14 14-Day Transfer Length Determined for G2A-East

I.8 Girder G2A-West




Figure I.15 Concrete Surface Strains for G2A-West




Figure I.16 14-Day Transfer Length Determined for G2A-West

I.9 Girder G2B-East




Figure I.17 Concrete Surface Strains for G2B-East




Figure I.18 14-Day Transfer Length Determined for G2B-East

I.10 Girder G2B-West




Figure I.19 Concrete Surface Strains for G2B-West




Figure I.20 14-Day Transfer Length Determined for G2B-West

I.11 Girder G2C-East




Figure I.21 Concrete Surface Strains for G2C-East




Figure I.22 14-Day Transfer Length Determined for G2C-East

I.12 Girder G2C-West




Figure I.23 Concrete Surface Strains for G2C-West




Figure I.24 14-Day Transfer Length Determined for G2C-West

APPENDIX J

TRANSFER LENGTH DATA FROM OTHER RESEARCHERS

This Appendix contains transfer length data from this project and other researchers. All transfer length data is based on the use of 0.6-inch prestressing strand. The data were used to evaluate the usefulness of the transfer length equations based on initial concrete compressive strength developed in Section 9.9.

Table J.1 Transfer Length Data from Researchers Using 0.6" Strand

Specimen	Name	Concrete	Specimen	#	Transfer	f _{ci} '
#	of	(LWC or	Cross	Strands	Length	AC1
"	Researcher	NWC)	Section	Buanus		(mai)
G1A-E	Meyer	LWC	AASHTO Type II	8	(in)	(psi)
GIA-E	Meyer	LWC		8	19.50	7465
G1B-E	Meyer	LWC	AASHTO Type II AASHTO Type II	8	18.75 25.00	7465
G1B-W	Meyer	LWC		8		7465
GIC-E	Meyer	LWC	AASHTO Type II	8	18.75	7465
G1C-B	Meyer	LWC	AASHTO Type II	8	28.00	6315
G1C-W		LWC	AASHTO Type II	8	21.50 17.50	
	Meyer		AASHTO Type II	8		9640
G2A-W	Meyer	LWC	AASHTO Type II		13.25	9640
G2B-E	Meyer	LWC	AASHTO Type II	8	13.00	9640
G2B-W	Meyer	LWC	AASHTO Type II	8	13.00	9640
G2C-E	Meyer	LWC	AASHTO Type II	8	19.00	8261
G2C-W	Meyer	LWC	AASHTO Type II	8	18.00	8261
FA4601N	Russell	NWC	AASHTO Type	4	24.00	4900
FA4601S	Russell	NWC	AASHTO Type	4	44.00	4900
FA4602N	Russell	NWC	AASHTO Type	4	33.00	4450
FA4602S	Russell	NWC	AASHTO Type	4	34.00	4450
FA4603N	Russell	NWC	AASHTO Type	4	32.00	4450
FA4603S	Russell	NWC	AASHTO Type	4	33.00	4450
FA4604N	Russell	NWC	AASHTO Type	4	25.00	4900
FA4604S	Russell	NWC	AASHTO Type	4	30.00	4900
FA4605N	Russell	NWC	AASHTO Type	4	33.00	4700
FA4605S	Russell	NWC	AASHTO Type	4	37.00	4700
FA4606N	Russell	NWC	AASHTO Type	4	33.00	4700
FA4606S	Russell	NWC	AASHTO Type	4	30.00	4700
6-1-EXT	Deatherage	NWC	AASHTO Type I	7	25.00	4100
6-1-INT	Deatherage	NWC	AASHTO Type I	7	27.00	4100
6-2-EXT	Deatherage	NWC	AASHTO Type I	7	30.00	4280
6-2-INT	Deatherage	NWC	AASHTO Type I	7	24.00	4280
6-3-EXT	Deatherage	NWC	AASHTO Type I	7	23.00	5230
6-3-INT	Deatherage	NWC	AASHTO Type I	7	21.00	5230
6-4-EXT	Deatherage	NWC	AASHTO Type I	7	22.00	5450
6-4-INT	Deatherage	NWC	AASHTO Type I	7	23.00	5450
LOB-A	Barnes	NWC	AASHTO Type I	6	26.00	4240
LOB-B	Barnes	NWC	AASHTO Type I	6	25.00	4240
LOB-C	Barnes	NWC	AASHTO Type I	6	30.00	4240
LOB-D	Barnes	NWC	AASHTO Type I	6	36.00	4240
MOB-A	Barnes	NWC	AASHTO Type I	8	22.00	6610
MOB-B	Barnes	NWC	AASHTO Type I	8	19.00	6610
MOB-C	Barnes	NWC	AASHTO Type I	8	18.00	6610
MOB-D	Barnes	NWC	AASHTO Type I	8	16.00	6610
HOB-A	Barnes	NWC	AASHTO Type I	8	15.00	11030
HOB-B	Barnes	NWC	AASHTO Type I	8	16.00	11030
HOB-C	Barnes	NWC	AASHTO Type I	8	16.00	11030
HOB-D	Barnes	NWC	AASHTO Type I	8	17.00	11030

Table J.1 Transfer Length Data from Researchers Using 0.6" Strand (Cont.)

Specimen	Name	Concrete	Specimen	#	Transfer	f _{ci} '
#	of	(LWC or	Cross	Strands	Length	-01
"	Researcher	NWC)	Section	Duanas	_	(noi)
G2A-S	Reutlinger	NWC)	AASHTO Type II	8	(in) 15.40	(psi)
G2A-N		NWC	AASHTO Type II	8		14989
G2B-S	Reutlinger Reutlinger	NWC	AASHTO Type II	8	17.00	12379
G2B-N	Reutlinger	NWC	AASHTO Type II	8	17.90 17.80	12379
G4A-S	Reutlinger	NWC	AASHTO Type II	8		11721
G4A-N	Reutlinger	NWC		8	16.70	14675
G4B-S	Reutlinger	NWC	AASHTO Type II AASHTO Type II	8	13.80	14395
		NWC		8	13.50	14395
G4B-N KLM1-C	Reutlinger		AASHTO Type II	. 8	13.40	14610
	Kaar Kaar	NWC			51.50	2220
KLM1-D		NWC			33.50	2220
KLM2-C	Kaar	NWC			52.00	2410
KLM2-D	Kaar	NWC			41.50	2410
KLM3-C	Kaar	NWC			49.00	3180
KLM3-D	Kaar	NWC			42.50	3180
KLM4-C	Kaar	NWC			36.00	4070
KLM4-D	Kaar	NWC			29.00	4070
KLM5-C	Kaar	NWC			39.50	5465
KLM5-D	Kaar	NWC			27.50	5465
Mayfield - A1	Mayfield	NWC			16.73	7120
Mayfield - A2	Mayfield	NWC			16.73	7120
Mayfield - A3	Mayfield	NWC			16.73	7120
Mayfield - A4	Mayfield	NWC		· · · · · · · · · · · · · · · · · · ·	16.73	7120
Mayfield - A5	Mayfield	NWC			16.73	7120
Mayfield - A6	Mayfield	NWC ·			16.73	7120
Mayfield - A7	Mayfield	NWC			16.73	7120
Mayfield - B1	Mayfield	NWC			26.07	7120
Mayfield - B2	Mayfield	NWC			26.07	7120
Mayfield - B3	Mayfield	NWC			26.07	7120
Mayfield - B4	Mayfield	NWC			26.07	7120
Mayfield - B5	Mayfield	NWC			26.07	7120
Mayfield - B6	Mayfield	NWC			26.07	7120
Mayfield - B7	Mayfield	NWC			26.07	7120
Mayfield - B8	Mayfield	NWC			26.07	7120
Mayfield - C1	Mayfield	NWC			29.53	6120
Mayfield - C2	Mayfield	NWC			29.53	6120
Mayfield - C3	Mayfield	NWC			29.53	6120
Mayfield - C4	Mayfield	NWC			29.53	6120
Mayfield - C5	Mayfield	NWC	· ·		29.53	6120
Mayfield - C6	Mayfield	NWC			29.53	6120
Mayfield - C7	Mayfield	NWC			29.53	6120
Mayfield - C8	Mayfield	NWC			29.53	6120
Mayfield - C9	Mayfield	NWC			29.53	6120

Table J.1 Transfer Length Data from Researchers Using 0.6" Strand (Cont.)

Specimen	Name	Concrete	Specimen	#	Transfer	f _{ci} '
- #	of	(LWC or	Cross	Strands	Length	
	Researcher	NWC)	Section		(in)	(psi)
16/31-1865 A	Mitchell	NWC	Rectangular	1	32.90	3000
16/31-1500 A	Mitchell	NWC	Rectangular	1	35.90	3000
16/31-1500 B	Mitchell	NWC	Rectangular	1	38.20	3000
16/65-1150 A	Mitchell	NWC	Rectangular	1	20.80	6950
16/65-1150 B	Mitchell	NWC	Rectangular	1	16.80	6950
16/65-725-A	Mitchell	NWC	Rectangular	1	21.10	6950
16/65-725-B	Mitchell	NWC	Rectangular	1	17.10	6950
16/89-675B	Mitchell	NWC	Rectangular	1	16.10	7310
16/89-975B	Mitchell	NWC	Rectangular	1	13.60	7310
FC160-12 N	Russell	NWC	Rectangular	1	48.00	3853
FC160-12 S	Russell	NWC	Rectangular	1	46.00	3853
FC360-1 N	Russell	NWC	Rectangular	3	42.00	4201
FC360-1 S	Russell	NWC	Rectangular	3	41.00	4201
FC360-2 N	Russell	NWC	Rectangular	3	37.00	4201
FC360-2 N	Russell	NWC	Rectangular	3	48.00	4201
FCT360-3 N	Russell	NWC	Rectangular	3	40.00	4201
FCT360-3 S	Russell	NWC	Rectangular	3	46.00	4201
FCT360-4 N	Russell	NWC	Rectangular	3	51.00	4792
FCT360-4 S	Russell	NWC	Rectangular	3	42.00	4792
FCT362-11 N	Russell	NWC	Rectangular	3	46.00	4759
FCT362-11 S	Russell	NWC	Rectangular	3	44.00	4759
FCT362-12 N	Russell	NWC	Rectangular	3	44.00	4759
FCT362-12 S	Russell	NWC	Rectangular	3	42.00	4759
FCT362-13 N	Russell	NWC	Rectangular	3	42.00	4759
FCT362-13 S	Russell	NWC	Rectangular	3	40.00	4759
FC560-1 S	Russell	NWC	Rectangular	5	46.00	4481
FC560-1 N	Russell	NWC	Rectangular	5	37.00	4481
FCT560-2 S	Russell	NWC	Rectangular	5	48.00	4481
FCT560-2 N	Russell	NWC	Rectangular	5	47.00	4481
FC560-3 S	Russell	NWC	Rectangular	5	48.00	4481
FC560-3 N	Russell	NWC	Rectangular	5	52.00	4481

APPENDIX K

GIRDER "AS-BUILT" ANALYSIS SPREADSHEET

Appendix K contains the individual pages from the Girder "AS-BUILT" Analysis Spreadsheet. This sheet was used to process the DAQ output from the 18 girder tests based on "as-built" girder characteristics. The entire set of worksheet pages is provided from girder test G1C-W. A similar series of worksheets was prepared for each of the 18 girder tests. Listed below are the individual worksheets within the overall spreadsheet and a brief description of the worksheet's function.

Table K.1 – DAQ Output – A sample of the raw data output from the data acquisition system. Only a small percentage of the total number of DAQ lines is shown.

Table K.2 – Load, Shear, Moment, Deflection, Strain and Curvature Values – The values are calculated based on DAQ and other user input values regarding the test. Only a small percentage of the total number of lines in this worksheet is shown.

Table K.3 – Calculated Principal Strains, Angles and Maximum Shear Strain – The values are calculated based on DAQ and other user input values regarding the test. Only a small percentage of the total number of lines in this worksheet is shown.

Table K.4 – Input Values for Girder Test – The user enters values in the shaded cells for LVDT gage length, test configuration and prestressing values.

Table K.5 – Section Properties for Girder "AS-BUILT" – The user enters all values in the table. The shaded values are the ones that change between tests.

Table K.6 – Support Conditions, Reactions, Max Load and Moment Furnished –

The user enters values in the shaded areas. All other values are calculated automatically based on input and values from other worksheets. This worksheet provides a visual depiction of the support conditions to verify their location.

Table K.7 – AASHTO Loss Calculations – This worksheet calculates losses using the AASHTO¹⁵² 1996 Standard Specifications. The user enters values in the shaded cells. Iteration may be required to determine the elastic shortening loss.

Table K.8 – Girder Shear Capacity by 1996 AASHTO⁴⁰ Standard Procedure – This worksheet calculates girder shear capacity at the tenth points of the shear span based on the 1996 AASHTO Standard Specification. The user enters the stirrup spacing in the shaded box.

Table K.9 – Deflection Calculations – This worksheet calculates predicted deflections at cracking and at ultimate condition.

Table K.10 – Variable Angle Truss Model – This worksheet determines the shear capacity of the girder, the angle of the compression strut, forces in the prestressing strand and bond stress using the variable angle truss model.

Figure K.1 – Force in Prestressing Strand vs. Distance from Girder End

Figure K.2 – Bond Stress of Prestressing Strand vs. Distance from Girder End

Table K.11 – Theoretical Moment-Curvature Stages 1-3 – This worksheet calculates moment and curvature for the elastic stages.

Table K.12 - Theoretical Moment-Curvature Stages 4-6 – This worksheet calculates moment and curvature for the stages after cracking; top of deck strain equal to 0.001, 0.002, 0.003 in/in. The user must enter values in the shaded boxes until the compression force and tension force are equal. ($F_{sc} = F_c$)

Figure K.3 – Moment-Curvature Plot

Table K.13 – Girder Shear Capacity by 1998 AASHTO⁹² LRFD Procedure – This worksheet calculates girder shear capacity at the tenth points of the shear span based on the 1998 AASHTO LRFD Specification. The user enters the values in the shaded boxes for crack angle, then the β value from the chart in the specification.

Table K.14 – Girder-Deck Interface Shear Calculations – This worksheet determines the interface shear adequacy between the girder and deck. The user enters values in the shaded boxes.

Table K.15 – Prestressing Strand Tension Curve – This worksheet provides a mathematical depiction of the stress strain curve for the prestressing strand. It is based on the actual curve received from the manufacturer.

Table K.16 – Principal Strain and Maximum Shear Strain Plots – Provides a visual depiction of the progression of principal strain angles and values as well as maximum shear strain. The user enters values for V_{crack} and the low and high values of crack angles.

Figure K.4 – Load vs. Displacement Plot

Table K.17 – Overview of Girder Test Results – This worksheet provides an overview of the most important values from the girder test. It is meant to provide a snapshot of the test output.

Table K.1 DAQ Output

LVDT 0 LVDT 45 LVDT 90	-0.00249 -0.002784 -0.001542	-0.002496 -0.00279 -0.001566	-0.002484 -0.002856 -0.001548	-0.002496 -0.0031 -0.001554	-0.002477 -0.003245 -0.001554	-0.002484 -0.00327 -0.00156		-0.002477 -0.003495 -0.001566	-0.003543	-0.002496 -0.003562 -0.001554	-0.002459 -0.00372 -0.001573	-0.003841	-0.002399 -0.004096 -0.001542	-0.002405 -0.004175 -0.001554	-0.002393 -0.004248 -0.001535	-0.002375 -0.004364 -0.001542	-0.002381 -0.004364 -0.001548	-0.002363 -0.004364 -0.001535	-0.002357 -0.004431 -0.001529	-0.002357 -0.004491 -0.00156	-0.00232 -0.004577 -0.001548		-0.002314 -0.004577 -0.001554	-0.002332 -0.004589 -0.001554	-0.00235 -0.004589 -0.001542	-0.002338 -0.004577 -0.001542	-0.002332 -0.004589 -0.001554	0.000326 -0.004577 -0.00156
Wire Pot L	2.465919 -0	2.461571 -0.	2.455239 -0.	2.433496 -0.	-	2.415569 -0.	2.410762 -0.	2.396878 -0.	2.392224 -0.	2.392148 -0.	2.377653 -0.	2.368269 -0.	2.349273 -0.	2.340576 -0.	2.332566 -0.	2.326692 -0.	2.326615 -0.	2.326615 -0.	2.321809 -0.	2.313188 -0.	2.308458 -0	2.308382 -0.	2.308382 -0.	2.308458 -0.	2.308535 -0	2.308306 -0.	2.308229 -0.	2.308382 -0.
LVDT Bottom	-0.001137	-0.001176	-0.00129	-0.001888	-0.00232	-0.00232	-0.002524	-0.002905	-0.003109	-0.003121	-0.003541	-0.003808	-0.004393	-0.004635	-0.0048	-0.005105	-0.005105	-0.005131	-0.005334	-0.005474	-0.005652	-0.00569	-0.005652	-0.005716	-0.005678	-0.005703	-0.005716	-0.00569
12:07 PM LVDT Top	-0.00048	-0.00056	-0.000659	-0.000462	0.000148	0.000173	0.000457	0.001055	0.001227	0.00127	0.001424	0.002059	0.002632	0.003138	0.003428	0.003797	0.003841	0.003834	0.004118	0.004291	0.004475	0.004728	0.004549	0.004697	0.004636	0.004697	0.004586	0.00463
11/02/2001 Load Cell	11.442372	13.463793	16.630684	27.815872	35.0256	34.789768	39.236893	45.536983	48.872326	48.653339	55.509319	61.371441	71.697525	75.369766	78.907257	83.1017	82.832176	82.663727	86.20121	89.233345	92.753983	92.551834	92.383385	92.248627	92.181244	92.063324	91.945412	91,878029

Table K.2 Calculated Load, Shear, Moment, Strain and Curvature Values

Г	Ι		\neg	Г	T-	_	Γ								, ,									_			_	-		_					_			_
	Phi		(rad/in)	000000	0.00000	0.000000	0.000001	0.000002	0.000002	0.000002	0.000003	0.000003	0.000004	0.000004	0.000005	0.00000	0.000007	0.000007	0.000008	0.000008	0.000008	0.000008	0.00000	0.00000	0.00000	0.00000	0.00000	0.00000	0.00000	0.00000	0.00000	0.00000	60000000	6000000	600000.0	0.00000	0.00000	
ear Assumption)	Total Strand	Strain	(in/in)	0.00505	0.00505	0.00506	0.00508	0.00510	0.00510	0.00511	0.00513	0.00514	0.00514	0.00515	0.00516	0.00519	0.00520	0.00521	0.00522	0.00522	0.00522	0.00523	0.00523	0.00524	0.00524	0.00524	0.00524	0.00524	0.00524	0.00524	0.00524	0.00524	0.00524	0.00524	0.00524	0.00524	0.00524	10000
Adjusted Values (Linear Assumption)	At Level of	Bot Strands	(in/in)	000	0.00000	0.00001	0.00003	0.00005	0.00005	0.00006	0.00007	0.00008	8000000	0.00010	0.00011	0.00014	0.00015	0.00015	0.00017	0.00017	0.00017	0.00017	0.00018	0.00019	0.00019	0.00019	0.00019	0.00019	0.00019	0.00019	0.00019	0.00019	0.00019	0.00019	0.00019	0.00019	0.00019	0,000,0
Adju	Top of Slab	(+) = Comp	(in/in)	000	0.00000	-0.00001	0.00000	0.00003	0.00003	0.00004	0.00007	0.00007	0.00008	800000	0.00011	0.00014	0.00016	0.00017	0.00019	0.00019	0.00019	0.00020	0.00021	0.00022	0.00023	0.00022	0.00022	0.00022	0.00022	0.00022	0.00022	0.00022	0.00022	0.00022	0.00023	0.00022	0.00022	1,0000
Neutral Axis	Location		(In from Bot)	AN	17.38	23.22	45.85	31.66	31.27	29.19	26.49	26.52	26.31	27.48	25.49	25.43	24.57	24.23	24.12	24.00	24.09	23.94	23.89	23.92	23.47	23.76	23.59	23.63	23.56	23.83	23.67	23.72	23.61	23.68	23.31	23.48	23.72	23.56
	Vertical	Deflection	(Inches)	0000000	0.004348	0.010680	0.032423	0.050427	0.050350	0.055157	0.069041	0.073695	0.073771	0.088266	0.097650	0.116646	0.125343	0.133353	0.139227	0.139304	0.139304	0.144110	0.152731	0.157461	0.157537	0.157537	0.157461	0.157384	0.157613	0.157690	0.157537	0.157384	0.157461	0.157613	0.157613	0.157461	0.157537	0 157527
	Bot Strain	(m-strain)	(+)=3	90 0	1.63	6.38	31.29	49.29	49.29	57.79	73.67	82.17	82.67	100.17	111.29	135.67	145.75	152.63	165.33	165.33	166.42	174.88	180.71	188.13	189.71	188.13	190.79	189.21	190.25	190.79	189.71	188.67	188.67	188.67	187.63	188.67	188.67	106.00
50	Bot LVDT	(Inches)	Tension $\varepsilon = (+)$	0000000	-0.000039	-0.000153	-0.000751	-0.001183	-0.001183	-0.001387	-0.001768	-0.001972	-0.001984	-0.002404	-0.002671	-0.003256	-0.003498	-0.003663	-0.003968	-0.003968	-0.003994	-0.004197	-0.004337	-0.004515	-0.004553	-0.004515	-0.004579	-0.004541	-0.004566	-0.004579	-0.004553	-0.004528	-0.004528	-0.004528	-0.004503	-0.004528	-0.004528	0.004464
At Point of Loading	Top Strain	(m-strain)	pression $\varepsilon = (-)$	00.0	3.33	7.46	-0.75	-26.17	-27.21	-39.04	-63.96	-71.13	-72.92	-79.33	-105.79	-129.67	-150.75	-162.83	-178.21	-180.04	-179.75	-191.58	-198.79	-206.46	-217.00	-209.54	-215.71	-213.17	-215.71	-211.08	-212.92	-210.83	-212.92	-211.63	-217.79	-215.46	-210.83	-210.83
At Pc	Top LVDT	(Inches)	Compressi	0000000	-0.000080	-0.000179	0.000018	0.000628	0.000653	0.000937	0.001535	0.001707	0.001750	0.001904	0.002539	0.003112	0.003618	0.003908	0.004277	0.004321	0.004314	0.004598	0.004771	0.004955	0.005208	0.005029	0.005177	0.005116	0.005177	0.005066	0.005110	0.005060	0.005110	0.005079	0.005227	0.005171	0.005060	0.005060
	Total	Moment	(ft-kips)	67.2	79.1	87.6	163.6	206.1	204.7	230.9	268.0	287.6	286.3	326.7	361.2	422.0	443.7	464.5	489.2	487.6	486.6	507.4	525.3	546.0	544.8	543.8	543.1	542.7	542.0	541.3	540.9	540.4	540.0	539.2	538.9	538.7	538.3	4370
	lied	Shear	(Kips)	0	1.7	4.3	13.6	19.6	19.4	23.1	28.3	31.1	30.9	36.6	41.5	50.1	53.1	56.1	59.6	59.3	59.2	62.2	64.7	67.6	67.4	67.3	67.2	67.1	67.0	6.99	6.99	66.8	66.7	66.6	9.99	66.6	66.5	66.4
	Applied	Load	(Kips)	00	2.0	5.2	16.4	23.6	23.3	27.8	34.1	37.4	37.2	44.1	49.9	60.3	63.9	67.5	71.7	71.4	71.2	74.8	77.8	81.3	81.1	6.08	80.8	80.7	9.08	80.5	80.4	80.4	80.3	80.1	80.1	80.1	80.0	70.0
Data	Point	#		6	-	2	3	4	5	9	7	8	6	10	11	12	13	14	15	16	17	18	61	20	21	22	23	24	25	26	27	28	29	30	31	32	33	3.4

Table K.3 Calculated Principal Strains, Angles and Maximum Shear Strain

LVDT 0 LVDT 45								- dio	Principal Strains		
	S LVDT 90	Strain 45	Strain XX	Strain YY	Strain XY	θ	Tension $S = (+)$	(+) = 3	Comp $\varepsilon = (-)$	(-) = :	Υщах
		(m-strain)	(m-strain)	(m-strain)	(m-rads)		13	θ_{p_1}	23	$\theta_{\mathbf{p}^2}$	
(Inches)	(Inches)	Compression $\varepsilon = (-)$	ion 8 = (-)	Tension $\varepsilon = (+)$	(+)=3	(degrees)	(m-strain)	(deg)	(m-strain)	(geb)	(m-rads)
0.00000	0.000000	0.00	-236.42	0.00	236.42	AN	48.96	AN	-285.39	AN	334.35
-0.00000	-0.000024	0.37	-235.86	2.26	232.86	-22.18	49.73	67.82	-283.33	-22.18	333.05
-0.000072	-0.000006	4.43	-236.99	0.56	227.56	-21.88	46.27	68.12	-282.69	-21.88	328.96
-0.000316	-0.000012	19.45	-235.86	1.13	195.84	-19.78	36.35	70.22	-271.08	-19.78	307.43
-0.000461	-0.000012	28.37	-237.65	1.13	179.78	-18.49	31.19	71.51	-267.70	-18.49	298.89
-0.000486	-0.000018	29.91	-236.99	1.69	175.48	-18.16	30.48	71.84	-265.77	-18.16	296.25
-0.000559	-0.000006	34.40	-238.21	0.56	168.85	-17.63	27.40	72.37	-265.05	-17.63	292.44
-0.000711	-0.000024	43.75	-237.65	2.26	147.88	-15.83	23.22	74.17	-258.61	-15.83	281.82
-0.000759	-0.000006	46.71	-238.78	0.56	144.80	-15.59	20.76	74.41	-258.97	-15.59	279.73
-0.000778	-0.000012	47.88	-235.86	1.13	138.98	-15.19	20.00	74.81	-254.73	-15.19	274.73
-0.000936	-0.000031	27.60	-239.34	2.92	121.22	-13.29	17.24	76.71	-253.66	-13.29	270.90
057	0.000025	65.05	-239.91	-2.35	112.17	-12.64	10.22	77.36	-252.48	-12.64	262.70
-0.001312	0.000000	80.74	-244.99	00.0	83.51	-9.41	6.92	80.59	-251.91	-9.41	258.83
-0.001391	-0.000012	85.60	-244.42	1.13	72.09	-8.18	6.31	81.82	-249.61	-8.18	255.92
-0.001464	0.000007	60.06	-245.55	99.0-	66.03	-7.54	3.71	82.46	-249.93	-7.54	253.64
-0.001580	0.00000.0	97.23	-247.25	0.00	52.79	-6.03	2.79	83.97	-250.03	-6.03	252.82
580	-0.000006	97.23	-246.68	0.56	51.66	-5.90	3.23	84.10	-249.35	-5.90	252.59
-0.001580	0.000007	97.23	-248.38	-0.66	54.57	-6.21	2.31	83.79	-251.35	-6.21	253.66
-0.001647	0.000013	101.35	-248.94	-1.22	47.46	-5.42	1.03	84.58	-251.19	-5.42	252.22
-0.001707	-0.000018	105.05	-248.94	1.69	37.16	4.22	3.06	85.78	-250.31	4.22	253.37
-0.001793	-0.000006	110.34	-252.42	0.56	31.18	-3.51	1.52	86.49	-253.38	-3.51	254.90
-0.001799	_	110.71	-251.29	0.00	29.88	-3.39	0.89	19:98	-252.18	-3.39	253.06
-0.00179		110.34	-252.99	1.13	31.18	-3.50	2.08	86.50	-253.94	-3.50	256.02
-0.00180		111.08	-251.29	1.13	28.01	-3.17	1.90	86.83	-252.07	-3.17	253.97
-0.00180	<u>.</u>	111.08	-249.60	0.00	27.45	-3.14	0.75	98.98	-250.35	-3.14	251.10
-0.00179	┈	110.34	-250.73	0.00	30.05	-3.42	06.0	86.58	-251.63	-3.42	252.52
-0.00180	5 -0.000012	111.08	-251.29	1.13	28.01	-3.17	1.90	86.83	-252.07	-3.17	253.97
-0.00179	3 -0.000018	110.34	-251.86	1.69	29.49	-3.32	2.55	89.98	-252.71	-3.32	255.26
-0.001786	36 -0.000012	16.601	-252.42	1.13	31.48	-3.54	2.10	86.46	-253.40	-3.54	255.50
~	-0.001793 0.000025	110.34	-251.29	-2.35	32.97	-3.77	-1.27	86.23	-252.38	-3.77	251.12
	-0.001786 -0.000006	16.601	-251.86	0.56	31.48	-3.55	1.54	86.45	-252.84	-3.55	254.38
ائت	-	111.08	-251.29	0.56	28.58	-3.24	1.37	86.76	-252.10	-3.24	253.48
	-	108.80	-251.86	0.00	34.26	-3.87	1.16	86.13	-253.02	-3.87	254.18
	~	109.91	-250.17	0.00	30.35	-3.46	0.92	86.54	-251.08	-3.46	252.00
21	-0.001786 -0.000012	109.91	-250.17	1.13	29.22	-3.32	1.98	89.98	-251.01	-3.32	252.99

Table K.4 Input Values for Girder Test

		17.00		Circ	Girder Test Information	Informa	ıtion			
		LIL	Test Configuration #	ion #	Single	_		Date)	105-A9A-70
		_	Surrup Dens	53	ongine	->				
	LVDT 0 Length	F-00/005-	Inches			-Top LVDT-			Enter fields	Enter values in shaded fields and adjust limits
	LVDT 45 Length LVDT 90 Length	100250	Inches	TT	Top LVDT Length Top Edge Distance	Π		Inches	of fun all dat	of functions to include all data points in DAQ file.
	\ \ [أ	Initial Cracking Load Cracking Moment	M _a	1144.85	Kips Ft-Kips		Actual Strand Prestressing Values (KSI) Jacking Stress fpt	Prestressing fpt	Values (KSI)
4	<u> </u>	•	Cracking Deflection	δα	77.0	Inches		Stress After Release		11.60
/	>		Max Applied Load	Pmax	299.04	Kips		Stress at 14 Days	s f _{se}	
	.· 	,,	Nominal Moment	M _n	1828.17	Ft-Kips		Strain at Test (µE)	s) ε _{se}	- 30¢a
+		\	Max Deflection	Smax	2.27	Inches		Stress At Testing	g f _{se}	147.61
•	- C		Max Deck Strain	123 2	0.0036	in/in		Actual Gird	Actual Girder Prestressing Values	ng Values
		>	Max Bot Strand Strn	sd ₃	1.3960	Percent		Initial X-X Stress (ksi)		пт 0.87
			Max Bot Strand Force	저	57.72	Kips		Initial X-X Strain (me)	me) ^E cipx	x 2.36E-04
	06						2 Cont. 12 C			
Meas	Measured Transfer Length	h (* 245)	Inches	Bott	Bottom LVDT Length		1, 10,00	Inches		
Actual	Actual Development Length	th	Inches	Bc	Bot Edge Distance		3.00	Inches		
E L	The M_{cr} and M_n values include the M_{DL} value.	include the M _{DL}	value.			-Bot LVDT-		T		

Table K.5 Section Properties for Girder "AS BUILT"

G1C-W			Section	Section Properties for "AS BUILT" Prestressed Girder Analysis	T." F	restres	sed C	irder	Anal	ysis		
Deck Variables	sə			Elasticity Modulus Values	alues			S	trand D	ata (No	Strand Data (No Drape)	
Deck Thickness	τ.	11/8/55	Z	Deck Mod. of Elast. at Testing (Actual)	E_{cd}	335E+06	PSI	Ref. Dist.	t Nbr % fp	% fpu	Fps	$F_{ps}d$
Deck Width	Wf	3050	Z	Beam Mod. Of Elast. At Testing (Est)	Ecg	3.69E+06	PSI	NI #	#	%	KIP	KP-IN
Concrete Actual Strength	ĵ.	SXX.	PSI	Modular Ratio (E _{cd} /E _{cb})	μ	0.907	None	TOP 33.5	5 2	0.63	78.20	2619.7
Concrete Weight	Wc	S 1	PCF	Non-Composite Beam Properties	ropertie			18	0	0.00	0.00	0.0
Beam Cross Section Variabl	Variables			Moment of Inertia	Inc	62605	IN	17	0	0.00	0.00	0.0
Girder Type		2	1-5,BT	Distance from Centroid to Top of Beam	$ m Y_{top}$	20.17	Z	16	0	0.00	0.00	0.0
Girder Top Flange Width		12	Z	Distance from Centroid to Bot. of Beam	Ybot	15.83	Z	15 31.0	0 0	0.00	0.00	0.0
Concrete Strength at Release	f _s ,	19.00	PSI	Section Modulus (Top)	Stop	2527.47	IN3	14 29.0	0 0	0.00	0.00	0.0
Concrete Actual Strength	f_c^{\prime}	1168	PSI	Section Modulus (Bot)	Sbot	3220.40	[N	13 27.0	0 0	0.00	0.00	0.0
Concrete Equilibrium Weight	M°	-1168	PCF	Cross Sectional Area	Abm	369	IN^2	12 25.0	0 0	0.00	0.00	0.0
LWC Reduction Factor	γ	0.85	None	Weight per Foot (Concrete & Steel)	W _D	0.307	K/FT	11 23.0	0 0	0.00	0.00	0.0
Strand Diameter	٩p	9.0	Z	Web Thickness	ws	- 9	Z	10 21.0	0 0	0.00	0.00	0.0
Strand C/S Area	Ast	0.2183	ľZ Ľ	Height of Beam	DB	36	Z	0.61 6	0 0	0.00	0.00	0.0
Strand Ultimate Strength	f_{pa}	283.25	KSI	Composite Beam Properties	erties			8 17.0	0 0	0.00	0.00	0.0
Strand Yield as % of Ultimate		6.0	None	Moment of Inertia	I,	144285.39	N	7 15.0	0 0	0.00	0.00	0.0
Strand Modulus of Elasticity	E ₂₈	29000	KSI	Distance from Centroid to Top of Beam	Ynop	10.74	Z	6 13.0	0 0	0.00	0.00	0.0
Stirrup Size		4	#	Distance from Centroid to Bot. of Beam	Y_{bot}	25.26	Z	5 11.0	0 0	0.00	0.00	0.0
Stirrup Yield Strength	fy	62	KSI	Section Modulus (Bot)	Spot	5711.81	Z	4 9.0	0	0.00	0.00	0.0
Distance from End to COB	XDIST	9.00	Z	Cross Sectional Area	A_{bm}	577.68	\mathbb{Z}_2	3 7.0	0	0.00	0.00	0.0
Tension Strength Factor	æ	7.50		Weight per Foot (Concrete & Steel)	W_{D}	0.5435	K/FT	2 5.0	0	0.00	0.00	0.0
Top of Beam to Top Strands	TCL	2.50	Z	First Moment of Deck About Centroid	S)	3480.00	'n	1 3.0	8	0.63	312.80	938.4
Bottom of Beam to Bottom Strands	BCL	3.00	Z	Overall Depth of Composite Beam	Н	47.875	Z	Ecce	ntricity	from N	Eccentricity from NC Centroid	pid
Strand Spacing	SPAC	2.00	Z	Miscellaneous Properties	rties			Ωį	Distance		-6.73	ZI
Miscellaneous Variables Normally		Constant		Stirrup Area	Av	0.4	IN^2	VaC	elopmen	it Leng	Development Length (Inches)	5)
Steel Weight Allowance / Cubic Ft		3.0	PCF	Depth to Prestressing Steel	d,	38.78	Z	AASHTO	Ц	100.56	Actual	91.00
Prestress stress for I _d calculation	fps	266	KSI	Ratio of Prestressed Reinforcement	p*	0.0029	None	COB Dist.		94.56	COB	85.00
Shear Strength Reduction Factor	φ°	1.00	None	Strand Yield to Ultimate Factor	Υp	0.28	None	T	ransfer	Length	Transfer Length (Inches)	
Flexural Strength Reduction Factor	φ ^t	1.00	None	Ratio of a/c (Based on Beam Concrete)	β	0.65	None	AASHTO	Ш	30.73	Actual	21.50

Table K.6 Support Conditions, Reactions, Max Load and Moment Furnished

	BRNG	42.00	478.80 504.00		0.13	0.53	112.7						b	ions	Z	None	KSI	0.234	orced	SS	Z	FT-KIP	
Support Conditions, Applied Load (KIP) and Moment Furnished (FT-KIP)	0.25L 0.30L 0.35L 0.40L 0.45L 0.50L 0.55L 0.60L 0.65L 0.70L 0.75L 0.80L 0.85L 0.90L 0.95L BRNG	37.80 39.90	3.60 478.80		1.24 0.69	4.96 2.74	59.6 586.2							Mr (Max) Calculations	38.78	0.00291	264.60	0.1428 .36b ₁	Beam is Under-reinforced	a < Deck Thickness	6.51	1709.6	
shed (F	0.85L 0.9	35.70 37	378.00 403.20 428.40 453.60		Н	7.17 4.	1059.6 1533.0 1709.6 1709.6 1709.6 1709.6 1709.6 1709.6 1709.6 1709.6 1709.6 1709.6 1709.6 1709.6 1709.6 1709.6							Mr (Ma	ф.	p*	f * 311	W _p 0.1	Beam is [a < D	а	Ψ̈́	
Furni	0.80L	33.60	403.20		Н	8.00	1709.6											المحا			اسيا		
ment	C 0.75L	31.50	0 378.00		Н	8.00	9.6021 9							FT	FT	FT	FT	FT	FT				RLS
nd Mo	SL 0.701	30 29.40	60 352.80		Н	0 8.00	9.6 1709.							7.08	42.00	0.00	42.00	34.92	0.00	NA			RCT
IP) al	90F 0.6	25.20 27.30	302.40 327.60	ning l _d	2.00 2.00	00 8.00	9.6 170							NI OSS	Sus.o. IN	0.00	504.0 IN	419.0 IN	0.0	2.36			SHEAR CTRLS
oad (K	.55L 0.	23.10 25	77.20 30	ed Assun	2.00	_	709.6								20	0	50	41	0	2.			
lied L	0.50L 0	21.00 2	151.20 176.40 201.60 226.80 252.00 277.20	Number of Strands Developed Assuming Id	-	8.00	1709.6			DECK		BEAM		load	upport	ort	B)	pport	COB				KIPS
, App	0.45L	18.90	226.80	of Stranc	2.00	8.00	1709.6					m		Distance from left support to point load	Distance from left support to right support	Distance from left COB to left support	Overall Length of Beam (COB-COB)	Distance from point load to right support	Distance from right support to right COB	depth			259
litions	. 0.40L	16.80	0 201.60	Number	2.00	\vdash	6 1709.6							eft suppo	eft suppor	eft COB t	of Beam (point load	ight suppo	listance to			22
t Conc	L 0.351	50 14.70	20 176.4		Н	\vdash	.6 1709.							nce from	nce from	nce from]	ill Length	nce from I	nce from 1	Ratio of shear distance to depth			OAD
nppor	ST 0.30	10.50 12.60	126.00 151.		2.00 2.00	8.00 8.00	9.6 1705							a Dista		L ₂ Dista				a/d Ratio			MAX LOAD
S	20L	8.40 10	100.80 126		2.00 2.	Н	709.6							Ľ	I,	1	Γ	ه ا	고	g.	<u> </u>		2
	0.15L 0		75.60 10		1.79	7.17	1533.0 17	279	->					Port	ion	S)	8	4	2		ap.	0	
Λ	0.10L	_	-		1.24	4.96	9.6501							R Support	Reaction	(KIPS)	11.68	47.04	58.72		Strength Reduction for Shear Cap.	0.930	
G1C-W	3 0.05L	2.10	Н		69.0	2.74	586.2							L. Support	Reaction	(KIPS)	11.68	231.87	243.55		uction for	STD	
	BRNG	0.00	0.00		0.13	0.53	112.7						4	LSt	Rea	R	=	23	24		ngth Red	STD,LRFD	
	REF	Ե	Z		# Top	# Bot	M	Max	Load (KIPS)	SUPT		-		Type	Jo	Load	Dead	Point	Total		Strei	STD,	
										_	189	9											

Table K.7 AASHTO⁴⁰ Loss Calculations

G1C-W			Pre	stressed Beam Lo	oss C	alculati	ons (A	Prestressed Beam Loss Calculations (AASHTO-STD '96)			
Beam Values				ES-Elastic Shortening (Release)	ortening	(Release)		CR-Creep (Slab Placement)	Placen	ent)	
Beam Length (COB-COB)	1	42.00	FT	Radius of Gyration	r ²	138.2	IN^2	Modular Ratio (Eps/Ecs)	u	7.85	None
Beam Cross Sectional Area	Abm	369	Z _Z	Initial Jacking Force	Ą.	391.0	KIPS	Stress at Steel Centroid	f_{cir}	-1.220	KSI
NC Moment of Inertia	٤.	50979	Z	Est. Jacking Force Loss	OK	2.1%	%	Addl. DL. Since Release	W_{SD}	0.000	K/FT
NC Section Modulus (Top)	Sup	2527.47	IN3	Final Jacking Force	P,	368.7	KIPS	Moment due to W _{SD}	M _{SD}	0.0	N-KIP
NC Section Modulus (Bot)	Spot	3220.40	.NJ	MAX Dead Load Moment	Μ _D	812.3	IN-KIPS	Stress at Steel Centroid	f_{csd}	0.000	KSI
Strand Eccentricity from NC Centroid	e e	-6.73	N	Stress at Steel Centroid	fcir	-1.220	KSI	LWC Factor		1.0	None
Beam Weight / Foot (Concrete & Steel)	W	0.307	KÆT	Modular Ratio (Epy/Ecib)	h	29.6	None	Creep Factor	K_{CR}	1.0	None
Deck Weight / Foot (Concrete & Steel)	Wsp	0.236	K/FT	ES Losses (KSI - %)	$\Delta_{\rm fpES}$	-11.79	~9.9-	CR Losses (KSI - %)	Δ _{fp} CR	-14.63	-8.2%
				R-Steel Stress Relax (Release)	s Relax	Release)		SH-Shrinkage (Slab Placement)	ab Place	ment)	
Steel Values				% Relax at Release		30%	%	Shrinkage Factor	K _{SH}	1.0	None
Area of Prestressing Steel	Aps	2.183	IN ₂	Time (Jack to Release)	tret	24	HRS	Relative Humidity	RH	70	%
Strand Ultimate Strength	f Pu	283.25	KSI	R Losses (KSI - %)	$\Delta_{ m fpR}$	-0.83	-0.5%	SH Losses (KSI - %)	Δфѕн	-6.50	-3.6%
Strand Yield Strength	fpy	254.925	KSI								
Strand Modulus of Elasticity	굒	29000	KSI	R-Steel Stress Relax (Slab Placement)	lax (Slai	Placement		R-Steel Stress Relax (Testing)	lax (Te	ting)	
Percent Strand Ultimate at Jacking	%	0.63	None	% Relax at Release		%09	%	% Relax at Release		10%	%
Strand Jacking Stress	r I	179.11	KSI	Time (Release to Slab)	tslab	30	DAYS	Time (Release to Test)	test	120	DAYS
			:	R Losses (KSI - %)	$\Delta_{ m fpR}$	-1.66	-0.9%	R Losses (KSI - %)	$\Delta_{ m fpR}$	-0.28	-0.2%
Concrete Values	ا پ			Steel Stress Relaxation Percentages-OK	ation Per	centages-O	K	Shrinkage Factors-OK	ctors-O	K	
Beam Concrete Design Strength	Ę,	8911	PSI	AASHTO Loss Calculations and PT (KSI)	culations	and PT (K	SI)	Actual Losses and PT (KSI)	od PT ((SI)	
Beam Design Modulus	E	3.69E+06	PSI	Stage	%	Loss	PT	Stage	%	Loss	PT
% Beam Concrete Strength at Release		71%	%	At Release, f _{si}	-7%	-12.62	166.49	At Release, f _{ii}	%6-	-17.00	162.1
Beam Concrete Strength at Release	f_{ci}	6315	PSI	At Slab Placement, fse	-20%	-35.41	143.70	At 14 Days, fse	-14%	-25.46	153.7
Beam Mod. Of Elast. at Release (Act)	Ech	3.00E.06	PSI	At Testing, fse	-20%	-35.69	143.42	At Testing, fse	-18%	-31.50 147.6	147.6

Table K.8 Girder Shear Capacity by 1996 AASHTO⁴⁰ Standard Procedure

2	G1C-W		9	irder S	hear C	Girder Shear Capacity AASHTO STD-96 (Left of Point Load)	AASH	TO ST	T) 96-Q	eft of F	oint Lo	ad)	
IN 0.00 8.50			L-SUPT	0.1 a	0.2 a	0.3 a	0.4 a	0.5 a	0.6 a	0.7 a	0.8 a	0.9 a	P-LOAD
FT-KIP 112.72 272.42 1.2.8 0.56 1.35 1.35 1.2.3 5.40 0.07 0.16 1.2.3 5.40 0.07 0.16 1.2.3 5.40 0.07 0.16 1.2.4 0.03 1.2.7 1.2.8 11.30 1.2.7 1.2.8 11.30 1.2.7 1.2.8 11.30 1.2.7 1.2.8 1.2.9	Distance from Left Support (Inches)	ZI	0.00	8.50	17.00	25.50	34.00	42.50	51.00	59.50	00:89	76.50	85.00
# 0.28 0.67 # 0.56 1.35 # 2.23 5.40 # 2.23 5.40 # 0.07 0.16 # 0.13 0.32 # 0.13 0.32 FT-KIP 0.00 7.95 KIP 11.68 11.30 FT-KIP 0.00 172.19 KIP 243.55 243.17 KSI 0.000 0.030 KIPS 21.25 31.34 KSI -0.102 -0.246 KIPS 21.25 31.34 KSI -0.102 -0.246 KIPS 31.73 491.86 KIPS 1.453 88.79 KIPS 243.55 243.17 KIPS 243.55 KIPS 243.55 243.17 KIPS 243.55 KIPS 243.55 243.17 KIPS 243.55 KIPS 243.55	Ultimate Moment Furnished	FT-KIP	Щ_	272.42	432.11	591.80	751.50	911.19	1070.88	1230.58	1390.27	1549.96	1709.64
# 0.56 1.35 # 2.23 5.40 # 2.23 5.40 # 0.07 0.16 # 0.13 0.32 # 0.13 0.32 # 0.53 1.27 FT-KIP 0.00 7.95 KIP 11.68 11.30 FT-KIP 0.00 172.19 KIP 243.55 243.17 KSI 0.000 0.030 KIPS 21.25 243.17 KSI -0.102 -0.246 KIPS 21.25 217.32 KIPS 31.73 491.86 KIPS 31.73 491.86 KIPS 31.73 88.79 KIPS 31.73 88.79 KIPS 243.55 243.17 KIPS 31.73 88.79 KIPS 243.55 243.17 KIPS 243.55 243.17 KIPS 243.55 243.17 KIPS 211.82 154.38 KIPS 210.81 137.37 KIPS 480.81 137.37 KIPS 512.54 526.16 KIPS 512.54 FAIL KIPS 512.54	Transferred Strands Factor		0.28	0.67	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
# 2.23 5.40 # 0.07 0.16 # 0.13 0.32 # 0.13 0.32 # 0.13 0.32 FT-KIP 0.00 7.95 FT-KIP 11.72 264.47 FT-KIP 0.00 172.19 KIP 243.55 243.17 KSI 0.000 0.030 KIPS 21.25 31.34 KSI -0.102 -0.246 KIPS 31.73 491.86 KIPS 31.73 491.86 KIPS 31.73 88.79 KIPS 31.73 88.79 KIPS 243.55 243.17 KIPS 31.73 88.79 KIPS 243.55 243.17 KIPS 244.57 KIPS 244.	Transferred # Top Strands	#	0.56	1.35	2.00	2.00	2.00	2.00	2.00	2.00	2.00	2.00	2.00
# 0.07 0.16 # 0.13 0.32 # 0.13 0.32 # 0.53 1.27 FT-KIP 0.00 7.95 KIP 11.68 11.30 FT-KIP 112.72 264.47 KIP 243.55 243.17 KS1 0.000 0.030 KIPS 21.25 51.34 KS1 -0.102 -0.246 KIPS 31.73 491.86 KIPS 31.73 88.79 KIPS 31.73 88.79 KIPS 31.73 88.79 KIPS 31.73 88.79 KIPS 243.55 243.17 KIPS 31.73 88.79 KIPS 243.55 243.17 KIPS 211.82 154.38 IN 4.54 6.23 KIPS 210.82 137.37 KIPS 480.81 137.37 KIPS 512.54 226.16 FT-KIP FASS FAIL FT-K	Transferred # Bottom Strands	#	2.23	5.40	8.00	8.00	8.00	8.00	8.00	8.00	8.00	8.00	8.00
# 0.13 0.32 # 0.53 1.27 FT-KIP 0.00 7.95 KIP 11.68 11.30 FT-KIP 112.72 264.47 FT-KIP 0.000 172.19 KIP 243.55 243.17 KSI 0.000 0.030 KIPS 21.25 51.34 KSI -0.102 -0.246 KIPS 31.73 491.86 KIPS 31.73 88.79 KIPS 31.73 88.79 KIPS 31.73 88.79 KIPS 243.55 243.17 KIPS 31.73 88.79 KIPS 243.55 243.17 KIPS 211.82 154.38 IN 4.54 6.23 IN 4.54 6.23 KIPS 210.84 137.37 KIPS 512.54 226.16 KIPS 512.54 54.15 KIPS 512.54 54.15 KIPS 512.54 526.16 KIPS 512.54 54.15 KIPS 512.54 54.15 KIPS 512.54 526.16 KIPS 512.54 FAIL	Developed Strands Factor		0.07	0.16	0.25	0.35	0.44	0.53	0.63	0.72	0.81	0.91	1.00
# 0.53 1.27 FT-KIP 0.00 7.95 KIP 11.68 11.30 FT-KIP 0.00 172.19 KIP 243.55 243.17 KSI 0.000 0.0300 KIPS 21.25 243.17 KSI 0.102 0.246 KIPS 21.25 21.34 KIPS 31.73 491.86 KIPS 31.73 491.86 KIPS 31.73 88.79 KIPS 31.73 88.79 KIPS 243.55 243.17 KIPS 243.55 243.17 KIPS 243.55 243.17 KIPS 243.55 243.17 KIPS 211.82 154.38 IN 4.54 6.23 KIPS 210.84 137.37 KIPS 210.85 154.38 KIPS 210.85 240.15 KIPS 24	Developed # Top Strands	#	0.13	0.32	0.51	69.0	0.88	1.07	1.25	1.44	1.63	1.81	2.00
FT-KIP 0.00 7.95 KIP 11.68 11.30 FT-KIP 11.272 264.47 KIP 243.55 243.17 KIP 243.55 243.17 KSI 0.000 0.030 KIPS 21.25 51.34 KSI -0.102 -0.246 KIPS 31.73 491.86 KIPS 31.73 491.86 KIPS 74.53 88.79 KIPS 74.53 88.79 KIPS 243.55 243.17 KIPS 243.55 243.17 KIPS 211.82 154.38 IN 4.54 6.23 IN 4.54 6.23 KIPS 511.82 137.37 KIPS 512.54 226.16 PASS FAIL	Developed # Bottom Strands	#	0.53	1.27	2.02	2.77	3.52	4.26	5.01	5.76	6.51	7.25	8.00
KIP 11.68 11.30 FT-KIP 11.272 264.47 KIP 243.55 243.17 KIP 243.55 243.17 KSI 0.000 0.030 KIPS 21.25 51.34 KSI -0.102 -0.246 KIPS 31.73 491.86 KIPS 31.73 491.86 KIPS 1.132 -0.132 KIPS 31.73 88.79 KIPS 243.55 243.17 KIPS 243.55 243.17 KIPS 243.55 243.17 KIPS 211.82 154.38 IN 4.54 6.23 IN 4.54 6.23 KIPS 511.82 137.37 KIPS 512.54 226.16 FAIR PASS FAIL	Non-composite DL Moment (BM+SL)	FT-KIP	L	7.95	15.62	23.02	30.15	37.01	43.60	49.91	55.95	61.71	67.21
FT-KIP 112.72 264.47 KIP 243.55 243.17 KIP 243.55 243.17 KSI 0.000 0.030 KIPS 21.25 51.34 KSI -0.102 -0.246 KRIP 277.69 332.36 KIPS 31.73 491.86 KRIPS 31.73 88.79 KIPS 74.53 88.79 KIPS 243.55 243.17 KIPS 243.55 243.17 KIPS 211.82 154.38 IN 4.54 6.23 IN 4.54 6.23 KIPS 211.82 137.37 KIPS 480.81 137.37 KIPS 512.54 226.16 P/F PASS FAIL	Total DL Shear (BM+SL)	ΚŢ	11.68	11.30	10.91	10.53	10.14	9.76	9.37	8.99	8.60	8.22	7.83
FT-KIP 0.00 172.19 KIP 243.55 243.17 KSI 0.000 0.030 KIPS 21.25 51.34 KSI -0.102 -0.246 KIPS 277.69 332.36 KIPS 31.73 491.86 KIPS 89.92 217.32 KIPS 74.53 88.79 KIPS 243.55 243.17 KIPS 243.55 243.17 KIPS 243.55 243.17 KIPS 211.82 154.38 IN 4.54 6.23 KIPS 4180.81 137.37 KIPS 512.54 226.16 KIPS 512.54 226.16 P/F PASS FAIL	Available Moment Capacity	FT-KIP	L	264.47	416.49	568.78	721.34	874.18	1027.29	1180.67	1334.32	1488.25	1642.43
KIP 243.55 243.17 KSI 0.000 0.030 KIPS 21.25 51.34 KSI -0.102 -0.246 KIPS 31.75 491.86 KIPS 31.75 491.86 KIPS 31.73 491.86 KIPS 10.132 -0.132 KIPS 74.53 88.79 KIPS 243.55 243.17 KIPS 243.55 243.17 KIPS 211.82 154.38 KIPS 211.82 154.38 KIPS 211.82 137.37 KIPS 4.54 6.23 KIPS 480.81 137.37 KIPS 512.54 226.16 P/F PASS FAIL	Ultimate Moment, M.,	FT-KIP	L	172.19	344.11	515.75	687.13	858.23	1029.05	1199.61	1369.89	1539.90	1709.64
KSI 0.000 0.030 KIPS 21.25 51.34 KSI -0.102 -0.246 KIPS 31.73 491.86 KIPS 31.73 491.86 KIPS 31.73 491.86 KIPS 137.32 0.336 KIPS 74.53 88.79 KIPS 243.55 243.17 KIPS 243.55 243.17 KIPS 243.55 243.17 KIPS 211.82 154.38 IN 4.54 6.23 KIPS 211.82 137.37 KIPS 480.81 137.37 KIPS 512.54 226.16 P/F PASS FAIL	Ultimate Shear, Vu	Ą	243.55	243.17	242.78	242.40	242.01	241.63	241.24	240.86	240.47	240.09	239.70
KIPS 21.25 51.34 KSI -0.102 -0.246 KIPS 31.73 491.86 KIPS 31.73 491.86 KIPS 217.32 217.32 KIPS 74.53 88.79 KIPS 243.55 243.17 KIPS 243.55 243.17 KIPS 243.55 243.17 KIPS 211.82 154.38 IN 4.54 6.23 KIPS 211.82 137.37 KIPS 480.81 137.37 KIPS 512.54 226.16 P/F PASS FAIL	fd	KSI	0.000	0:030	0.058	980'0	0.112	0.138	0.162	0.186	0.208	0.230	0.250
KSI -0.102 -0.246 KIPS 277.69 332.36 KIPS 31.73 491.86 KIPS 31.73 491.86 KSI -0.132 -0.336 KIPS 74.53 88.79 KIPS 31.73 88.79 KIPS 243.55 243.17 YN YES YES KIPS 211.82 154.38 IN 4.54 6.23 KIPS 210.82 137.37 KIPS 512.54 226.16 RIPS 512.54 226.16 P/F PASS FAIL	SFPF (Based on l _d)	KIPS	21.25	51.34	81.44	111.54	141.64	171.74	201.84	231.94	262.04	292.13	322.23
FT-KIP 277.69 332.36 KIPS 31.73 491.86 KIPS 89.92 217.32 KSI -0.132 -0.336 KIPS 74.53 88.79 KIPS 31.73 88.79 KIPS 243.55 243.17 YN YES YES KIPS 211.82 154.38 IN 4.54 6.23 KIPS 480.81 137.37 KIPS 512.54 226.16 RIPS 512.54 226.16 PASS FAIL FAIL	fne	KSI	-0.102	-0.246	-0.391	-0.535	-0.680	-0.824	-0.969	-1.113	-1.258	-1.402	-1.547
KIPS 31.73 491.86 KIPS 89.92 217.32 KIPS -0.132 -0.336 KIPS 74.53 88.79 KIPS 31.73 88.79 KIPS 243.55 243.17 YN YES YES KIPS 211.82 154.38 IN 4.54 6.23 KIPS 480.81 137.37 KIPS 512.54 226.16 P/F PASS FAIL	McR	FT-KIP	277.69	332.36	387.51	443.15	499.27	555.87	612.96	670.53	728.58	787.12	846.13
KIPS 89.92 217.32 KSI -0.132 -0.336 KIPS 74.53 88.79 KIPS 243.55 243.17 KIPS 243.55 243.17 YNN YES YES KIPS 211.82 154.38 IN 4.54 6.23 KIPS 480.81 137.37 KIPS 512.54 226.16 KIPS 512.54 226.16 P/F PASS FAIL	Ve (Flexure Shear)	KIPS	31.73	491.86	295.52	230.01	197.19	177.46	164.27	154.82	147.70	142.14	137.67
KSI -0.132 -0.336 KIPS 74.53 88.79 KIPS 31.73 88.79 KIPS 243.55 243.17 Y/N YES YES Y/N YES YES KIPS 211.82 154.38 IN 4.54 6.23 KIPS 480.81 137.37 KIPS 512.54 226.16 RMPS 512.54 226.16 P/F PASS FAIL	FPF (Based on I _t)	KIPS	89.92	217.32	322.23	322.23	322.23	322.23	322.23	322.23	322.23	322.23	322.23
KIPS 74.53 88.79 KIPS 31.73 88.79 KIPS 243.55 243.17 YN YES YES YNS YES YES KIPS 211.82 154.38 IN 4.54 6.23 KIPS 480.81 137.37 KIPS 512.54 226.16 F/F PASS FAIL	fic	KSI	-0.132	-0.336	-0.507	-0.523	-0.539	-0.554	-0.569	-0.583	-0.596	-0.609	-0.621
KIPS 31.73 88.79 KIPS 243.55 243.17 Y/N YES YES KIPS 211.82 154.38 IN 4.54 6.23 IN 2.00 Exercises KIPS 312.54 256.16 KIPS 512.54 226.16 P/F PASS FAIL	V _{cw} (Web Shear)	KIPS	74.53	88.79	100.70	101.85	102.96	104.02	105.04	106.02	106.95	107.85	108.70
KIPS 243.55 243.17 Y/N YES YES Y/N YES YES KIPS 211.82 154.38 IN 4.54 6.23 KIPS 480.81 137.37 KIPS 512.54 226.16 P/F PASS FAIL	Vc	KIPS	31.73	88.79	100.70	101.85	102.96	104.02	105.04	106.02	106.95	107.85	108.70
Y/N YES YES KIPS 211.82 154.38 IN 4.54 6.23 IN 2.00 2.00 KIPS 480.81 137.37 KIPS 512.54 226.16 2 P/F PASS FAIL 4	φ/*Λ	KIPS	243.55	243.17	242.78	242.40	242.01	241.63	241.24	240.86	240.47	240.09	239.70
CRUSH CRUSH CRUSH CRUSH CRUSH IN 4.54 6.23 CRUSH IN 2.00 CRUSH IN 3.00 CRUSH	Shear Steel Beyond Minimum Required	Υ/N	YES	YES	YES	YES	YES	YES	YES	YES	YES	YES	YES
KIPS 211.82 154.38	Web Crushing		CRUSH	CRUSH	oK K	OK	OK K	OK	OK OK	ğ	ÖK	OK	ğ
IN 4.54 6.23	Required Strength of Steel, Vs	KIPS	211.82	154.38	142.08	140.55	139.06	137.61	136.21	134.84	133.52	132.24	131.01
N	Required Stirrup Spacing, s	Z	4.54	6.23	6.77	6.84	6.92	66.9	7.06	7.13	7.20	7.27	7.34
KIPS 480.81 137.37 KIPS 512.54 226.16 PF PASS FAIL	Actual Stirrup Spacing, s	Z	2.00						OR		1. 建二十二十二十二十二十二十二十二十二十二十二十二十二十二十二十二十二十二十二十		
KIPS 512.54 226.16 P/F PASS FAIL	Strength of Steel, Vs	KIPS	480.81	137.37	137.37	137.37	137.37	137.37	137.37	137.37	137.37	137.37	137.37
P/F PASS FAIL	Total Beam Shear Strength, Vc + Vs	KIPS	512.54	226.16	238.08	239.23	240.33	241.39	242.41	243.39	244.33	245.22	246.07
	Beam "AS BUILT" Shear Capacity	P/F	PASS	FAIL	FAIL	FAIL	FAIL	FAIL	PASS	PASS	PASS	PASS	PASS
Ratio of (Vc + Vs) / (Vu / \phi) NONE 2.10 0.93 0.98	Ratio of (Vc + Vs) / (Vu / ϕ)	NONE	2.10	0.93	0.98	0.99	0.99	1.00	1.00	1.01	1.02	1.02	1.03

Table K.9 Deflection Calculations

GIC-W				Predicted	Approxim	ate Deflec	Predicted Approximate Deflection Calculations	lations		
Member and Section D	Jimensions					First Mon	First Moment WRT Right Support	ht Support		
Distance from Left Support to Load	а	85.001	Z	Dist From L Supt (IN)	Supt (IN)	Area of Se	Area of Section (RAD)	Dist Cent to	Dist Cent to R Supt (IN)	A*C (IN)
Distance from Load to Right Support	q	418.999	Z	Xı	44.92	Aı	0.0002944	CI	474.05	0.1396
Distance Between Supports	L,	504	Z	X ₂	62.56	A_2	0.0002313	C_2	450.26	0.1041
Height of Beam	DB	36	Z	X³	85.00	A_3	0.0030466	ပီ	447.32	1.3628
Deck Thickness	₽,	11.875	Z	X4	107.44	A4	0.0080421	۲,	430.22	3.4599
Bottom of Beam to Bottom Strands	BCL	3.00	Z	X ₅	282.58	As	0.0080421	င်	407.78	3.2794
Moment of Inertia	a	144285	Ž	%X	504.00	A ₆	0.0022959	ပီ	308.99	0.7094
Beam Mod. Of Elast. At Testing (Est)	E.	3.69E+06	PSI			Α,	0.0302401	C,	338.18	10.2266
Web Thickness	SM	9	Z			A_8	0.0014512	C ₈	147.61	0.2142
Depth to Prestressing Steel	ф	38.78	Z						θ [*] L (IN)	19.4960
Shear Modulus Factor (Cracking)	G Factor		None						θ_{L} (RAD)	0.0387
Shear Modulus Factor (Ultimate)	G Factor	FOres,	None						θ _L *a (IN)	3.2881
Shape Factor for Shear (I Section)	k	1	None							
Length of Plastic Hinge at Point of Loading	Lhge	44.88	Z		3					
Girder Predicted V	Values					First Mome	First Moment WRT Point of Loading	of Loading		
Predicted Cracking Moment	Ma	69.076	FT-KIP			Area of Se	Area of Section (RAD)	Dist Cent t	Dist Cent to Load (IN)	A*C(IN)
Dead Load Moment	Mot	67.21	FT-KIP			A_1	0.0002944	CP_1	55.06	0.0162
Predicted Applied Cracking Load	Per	153.41	KIP			A2	0.0002313	CP,	31.26	0.0072
Predicted L Support Reaction at Cracking	Rice	127.54	Κ₽			A ₃	0.0030466	CP,	28.32	0.0863
Predicted R Support Reaction at Cracking	Rrer	25.87	KIP			Å	0.0080421	CP4	11.22	0.0902
Predicted Curvature at Cracking	фст	0.000013	RAD/IN						ΔP_{θ}	0.1999
e Values Using		a Cracked Section Analysis	lysis							
Maximum Experimentally Applied Load	P _{elt}	290.31	KIP		Deflection	s Due to Prec	Deflections Due to Predicted Loads at Cracking and Ultimate	Cracking and	I Ultimate	
Maximum Left Support Reaction	$R_{\rm l}$	241.35	KIP	Stage of Loading	Loading	Flexure	Shear	Flexure	Flexure + Shear	Units
Maximum Right Support Reaction	R,	48.96	KIP	Cracking	king	0.241	0.03154	0.	0.273	Z
Predicted Curvature at Ultimate	ф _{eth}	0.000358	RAD/IN	Ultimate	nate	3.088	0.05968	3.	3.148	Z

Table K.10 Variable Angle Truss Model

G1C-W				Var	iable A	Variable Angle Truss Model	iss Mode	1			
Variables and Values	es		Distance	Stirrup		FStrand	FStrand		Plot Data)ata	
V.* = Vr. + Vi.	260.29 KIPS	Stirrup	From Load	Force	p[/X	Reduction	Remaining	Distance	Fstrand	le I	Chond
Shear Area, A.,	0.4 IN^2	#: 	a	(KIPS)		(KIPS)	(KIPS)	N	KIPS	Z	KSI
Yield Strength of Stirrups, f.	\vdash	-	15.00	24.80	0.422	10.47	516.06	85.00	526.54	91.00	0.3070
Top of Deck to Centroid of PT, d,	38.78 IN	2	22.00	24.80	0.619	15.36	500.70	70.00	526.54	76.00	0.3675
Maximum Depth of RSB, a	15	3	29.00	24.80	0.817	20.25	480.45	70.00	516.06	76.00	0.3602
**************************************	264.60 KSI	4	36.00	24.80	1.014	25.14	455.32	63.00	516.06	69.00	0.3968
Stirrup Spacing	7.00 IN	5	43.00	24.80	1.211	30.03	425.29	63.00	500.70	69.00	0.3850
Shear Span	L	٥	50.00	24.80	1.408	34.91	390.38	26.00	500.70	62.00	0.4284
XDIST	00.9	7	57.00	24.80	1.605	39.80	350.58	26.00	480.45	62.00	0.4111
Maximum Crack Angle	F	∞	64.00	24.80	1.802	44.69	305.89	49.00	480.45	55.00	0.4634
Minimum Crack Angle (A2.5)		6	71.00	24.80	1.999	49.58	256.31	49.00	455.32	55.00	0.4392
Feirm		2	78.00	24.80	1.774	43.99	212.32	42.00	455.32	48.00	0.5032
Min 1st Stirrup Distance from Load	12.93 IN	Ξ	85.00	24.80	1.774	43.99	168.33	42.00	425.29	48.00	0.4700
Max Nth Stirrup Distance from Load	17							35.00	425.29	41.00	0.5503
Maximum Stirrups in Fan	9 EACH							35.00	390.38	41.00	0.5051
# Stirrups Read for V.,1	11 EACH							28.00	390.38	34.00	0.6091
Total Stirrups Available	11 EACH							28.00	350.58	34.00	0.5470
Internal Moment Arm, id	35.52 IN							21.00	350.58	27.00	0.6888
Total Strand Force Based on fsu*, fse	526.54 KIPS							21.00	305.89	27.00	0.6010
Nominal Strand Circumference	1.885 IN							14.00	305.89	20.00	0.8114
Maximum VATM Predicted Shear	223.2 KIPS							14.00	256.31	20.00	0.6799
Maximum VATM Predicted Moment	1581.0 FT-KIP							7.00	256.31	13.00	1.3075
Compression Field Crack Angle 9	29.41 DEG							7.00	212.32	13.00	1.0831
Compression Strut (Based on V.	i on V _{at.})							0.00	212.32	90.9	2.3467
Width of Strut (id cos 0)	30.94 IN	Angle	minimum ar	nd maximun	n values and	Angle minimum and maximum values and the allowable stress in the	stress in the	0.00	168.33	90.9	1.8605
Compressive Force D	530.01 KIPS		ressive strut	are based on	ACI318-02	compressive strut are based on ACI318-02. Changes are in CI, June	in CI, June		168.33		
Compressive Stress in Strut, fa	2.86 KSI	2001, 1	p. 125-132.	Bond stress	inside 1 sti	2001, pp. 125-132. Bond stress inside 1 stirrup space from the support	n the support				
Lightweight Concrete Factor, 1	0.85 None	=	ed on only th	e bottom 8	strands. Stir	is based on only the bottom 8 strands. Stirrup spacing initiates at the	tiates at the				
Allowable Stress in Strut, A3.2	3.86 KSI	oddns	nt and moves	to the load.	All plot da	support and moves to the load. All plot data is based on the ultimate	the ultimate				
VATM IS CONSERVATIVE	TIVE			(experime	(experimental) shear value.	value.					




Figure K.1 Force in Prestressing Strands vs. Distance From Girder End




Figure K.2 Prestressing Strand Bond Stress vs. Distance From Girder End

Table K.11 Theoretical Moment-Curvature Stages 1 - 3 (Elastic Portion)

G1C-W				Theoretical N	[omen	t-Curvat	ture (E	Theoretical Moment-Curvature (Elastic Portion)			
Stage 1 - No Load	No Load			Stage 2 - Zero Strain in Conc at Bot Strand Level	onc at Bo	ot Strand L	evel	Stage 3 - Cracking on Bottom Fiber	on Botte	om Fiber	
NC Moment of Inertia	I.e.	50979	ž	C Moment of Inertia	1	144285	IN.	Tension Strength Factor	а	7.5	None
Top)	Stop-nc	2527.47	IN3	C Section Modulus (Girder)	Stope	13436	IN ₃	LWC Reduction Factor	-	0.85	None
	Spot-nc	3220.40	IN3	C Section Modulus (Girder)	Sbote	5712	ľŊ	Concrete Actual Strength	ť.	8911	PSI
	Anc	369	IN ₂	C Girder Area	Ac	89.778	IN^2	Rupture Stress	f,	0.602	KSI
NC Girder Height	DB	36	Z	Deck Thickness	₹.	11.875	Z	Required Addl Stress	f_3	0.518	KSI
Ecc from NC Centroid	o	-6.73	Z	C Centroid to NC Girder Bot	Ybotec	25.26	N.	Required Addl Moment	M,	246.59	FT-KIP
Girder E. (Est)	Ē	3.69E+06	PSI	NC Girder Top to Top Strds	TCL	2.50	N.	Total Moment (M _{DL} +M ₂ +M ₃)=M _{CR}	M_{CR}	970.63	FT-KIP
Effective PT Force	Fse	322.23	KIPS	NC Girder Bot to Bot Strds	BCL	3.00	Z	NC Girder Stress	TOP	BOTTOM	
Mpi	M_{DL}	67.21	FT-KIP	Required Additional Moment	M_2	656.83	FT-KIP	FT-KIP Axial Prestress	-0.873	-0.873	KSI
NC Girder Stress	TOP	TOP BOTTOM		Total Moment (M _{DL} +M ₂)		724.04	FT-KIP	Eccentricity Prestress	0.858	-0.673	KSI
Axial Prestress	-0.873	-0.873	KSI	NC Girder Stress	TOP	BOTTOM		Dead Load Moment	-0.319	0.250	KSI
Eccentricity Prestress	0.858	-0.673	KSI	Axial Prestress	-0.873	-0.873	KSI	Additional Moment M2	-0.587	1.380	KSI
Dead Load Moment	-0.319	0.250	KSI	Eccentricity Prestress	0.858	-0.673	KSI	Additional Moment M3	-0.22	0.518	KSI
Total Concrete Stress	-0.334	-1.296	KSI	Dead Load Moment	-0.319	0.250	KSI	Total Concrete Stress	-1.141	0.602	KSI
Total Concrete Strain	-90.5	-350.9	3rd	Additional Moment M2	-0.587	1.380	KSI	Total Concrete Strain	-309.0	162.9	me
Conc Strain at Bot Strands	3 3	-329.2	311	Total Concrete Stress	-0.921	0.084	KSI	Conc Strain at Bot Strands	3 ² 3	123.6	me
Conc Stress at Bot Strands	ge	-1.2161	KSI	Total Concrete Strain	-249	23	3rd	Conc Strain on Top of Deck	ϵ_{cd}	-460.0	me
Steel Strain in Bot Strands	S _{re}	5053.0	आ	Steel Strain in Bot Strands	£42	5382.2	and	Steel Strain in Bot Strands	£ ₅ 3	5505.8	шc
Curvature of Girder	-7.	-7.23E-06	rad/in	Curvature of Girder	7.50	7.56E-06	rad/in	Curvature of Girder	1.3	1.31E-05	rad/in

Table K.12 Theoretical Moment-Curvature Stages 4-6 (Cracked Portion)

G1C-W				Theoretical M	oment	-Curvatı	ıre (C	Theoretical Moment-Curvature (Cracked Portion)			
Stage 4 - Deck Strain =	train =	1000	an	Stage 5 - Deck Strain =	Strain =	2000	आ	Stage 6 - Deck Strain =	train =	3000	an
Conc Strain on Top of Deck	Pog	0.0001	an	Conc Strain on Top of Deck	po ₃	2000.0	3rl	Conc Strain on Top of Deck	Ecd	3000.0	311
Guess for NA Depth "c"	υ	00.91	Z	Guess for NA Depth "c"	၁	68.6	N	Guess for NA Depth "c"	၁		Z
Resulting Top Strand Strain	See	5011.3	ari	Resulting Top Strand Strain	Eset	6216.4	эn	Resulting Top Strand Strain	Eset	7698.8	311
Resulting Top Strand Stress	Sect	146.39	KSI	Resulting Top Strand Stress	Set	181.59	KSI	Resulting Top Strand Stress	Set	224.10	KSI
Resulting Top Strand Force	Fsd	63.91	KIPS	Resulting Top Strand Force	Fset	79.28	KIPS	Resulting Top Strand Force	Fset	97.84	KIPS
Bot Strand Strain Increase	8 _{sebi}	2991.7	art	Bot Strand Strain Increase	Eschi	9074.8	आ	Bot Strand Strain Increase	Eschi	16084.2	an.
Resulting Bot Strand Strain	фs ₃	8373.9	an	Resulting Bot Strand Strain	E _{sch}	14457.1	अर्ग	Resulting Bot Strand Strain	Esch	21466.5	311
Resulting Bot Strand Stress	$\sigma_{\rm scb}$	239.20	KSI	Resulting Bot Strand Stress	Sch	264.58	KSI	Resulting Bot Strand Stress	σ_{scb}	267.17	KSI
Resulting Bot Strand Force	F_{sch}	417.73	KIPS	Resulting Bot Strand Force	Fscb	462.06	KIPS	Resulting Bot Strand Force	Fscb	466.58	KIPS
Resulting Strand Force	Fse	481.65	KIPS	Resulting Strand Force	Fse	541.34	KIPS	Resulting Strand Force	Fse	564.42	KIPS
Resulting Concrete Force	F_c	481.22	KIPS	Resulting Concrete Force	Fc	542.26	KIPS	Resulting Concrete Force	Fc	564.83	KIPS
Within Tolerance		XES	Y/N	Within Tolerance		YES	Y/N	Within Tolerance		YES	Y/N
Resulting Moment	M4	1433.0012	FT-KIP	Resulting Moment	Ms	1661.3037	FT-KIP	Resulting Moment	M ₆	1709.5994	FT-KIP
Curvature of Girder	9.9	6.67E-05	rad/in	Curvature of Girder	2.0	2.02E-04	rad/in	Curvature of Girder	3.5	3.58E-04	rad/in
Todeschini Variable	f".	4845.6	ISd	Todeschini Variable	fe"	4845.6	PSI	Todeschini Variable	fe"	4845.6	PSI
Todeschini Variable	80	2748.3	311	Todeschini Variable	80	2748.3	आ	Todeschini Variable	မ	2748.3	3rd
Todeschini Variable	×	0.364	None	Todeschini Variable	×	0.728	None	Todeschini Variable	×	1.092	None
Todeschini Variable	βι	0.342	None	Todeschini Variable	βι	0.584	None	Todeschini Variable	β_1	0.719	None
Todeschini Variable	k_2	0.342	None	Todeschini Variable	\mathbf{k}_2	0.362	None	Todeschini Variable	k ₂	0.387	None
Average Stress	S avg	1656	PSI	Average Stress	Gavg	2830	PSI	Average Stress	σ_{avg}	3483	PSI .




Figure K.3 Moment-Curvature Plot

Table K.13 Girder Shear Capacity by 1998 AASHTO⁹² LRFD Procedure


G1C-W		B	am Sh	ear Ca	Beam Shear Capacity AASHTO LRFD-98 (Left of Point Load	ASHT	O LRF	D-98 (L	eft of F	oint Lo	ad)	
District from I off Comment	I.G.	L-SUPT	0.1 a	0.2 a	0.3 а	0.4 a	0.5 a	в 9.0	0.7 а	0.8 a	0.9 a	P-LOAD
Distance from Lett Support (menes)	NI I	0.00	8.50	17.00	25.50	34.00	42.50	51.00	59.50	68.00	76.50	85.00
Ultimate Moment Furnished	FT-KIP	112.72	272.42	432.11	591.80	751.50	911.19	1070.88	1230.58	1390.27	1549.96	1709.64
Developed # Top Strands	#	0.13	0.32	0.51	0.69	0.88	1.07	1.25	1.44	1.63	1.81	2.00
Developed # Bottom Strands	#	0.53	1.27	2.02	2.77	3.52	4.26	5.01	5.76	6.51	7.25	8.00
Non-composite DL Moment (BM+SL)	FT-KIP	0.00	7.95	15.62	23.02	30.15	37.01	43.60	49.91	55.95	61.71	67.21
Total DL Shear (BM+SL)	KIP	11.68	11.30	10.91	10.53	10.14	9.76	9.37	8.99	8.60	8.22	7.83
Available Moment Capacity	FT-KIP	112.72	264.47	416.49	568.78	721.34	874.18	1027.29	1180.67	1334.32	1488.25	1642.43
Ultimate Moment, M _u	FT-KIP	0.00	172.19	344.11	515.75	687.13	858.23	1029.05	1199.61	1369.89	1539.90	1709.64
Ultimate Shear, Vu	KIP	243.55	243.17	242.78	242.40	242.01	241.63	241.24	240.86	240.47	240.09	239.70
Stress in Prestressing Strands at M _u , f _{ps}	KSI	6.73	23.52	37.31	51.10	64.88	78.67	92.46	106.25	120.03	133.82	264.60
Depth of Compression Block, a	I.	0.24	0.58	0.92	1.26	1.60	1.94	2.28	2.62	2.96	3.29	6.51
Effective Shear Depth, d,	R	38.66	38.49	38.32	38.15	37.98	37.81	37.64	37.47	37.30	37.13	35.52
Effective Area of Prestress, Apse	IN^2	0.12	0.28	0.44	09:0	0.77	0.93	1.09	1.26	1.42	1.58	1.75
Shear Stress on Concrete, v / f.	None	0.118	0.118	0.119	0.119	0.119	0.120	0.120	0.120	0.121		0.126
Measured θ From Beam	DEG	3.00	08.40	30	- 30	30° ×	10	200 20	1.50	30	300	100
Strain in Reinforcement, Ex, Actual	IN/IN	0.0581	0.0277	0.0198	0.0161	0.0141	0.0128	0.0118	0.0112	0.0107	0.0103	0.0104
Strain in Reinforcement, Ex. Allowed	IN/IN	0.0020	0.0020	0.0020	0.0020	0.0020	0.0020	0.0020	0.0020	0.0020	0.0020	0.0020
Adjustment Factor for "-" Value, Fe	None	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Strain in Reinforcement, Ex. Allowed	IN/IN	0.0020	0.0020	0.0020	0.0020	0.0020	0.0020	0.0020	0.0020	0.0020	0.0020	0.0020
Value of β From Figure	None			W 1.3			A 1.25		11.5	1.3		La
Shear Strength of Concrete, V _c	KIPS	24.18	24.07	23.96	23.86	23.75	23.64	23.54	23.43	23.33	23.22	22.21
Stirrup Spacing, s	Z	2.00	7.00	7.00	7.00	7.00	7.00	00'2	7.00	7.00	7.00	7.00
Strength of Steel, Vs	KIPS	830.21	236.16	235.12	234.08	233.04	232.00	230.95	229.91	228.87	227.83	217.95
Total Beam Shear Strength, V _c + V _s	KIPS	854.39	260.23	259.08	257.94	256.79	255.64	254.49	253.35	252.20	251.05	240.16
Beam "AS BUILT" Shear Capacity	P/F	PASS	PASS	PASS	PASS	PASS	PASS	PASS	PASS	PASS	PASS	PASS
Ratio of (Vc + Vs) / (Vu / Φ)	NONE	3.51	1.07	1.07	1.06	1.06	1.06	1.05	1.05	1.05	1.05	1.00
Longitudinal Reinforcement Satisfied	Υ/N	YES	ON	NO	ON	NO	ON	ON	ON	NO	NO	NO
Addl Non-Prestressed Steel Required	$ m N^2$	NA	3.17	3.35	3.54	3.73	3.93	4.14	4.35	4.57	4.80	5.52

Table K.14 Girder-Deck Interface Shear Calculations

G1C-W		Deck / B	eam Int	Deck / Beam Interface Shear Calculations (AASHTO-STD '96)	ASHTO-S	(96, QI	
Interface Shear Ca	Iculation Values	nes		Tensile Stress at Interface	at Interface		
Lightweight Concrete Reduction Factor	1	0.85	None	Deck Concrete Actual Strength	f,	5384	PSI
Shear Strength Reduction Factor	φ³	1.00	None	Maximum Allowable Deck Tensile Stress		550.32	PSI
Maximum Unfactored Shear	η	243.55	KIPS	Beam Concrete Actual Strength	- ² -	8911	PSI
First Moment of Deck About Centroid	SÒ	3480.00	IN ₃	Maximum Allowable Beam Tensile Stress		601.79	PSI
Composite Moment of Inertia	η	144285	IN ⁴	Maximum Interface Shear Stress (VQ/Ib)	Vb	489.52	PSI
Interface Shear Contact Width	b,	12	Z	Effective Prestress Force	Тse	322.23	KIPS
Contact Length, d (a+XDIST<=SPAN/10)	Span/10	50.40	Z	Beam Cross Sectional Area	Abm	369	ž
Contact Area (b,*Contact Length)	Αc	604.8	IN^2	Strand Eccentricity from NC Centroid	e	-6.73	Z
Yield Strength of Tie Reinforcement	ť	62	KSI	Distance from NC Centroid to Beam Top	Yeop	20.17	Z
Stirrup Area	A,	0.4	IN ₂	Distance from C Centroid to Beam Top	Yup	10.74	呂
				Non-Composite Moment of Inertia	Inc	50979	ž
Interface C	ondition			Composite Moment of Inertia	1	144285	Ž
Contact Surface Clean		A SALVANIA	YES/NO	Dead Load Moment	M _{DL}	67.21	FT-KIP
Contact Surface Roughened 1/4"		Part SIGN	YES/NO	Live Load Moment	MLL	1642.43	FT-KIP
Minimum Ties Provided		AVES	YES/NO	Maximum Compressive Stress at Interface	fa	-1801.27	PSI
Maximum Basic Interface Stress		350	ISd	Maximum Tensile Stress at Interface	f,	124.438	PSI
Maximum Basic Interface Force	V _{ph}	211.68	KIPS	Tensile Stress at Interface is OK	Interface is OF		
Basic Interface Shear C	apacity Inadequate	lequate					

Additional Interface Capacity Required Worst Case Stirrup Spacing over "a" s Minimum Tie Area per Inch of Beam	31.87	
Norst Case Stirrup Spacing over "a" s Minimum Tie Area per Inch of Beam		Sala
dinimum Tie Area per Inch of Beam	7.00	Z
	0.0097	IN ² /IN
Additional V _m Capacity per Percent	150.0	KIPS
Additional Percent Required	0.21	%
Additional Required Tie Area	0.000021	IN ² /IN
Total Tie Area Required	0.009698	IN ² /IN
Min. Tie Area Provided by V Reinforcement	0.057143	IN ² /IN
Resulting Contact Area Stress	402.70	PSI
Interface Shear Capacity Adequate		

Table K.15 Prestressing Strand Tension Test Curve



- - 2nd Principal Strain (Compression) ----- 1st Principal Strain (Tension) High Crack Angle 12 40 90 4 Angle CCW From Horizontal (degrees) Strain (microstrain) -5000 -10000 -20 -15000 -30 Applied Shear (kips) Applied Shear (Kips) Low Crack Angle 2269 Angle CCW From Horizontal (degrees) Shear Strain (micro-radians) Applied Shear (kips) - 92 Applied Shear (kips) ŝ

Table K.16 Principal Strain and Maximum Shear Strain Plots




Figure K.4 Load Displacement Plot

Table K.17 Overview of Girder Test Results

G1C-W	4	Single	02-Nov-01	Girder	Girder Test Overview	verview		
Support and Load Di	Load Din	imensions		Value		Predicted	Experimental	Units
Shear Span	а	85.001	Z	Transfer Length	1	30.73	21.50	Z
Distance Between Supports	LI	504	N.	Development Length	. P	100.56	91.00	Z
Deck	Deck Variables			Cracking Load	P	153.41	183.00	KIPS
Deck Thickness	ţ	11.875	N	Cracking Moment	Ma	970.63	1144.85	FT-KIPS
Deck Width	Wr	19.375	Z	Rupture Stress	Į,	601.79	967.82	PSI
Concrete Strength at Testing	£°	5384	PSI	Ultimate Load (AASHTO-Flexure)	Pult	278.91	299.04	KIPS
Elasticity Modulus at Testing	Ecd	3.35E+06	PSI	Ultimate Moment (AASHTO-Flexure)	Mult	1709.64	1828.17	FT-KIPS
Girder	Girder Variables	Ş		Ultimate Load (Cracked Section)	Put	290.31	299.04	KIPS
Concrete Strength at Release	f _{ei} '	6315	PSI	Ultimate Moment (Cracked Section)	Mult	1709.60	1828.17	FT-KIPS
Concrete Strength at Testing	f°,	8911	PSI	Deflection at Cracking (Flex & Shear)	Scr	0.273	0.441	Z
Concrete Equilibrium Weight	Wc	116.8	PCF	Ultimate Deflection (Flex & Shear)	Sult	3.148	2.270	Z
Lightweight Concrete Factor	1	0.85	None	Ultimate Concrete Deck Surface Strain	123	0.0030	0.0036	ZVZ
Elasticity Modulus at Release	Eci	3.00E+06	PSI	Initial Losses on Release	ES	-12.62	-17.00	KSI
Elasticity Modulus at Test (Est)	Ea	3.69E+06	PSI	Time Dependant Losses (14-Day)	CR,SH	-35.41	-25.46	KSI
Prestressing Strand		Variables		Time Dependant Losses (Test)	CR,SH	-35.69	-31.50	KSI
Strand C/S Area	Ast	0.2183	$ m IN^2$	Web Shear Strength (Vow. ALT / Venck)	Vcw	123.3	134.2	KIPS
Strand Ultimate Strength	f.	283.25	KSI	Tensile Strength for Shear Cracking	$f_{\rm t}^n$	0.321	0.363	KSI
Strand Modulus of Elasticity	먠	29000	KSI	Tensile Strength Factor (Includes λ)	ζ.	4.00	4.52	None
Strand Percent fpu at Jacking		63%	%	Strand Stress at Ultimate Load	fps	264.60	264.40	KSI
Stress at Jacking	f_{pt}	179.11	KSI	Ultimate Shear Capacity (VATM/Vexp)	V _U -vatm	223.20	260.29	KIPS
Stress after Release	f_{si}	162.11	KSI	Ultimate Shear Capacity (STD/V _{exp})	V _U -srp	241.39	260.29	KIPS
Stress after 14 Days	fse	153.65	KSI	Comp Field Angle (VATM/Girder) θ		29.4	30.0	DEG
Stress at Testing	fæ	147.61	KSI	LVDT Rosette Tension Crack Angles (Low/High)	High)	22.7	40.9	DEG
Strain at Testing	S,e	5053	311	The predicted f," is based on the ACI alternate technique specified in 11.4.2.2 using a of 4. The	mate techni	que specified in	11.4.2.2 using a of	4. The
Strain at Ultimate Load	*#3	13960	an	regular approach in 11.4.2.2 uses 3.5 as the multiplier as is seen in equation 11-12. a can be changed	multiplier a	s is seen in equa	tion 11-12. a can !	e changed
Stirrup	Stirrup Variables	88		in the "predicted a" cell. The experimental V _{cw} value is shear at which shear cracking occurred. The	V _{cw} value is	shear at which	shear cracking occu	irred. The
Stirrup Size		4	#	predicted ft is based on the equation from Burns' book, page 254. The fx value comes from the STD	urms' book,	page 254. The	fpc value comes fro	n the STD
Stirrup Yield Strength	f,	62	KSI	Shear Pa	Shear Page at the 0.5a location	ia location.		

APPENDIX L

MOMENT vs. CURVATURE PLOTS AND LOAD vs. DEFLECTION PLOTS

Appendix L contains moment vs. curvature plots and load vs. displacement plots for each girder test. The predicted and experimental values are listed on both plots. The following sections describe the calculations required for both plots.

L.1 Moment-Curvature

Predicted moment and curvature values were determined at several stages progressing from zero applied load to the ultimate applied load. The predicted moment and curvature values were then used to predict deflections at the point of loading and for comparison with experimental values. The process for calculating moment and curvature values can be found in *Design of Prestressed Concrete Structures*, T.Y. Lin and Ned H. Burns. The process for determining stresses in a composite section can be found in *Prestressed Concrete Structures*, Michael P. Collins and Denis Mitchell. Several assumptions were made to determine the values.

- The concrete and prestressing strands were considered perfectly bonded.
 Strains in the concrete and steel were considered to be the same.
 - 2. The stress-strain relationship was known for the concrete and steel.

- 3. Strains were distributed linearly over the height of the girder.
- 4. The girder was in static equilibrium.

A Todeschini¹⁵¹ stress distribution was assumed for the deck during the cracked section analysis. Moment and curvature values were determined at six specific points as described in the following sections. Tables K.11 and K.12 show calculation of moment and curvature values. Variables are defined in Appendix T.

L.1.1 Stage 1 - Zero Applied Load

The following procedure was used to determine curvature with zero applied load.

$$f_{top} = -\frac{F_{se}}{A_{nc}} - \frac{F_{se} e}{S_{top-nc}} - \frac{M_{DL}}{S_{top-nc}}$$
 (L.1)

$$f_{bot} = -\frac{F_{se}}{A_{nc}} + \frac{F_{se} e}{S_{bot-nc}} + \frac{M_{DL}}{S_{bot-nc}}$$
(L.2)

Strains at the top and bottom of the girder were calculated with the following equations:

$$\varepsilon_{top} = \frac{f_{top}}{E_{cg}} \tag{L.3}$$

$$\varepsilon_{bot} = \frac{f_{bot}}{E_{cg}} \tag{L.4}$$

The predicted curvature at Stage 1 was calculated with the following equation:

$$\phi = \frac{-(\varepsilon_{top} - \varepsilon_{bot})}{h_{s-nc}} \tag{L.5}$$

The resulting stress in the concrete at the level of the bottom strands was calculated as:

$$\sigma_{ce} = \frac{(\varepsilon_{top} + (\varepsilon_{bot} - \varepsilon_{top})) * (h_{g-nc} - BCL)}{h_{g-nc}} * E_{cg}$$
 (L.6)

L.1.2 Stage 2 - Zero Concrete Strain at the Level of Bottom Strands

The following procedure was used to determine the curvature at the point where the applied load produced zero concrete strain at the level of the bottom strands. This point is known as the "decompression load." The effect of the applied load was determined using the composite section properties. The effects of prestressing and any dead load moment were the same as in Stage 1. The effect of the applied load was added to the Stage 1 values to determine the total affect. To determine the applied moment required, M₂, to produce zero strain and thus zero stress in the concrete at the level of the bottom strands, the following equation was used. Refer to Table K.11.

$$M_2 = \frac{-\sigma_{ce}I_c}{(y_{bot-c} + BCL)} \tag{L.7}$$

The resulting stresses at the top and bottom of the girder were calculated with the following equations:

$$f_{top} = -\frac{F_{se}}{A_{nc}} - \frac{F_{se} e}{S_{top-nc}} - \frac{M_{DL}}{S_{top-nc}} - \frac{M_{2}}{S_{top-c}}$$
 (L.8)

$$f_{bot} = -\frac{F_{se}}{A_{nc}} + \frac{F_{se} e}{S_{bot-nc}} + \frac{M_{DL}}{S_{bot-nc}} + \frac{M_{2}}{S_{bot-c}}$$
(L.9)

The resulting strains at the top and bottom of the girder were calculated using equations L.3 and L.4. The resulting strain in the bottom strands was calculated using the following equation where the effective strain prior to applying load, ε_{se} , was determined from VWSG readings prior to girder testing.

$$\varepsilon_{s2} = \varepsilon_{se} - \frac{\sigma_{ce}}{E_{ce}} \tag{L.10}$$

Curvature was calculated using equation L.5.

L.1.3 Stage 3 - Cracking Stress on Bottom Fiber

The following procedure was used to determine the curvature at the point where the additional applied load produced a stress at the bottom fiber equal to the predicted cracking stress, f_{cr} . The moment that produces the cracking stress on the bottom fiber is the cracking moment, M_{cr} . The predicted cracking stress was calculated using the following equation:

$$f_{cr} = 7.5\lambda \sqrt{f_c'} \tag{L.11}$$

The effect of the applied load was determined using the composite section properties. The effects of prestressing and any dead load moment were the same as in Stage 1. The effect of the applied load was added to the Stage 1 values to determine the total effect. To determine the additional applied moment required, M_3 , to produce M_{cr} and the cracking stress, f_{cr} , at the bottom fiber, the following equation was used. The subscript "-2" indicates the bottom stress from Stage 2.

$$M_3 = (f_{cr} - f_{bot-2})S_{bot-c} (L.12)$$

The cracking moment, M_{cr}, was determined with the following equation:

$$M_{cr} = M_{DL} + M_2 + M_3 \tag{L.13}$$

The total concrete stress at the top and bottom of the girder were calculated with the following equations:

$$f_{lop} = -\frac{F_{se}}{A_{nc}} - \frac{F_{se}e}{S_{lop-nc}} - \frac{M_{DL}}{S_{lop-nc}} - \frac{M_2}{S_{lop-c}} - \frac{M_3}{S_{lop-c}}$$
(L.14)

$$f_{bot} = -\frac{F_{se}}{A_{nc}} + \frac{F_{se} e}{S_{bot-nc}} + \frac{M_{DL}}{S_{bot-nc}} + \frac{M_2}{S_{bot-c}} + \frac{M_3}{S_{bot-c}}$$
(L.15)

The resulting strains at the top and bottom of the girder were calculated with equations L.3 and L.4. The resulting strain in the bottom strands, ε_{s3} , was calculated with the following equation:

$$\varepsilon_{s3} = \varepsilon_{s2} + \frac{(f_{cr} - f_{bot-2})}{E_{cg}} * \left(\frac{y_{bot-c} - BCL}{y_{bot-c}}\right)$$
 (L.16)

Curvature was calculated using equation L.5.

L.1.4 Cracked Section Analysis

Force equilibrium was used to calculate the moment and curvature values after cracking occurred. Once a strain on the surface of the deck or in the prestressing strand was assumed, the depth to the neutral axis was determined which balanced the tension and compression forces. The procedure was identical for the assumed deck strains, ε_{cd} , of 0.001 in/in (Stage 4), 0.002 in/in (Stage 6) and 0.003 in/in (Stage 7). Stage 5 was the point at which the strand was at a strain of 0.01 in/in and began to yield. To approximate the stress distribution for the deck, a Todeschini¹⁵¹ distribution was used since the deck

concrete was a normal weight concrete with less than 6,000 psi compressive strength.

Details of the Todeschini distribution are shown in Figure L.1




Figure L.1 Todeschini Stress Distribution

Once a deck surface strain or prestressing strand strain was selected and an estimate entered for the depth to the neutral axis, c, it was necessary to determine the force in the prestressing strands. After Stage 3, the strain in the bottom strands, ϵ_{s3} , was known. Since there was very little rotation in the girder up to the cracking load, it was assumed that the strain in the top strands at M_{cr} was the effective prestress strain, ϵ_{se} . An "if" statement was used in the spreadsheet to calculate resulting strand forces in the top strands based on the location of the assumed neutral axis relative to the top strands. If the neutral axis fell below the top strands, there would be a reduction in strand strain as calculated below:

$$\varepsilon_{set} = \varepsilon_{se} - \frac{(c - (t_d + TCL))}{c} \varepsilon_{cd} \tag{L.17}$$

If the neutral axis fell above the top strands, there would be an increase in strand strain as calculated below:

$$\varepsilon_{set} = \varepsilon_{se} + \frac{(t_d + TCL - c)}{(t_d + h_{g-nc} - c - BCL)} \varepsilon_{sebi}$$
 (L.18)

The force in the top strands was then calculated using the prestressing strand stress-strain plot described in Chapter 8. The strain in the bottom strands was calculated using the following equations:

$$\varepsilon_{seb} = \frac{(t_d + h_{g-nc} - BCL)}{c} \varepsilon_{cd} + \varepsilon_{se2}$$
 (L.19)

$$\varepsilon_{sebi} = \varepsilon_{seb} - \varepsilon_{se2} \tag{L.20}$$

The force in the bottom strands was then calculated using the prestressing strand tension curve plot seen in Table K.15. The total tension force, F_s , was the sum of the force in the top strands and the force in the bottom strands.

The concrete compression force, F_c, was calculated using the Todeschini technique. Referring to Figure L.1, the compressive force was calculated as below:

$$F_c = f_{avg} W_f c \tag{L.21}$$

Values of "c" were varied until F_c was within 1 kip of F_s .

The resulting moment was calculated using the equation below based on the force in the top and bottom strands.

$$M_{4,5,6} = F_{top}(t_d + TCL - k_2c) + F_{bot}(t_d + h_{g-nc} - BCL - k_2c)$$
 (L.22)

The curvature was calculated using the equation:

$$\phi_{4,5,6,7} = \frac{\varepsilon_{cd}}{c} \tag{L.23}$$

This procedure was used for each of the selected deck strain values. The girder's ultimate moment and curvature values were determined at a deck surface strain of 0.003 in/in.

L.1.5 Experimental Moment-Curvature

The experimental moment and curvature were calculated using the equations below:

$$M_{\rm exp} = M_{DL} + P \frac{(L_1 - a)}{L_1} a \tag{L.24}$$

$$\phi = \frac{\varepsilon_{bot} - \varepsilon_{top}}{h_{g}} \tag{L.25}$$

 M_{DL} is the dead load moment caused by the girder and deck. P is the applied load. L_1 and "a" are the distance between supports and shear span respectively. ϵ_{bot} and ϵ_{top} are the strains at the bottom and top of the composite girder that were calculated from strain readings recorded using LVDTs placed close to the bottom and top of the composite girder assuming a linear strain distribution. Table L.1 lists the L_1 and "a" distances for each girder test.

The predicted plot begins with a negative curvature reflecting the initial upward camber due to prestressing. The moment value also starts above zero in most cases reflecting the initial dead load moment.

Table L.1 Dimensions "a" and L₁ for Girder Tests

Girder Test	Configuration	Shear Span "a"	Support to Support
#	#		Distance L ₁
		(inches)	(inches)
G1A-East, G2A-East	2	61	316
G1A-West, G2A-West	1	90	456
G1A-Center, G2A-Center	7	82	185
G1B-East, G2B-East	5	61	456, 321
G1B-West, G2B-West	3	75	345, 456
G1B-Center, G2B-Center	8	96	210
G1C-East, G2C-East	6	75	369
G1C-West, G2C-West	4	85	504
G1C-Center, G2C-Center	9	120	244

L.2 Deflection

Calculations for deflection at cracking and at ultimate were compared to experimental results. An elastic technique was used to calculate the deflection at cracking and a moment area technique was used for the ultimate deflection. The moment area technique used provided a good estimate but was not an exact solution. Table K.9 provides details on deflection calculations. Table K.2 shows experimental deflections.

L.2.1 Calculations for Deflection at Flexural Cracking

An elastic technique was used to predict the deflection at initial flexural cracking as specified in *Mechanics of Materials*, Gere and Timoshenko.¹²⁴ Table K.9 provides details on elastic deflection calculations. Included in the elastic deflection calculations were components due to both flexure and shear. Figure L.2 provides a diagram of variables used in calculating elastic deflections.




Figure L.2 Diagram Showing Variables for Elastic Deflection Calculations

 P_{cr} was the predicted cracking load. The value of 0.4 E_{cg} was used for the shear modulus, G. The cracking deflection at the point of load application was calculated with the following equations for flexural deflection and shear deflection:

$$\delta_{cr-flex} = \frac{P_{cr}ba}{6E_{cr}I_cL_1} (L_1^2 - b^2 - a^2)$$
 (L.26)

$$\delta_{cr-shear} = R_L \frac{a}{0.4E_{cg} b d_p} \tag{L.27}$$

The total elastic cracking deflection was the sum of the flexural and shear deflections.

L.2.2 Calculations for Ultimate Deflection

A moment area technique was used to calculate deflection at the ultimate condition as described in *Mechanics of Materials*, Gere and Timoshenko. 124 At the ultimate condition, a plastic hinge forms at the point of load application. The length of the plastic hinge was assumed to equal the distance from the surface of the deck to the bottom strands. Over the plastic hinge, the curvature was assumed to be at ϕ_{ult} as described in Section L.1.4. The variables shown in Figure L.2 also apply during the ultimate deflection calculations.

Two different curvature diagrams were required for ultimate deflection calculations. The diagram shown in Figure L.3, the "modified" curvature diagram, applied when distances from the point of loading to a support were small. The hinge

region effectively encompassed the region where a yielding curvature point, ϕ_y , would be considered. Figure L.4, the "normal" curvature diagram, applied when the distances from the point of loading to a support would allow consideration of a yielding curvature point, ϕ_y . The yielding curvature, ϕ_y , was the point at which the prestressing strand first yielded. The curvature value, ϕ_{cr} , was the curvature at initial flexural cracking. The curvature value, ϕ_{ult} was the curvature at ultimate. The calculations in Table K.9 automatically determined the characteristics of the curvature diagram based on the dimensions of the girder test and curvature values. In most cases, the diagram to the left of the load was the modified diagram and to the right of the load was the normal diagram




Figure L.3 "Modified" Curvature Diagram for Ultimate Deflection Calculations




Figure L.4 "Normal" Curvature Diagram for Ultimate Deflection Calculations

The values X_x , CR_x and CP_x , and A_x are referenced in Table K.9 and shown in Figure L.3. The same definitions apply to Figure L.4. The X distances are distances from the left support to the far side of a particular area. The CR values measure the distance from the centroid of an area to the right support. The CP values measure the distance from the centroid of an area to the point of load application.

Figure L.5 shows a diagram describing the calculation of deflections. It is important to emphasize again that the resulting ultimate deflection calculation was a good estimate, but not an exact value.




Figure L.5 Diagram Showing Ultimate Deflection Calculation

The following equations were used to calculate the ultimate deflection, $\Delta P_{\text{ult}} :$

$$\theta_L a = \sum A_x C R_x \frac{a}{L_1} \tag{L.28}$$

$$\Delta_{p\theta} = \sum A_x C P_x \tag{L.29}$$

$$\Delta P_{ult} = \theta_L a - \Delta P_\theta + R_L \frac{a}{0.4 E_{cg} b d_p}$$
 (L.30)

Equation L.30 reflects the deflection component due to shear deformation. The percentage of total deflection due to shear is much less in the ultimate deflection; however, it must be included for accuracy. The value $0.4E_{\rm cg}$ used in the denominator represents the shear modulus, G. If cracking was extreme during a test, this value was reduced to $0.2E_{\rm cg}$ to reflect a reduced shear modulus.

L.2.3 Experimental Deflections

Measurement of experimental deflections was accomplished with a wire potentiometer placed under girder at the point of load application.

L.3 Girder Test G1A-East




Figure L.6 G1A-East Moment vs. Curvature Plot




Figure L.7 G1A-East Load vs. Deflection Plot

L.4 Girder Test G1A-West




Figure L.8 G1A-West Moment vs. Curvature Plot




Figure L.9 G1A-West Load vs. Deflection Plot

L.5 Girder Test G1A-Center




Figure L.10 G1A-Center Moment vs. Curvature Plot




Figure L.11 G1A-Center Load vs. Deflection Plot

L.6 Girder Test G1B-East




Figure L.12 G1B-East Moment vs. Curvature Plot




Figure L.13 G1B-East Load vs. Deflection Plot

L.7 Girder Test G1B-West




Figure L.14 G1B-West Moment vs. Curvature Plot




Figure L.15 G1B-West Load vs. Deflection Plot

L.8 Girder Test G1B-Center




Figure L.16 G1B-Center Moment vs. Curvature Plot




Figure L.17 G1B-Center Load vs. Deflection Plot

L.9 Girder Test G1C-East




Figure L.18 G1C-East Moment vs. Curvature Plot




Figure L.19 G1C-East Load vs. Deflection Plot

L.10 Girder Test G1C-West




Figure L.20 G1C-West Moment vs. Curvature Plot




Figure L.21 G1C-West Load vs. Deflection Plot

L.11 Girder Test G1C-Center




Figure L.22 G1C-Center Moment vs. Curvature Plot




Figure L.23 G1C-Center Load vs. Deflection Plot

L.12 Girder Test G2A-East




Figure L.24 G2A-East Moment vs. Curvature Plot




Figure L.25 G2A-East Load vs. Deflection Plot

L.13 Girder Test G2A-West




Figure L.26 G2A-West Moment vs. Curvature Plot




Figure L.27 G2A-West Load vs. Deflection Plot

L.14 Girder Test G2A-Center




Figure L.28 G2A-Center Moment vs. Curvature Plot




Figure L.29 G2A-Center Load vs. Deflection Plot

L.15 Girder Test G2B-East




Figure L.30 G2B-East Moment vs. Curvature Plot




Figure L.31 G2B-East Load vs. Deflection Plot

L.16 Girder Test G2B-West




Figure L.32 G2B-West Moment vs. Curvature Plot




Figure L.33 G2B-West Load vs. Deflection Plot

L.17 Girder Test G2B-Center




Figure L.34 G2B-Center Moment vs. Curvature Plot




Figure L.35 G2B-Center Load vs. Deflection Plot

L.18 Girder Test G2C-East




Figure L.36 G2C-East Moment vs. Curvature Plot




Figure L.37 G2C-East Load vs. Deflection Plot

L.19 Girder Test G2C-West




Figure L.38 G2C-West Moment vs. Curvature Plot




Figure L.39 G2C-West Load vs. Deflection Plot

L.20 Girder Test G2C-Center




Figure L.40 G2C-Center Moment vs. Curvature Plot




Figure L.41 G2C-Center Load vs. Deflection Plot

APPENDIX M

PHOTOS OF GIRDER CENTER SPAN TESTS

Appendix M contains photos from each center span girder test. Photos of the girder end spans are located in Appendix Q. The photos in this appendix are matched by test configuration. For example, Girder tests G1A-Center and G2A-Center are shown on the same page to allow comparison of test results between the two grades of HSLC.

M.1 Girder Test G1A-Center



Figure M.1 G1A-Center Crack Patterns

M.2 Girder Test G2A-Center



Figure M.2 G2A-Center Crack Patterns

M.3 Girder Test G1B-Center




Figure M.3 G1B-Center Crack Patterns

M.4 Girder Test G2B-Center




Figure M.4 G2B-Center Crack Patterns

M.5 Girder Test G1C-Center




Figure M.5 G1C-Center Crack Patterns

M.6 Girder Test G2C-Center




Figure M.6 G2C-Center Crack Patterns

APPENDIX N

VARIABLE ANGLE TRUSS MODEL PLOTS OF STRAND FORCE AND BOND STRESS

Appendix N contains plots of strand force and bond stress as predicted using the variable angle truss model for girder tests that failed due to shear induced by strand slip. For the girder tests, it was assumed that once the strands were within a distance equal to one stirrup space from the support that only the bottom eight strands carried the strand force.

N.1 Girder Test G1A-East




Figure N.1 G1A-East Strand Force Plot




Figure N.2 G1A-East Bond Stress Plot

N.2 Girder Test G1B-East




Figure N.3 G1B-East Strand Force Plot




Figure N.4 G1B-East Bond Stress Plot

N.3 Girder Test G1C-East




Figure N.5 G1C-East Strand Force Plot




Figure N.6 G1C-East Bond Stress Plot

APPENDIX O

DEVELOPMENT LENGTH DAQ OUTPUT PROCESSING SPREADSHEET

Appendix O contains the individual pages from the Development Length DAQ

Output Processing Spreadsheet. This sheet was used to process the DAQ output from the

12 development length tests. The entire set of worksheet pages is provided from

development length test G1C-W. The pages are listed in the order the calculations occur.

A similar series of worksheets was prepared for each development length test. Listed

below are the individual worksheets within the overall spreadsheet and a brief description

of the worksheet's function.

Table 0.1 – Input Variables – Used to enter information about the development length test. The user enters values in the shaded fields. All other fields are automatic and provide key information about the test. The value for P_{crack} must be determined and entered by the user from the load-displacement curve.

Table O.2 – DAQ Output – A sample of the raw data output from the data acquisition system. Only a small percentage of the total number of DAQ lines is shown.

Table O.3 – Prestressing Strand Tension Test Curve – Used to determine forces and stresses in prestressing strand based on strand strain data.

Table O.4 – Load, Strain, Deflection and Strain Values – Calculates applied load and shear, vertical deflection, and strain values on the top surface of the deck and at bottom strand level. Calculates the position of the neutral axis based on a linear strain distribution assumption.

Table O.5 – Strand Slip – Calculates strand slip values for each strand and the average slip.

Figure O.1 – Load vs. Vertical Displacement Plot

Figure O.2 – Applied Shear vs. Average Strand Slip

Figure O.3 – Load vs. Top of Deck Strain

Figure O.4 – Load vs. Strand Strain – Calculates total strain in strand by adding the strain due to effective prestressing and flexural strain due to load application.

Table O.1 Input Variables




Table O.2 DAQ Output

LIN7	0.000946 0.001041 0.001009 0.000946	0.000946	0.000915	0.000978	0.000915	0.000978	0.000946	0.000946	0.000946	0.000915	0.000978	0.001009	0.000946	0.000946	0.000883	0.001009	0.000883	0.000946	0.000978	0.000946	0.000946	0.000978	0.000978	0.000978	0.000940	0.0000883	0.000078	0.000978	0.001009	0.000915	0.000946	0.000915	0.000883
FIN 6	0.000915 0.000946 0.000978 0.000978	0.001000	0.000852	0.000915	0.000883	0.000915	0.000883	0.000915	0.000946	0.000915	0.000883	0.000915	0.000852	0.000946	0.000883	0.000852	0.000883	0.000978	0.000852	0.000946	0.000852	0.0000915	0.000946	0.000946	0.000978	0.000883	91,000,0	0.000915	0.000852	0.000915	0.000946	0.000852	0.000915
LIN S	0.000946 0.000978 0.000978 0.001072	0.001000	0.000978	0.000946	0.001072	0.000946	0.001072	0.000946	0.001009	0.000978	0.001009	0.000978	0.000946	0.001041	0.000946	0.000978	0.001009	0.000946	0.000946	0.000978	0.000978	0.000883	0.000946	0.001041	0.00000	0.000013	0.00000	0.000978	0.001009	0.001041	0.001009	0.000978	0.000946
LIN 4	0.000883 0.000883 0.000852 0.000915	0.000852	0.000915	0.000852	0.000821	0.000821	0.000821	0.000883	0.000883	0.000883	0.000852	0.000821	0.000821	0.000821	0.000789	0.000821	0.000883	0.000821	0.000852	0.000852	0.000852	0.000821	0.000946	0.000883	0.000621	0.000852	0.00000	0.000032	0.000789	0.000852	0.000821	0.000789	0.000883
LIN 3	0.000915 0.000915 0.000883 0.000978	0.000883	0.000883	0.000852	0.000978	0.000978	0.000883	0.000978	0.000946	0.000915	0.000852	0.000915	0.000915	0.000852	0.000883	0.000883	0.000883	0.000946	0.000946	0.000978	0.000946	0.000852	0.000915	0.000946	0.00000	0.000978	0.00000	0.000346	0.000946	0.000883	0.000978	0.000915	0.000978
LIN 2	0.000915 0.000883 0.001009 0.000978	0.000946	0.000915	0.001009	0.000946	0.000883	0.001009	0.000946	0.000946	0.001009	0.000978	0.000883	0.000946	0.000946	0.000915	0.000946	0.001000	0.000946	0.001041	0.001072	0.000946	0.000915	0.000946	0.001000	0.001000	0.000940	0.000013	0.000938	0.001009	0.000978	0.000978	0.000915	0.000946
LPN 1	0.001449 0.001386 0.001418 0.001512	0.001449	0.001355	0.001386	0.001386	0.001386	0.001386	0.001386	0.001449	0.001386	0.001418	0.001418	0.001386	0.001449	0.001481	0.001355	0.001386	0.001323	0.001418	0.001355	0.001386	0.001386	0.001386	0.001363	0.001232	0.001449	0.001386	0.001360	0.001418	0.001481	0.001418	0.001418	0.001386
CIN 0	0.002204 0.002267 0.002046 0.002172	0.002172	0.002172	0.002204	0.002078	0.002109	0.002015	0.002141	0.002046	0.002046	0.002204	0.002046	0.002046	0.002015	0.002046	0.002109	0.002046	0.002046	0.002078	0.002015	0.002015	0.002078	0.002015	0.002046	10000	0.002013	200000	0.002013	0.001984	0.001984	0.002078	0.002046	0.001984
LVDT 90	-0.001542 -0.001566 -0.001548 -0.001554	-0.001554	-0.00156	-0.001548	-0.001548	-0.001554	-0.001573	-0.001542	-0.001554	-0.001535	-0.001542	-0.001548	-0.001535	-0.001529	-0.00156	-0.001548	-0.001542	-0.001554	-0.001554	-0.001542	-0.001542	-0.001554	0.00156	0.001534	0.001510	0.001348	0.001543	0.001542	-0.001554	-0.00156	-0.001554	-0.001548	-0.001554
LVDT 45	-0.002784 -0.00279 -0.002856 -0.0031	-0.003245	-0.00327	-0.003343	-0.003543	-0.003562	-0.00372	-0.004096	-0.004175	-0.004248	-0.004364	-0.004364	-0.004364	-0.004431	-0.004491	-0.004577	-0.004583	-0.004577	-0.004589	-0.004589	-0.004577	-0.004589	-0.00457/	0.00457	1754000	0.00437	0.004557	-0.00457	-0.00457	-0.00457	-0.004564	-0.004546	-0.004552
LVDT 0	-0.00249 -0.002496 -0.002484 -0.002486	-0.002477	-0.002484	-0.002471	-0.002465	-0.002496	-0.002459	-0.002399	-0.002405	-0.002393	-0.002375	-0.002381	-0.002363	-0.002357	-0.002357	-0.00232	-0.002332	-0.002314	-0.002332	-0.00235	-0.002338	-0.002332	0.002326	0.000222	0.00033	0.002320	0.00226	-0.002344	-0.002344	-0.00235	-0.002344	-0.002332	-0.002296
Wire Pot	2.465919 2.461571 2.455239 2.433496	2.415492	2.415569	2.396878	2.392224	2.392148	2.368269	2.349273	2.340576	2.332566	2.326692	2.326615	2.326615	2.321809	2.313188	2.308458	2.308382	2.308382	2.308458	2.308535	2.308306	2.308229	7.50852	2.308333	2000000	2 308306	2 308458	2.308382	2.308382	2.308535	2.308382	2.308382	2.308535
LVDT Bot	-0.001137 -0.001176 -0.00129 -0.001888	-0.00232	-0.00232	-0.002524	-0.003109	-0.003121	-0.003808	-0.004393	-0.004635	-0.0048	-0.005105	-0.005105	-0.005131	-0.005334	-0.005474	-0.005652	-0.00569	-0.005652	-0.005716	-0.005678	-0.005703	-0.005716	-0.00565	0.002002	500000	0.002003	0.005665	-0.005665	-0.005601	-0.005678	-0.005652	-0.005665	-0.005652
12:07 PM LVDT Top LVDT Bot	-0.00048 -0.00056 -0.000659 -0.000462	0.000148	0.000173	0.0001055	0.001227	0.00127	0.001424	0.002632	0.003138	0.003428	0.003797	0.003841	0.003834	0.004118	0.004291	0.004475	0.004728	0.004549	0.004697	0.004636	0.004697	0.004586	0.00463	0.00458	204500	0.004539	0.004691	0.00458	0.00458	0.004389	0.004482	0.004531	0.004475
11/02/2001 Load Cell	11.442372 13.463793 16.630684 27.815872	35.0256	34.789768	39.256693	48.872326	48.653339	55.509319	71.697525	75.369766	78.907257	83.1017	82.832176	82.663727	86.20121	89.233345	92.753983	92.551834	92.383385	92.248627	92.181244	92.063324	91.945412	91.8/8029	91.7938	01 501267	91 541122	01 507420	91.440056	91.372681	91.30529	91.288452	91.187378	91.120003

Table O.3 Prestressing Strand Tension Curve




Table O.4 Load, Shear, Deflection and Strain Values

				-	OF CIP	Pod	l doite	nd Ctrain Valu	301		
				7	oau, out	iai, Dell	בכנותו ש	Loau, Shear, Denection and Strain Values			
Data			At	t Point of Loading				Neutral Axis	Adjuste	Adjusted Values (Linear Assumption)	ımption)
Point #	Load	Shear	Top LVDT (Inches)	Top Strain (m-strain)	Bot LVDT (Inches)	Bot Strain (m-strain)	Vertical Deflection	Location	Top of Slab	At Level of Bottom Strands	Total Strand Strain
:	(Kips)	(Kips)	7(ssion e = (-)	Tension C = (+)	e = (+)	(Inches)	(Inches from Bot)	(in/in)	(m-strain)	(percent strain)
6	0.0	0.0	0.000000	0.00	0.000000	0.00	0.000000	NA	0.00	00.0	0.505
-	2.0	1.7	-0.000080	3.33	-0.000039	1.63	0.004348	17.38	0.00000	1.63	0.505
7	5.2	4.3	-0.000179	7.46	-0.000153	6.38	0.010680	23.22	-0.00001	6.38	0.506
3	16.4	13.6	0.000018	-0.75	-0.000751	31.29	0.032423	45.85	0.0000	31.29	0.508
4	23.6	9.61	0.000628	-26.17	-0.001183	49.29	0.050427	31.66	0.00003	49.29	0.510
5	23.3	19.4	0.000653	-27.21	-0.001183	49.29	0.050350	31.27	0.00003	49.29	0.510
۰	27.8	23.1	0.000937	-39.04	-0.001387	57.79	0.055157	29.19	0.00004	57.79	0.511
7	34.1	28.3	0.001535	-63.96	-0.001768	73.67	0.069041	26.49	0.00007	73.67	0.513
∞	37.4	31.1	0.001707	-71.13	-0.001972	82.17	0.073695	26.52	0.00007	82.17	0.514
6	37.2	30.9	0.001750	-72.92	-0.001984	82.67	0.073771	26.31	0.00008	82.67	0.514
21	44.1	36.6	0.001904	-79.33	-0.002404	100.17	0.088266	27.48	0.00008	100.17	0.515
=	49.9	41.5	0.002539	-105.79	-0.002671	111.29	0.097650	25.49	0.00011	111.29	0.516
12	60.3	50.1	0.003112	-129.67	-0.003256	135.67	0.116646	25.43	0.00014	135.67	0.519
2	63.9	53.1	0.003618	-150.75	-0.003498	145.75	0.125343	24.57	0.00016	145.75	0.520
14	67.5	56.1	0.003908	-162.83	-0.003663	152.63	0.133353	24.23	0.00017	152.63	0.521
15	71.7	59.6	0.004277	-178.21	896£00′0-	165.33	0.139227	24.12	0.00019	165.33	0.522
16	71.4	59.3	0.004321	-180.04	896600.0-	165.33	0.139304	24.00	0.00019	165.33	0.522
17	71.2	59.2	0.004314	-179.75	-0.003994	166.42	0.139304	24.09	0.00019	166.42	0.522
22	74.8	62.2	0.004598	-191.58	-0.004197	174.88	0.144110	23.94	0.00020	174.88	0.523
19	77.8	64.7	0.004771	-198.79	-0.004337	180.71	0.152731	23.89	0.00021	180.71	0.523
70	81.3	9.79	0.004955	-206.46	-0.004515	188.13	0.157461	23.92	0.00022	188.13	0.524
21	81.1	67.4	0.005208	-217.00	-0.004553	189.71	0.157537	23.47	0.00023	189.71	0.524
22	80.9	67.3	0.005029	-209.54	-0.004515	188.13	0.157537	23.76	0.00022	188.13	0.524
23	80.8	67.2	0.005177	-215.71	-0.004579	190.79	0.157461	23.59	0.00022	190.79	0.524
42	80.7	67.1	0.005116	-213.17	-0.004541	189.21	0.157384	23.63	0.00022	189.21	0.524
25	90.8	67.0	0.005177	-215.71	-0.004566	190.25	0.157613	23.56	0.00022	190.25	0.524
26	80.5	6.99	0.005066	-211.08	-0.004579	190.79	0.157690	23.83	0.00022	190.79	0.524
27	80.4	6.99	0.005110	-212.92	-0.004553	189.71	0.157537	23.67	0.00022	189.71	0.524
78	80.4	8.99	0.005060	-210.83	-0.004528	188.67	0.157384	23.72	0.00022	188.67	0.524
29	80.3	2.99	0.005110	-212.92	-0.004528	188.67	0.157461	23.61	0.00022	188.67	0.524
æ	80.1	9.99	0.005079	-211.63	-0.004528	188.67	0.157613	23.68	0.00022	188.67	0.524
31	80.1	9.99	0.005227	-217.79	-0.004503	187.63	0.157613	23.31	0.00023	187.63	0.524
32	80.1	9.99	0.005171	-215.46	-0.004528	188.67	0.157461	23.48	0.00022	188.67	0.524
33	80.0	66.5	0.005060	-210.83	-0.004528	188.67	0.157537	23.72	0.00022	188.67	0.524
34	79.9	66.4	0.005060	-210.83	-0.004464	186.00	0.157537	23.56	0.00022	186.00	0.524

Table O.5 Strand Slip

						_				
				St	Strand Slip					
Data	Applied				Str	Strand Slip Indicators	tors			
Point	Shear	LIN 0	LIN 1	LIN 2	FIN 3	LIN4	LINS	PIN 6	LIN 7	Avg Slip
#	(kips)	(Inches)	(Inches)	(Inches)	(Inches)	(Inches)	(Inches)	(Inches)	(Inches)	(Inches)
0	0.0	0.00000	0.000000	0.000000	0.000000	0.00000	0.000000	0.000000	0.000000	0.000000
	1.7	0.000063	-0.000063	-0.000032	0.000000	0.00000	0.000032	0.000031	0.000095	0.000016
2	4.3	-0.000158	-0.000031	0.000094	-0.000032	-0.000031	0.000032	0.000063	0.000063	0.000000
3	13.6	-0.000032	0.000063	0.000063	0.000063	0.000032	0.000126	0.000063	0.000000	0.000047
4	19.6	-0.000032	0.000000	0.000031	-0.000032	-0.000031	0.000063	0.000094	0.00000	0.000012
5	19.4	-0.000032	-0.000094	0.00000	-0.000032	0.000032	0.000032	-0.000063	-0.000031	-0.000024
9	23.1	0.000000	-0.000063	0.000094	-0.000063	-0.000031	0.000000	0.000000	0.000032	-0.000004
7	28.3	-0.000158	0.000032	0.000094	-0.000063	-0.000094	0.000063	0.000000	0.000032	-0.000012
œ	31.1	-0.000126	-0.000063	0.000031	0.000063	-0.000062	0.000126	-0.000032	-0.000031	-0.000012
6	30.9	-0.000095	-0.000063	-0.000032	0.000063	-0.000062	0.000000	0.000000	0.000032	-0.000020
10	36.6	-0.000189	-0.000063	0.000063	-0.000032	-0.000062	0.000126	-0.000032	0.00000	-0.000024
11	41.5	0.000000	-0.000063	0.000094	-0.000032	-0.000188	0.000032	-0.000032	0.000032	-0.000020
12	50.1	-0.000063	-0.000063	0.000031	0.000063	0.00000	0.000000	0.000000	0.00000	-0.000004
13	53.1	-0.000158	0.000000	0.000031	0.000031	0.00000	0.000063	0.000031	0.000000	0.00000
14	56.1	-0.000158	-0.000063	0.000094	0.000000	0.00000	0.000032	0.000000	-0.000031	-0.000016
15	59.6	0.000000	-0.000031	0.000063	-0.000063	-0.000031	0.000063	-0.000032	0.000032	0.000000
16	59.3	-0.000158	-0.000031	-0.000032	0.00000	-0.000062	0.000032	0.000000	0.000063	-0.000024
17	59.2	-0.000158	-0.000063	0.000031	0.00000	-0.000062	0.000000	-0.000063	0.000000	-0.000039
18	62.2	-0.000189	0.00000	0.000031	-0.000063	-0.000062	0.000095	0.000031	0.00000	-0.000020
19	64.7	-0.000158	0.000032	0.00000	-0.000032	-0.000094	0.00000	-0.000032	-0.000063	-0.000043
20	9.79	-0.000095	-0.000094	0.000031	-0.000032	-0.000062	0.000032	-0.000063	0.000063	-0.000028
21	67.4	-0.000158	-0.000063	0.000094	-0.000032	0.00000	0.000063	-0.000032	-0.000063	-0.000024
22	67.3	-0.000158	-0.000126	0.000031	0.000031	-0.000062	0.00000	0.000063	0.00000	-0.000028
23	67.2	-0.000126	-0.000031	0.000126	0.000031	-0.000031	0.00000	-0.000063	0.000032	-0.000008
24	67.1	-0.000189	-0.000094	0.000157	0.000063	-0.000031	0.000032	0.000031	0.00000	-0.00004
25	0.79	-0.000189	-0.000063	0.000031	0.000031	-0.000031	0.000032	-0.000063	0.00000	-0.000032
26	6.99	-0.000126	-0.000063	0.00000	-0.000063	-0.000062	-0.000063	0.00000	0.000032	-0.000043
27	6.99	-0.000189	-0.000063	0.000031	0.00000	0.000063	0.00000	0.000031	0.000032	-0.000012
28	8.99	-0.000158	-0.000126	0.000094	0.000031	0.000000	0.000095	0.000031	0.000032	0.00000
29	2.99	-0.000220	-0.000157	0.000094	-0.000032	-0.000062	0.00000	0.000063	0.00000	-0.000039
30	9.99	-0.000189	0.00000	0.000031	0.000063	-0.000031	-0.000031	-0.000032	-0.000063	-0.000032
31	9.99	-0.000252	0.00000	0.00000	-0.000032	-0.000031	0.000032	0.000031	0.000032	-0.000028
32	9.99	-0.000189	-0.000063	-0.000032	0.000031	-0.000031	0.000032	0.00000.0	0.000032	-0.000028
33	66.5	-0.000220	-0.000094	0.000063	0.000031	-0.000031	-0.000063	0.00000	-0.000031	-0.000043
34	66.4	-0.000220	-0.000031	0.000094	0.000031	-0.000094	0.000063	-0.000063	0.000063	-0.000020
35	66.4	-0.000220	0.000032	0.000063	-0.000032	-0.000031	0.000095	0.00000	-0.000031	-0.000016




Figure O.1 Load vs. Vertical Deflection Plot for Girder Test G1C-West




Figure O.2 Applied Shear vs. Average Strand Slip for Girder Test G1C-West




Figure O.3 Load vs. Top of Deck Strain for Girder Test G1C-West




Figure O.4 Load vs. Total Strand Strain for Girder Test G1C-West

APPENDIX P

DEVELOPMENT LENGTH CSS DATA PROCESSING SPREADSHEET

Appendix P contains the individual pages from the Development Length CSS

Data Processing Spreadsheet. This sheet was used to process the CSS data collected

before and during the 12 development length tests. The entire set of worksheet pages is

provided from development length test G1C-West. The pages are listed in the order the

calculations occur. A similar series of worksheets was prepared for each development

length test. Listed below are the individual worksheets within the overall spreadsheet and

a brief description of the worksheet's function.

Table P.1 – Girder Information Sheet – Used to enter information about the girder end being tested. The diagram depicts both sides of the girder end being tested. The user enters values in the shaded boxes. The program automatically calculates the values that are displayed in unshaded boxes.

Table P.2, Table P.3 – Initial Readings (Release and Testing) and 14-Day Readings – Used to enter CSS readings just before strand release, 14 days after strand release, and just prior to testing. Table P.2 is for the North side of the girder; Table P.3 is for the South side.

Table P.4, Table P.5 – CSS Data Taken During Development Length Test – Used to record CSS data during the development length test. Table P.4 is for the North side of the girder; Table P.5 is for the South side of the girder.

Table P.6, Table P.7 – Calculated Raw Strains - Table P.6 is for the North side of the girder; Table P.7 is for the South side of the girder.

Table P.8 - Average Raw Strains - Averages raw strains from Tables P.6 and P.7.

Table P.9 – Smoothed Strains – Calculates a three point floating average of the average raw strain values from Table P.8.

Table P.10 – Strand Stress Values Based on Smoothed CSS Values – Calculates the total strand strain based on the smoothed CSS values from Table P.9 and the initial strand strain due to the effective prestress.

Figure P.1 – Plot of Strand Stress vs. Distance from Girder End – Plots stress in the strand at the following stress levels:

- When the strand stress is at effective prestress.
- When the strand stress at the point of loading is approximately at yield stress.
- When the strand stress at the point of loading is at ultimate stress.
- The ultimate stress the strand reaches at the point of loading

The plot also indicates locations where shear cracking passed through bottom layer of strands.

Table P.11 – Smoothed CSS Data for Tracking Effect of Surface Cracking – Lists pure CSS data for tracking the effect of shear cracking.

Table P.12 – Plot of CSS with Information About Crack Formation – The user enters data into the shaded fields reference the location of shear cracks in or near the transfer length region at the level of the bottom strands. The plot indicates CSS data at key applied shear levels that coincide with the formation of shear cracks. Also depicted in the plot is the transfer length, and the location of cracks.

Table P.13 – Prestressing Strand Tension Curve – Used to determine forces and stresses in prestressing strand based on strand strain data.

Table P.1 Girder Information Sheet

	Top - R 11	20				-	147.6 ksi	264.4 ksi		32.2 trins		. 57.7 kips		Gage Lgth	N	ſ		_ > Z	-	1
ots		Bot - R	< Elevation (IN)>	Lgth	8:00 8:00	8.01	8.00	8.00	7.97	7.93		8.00 F	8.03		8.00	8.00			8.02]]
gth Plo	WM			3ot - R Init	32-17	98	4	13	-331	-659	-527	36	276 8	Н	+	-11-	+-	-	_	45.98
ment Len	6	6		1 1	2.99 43.48 2.99 41.48	2.99 39.48	+	⊢	2.98 31.48	1	\vdash	2.96 21.52	2.96 19.52	Н	\dashv	2.95 13.51	+-	┥	2.94 5.50	Length =>
Girder Information for Development Length Plots	1 Top-C	1 Bot-C	d to 1st Gage (IN)	Based on Readings	Girder Testing	Les Child Services	T	107	(II)		ne) ===================================	care spreadsneer	ips)		2008	readsheet	(n) (v) (n)			100 TO 10
Girder Informa	Top - C 9	Bot-C 9	—— Distance from Beam End to 1st Gage (IN)	Initial Gage Lengths are Based on Readings	Taken Just Prior to Girder Testing	Date of Strond Dolonco	Date of Girder End Test	Age at Testing (Days)	14-Day Transfer Leth (in)		Strand Initial Strain (me)	From Fresuess Force Care Spreadsneet	Load at ~1% Strain (kips)	Ultimate Load (kips)	Ultimate CSS (me)	From DAQ Spreadsheet	Embedment Length (in)	Shear Span "a" (in)	Supt to Supt Dist. (in)	Strand Area (in-)
				tot - L Init	6 154 8.02 5 -263 7.97	4 -248 7.98	1 <u>8</u>	-111	7 7	-401	-188	7 -200 7.98	151	1 -180 7.98	-241	0 -213 7.98	-548	-307	5 -192	€
		, 20	(II)	H	3.12 4.76 3.12 6.75	3.11 8.74	+	₩	3.10 16.74	1	\vdash	3.09 26.71	╌	Н	-	3.08 34.70	-	-	3.07 42.65	Length =>
GHC-W	1 Top • L 1	1 Bot-L	3425 < Elevation (IN)-											Beam Lgth	48100, FT		7	3	2	

Table P.2 Initial Readings Prior to Testing, Initial Readings Prior to Release and 14 Day Readings (North Side)

Test # 4 Read LEFT to RIGHT	to Release and 14-Day Readings	age on Bar Before Taking Readings	30 Inch Top Right								48 Inch Bottom Right	Test#1 Test#2 Rel#1 Rel#2 14-Dav		に選択している。これに対しては、は、これにはなった。							10000		700	100	THOU T		C1 (0.89)	
Beam Side North	s Just Prior to Testing, Initial Readings Prior to Release and 14-Day Readings	teadings - Gage Length is 8" on DEMEC Gage Reader - Zero Gage on Bar Before Taking Readings	26 Inch Top Center	Н	(2) 100 (2) (2) (2) (3) (3) (3) (4) (4) (4) (4) (4) (4) (4) (4) (4) (4	15 0886 1 1 1 0 8 8 8 1 1 1 1 1 1 1 1 1 1 1 1 1				1. THE FEB 18 THE SECTION OF THE SEC	26 Inch Bottom Center	Test # 1 Test # 2		1 (0.886 c) 1 (0.806 c)	30	10 20 10 10 10 10 10 10 10 10 10 10 10 10 10	1 2 (0 o v 4 1 1 v 2 0) v 3 1		*** 10900 1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-				•			1		7
Beam# G1C-W Bea	Initial Readings Just Pr	Notes for Readings - G	30 Inch Top Left								48 Inch Bottom Left																	

Table P.3 Initial Readings Prior to Testing, Initial Readings Prior to Release and 14 Day Readings (South Side)

4 Read LEFT to RIGHT	14-Day Readings	ıking Readings	30 Inch Top Right											48 Inch Bottom Right																					
South Test #	Initial Readings Just Prior to Testing, Initial Readings Prior to Release and 14-Day Readings	eadings - Gage Length is 8" on DEMEC Gage Reader - Zero Gage on Bar Before Taking Readings	26 Inch Top Center	#1 Test#2					21/17		4			26 Inch Bottom Center	#1 Test #2			0000		8 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		8 15 050		6.4.1											
G1C-W Beam Side	Initial Readings Just Prior to	Notes for Readings - Gage Leng	30 Inch Top Left	Test#1			2000	90%	\$40,00884	\$490.	90 %			48 Inch Bottom Left	Rel # 1 Rel # 2 14-Day Test # 1	THE RESERVE OF THE PARTY OF THE		1 1000			2-40000 TEM 0025 TEM 0045 TEM 044						11000					0.0850		Sec. 25	20108 F 20106 6 F C 0.108 F
Beam #			30 L	Test # 1 Test # 2	1. C. 1. C.	0.886	27.00	72 (WGL-21) P. (1488)	0.0		1. (1. (1. (1. (1. (1. (1. (1. (1. (1. (1088			Test #1 Test #2	STATE OF THE PARTY.	2070×	1, 10247	*** 0042*	10010 - 10010 - 10010 - 10010 - 10010 - 10010 - 10010 - 10010 - 10010 - 10010 - 10010 - 10010 - 10010 - 10010	- FT 10 m		0153		8810	0207	* -038 L	0149	1.8110	.0242	*******	as \$700 as	-0570 9760-	-0805-4 (-0900)	$\sim 0.00 - 1.000$

Table P.4 CSS Data Taken During Development Length Testing (North Side)

Beam #				_								_							
	#1	GIC-W	Α-		Side		Ź	North		Te	Test#		4		Read	Read LEFT to RIGHT	RIGH	T	3
			Notes for R		ings - Ga	ge Lengtl	ı is 8" (n DEM	EC Gag	e Reader	- Zero G	nge on B	ır Before	eadings - Gage Length is 8" on DEMEC Gage Reader - Zero Gage on Bar Before Taking Readings	adings				
Reading	-	2	3	4	5	9	H	7	80	6	10	11	12	13	14	15	Ĭ	9	17
Load (K) 1786 12 mit 65	80.68	1000				B75-998				PARTY TO THE PARTY OF THE PARTY	100	300 m	- 100 m	eir i			Ц	H	
Gage #																			
-	2000	Table of the same	1000	1.00	SECTION.	7. 1. to an		100	A SKI	To the last	Part Section	では大き	* (A. C.)	79.9			_	┞	
2	10000			1000			1				17.1	1		3182		L	_	\vdash	
3	1010			a turn		经营业		Tarket I		10.00		10 mm	1	223			L		
4	1000 E	Table 1	1000	1000	TANK THE			0.55 Feb.		To Street		1000	No. of Parties				_	-	
5	10 (M)	161101		97							7.77	での		tyens.		L		-	
9		100	15.0			1		12.00	1000	2000	The second							-	
7	7760	10.4				102			8870									-	
80	10:0	840		87.7	THE CASE		2	500	\$4 DATE:			THE REAL PROPERTY.		390			L		
6	*40660	17.00							9000	1000		4.5	1000	7.48			L		
10	10 SH 64						建县	A 107	207	200		5				L			
11	- 00	#100 ×		To the				20 M	1000		6.11	736	1000	2.3				_	
12	Total S	1866063.			2004	100		1672 R		A 150			000000						
13	0.88	1000		1000				1	100	1000									
14	-6610			20.00				100	100			1000		(185) X				F	
15		TOWNS.		200	1000	100			1000	TO THE				e a		L	L	-	
16	1000054	10000		20063		200		1910	66.0		A COLUMN		9 77	100				-	
17	-6200	-0800	1.0011075	1008	1080	0.0	9	15.5	1020	170		***	0960	24					
18	*1100	040	2019	2012	A COUNTY	202	W. 40	281 = k	40.20 P	. T. C.	10.0		15.70	2.32					
19	-02155	0.226	0.10	10000	303 P	97.0		278	468Z0	1278		1016	100						
20	010	8910	1910	¥0183	900m	100	9	236.+	0530	1020 ·	. ee.	35.0	F0259	24年					

Table P.5 CSS Data Taken During Development Length Testing (South Side)

Beam #	# w	G1C-W	W	S	Side		South		Test#	t#	4			ead LI	Read LEFT to RIGHT	SIGHT	
			Notes for Ro		igs - Gage	cadings - Gage Length is 8" on DEMEC Gage Reader - Zero Gage on Bar Before Taking Readings	8" on DE	MEC Gage	e Reader -	Zero Ga	ge on Bar	Before Ta	king Rea	dings			
Reading	1	2	3	4	5	9	7	8	6	10	11	12	13	14	15	16	17
Load (K)	80	110	140	155	184	215	240	261	276	287	295	296					
Gage#																	Ā
_		TOTAL STREET	NO COLUMN		100 To 10	10000	11.50	56.00	A STATE OF								
7	10.00	-05.50	10.00E		20.00		0.83	.020	1020	1000	1707						
3	10,718	2880.	0570	61.50	0.070	(20.5)	10000	9010E	11.88	-80 (B)	4017	(11)					
4	15600	W 100 T	10000	1000	50105	\$100 kg	2500	2010	30000		1000						
8	\$ 010 G	\$0.00	S (010)	0.00	10184	S (0)	71000	20016	1000	766 S (0)	THE STATE OF	T/31%					
وا	Of IUS	20107	5010		2008 Jac	1,000	**00°	**000°	0.00		1000	* The (1)					
7		1	38010	a de la companya de l	Suga	Call House	£900%		1000m	100	*OAFFEE.	1000					
000		100	1114	40140	00100	SOUTON.	10000	77.00	**************************************	1000	.0156×	5 (169.5)					
6			10804	0880	0390	10850	40380	6/60	# S ()	1000	75705	0.0					
10			-0810	40178	2010 E	8/40	5210	1010	* 01/2	100	Tillet -	1100					
111		0.00	2.5	68175	20102	.68ID	-0180×	12810°	0.8	11 80	4000						
12	A 100 m	100	*89.O	1000	1080	Ter-0	7980	-1980c	-0302		101.68	ACOD					
13	* 13.0	. 010	2 OR4	0.010	010	0.010	700	*5210	0.00	412.08	1910						
14	12100	**************************************	1910	ante.	1910	1010	\$1010E	7510	-0190	THE PARTY	5000	77 1809					
15			94670	1000	8700	0870	1000 mg	-0.27	2070		C-10149	5.02(16)					
16	5	20205	20707	0010	1010T	.7010	**-0184		*-018 t	10 10	P. 1110	1000					
17		2990Hall 2990-2	.0990%	15,90	9,90	1890	1.005	9690	0.000	16502	3851	1393					
18	0500	-6ESOT	10. CH	*0250	4.0531	21640	*£250**		1000 m	80.48	10469	167.0					
19	.0293	::020:	-0202	- 0287	-0288	-0282	SLZ0-+	-0220-	-2610	0155	1010	1115					
	1970 - 1880 - 1079 -	- 0178	* 017.4	- 0T68	-0167	#6910F	5510	12105	-9800-	0044		00.00					

Table P.6 Calculated Raw Strains (North Side)

G1C-W									Ray	v Stra	Raw Strains - North Side	orth S	ide							
48									CSS	Reading	CSS Reading (microstrains)	ains)								
Gage	Tra	Transfer Length	ngth								Develo	Development Length	ength							
Point	Rel	14-Day	Test	-	2	3	4	5	9	7	8	6	10	11	12	13	14	15	16	17
Load	0	0	0	08	110	140	155	184	215	240	261	276	287	295	796	0	0	0	0	0
1	0	1175	1507	194	194	231	698	381	469	955	776	1769	2469	2694	3057					
7	0	1175	1456	219	231	294	381	469	695	899	1056	1881	2693	2830	3043					
3	0	943	1299	219	243	798	368	418	518	581	1130	2042	2966	3153	3515					
4	0	1069	1432	175	188	213	313	388	488	550	713	1013	1500	1600	1688					
3	0	666	1274	187	175	237	275	362	425	487	700	800	1049	1049	775			_		
9	0	694	1194	200	250	275	337	425	200	295	700	875	1450	1662	1700					
7	0	1067	1400	207	207	220	320	383	408	483	533	496	973	1462	1789					
œ	0	1080	1400	182	107	220	295	333	358	446	496	496	1036	1965	10894					
6	0	1273	1620	158	208	208	296	372	359	410	485	460	1002	1909	11211					
10	0	1026	1353	138	164	189	277	352	340	440	466	528	617	1208	10532					
11	0	788	1232	156	194	194	281	394	381	456	909	929	594	844	10110					
12	0	950	1143	691	169	181	244	356	369	394	444	519	444	431	899					
13	0	884	1059	149	187	224	336	461	436	498	573	869	2952	5568	6054					
14	0	736	298	143	143	118	218	330	368	405	443	555	3087	2962	6553					
15	0	464	738	119	106	9	901	231	344	1132	1832	2583	5247	8586	9024					
16	0	425	838	138	213	138	175	200	388	1088	1750	2513	5288	8589	6806					
17	0	287	668	112	125	100	162	200	412	1062	1711	2410	2897	3547	3622					
18	0	611	868	62	50	12	237	537	1048	1809	2533	3369	3594	4218	3968					
19	0	655	673	131	268	811	305	605	1004	916	1054	1166	1315	1390	1365					
70	0	150	774	175	137	162	362	199	948	1023	1060	1198	1223	1260	1310					
	Ŝ	Compression +	+ u								I	Tension +								

Table P.7 Calculated Raw Strains (South Side)

G1C-W	W-								Ra	Raw Strains - South Side	ins - S	outh S	ide							
48"									CSS	CSS Reading (microstrains)	(microst	rains)								
Gage	Tra	Transfer Length	ıgth								Develo	l۳	Length							
Point	Rel	14-Day	Test	1	7	3	4	5	9	7	8	6	10	11	12	13	14	15	16	17
Load	0	0	0	80	110	140	155	184	215	240	261	276	287	295	296	0	0	0	٥	0
1	0	-561	-674	175	137	791	362	199	846	1023	1060	8611	1223	1260	1310					
2	0	702	068	113	163	707	451	564	564	640	702	062	890	916	996					
3	0	451	969	9-	132	94	445	520	533	965	646	746	871	934	947					
4	0	175	1126	88	63	22	100	213	896	1463	9261	2601	4940	5403	5390					
S	0	574	874	75	62	25	100	674	1411	2047	2697	3296	5730	5630	5543					
9	0	928	1170	-13	50	75	150	751	1477	2115	2866	3918	6647	8837	9013					
7	0	832	1120	63	75	20	125	764	1540	2191	2904	3918	6672	9200	9363					
∞	0	856	1252	106	106	141	169	570	569	820	1046	1346	1860	3901	4064					
6	0	704	1106	75	88	88	151	138	151	201	276	528	8/9	3467	3731					
10	0	1065	1410	94	94	94	182	901	119	157	781	194	157	232	219				1	
111	0	952	1385	157	132	132	202	691	207	320	232	569	583	2137	7726					
12	0	1262	1608	69	107	144	182	82	82	121	121	182	546	2531	8647					
13	0	1085	1273	162	150	162	237	125	299	287	566	274	711	2645	12514					
14	0	1485	1798	113	150	163	238	213	238	238	326	376	805	5869	12704				i .	
15	0	969	1078	107	94	611	691	157	132	244	691	445	608	1147	8655					
16	0	1601	1410	88	100	138	288	238	263	363	514	752	596	066	4725					
17	0	208	1166	95	120	158	233	208	221	122	460	799	952	1103	226					
18	0	673	994	94	107	132	220	208	208	308	447	673	875	1064	1466					
19	0	1318	1619	176	176	188	251	238	314	402	626	1443	1907	2133	2409					
20	0	681	1065	138	175	213	301	313	338	464	890	1328	1854	2118	2531					
	COI	Compression +	+ 1									Tension +								

Table P.8 Average Raw Strains

G1C-W	≱					Av	erage	of Nor	th and	Sout	h Data	(Froi	n Nor	th Per	Average of North and South Data (From North Perspective)	é				
48									CSS	CSS Reading (microstrains)	microsti	rains)				$\ $				bracklet
Gage	Tra	Transfer Length	lgth								Develo	Development Length	ength							
Point	Rel	14-Day	Test	1	7	3	7	5	9	7	∞	6	10	F	12	13	14	15	91	17
Load	0	0	0	08	110	140	155	184	215	240	261	276	287	295	296	0	0	0	0	0
1	0	786	1286	166	185	222	335	347	404	510	617	1549	2912	2406	2794					
2	0	1246	1537	161	203	241	316	353	441	535	1017	1662	2300	2482	2726					
3	0	808	1146	156	175	200	294	313	363	444	788	1357	1920	2108	2491					
4	0	938	1299	135	154	185	273	298	354	411	989	837	1226	1352	1332					
2	0	1048	1342	138	138	188	282	300	344	425	209	922	1007	1020	2750					
9	0	569	1136	153	172	197	253	291	316	403	435	099	1129	1405	3649					
7	0	1276	1599	160	6/1	161	279	298	323	361	430	436	887	2166	7246					
«	0	1083	1336	172	128	161	566	229	329	366	398	385	874	2305	11704					
6	0	1268	1614	113	157	176	239	227	220	283	321	321	774	2220	9929					
10	0	686	1369	148	148	160	242	261	273	380	349	399	009	1672	9129					
11	0	926	1321	125	144	144	232	250	250	307	344	375	375	538	5165					
12	0	827	1124	122	128	135	161	247	760	297	360	523	561	1949	2200					
13	0	921	1156	128	147	184	253	\$18	999	629	608	1022	2406	4735	5059					
14	0	784	994	103	109	84	172	247	954	1298	1673	2236	4879	7584	8562					
15	0	726	954	53	78	41	128	491	911	1624	2349	3250	5947	8712	8106					
16	0	200	856	106	137	81	137	437	668	1568	2223	2904	5509	7110	7316					
17	0	681	1012	100	94	87	131	506	889	1262	1844	2506	3919	4475	4506					
18	0	531	797	28	91	53	341	528	791	1203	1589	2058	2233	2576	2457					
19	0	829	931	122	216	160	378	585	784	778	878	8/6	1103	1153	1165					
20	0	-206	50	175	137	162	362	199	948	1023	0901	1198	1223	1260	1310					
	ပိ	Compression +	+								1	Tension +								

Table P.9 Smoothed Strains

5	G1C-W					S	mootl	ed A	verag	e Plot	Smoothed Average Plot Data From the SOUTH Perspective	Fron	n the	SOL)TH	Persp	ective	63				
48"	Distance									Strain	Strain Readings (microstrains)	ngs (mi	crostra	ns)								
Gage	From	L	Transfer Lgth CSS	P CSS					Dev	elopmer	Development Length Test CSS + Initial Strand Strain Due to Pretensioning	h Test	CSS + 1	nitial St	trand St	rain Du	ie to Pri	etension	ing			
Point	End	Rel	Rel 14-Day	Test	Strand	-	7	3	4	2	9	7	8	6	10	11	12	13	14	15	16	17
Load	(inches)	-	0	0	Initial	08	110	140	155	184	215	240	261	276	287	295	296	0	0	0	0	0
٥	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0					
7	7.13	0	335	593	1675	1783	1823	1800	2035	5266	2516	2676	2851	3086	3194	3338	3319					
3	9.13	0	630	914	2145	2228	2278	2245	2429	2585	2899	3226	3582	3992	4563	4880	4855					
4	11.13	0	571	888	2615	2693	2723	2689	2819	3006	3408	3959	4501	5105	6502	7335	7375					
2	13.13	0	989	941	3086	3172	3189	3156	3218	3464	3918	4570	5225	5973	8211	9851	10033					
9	15.13	0	0/9	934	3556	3643	3664	3624	3701	4047	4477	5052	5638	6353	9001	11357	11653					
7	17.13	0	810	1034	4025	4120	4136	4128	4209	4543	4835	5219	5636	6195	8436	11035	11370					
∞	19.13	0	844	1001	4495	4613	4623	4630	4702	4932	5088	5247	5443	5756	7111	9251	8956					
6	21.13	0	891	1200	4965	2090	5105	5119	5192	5302	5323	5386	5469	5095	6009	7372	9106					
2	23.12	0	914	1271	5053	5185	5193	5199	5277	5306	5314	5381	5404	5485	5565	6439	10551					
=	25.12	0	1061	1434	5053	5182	5203	5213	5290	5299	5301	5376	5391	5418	5636	6530	13127					
12	27.11	0	1113	1440	5053	5197	5197	5229	5302	5292	5327	5396	5409	5421	5802	7119	15307					
13	29.10	0	1209	1516	5053	5201	5208	5239	5314	5304	5344	5390	5436	5434	5898	7283	14679					
14	31.10	0	1018	1357	5053	5215	5213	5246	5319	5326	5375	-	5474	5547	6016	7011	12586					
15	33.09	0	1006	1359	5053	5203	5216	5245	5324	5349	5381	5449	5543	5677	6061	6583	9601					
9	35.09	٥	894	1259	5053	5195	5207	5243	5322	5349	5391	-	5596	5811	6174	6312	7630					
17	37.08	0	931	1262	5053	9615	5208	5244	5336	5357	5407	5480	5714	6043	6437	6546	7244					
18	39.07	0	266	1327	5053	5216	5230	5262	5347	5374	5439	5516	5850	6339	8989	7034	7236					
19	41.07	0	1012	1323	5053	5226	5241	5274	5368	5391	5456	5549	5961	6576	7180	7385	7723		1			
70	43.07	0																				
		ರ	Compression +	+ uo				ř					Tension +	+ u.								

Table P.10 Strand Stress Values Based on Smoothed CSS Values

GI	G1C-W			Sı	Smoothed Average Plot Data From	d Aver	age Plo	t Data	From	os	TH	SOUTH Perspective	ctive					
48"	Distance																	
Gage	From					Str	ess in Str.	and due to	Stress in Strand due to Effective Prestress and Load Applied to Girder	e Prestre	s and Lo	ad Applic	ed to Gird	er				
Point	End	1	2	3	4	5	9	7	8	6	10	11	12	13	14	15	16	17
Load	(inches)	80	110	140	155	184	215	240	261	276	287	295	596	0	0	0	0	0
0	0	0	0	0	0	0	0	0	0	0	0	0	0					
2	7.13	52.09	53.25	52.58	59.46	66.21	73.50	78.18	83.28	90.15	93.32	97.51	96.96					
3	9.13	62:09	66.55	65.58	70.94	75.50	84.69	94.24	104.64	116.62	133.30	142.54	141.81					
4	11.13	78.68	79.53	78.56	82.34	87.81	99.55	115.66	131.48	149.12	189.94	213.82	215.02					
S	13.13	92.67	93.16	92.18	94.01	101.19	114.46	133.51	152.62	174.47	235.99	257.63	258.83					
9	15.13	106.42	107.03	105.87	108.12	118.23	130.77	147.58	164.69	185.57	249.16	263.03	263.26					
7	17.13	120.35	120.83	120.59	122.96	132.71	141.24	152.45	164.63	180.96	240.34	262.57	263.04					
∞	19.13	134.75	135.06	135.24	137.37	144.07	148.64	153.27	159.00	168.14	207.72	252.20	255.37					
6	21.13	148.69	149.11	149.54	151.67	154.90	155.51	157.33	159.77	163.73	177.58	214.94	250.50					
10	23.12	151.45	151.70	151.88	154.14	154.99	155.23	157.19	157.86	160.24	162.56	188.11	261.28					
11	25.12	151.37	151.98	152.29	154.55	154.79	154.85	157.05	157.48	158.27	164.64	190.75	264.09					
12	27.11	151.82	151.83	152.74	154.88	154.58	155.62	157.63	158.00	158.37	169.49	207.96	264.89					
13	29.10	151.95	152.13	153.05	155.25	154.94	156.10	157.45	158.79	158.73	172.29	212.21	264.66					
14	31.10	152.33	152.27	153.25	155.38	155.57	157.03	158.62	159.90	162.03	175.75	204.82	263.89					
15	33.09	152.00	152.36	153.22	155.53	156.26	157.18	159.19	161.93	165.83	177.05	192.30	255.67					
16	35.09	151.75	152.12	153.16	155.47	156.26	157.48	159.68	163.46	169.74	180.35	184.38	222.28					
17	37.08	151.78	152.15	153.19	155.87	156.48	157.94	160.08	166.90	176.53	188.05	191.23	210.98					
18	39.07	152.36	152.79	153.71	156.21	157.00	158.89	161.14	170.90	185.16	200.64	205.46	210.72					
19	41.07	152.67	153.09	154.07	156.81	157.48	159.37	162.11	174.12	192.09	208.94	215.32	224.73					
2	43.07																	

G1C-W		Plot Data fo	or Strand Stress vs D	Plot Data for Strand Stress vs Distance from Girder End
	Distance From Girder End (in)	Strain in Strand (me)	Stress in Strand (ksi)	
Girder End	. 0	0	0	Load at ~ 1% Strand St
Transfer Lgth	21.5	5053	147.61	
End of Plot	109.2	5053	147.61	
e _{25-ULT}	16	13960	264.40	

Kips
291
- 1% Strand Strain
at ~




Figure P.1 Plot of Strand Stress vs. Distance From Girder End


Table P.11 Smoothed CSS Data for Tracking Effect of Surface Cracking

5	G1C-W				S	mooth	ed Ave	Smoothed Average Plot Data From the	lot Da	ta Fro	m the	SOUTH	- 11	Perspective	ective		<u>ن</u>	(CSS Only)	3
48.	Distance								Strain 1	Strain Readings (microstrains)	(microst	trains)							
Gage	From								Develo	Development Length Test CSS	angth Tes	t CSS							
Point	End	Strand	1	2	3	4	5	9	7	8	6	10	11	12	13	14	15	16	17
Load	(inches)	Initial	80	110	140	155	184	215	240	261	276	287	295	296	0	0	0	0	0
0	0	0	0	0	0	0	0	0	0	0	0	0	0	1					
7	7.13	0	108	148	125	360	165	841	1001	1176	1411	1519	1663	1644					
3	9.13	0	83	133	100	284	440	754	1081	1437	1847	2418	2735	2710					
4	11.13	0	28	107	74	203	168	792	1344	1885	2489	3887	4720	4760					
S	13.13	0	98	103	20	132	378	832	1485	2139	2887	5125	6765	6947					
9	15.13	0	8.7	801	69	146	492	921	1496	2082	2797	5445	7802	8097					
7	17.13	0	95	1111	103	184	518	810	1194	1611	2170	4411	7010	7345					
∞	19.13	0	118	128	134	207	437	593	752	948	1261	2615	4756	5072					
6	21.13	0	125	140	154	227	338	358	421	504	640	1114	2407	4141					
10	23.12	0	132	140	146	224	253	261	328	351	432	512	1386	5498					
11	25.12	0	129	150	160	237	246	248	323	338	365	583	1477	8074					
12	27.11	0	144	144	176	249	239	274	343	356	368	749	5066	10254					
13	29.10	0	148	155	186	261	251	291	337	383	381	845	2230	9626					
14	31.10	0	162	160	193	566	273	322	377	421	494	963	1958	7533					
15	33.09	0	150	163	192	271	596	328	396	490	624	1008	1530	4548					
16	35.09	0	142	154	190	569	596	338	413	543	758	1121	1259	2577					
17	37.08	0	143	155	161	283	304	354	427	199	066	1384	1493	2191					
18	39.07	0	163	121	500	294	321	386	463	762	1286	1815	1981	2183					
19	41.07	0	173	188	221	315	338	403	496	806	1523	2127	2332	2670					
20	43.07																		
										Tension +	+ u o								
[5	G1C-W						Plottin	Plotting Data for Transfer Length on Crack ID Plot	for Tr	ansfer	Lengt	h on C	rack]	D Plot	_				
		Distanc	Distance From Girder	Girder	Plot														
			End (in)		Data														
Ċ			,	ſ	į														

Table P.12 Plot of CSS with Information About Crack Formation

	10			0	0	Load Step vs Shear	Shear (kips)	29	16	116	129	153	179	200	217	229	239	245	246	0	0	0
Strips	6			0	0	Load Ste	Step	1	2	3	4	5	9	7	8	6	10	11	12	13	14	51
IEC Gage	8			0	0						-	CK CK		153 K	200 K	246 K						
sing DEN	7			0	0						;	X Crack	<u> </u>	V=153 K	→ V=200 K	→ V=246 K						
cks Cros	9		7296	246	0												1		*			
on of Cra	5	1.0	240	200	0														K	•	(e)	
Crack Data - Enter Location of Cracks Crossing DEMEC Gage Strips	4	4 327-5	296	246	0		CSS vs Distance From Girder End					_	~	+					X	30	Distance From Girder End (Inches)	,
Data - En	3	- 28 -	296	246	0		e From G					\	/	-	\				· -		Girder En	
Crack	2	2	1	153	0		s Distanc						مم	+	,					20	ce From (
	1	(1.59)	184	153	0		CSS V							1	`		•		X -	10	Distano	
G1C-W	Crack Number	Distance from Girder End (in)	Load at Which Crack Crosses Strand	Shear at Which Crack Crosses Strand	Plotting Data for Y-Axis				22 12000		Str 10000	шо	((he))	0004	at 2000			0		

Table P.13 Prestressing Strand Tension Curve



APPENDIX Q

PHOTOS AND STRAND STRESS PLOTS FROM DEVELOPMENT LENGTH TESTS

Appendix Q contains a photo and a plot of stress in the prestressing strand from each of the 12 development length tests. The stress increase in the prestressing strand during loading was determined with concrete surface strain (CSS) data taken at the level of the bottom strands over the initial 48 inches of the girder. The CSS data was measured using DEMEC points with an 8-inch gage length; a three gage moving average was used to determine each value. This additional stress due to loading was added to the effective prestress to plot the resulting strand stress. The following items are shown on each plot.

- Effective stress due to prestressing over entire embedment length (dashed line)
- Stress in the strand over the initial 48 inches of the girder when the strand begins to yield at the point of load application (line with diamonds)
- Stress in the strand over the initial 48 inches of the girder when the strand is at ultimate stress at the point of load application (line with triangles)
- Stress in the strand at ultimate load at the point of load application (triangle). The CSS data at the load point was found using an LVDT with a gage length of 24 inches.
- Point of load application indicator (downward arrow along x-axis)

Cracks passing through the level of the bottom strands along the initial 48 inches
of the girder (marked with X along x-axis)

In the tests where the average strand end slip is over 0.01" (G1A-East, G1B-East and G1C-East), the level of stress indicated in the strand indicated is not considered accurate. With slip between the strand and concrete, it is impossible to know with any certainty the level of stress in the strand using CSS data. If the level of average strand end slip is less than 0.01 inches, it is assumed the resulting strand stress plots are reasonable because the affect on strand stress calculations would be less than 0.015 percent. On the plots, cracking in the girder causes the peaks and valleys. The sections correspond with the individual development length tests as follows:

Section Q.1 – Test G1A-East

Section Q.2 – Test G1A-West

Section Q.3 – Test G1B-East

Section Q.4 – Test G1B-West

Section Q.5 – Test G1C-East

Section Q.6 – Test G1C-West

Section Q.7 – Test G2A-East

Section Q.8 – Test G2A-West

Section Q.9 – Test G2B-East

Section Q.10 – Test G2B-West

Section Q.11 – Test G2C-East

Section Q.12 – Test G2C-West

Q.1 Development Length Test G1A-East




Figure Q.1 G1A-East Crack Patterns from Development Length Test




Figure Q.2 G1A-East Strand Stress vs Distance from Girder End

Q.2 Development Length Test G1A-West



Figure Q.3 G1A-West Crack Patterns from Development Length Test




Figure Q.4 G1A-West Strand Stress vs Distance from Girder End

Q.3 Development Length Test G1B-East




Figure Q.5 G1B-East Crack Patterns from Development Length Test




Figure Q.6 G1B-East Strand Stress vs Distance from Girder End

Q.4 Development Length Test G1B-West




Figure Q.7 G1B-West Crack Patterns from Development Length Test




Figure Q.8 G1B-West Strand Stress vs Distance from Girder End

Q.5 Development Length Test G1C-East




Figure Q.9 G1C-East Crack Patterns from Development Length Test




Figure Q.10 G1C-East Strand Stress vs Distance from Girder End

Q.6 Development Length Test G1C-West




Figure Q.11 G1C-West Crack Patterns from Development Length Test




Figure Q.12 G1C-West Strand Stress vs Distance from Girder End

Q.7 Development Length Test G2A-East




Figure Q.13 G2A-East Crack Patterns from Development Length Test




Figure Q.14 G2A-East Strand Stress vs Distance from Girder End

Q.8 Development Length Test G2A-West




Figure Q.15 G2A-West Crack Patterns from Development Length Test




Figure Q.16 G2A-West Strand Stress vs Distance from Girder End

Q.9 Development Length Test G2B-East




Figure Q.17 G2B-East Crack Patterns from Development Length Test




Figure Q.18 G2B-East Strand Stress vs Distance from Girder End

Q.10 Development Length Test G2B-West



Figure Q.19 G2B-West Crack Patterns from Development Length Test




Figure Q.20 G2B-West Strand Stress vs Distance from Girder End

Q.11 Development Length Test G2C-East




Figure Q.21 G2C-East Crack Patterns from Development Length Test




Figure Q.22 G2C-East Strand Stress vs Distance from Girder End

Q.12 Development Length Test G2C-West




Figure Q.23 G2C-West Crack Patterns from Development Length Test




Figure Q.24 G2C-West Strand Stress vs Distance from Girder End

APPENDIX R

SHEAR vs. STRAND SLIP PLOTS AND CSS vs. DISTANCE FROM GIRDER END PLOTS FROM DEVELOPMENT LENGTH TESTS

Appendix R contains a plot comparing the applied shear vs. average strand slip and CSS vs. distance from girder ends for each development length test. For many of the applied shear vs. average strand slip plots, there is no definitive point where strand slip begins. The scatter of data on the graph as the applied shear increased due to variability in the data acquisition system and noise. In most cases, the variability of the data is less than 0.0006 inches, which essentially indicates "zero slip." On the CSS vs. distance from girder end plots, the CSS data were collected after each load step. Only the plots at applied shear levels where cracking occurred through the initial 48 inches of the girder at the lower strand level are shown. The sections correspond with the individual development length tests as follows:

Section R.1 – Test G1A-East

Section R.2 – Test G1A-West

Section R.3 – Test G1B-East

Section R.4 – Test G1B-West

Section R.5 – Test G1C-East

Section R.6 - Test G1C-West

Section R.7 – Test G2A-East

Section R.8 – Test G2A-West

Section R.9 – Test G2B-East

Section R.10 – Test G2B-West

Section R.11 – Test G2C-East

Section R.12- Test G2C-West

R.1 Development Length Test G1A-East





Figure R.1 G1A-East Applied Shear vs. Average Strand Slip



		Shear	Crack 1	Data						
Distance From End (Inches)	5.0	7.0	12.5	20.5	23.5	26.5	34.0	42.0	44.0	47.5
Applied Shear at Cracking (Kips)	169	315	242	339	315	355	339	339	291	355

Figure R.2 G1A-East CSS and Shear Cracking vs. Distance from Girder End

R.2 Development Length Test G1A-West





Figure R.3 G1A-West Applied Shear vs. Average Strand Slip



		Shear (Crack D	ata				
Distance From End (Inches)	5.5	6.5	15.0	38.5	45.0	46.5		
Applied Shear at Cracking (Kips)	177	177	217	228	228	217		

Figure R.4 G1A-West CSS and Shear Cracking vs. Distance from Girder End

R.3 Development Length Test G1B-East





Figure R.5 G1B-East Applied Shear vs. Average Strand Slip



		Shear C	Crack D	ata					
Distance From End (Inches)	8	10.75	12.5	15	19	26	34	42	
Applied Shear at Cracking (Kips)	156	191	208	295	295	295	295	277	

Figure R.6 G1B-East CSS and Shear Cracking vs. Distance from Girder End

R.4 Development Length Test G1B-West





Figure R.7 G1B-West Applied Shear vs. Average Strand Slip



		Shear	Crack 1	Data				
Distance From End (Inches)	5	7.5	12	29	39.5	42.5		
Applied Shear at Cracking (Kips)	243	266	266	286	286	286		

Figure R.8 G1B-West CSS and Shear Cracking vs. Distance from Girder End

R.5 Development Length Test G1C-East





Figure R.9 G1C-East Applied Shear vs. Average Strand Slip



	S	hear C	rack D	ata				
Distance From End (Inches)	9	14	17	20	30	39		
Applied Shear at Cracking (Kips)	147	261	243	261	261	277		

Figure R.10 G1C-East CSS and Shear Cracking vs. Distance from Girder End

R.6 Development Length Test G1C-West





Figure R.11 G1C-West Applied Shear vs. Average Strand Slip



	S	hear C	rack D	ata			 	
Distance From End (Inches)	6.5	15	28	32	37	43		
Applied Shear at Cracking (Kips)	153	153	246	246	200	246		

Figure R.12 G1C-West CSS and Shear Cracking vs. Distance from Girder End

R.7 Development Length Test G2A-East





Figure R.13 G2A-East Applied Shear vs. Average Strand Slip



		Shear	Crack I)ata					
Distance From End (Inches)	7.5	11	14.5	23	34	39.5	46		
Applied Shear at Cracking (Kips)	245	355	343	343	318	318	355		

Figure R.14 G2A-East CSS and Shear Cracking vs. Distance from Girder End

R.8 Development Length Test G2A-West




Figure R.15 G2A-West Applied Shear vs. Average Strand Slip




Figure R.16 G2A-West CSS and Shear Cracking vs. Distance from Girder End

R.9 Development Length Test G2B-East





Figure R.17 G2B-East Applied Shear vs. Average Strand Slip



| Shear Crack Data | | Distance From End (Inches) | 4 | 10 | 13.5 | 30 | 37 | 43.5 | | Applied Shear at Cracking (Kips) | 177 | 225 | 322 | 344 | 299 | 299 | | | |

Figure R.18 G2B-East CSS and Shear Cracking vs. Distance from Girder End

R.10 Development Length Test G2B-West





Figure R.19 G2B-West Applied Shear vs. Average Strand Slip



41.5 Distance From End (Inches) 18.5 Applied Shear at Cracking (Kips)

Figure R.20 G2B-West CSS and Shear Cracking vs. Distance from Girder End

R.11 Development Length Test G2C-East




Figure R.21 G2C-East Applied Shear vs. Average Strand Slip




Figure R.22 G2C-East CSS and Shear Cracking vs. Distance from Girder End

R.12 Development Length Test G2C-West





Figure R.23 G2C-West Applied Shear vs. Average Strand Slip



		Shear (Crack Da	ita			
Distance From End (Inches)	7	12	43.5				
Applied Shear at Cracking (Kips)	156	218	230				

Figure R.24 G2C-West CSS and Shear Cracking vs. Distance from Girder End

APPENDIX S

VWSG AND CONCRETE SURFACE STRAIN DATA FROM DEVELOPMENT LENGTH TESTS

Appendix S contains raw data for each development length test. Prior to a test, values from the vibrating wire strain gage (VWSG) were recorded. During the test, CSS readings were taken at the tested end and at midspan at the level of the top and bottom strands. The sections correspond with the individual development length tests as follows

Section S.1 – Consolidated VWSG Data

Section S.2 – Test G1A-East

Section S.3 – Test G1A-West

Section S.4 – Test G1B-East

Section S.5 - Test G1B-West

Section S.6 – Test G1C-East

Section S.7 – Test G1C-West

Section S.8 – Test G2A-East

Section S.9 – Test G2A-West

Section S.10 – Test G2B-East

Section S.11 - Test G2B-West

Section S.12 – Test G2C-East

Section S.13 – Test G2C-West

S.1 Consolidated Vibrating Wire Strain Gage Data

Table S.1 Vibrating Wire Strain Gage Data From Development Length Tests

Development	Vibrating Wire	Thermistor	Strain in Concrete	Effective Stress
Length	Strain Gage Reading	Reading	At Bottom Strands	In Bottom Strands
Test #				f_{se}
	(Hz)	(ohms)	(microstrains)	(ksi)
G1A-East	774.77	3780	-378.9	153.7
G1A-West	763.93	3131	-343.7	152.3
G1B-East	762.59	3035	-353.8	151.2
G1B-West	754.38	3770	-360.4	149.7
G1C-East	718.33	3410	-359.4	149.0
G1C-West	708.37	3360	-329.2	147.6
G2A-East	836.69	3450	-418.9	175.8
G2A-West	836.12	3450	-387.4	175.7
G2B-East	817.63	3760	-418.6	176.2
G2B-West	813.30	3550	- 393.9	175.6
G2C-East	801.33	Inoperative	-350.8	159.3
G2C-West	797.96	Inoperative	-327.2	158.8

S.2 G1A-East

Table S.2 Raw Concrete Surface Strains Data for Development Length Test G1A-East

Step	1	2	3	4	5	6	7	8	9	10	11	12	13
Load (Kips)	80	120	150	180	210	241	270	300	330	360	390	420	440

1	Gage			•			Jarth O	ida Ce	Ci					
2 94 181 181 206 457 632 995 1145 1183 1370 1733 1996 22 3 113 125 150 150 150 188 163 363 800 1551 2239 3339 4565 58 4 112 137 137 137 150 162 262 2723 1509 2233 3056 3967 52: 5 119 169 169 181 181 181 306 756 1556 2419 3157 4044 536 6 144 207 182 257 282 219 470 933 1773 2600 3427 4354 57: 7 125 125 150 175 175 175 225 213 301 376 426 1340 28: 8 94 219 232 269 282 219 194 320 470 457 1021 1923 288 9 131 181 194 306 331 344 381 419 519 481 1281 2094 30: 10 113 163 188 238 276 263 288 338 363 413 1177 2142 40: 11 187 250 275 337 375 412 400 487 525 575 1312 1625 25: 12 112 162 237 287 350 337 337 412 387 512 787 1062 20: 13 150 163 200 250 225 275 363 388 401 388 601 864 20: 14 44 181 131 257 307 369 407 332 469 619 1608 2196 24: 15 100 201 213 288 326 313 389 426 426 527 1630 2320 232 16 144 169 194 219 257 307 357 407 445 770 620 1509 2211 22: 18 150 187 225 275 312 337 412 425 437 762 1137 1536 199 19 188 175 263 313 363 388 463 550 563 1588 2326 3064 39 20 157 194 244 294 369 407 457 570 607 1521 2248 3199 42: South Side CSS - microstrains 1 125 162 224 287 324 449 486 586 1134 2419 3154 4239 52: 2 87 112 437 475 362 387 450 487 487 525 587 100 10: 3 112 137 187 312 300 375 450 462 487 587 1137 1536 199 9 231 144 131 306 218 393 368 106 343 181 1541 1941 26: 1 125 162 224 287 324 449 486 586 1134 2419 3154 4239 52: 2 87 112 437 475 362 387 450 487 487 525 587 700 10: 3 112 137 187 312 300 375 450 462 487 587 1137 1802 2264 25: 5 87 100 162 175 200 325 387 350 537 774 1861 2398 266 106 106 293 206 293 468 355 480 443 717 1802 2264 25: 1 125 162 525 252 131 334 339 340 393 729 1265 1602 27. 9 231 144 131 306 218 393 368 106 343 181 1541 1941 26: 10 118 118 128 282 260 368 330 380 393 542 1876 2936 376 114 69 44 106 144 131 106 543 399 379 29 1265 1602 27. 9 231 144 131 306 218 393 368 106 343 181 1541 1941 26: 10 118 118 218 268 255 143 193 243 305 342 305 332 499 335 490 3275 381 115 144 231 119 94 231 681 1156 1518 2131 3968 3218 39. 16 13 88 75 138 113 130 63 38 373 387 340		113	113	113	138						1404	1742	2060	2210
3														
4 112 137 137 150 162 262 723 1509 2233 3056 3967 52 5 119 169 169 181 181 181 181 3150 66 144 207 182 257 282 219 470 933 1773 2600 3427 4354 577 7 125 125 150 175 175 175 225 213 301 376 426 1340 288 8 94 219 232 269 282 219 194 320 470 457 1021 1923 288 9 131 181 184 306 331 344 381 419 519 481 1281 2094 30 10 113 163 388 238 236 337 337 412 430 481 1177 121 481														
5 119 169 169 181 181 181 181 306 756 1556 2419 3157 4044 53 6 144 207 182 257 282 219 470 933 1773 2600 3427 4354 57 7 125 125 150 175 175 175 225 213 301 376 426 1340 288 8 94 219 232 269 282 219 194 320 470 457 1021 1923 288 9 131 181 194 306 331 344 381 419 519 481 1281 294 300 10 113 163 188 238 276 263 288 338 363 413 1177 2142 400 11 187 250 275 337 357 <th< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></th<>														
6 144 207 182 257 282 219 470 933 1773 2600 3427 4354 577 7 125 125 150 175 175 175 225 213 301 376 426 1340 28. 8 94 219 232 269 282 219 194 320 470 457 1021 1923 289 9 131 181 194 306 331 344 381 419 519 481 1281 2949 30- 10 113 163 188 238 276 263 288 338 363 413 1177 2142 40- 11 187 250 275 337 375 412 400 487 525 575 1312 162 251 12 112 162 237 287 350 337 <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>														
7 125 125 150 175 175 175 225 213 301 376 426 1340 28 8 94 219 232 269 282 219 194 320 470 457 1021 1923 286 9 131 181 194 306 381 344 381 419 519 481 1281 2094 300 10 113 163 188 238 276 263 288 338 363 413 1177 2142 40 11 187 250 275 337 375 412 400 487 525 575 1312 1625 255 12 112 162 237 287 350 337 337 412 387 512 787 1062 20 13 150 163 200 250 2225 275 3														5369
8 94 219 232 269 282 219 194 320 470 457 1021 1923 288 9 131 181 194 306 331 344 381 419 519 481 1281 2094 30 10 113 163 188 238 276 263 288 338 363 413 1177 2142 400 11 187 250 275 337 375 412 400 487 525 575 1312 1622 25 12 112 162 237 287 350 337 337 412 387 512 787 1062 201 13 150 163 200 250 225 275 363 388 401 388 601 864 200 14 44 181 131 257 307 367 39														5795
9 131 181 194 306 331 344 381 419 519 481 1281 2094 30 10 113 163 188 238 276 263 288 338 363 413 1177 2142 40 11 187 250 275 337 375 412 400 487 525 575 1312 1625 25 12 112 162 237 287 350 337 337 412 387 512 787 1062 203 13 150 163 200 250 225 275 363 388 401 388 601 864 200 14 44 181 131 257 307 369 407 332 469 619 1608 2196 24 15 100 201 213 288 326 313 389 426 426 527 1630 2320 233 16 144 169 194 219 257 307 357 395 407 570 1560 2250 225 17 132 182 207 294 332 357 407 445 470 620 1509 2211 222 18 150 187 225 275 312 337 412 425 437 762 1137 1536 199 19 188 175 263 313 363 388 463 550 563 1588 2326 3064 39 20 157 194 244 294 369 407 457 570 607 1521 2248 3199 422 Gage South Side CSS - microstrains 1 125 162 224 287 324 449 486 586 1134 2419 3154 4239 522 2 87 112 437 475 362 387 450 462 487 587 1137 1400 210 4 138 113 213 275 300 363 438 413 438 663 1777 2403 28 5 87 100 162 175 200 325 387 350 433 343 343 181 1541 1941 262 6 106 106 293 206 293 468 355 480 443 777 486 292 1252 8 9 481 181 231 1378 312 324 349 337 362 699 1322 1572 15 8 94 81 181 231 1378 318 393 368 106 343 181 1541 1941 262 10 118 118 128 268 206 368 330 380 393 729 1265 1602 27 11 18 118 18 18 218 268 206 368 330 380 393 542 1876 2936 321 16 18 69 44 106 144 131 106 543 967 1279 1841 2340 2939 352 15 81 144 231 119 94 231 681 1156 1518 2131 3968 3218 39 16 13 88 75 138 113 113 126 179 56 815 1213 1524 1910 2793 4000 460 14 69 44 106 144 131 106 543 967 1279 1841 2340 2939 352 15 81 144 231 119 94 231 681 1156 1518 2131 3968 3218 39 16 13 88 75 138 113 138 525 1113 1488 2038 2700 3275 388 17 25 212 300 312 287 300 387 357 549 387 350 337 340 387 350 351 358 3218 399 16 13 88 75 138 113 138 525 1113 1488 2038 2700 3275 388 17 25 212 300 312 287 300 387 359 31052 1326 1476 1774 2048 21														
10														2863
11														3044
12														4045
13														2500
14														2087
15														2003
16														2459
17														2382
18 150 187 225 275 312 337 412 425 437 762 1137 1536 199 19 188 175 263 313 363 388 463 550 563 1588 2326 3064 39 20 157 194 244 294 369 407 457 570 607 1521 2248 3199 422 Gage South Side CSS - microstrains 1 125 162 224 287 324 449 486 586 1134 2419 3154 4239 525 2 87 112 437 475 362 387 450 487 487 525 587 700 102 3 112 137 187 312 300 375 450 462 487 587 1137 1400 216 4 138 11														2287
19														2298
20 157 194 244 294 369 407 457 570 607 1521 2248 3199 42 Gage South Side CSS - microstrains 1 125 162 224 287 324 449 486 586 1134 2419 3154 4239 52 2 87 112 437 475 362 387 450 487 487 525 587 700 10 3 112 137 187 312 300 375 450 462 487 587 1137 1400 210 4 138 113 213 275 300 363 438 413 438 663 1777 2403 28 5 87 100 162 175 200 325 387 350 537 774 1861 2398 26 6 106 106														1998
Gage South Side CSS - microstrains 1 125 162 224 287 324 449 486 586 1134 2419 3154 4239 52: 2 87 112 437 475 362 387 450 487 487 525 587 700 10: 3 112 137 187 312 300 375 450 462 487 587 1137 1400 21: 4 138 113 213 275 300 363 438 413 438 663 1777 2403 28 5 87 100 162 175 200 325 387 350 537 774 1861 2398 26 6 106 106 293 206 293 468 355 480 443 717 1802 2264 255 7 162 50 225														3914
1 125 162 224 287 324 449 486 586 1134 2419 3154 4239 522 2 87 112 437 475 362 387 450 487 487 525 587 700 100 3 112 137 187 312 300 375 450 462 487 587 1137 1400 210 4 138 113 213 275 300 363 438 413 438 663 1777 2403 286 5 87 100 162 175 200 325 387 350 537 774 1861 2398 266 6 106 106 293 206 293 468 355 480 443 717 1802 2264 255 7 162 50 225 225 312 324 349		157	194	244	294		1				1521	2248	3199	4238
2 87 112 437 475 362 387 450 487 487 525 587 700 100 3 112 137 187 312 300 375 450 462 487 587 1137 1400 210 4 138 113 213 275 300 363 438 413 438 663 1777 2403 286 5 87 100 162 175 200 325 387 350 537 774 1861 2398 266 6 106 106 293 206 293 468 355 480 443 717 1802 2264 255 7 162 50 225 225 312 324 349 337 362 699 1322 1572 155 8 94 81 181 231 1378 318 393 <td>Gage</td> <td></td> <td></td> <td>······································</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>,</td> <td>····</td> <td></td> <td></td>	Gage			······································							,	····		
3 112 137 187 312 300 375 450 462 487 587 1137 1400 216 4 138 113 213 275 300 363 438 413 438 663 1777 2403 286 5 87 100 162 175 200 325 387 350 537 774 1861 2398 266 6 106 106 293 206 293 468 355 480 443 717 1802 2264 255 7 162 50 225 225 312 324 349 337 362 699 1322 1572 155 8 94 81 181 231 1378 318 393 430 393 729 1265 1602 277 9 231 144 131 306 218 393 368 106 343 181														5286
4 138 113 213 275 300 363 438 413 438 663 1777 2403 286 5 87 100 162 175 200 325 387 350 537 774 1861 2398 266 6 106 106 293 206 293 468 355 480 443 717 1802 2264 25 7 162 50 225 225 312 324 349 337 362 699 1322 1572 153 8 94 81 181 231 1378 318 393 430 393 729 1265 1602 273 9 231 144 131 306 218 393 368 106 343 181 1541 1941 266 10 118 118 218 268 206 368 330														1037
5 87 100 162 175 200 325 387 350 537 774 1861 2398 266 6 106 106 293 206 293 468 355 480 443 717 1802 2264 255 7 162 50 225 225 312 324 349 337 362 699 1322 1572 155 8 94 81 181 231 1378 318 393 430 393 729 1265 1602 275 9 231 144 131 306 218 393 368 106 343 181 1541 1941 265 10 118 118 218 268 206 368 330 380 393 542 1876 2936 375 11 68 255 143 193 243 305 34														2100
6 106 106 293 206 293 468 355 480 443 717 1802 2264 255 7 162 50 225 225 312 324 349 337 362 699 1322 1572 153 8 94 81 181 231 1378 318 393 430 393 729 1265 1602 273 9 231 144 131 306 218 393 368 106 343 181 1541 1941 263 10 118 118 218 268 206 368 330 380 393 542 1876 2936 373 11 68 255 143 193 243 305 342 305 392 479 1861 2882 363 12 25 99 249 199 174 187 31														2841
7 162 50 225 225 312 324 349 337 362 699 1322 1572 153 8 94 81 181 231 1378 318 393 430 393 729 1265 1602 273 9 231 144 131 306 218 393 368 106 343 181 1541 1941 266 10 118 118 218 268 206 368 330 380 393 542 1876 2936 373 11 68 255 143 193 243 305 342 305 392 479 1861 2882 363 12 25 99 249 199 174 187 311 286 336 336 1069 1865 179 13 81 131 180 193 -19 56 815														2648
8 94 81 181 231 1378 318 393 430 393 729 1265 1602 277 9 231 144 131 306 218 393 368 106 343 181 1541 1941 260 10 118 118 218 268 206 368 330 380 393 542 1876 2936 370 11 68 255 143 193 243 305 342 305 392 479 1861 2882 360 12 25 99 249 199 174 187 311 286 336 336 1069 1865 179 13 81 131 180 193 -19 56 815 1213 1524 1910 2793 4000 469 14 69 44 106 144 131 106														2538
9 231 144 131 306 218 393 368 106 343 181 1541 1941 263 10 118 118 218 268 206 368 330 380 393 542 1876 2936 373 11 68 255 143 193 243 305 342 305 392 479 1861 2882 36 12 25 99 249 199 174 187 311 286 336 336 1069 1865 179 13 81 131 180 193 -19 56 815 1213 1524 1910 2793 4000 469 14 69 44 106 144 131 106 543 967 1279 1841 2340 2939 359 15 81 144 231 119 94 231 <td< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>1559</td></td<>														1559
10 118 118 218 268 206 368 330 380 393 542 1876 2936 372 11 68 255 143 193 243 305 342 305 392 479 1861 2882 36 12 25 99 249 199 174 187 311 286 336 336 1069 1865 179 13 81 131 180 193 -19 56 815 1213 1524 1910 2793 4000 469 14 69 44 106 144 131 106 543 967 1279 1841 2340 2939 359 15 81 144 231 119 94 231 681 1156 1518 2131 3968 3218 399 16 13 88 75 138 113 138 <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>2724</td></t<>														2724
11 68 255 143 193 243 305 342 305 392 479 1861 2882 360 12 25 99 249 199 174 187 311 286 336 336 1069 1865 179 13 81 131 180 193 -19 56 815 1213 1524 1910 2793 4000 469 14 69 44 106 144 131 106 543 967 1279 1841 2340 2939 359 15 81 144 231 119 94 231 681 1156 1518 2131 3968 3218 399 16 13 88 75 138 113 138 525 1113 1488 2038 2700 3275 380 17 25 212 300 312 287 300	L											1541		2627
12 25 99 249 199 174 187 311 286 336 336 1069 1865 179 13 81 131 180 193 -19 56 815 1213 1524 1910 2793 4000 469 14 69 44 106 144 131 106 543 967 1279 1841 2340 2939 359 15 81 144 231 119 94 231 681 1156 1518 2131 3968 3218 399 16 13 88 75 138 113 138 525 1113 1488 2038 2700 3275 389 17 25 212 300 312 287 300 387 387 549 387 936 1061 12 18 6 168 156 68 492 616 <td< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>3722</td></td<>														3722
13 81 131 180 193 -19 56 815 1213 1524 1910 2793 4000 469 14 69 44 106 144 131 106 543 967 1279 1841 2340 2939 359 15 81 144 231 119 94 231 681 1156 1518 2131 3968 3218 399 16 13 88 75 138 113 138 525 1113 1488 2038 2700 3275 380 17 25 212 300 312 287 300 387 387 549 387 936 1061 12 18 6 168 156 68 492 616 953 1052 1326 1476 1774 2048 213														3629
14 69 44 106 144 131 106 543 967 1279 1841 2340 2939 35 15 81 144 231 119 94 231 681 1156 1518 2131 3968 3218 39 16 13 88 75 138 113 138 525 1113 1488 2038 2700 3275 38 17 25 212 300 312 287 300 387 387 549 387 936 1061 123 18 6 168 156 68 492 616 953 1052 1326 1476 1774 2048 213													1865	1790
15 81 144 231 119 94 231 681 1156 1518 2131 3968 3218 399 16 13 88 75 138 113 138 525 1113 1488 2038 2700 3275 380 17 25 212 300 312 287 300 387 387 549 387 936 1061 12 18 6 168 156 68 492 616 953 1052 1326 1476 1774 2048 213													4000	4697
16 13 88 75 138 113 138 525 1113 1488 2038 2700 3275 380 17 25 212 300 312 287 300 387 387 549 387 936 1061 12 18 6 168 156 68 492 616 953 1052 1326 1476 1774 2048 21												2340	2939	3525
16 13 88 75 138 113 138 525 1113 1488 2038 2700 3275 380 17 25 212 300 312 287 300 387 387 549 387 936 1061 1236 18 6 168 156 68 492 616 953 1052 1326 1476 1774 2048 213									1156		2131	3968	3218	3930
17 25 212 300 312 287 300 387 387 549 387 936 1061 123 18 6 168 156 68 492 616 953 1052 1326 1476 1774 2048 213						113		525	1113	1488	2038	2700		3800
18 6 168 156 68 492 616 953 1052 1326 1476 1774 2048 213	17	25	212	300	312	287	300	387	387	549	387	936		1286
	18	6	168	156	68	492	616	953	1052	1326	1476	1774		2123
	19	107	194	232	357	545	758	871	1159	1172	1334	1560	1898	1886
	20	63	88	113	50	289								1606

S.3 G1A-West

Table S.3 Raw Concrete Surface Strains Data for Development Length Test G1A-West

Γ	Step	1	2	3	4	5	6	7	8	9	10	11
	Load (Kips)	50	100	150	194	221	248	270	284	292	294	290

Gage					North S	Side CSS	S - microst	rains	-		
1	94	144	207	307	370	495	1059	1987	1849	1949	1812
2	88	100	200	225	301	401	476	764	1565	1828	1778
3	88	75	163	250	301	388	1703	714	1540	1741	1728
4	63	113	163	226	276	338	439	765	1617	1855	1805
5	94	119	195	270	320	420	345	195	1525	1537	1512
6	88	138	164	239	252	340	315	340	378	466	491
7	188	201	239	289	364	402	389	490	502	615	628
8	69	81	106	182	182	269	282	332	370	382	395
9	38	75	100	138	176	251	238	276	301	313	288
10	81	81	119	243	281	343	343	381	443	443	406
11	119	157	207	257	244	332	307	407	432	357	395
12	44	82	107	157	157	194	207	220	257	232	270
13	75	63	88	75	213	276	376	326	288	288	451
14	0	50	38	113	138	301	890	1266	1530	1655	1655
15	37	37	12	62	62	287	923	1273	1535	1635	1647
16	31	94	81	157	144	407	959	1359	1547	1410	1673
17	38	63	113	88	125	651	1139	1690	1940	1815	1490
18	31	44	44	232	444	807	983	1020	995	995	945
19	0	50	63	251	790	752	840	865	840	865	990
20	12	37	12	187	399	648	499	785	773	785	773
Gage		r					S - microst				
1	56	6	31	332	557	720	683	833	833	795	946
2	94	132	56	244	457	633	457	720	633	708	733
3	25	-12	-12	237	424	748	898	1010	1010	998	1048
4	19	-44	-31	143	343	842	1503	1790	1790	1728	1728
5	-13	-75	-138	-163	-13	325	888	1200	1463	1526	1601
6	-19	6	-56	-81	-81	319	956 777	1306 1041	1556 1542	1606 1442	1656 1780
7	50	0	-25	-38	6	351 56	119	306	556	731	818
8	56 69	19 -69	-31 56	-19 -19	-31	82	44	157	144	44	182
10	44	69	69	107	132	195	220	295	308	232	308
11	157	31	107	132	31	6	-19	107	144	56	282
12	82	120	132	107	132	196	145	284	360	322	423
13	169	219	132	69	-56	319	6	307	432	420	432
14	94	107	94	107	244	295	81	194	357	332	370
15	88	113	113	100	363	388	325	463	538	713	688
16	62	75	112	137	312	374	399	973	1559	1771	1808
17	62	25	112	62	262	225	37	686	1447	1347	1285
18	93	118	205	193	193	504	504	964	1599	1686	1736
19	249	374	237	249	224	411	399	872	1445	1495	1520
20	162	-37	174	162	237	349	1170	1544	1668	1606	1693
	1.02		<u> </u>				<u> </u>	L		<u> </u>	

S.4 G1B-East

Table S.4 Raw Concrete Surface Strains Data for Development Length Test G1B-East

Step	1	2	3	4	5	6	7	8	9	10	11	12	13
Load (Kips)	100	120	140	160	180	200	220	240	260	280	300	320	340

1 -31 -31 -44 -56 168 454 479 479 466 541 752 963 1187	Gage						North S	ida CSS	mioro	atraina				 -
2		21	21	11	56	168					5/1	752	062	1107
3														
4 106 94 119 106 319 1007 1483 1984 2697 3623 4436 6051 9129 5 -50 0 38 25 38 364 829 1344 1935 3154 4021 5817 946 6 38 38 63 75 75 250 300 400 763 1951 2651 3939 6966 7 -94 -31 -31 -19 219 181 106 84 8 56 556 943 1443 5654 8 -25 -38 -13 -13 50 88 88 113 113 338 614 1077 4045 9 131 106 144 181 207 219 257 257 294 344 507 2772 11 0 -25 38 50 -25 175 188														
5 -50 0 38 25 38 364 829 1344 1935 3154 4021 5817 9461 6 38 38 63 75 75 250 300 400 763 1951 2651 3939 6966 7 -94 -31 -31 -19 219 181 106 81 56 556 943 1443 5654 8 -25 -38 -13 -13 50 88 88 113 113 338 614 1077 4045 9 131 106 119 144 219 244 269 306 281 306 343 518 2841 10 94 81 106 114 181 207 257 257 294 344 343 518 2841 11 0 -25 38 0 -25 175 188														
6 38 38 63 75 75 250 300 400 763 1951 2651 3939 6966 7 -94 -31 -31 -19 219 181 106 81 56 556 943 1443 5654 8 -25 -38 -13 -13 50 88 88 113 113 338 614 1077 4045 9 131 106 119 144 219 244 269 306 281 306 343 518 2841 10 94 81 106 144 181 207 219 257 257 294 344 507 2772 11 0 -25 38 50 -25 175 188 188 200 263 375 538 438 12 50 50 87 75 125 199 224 <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>														
The color of the														
8 -25 -38 -13 -13 50 88 88 113 113 338 614 1077 4045 9 131 106 119 144 219 244 269 306 281 306 343 518 2841 10 94 81 106 144 181 207 219 257 257 294 344 507 2772 11 0 -25 38 50 -25 175 188 188 200 263 375 538 438 12 50 50 87 75 125 199 224 237 262 312 411 436 461 13 99 124 137 149 199 248 286 360 311 410 472 460 783 14 143 155 30 265 326 386 323 <														
9														
10				2.2										
11														
12 50 50 87 75 125 199 224 237 262 312 411 436 461 13 99 124 137 149 199 248 286 360 311 410 472 460 783 14 143 155 193 205 267 329 354 379 391 416 540 764 1361 15 75 62 99 137 75 236 286 323 286 385 447 559 1242 16 106 106 156 131 194 319 344 407 394 469 557 845 1445 17 107 94 69 119 119 295 270 333 370 496 634 1601 2216 18 19 82 119 157 207 282 333 383 408 533 621 1374 1563 19 132 169 194 219 269 382 370 432 482 645 808 1760 2224 20 88 113 163 175 200 300 300 388 363 538 1013 1875 2288 Gage														
13 99 124 137 149 199 248 286 360 311 410 472 460 783 14 143 155 193 205 267 329 354 379 391 416 540 764 1361 15 75 62 99 137 75 236 286 323 286 385 447 559 1242 16 106 106 156 131 194 319 344 407 394 469 557 845 1445 17 107 94 69 119 119 295 270 333 370 496 634 1601 2216 18 19 82 119 157 207 282 333 383 408 533 621 1374 1563 19 132 169 194 219 269 382 370 432 482 645 808 1760 2224 20 88 113 163 175 200 300 300 388 363 538 1013 1875 2288 Gage														
14														
15														
16 106 106 156 131 194 319 344 407 394 469 557 845 1445 17 107 94 69 119 119 295 270 333 370 496 634 1601 2216 18 19 82 119 157 207 282 333 383 408 533 621 1374 1563 19 132 169 194 219 269 382 370 432 482 645 808 1760 2224 20 88 131 163 175 200 300 300 388 363 538 1013 1875 2228 Gage South Side CSS - microstrains 1 220 321 321 396 572 522 937 786 723 1075 2597 3163 2 113 201 176<														
17														
18 19 82 119 157 207 282 333 383 408 533 621 1374 1563 19 132 169 194 219 269 382 370 432 482 645 808 1760 2224 20 88 113 163 175 200 300 300 388 363 538 1013 1875 2288 Gage South Side CSS - microstrains 1 220 321 321 396 572 522 937 786 723 1075 2597 3163 2 113 201 176 252 239 415 516 705 1032 793 768 1851 1737 3 264 352 326 377 427 515 615 778 979 866 916 1770 1958 4 340 302 32														
19														
Company 88 113 163 175 200 300 300 388 363 538 1013 1875 2288 Gage South Side CSS - microstrains 1 220 321 321 396 572 522 937 786 723 1075 2597 3163 2 113 201 176 252 239 415 516 705 1032 793 768 1851 1737 3 264 352 326 377 427 515 615 778 979 866 916 1770 1958 4 340 302 327 365 390 504 617 818 1095 718 995 1699 2027 5 334 334 372 359 385 624 586 864 498 889 1255 1835 2566 6 227 240														
Gage South Side CSS - microstrains 1 220 321 321 396 572 522 937 786 723 1075 2597 3163 2 113 201 176 252 239 415 516 705 1032 793 768 1851 1737 3 264 352 326 377 427 515 615 778 979 866 916 1770 1958 4 340 302 327 365 390 504 617 818 1095 718 995 1699 2027 5 334 334 372 359 385 624 586 864 498 889 1255 1835 2566 6 227 240 164 328 265 492 467 505 821 606 644 1073 2159 7 126 139 1														
1 220 321 321 396 572 522 937 786 723 1075 2597 3163 2 113 201 176 252 239 415 516 705 1032 793 768 1851 1737 3 264 352 326 377 427 515 615 778 979 866 916 1770 1958 4 340 302 327 365 390 504 617 818 1095 718 995 1699 2027 5 334 334 372 359 385 624 586 864 498 889 1255 1835 2566 6 227 240 164 328 265 492 467 505 821 606 644 1073 2159 7 126 139 126 38 177 215 38 <t< td=""><td></td><td>88</td><td>113</td><td>163</td><td>175</td><td>200</td><td></td><td></td><td></td><td></td><td>538</td><td>1013</td><td>1875</td><td>2288</td></t<>		88	113	163	175	200					538	1013	1875	2288
2 113 201 176 252 239 415 516 705 1032 793 768 1851 1737 3 264 352 326 377 427 515 615 778 979 866 916 1770 1958 4 340 302 327 365 390 504 617 818 1095 718 995 1699 2027 5 334 334 372 359 385 624 586 864 498 889 1255 1835 2566 6 227 240 164 328 265 492 467 505 821 606 644 1073 2159 7 126 139 126 38 177 215 38 442 1175 720 581 1112 2768 8 190 203 228 215 354 354 <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>r</td><td></td><td></td><td></td></t<>											r			
3 264 352 326 377 427 515 615 778 979 866 916 1770 1958 4 340 302 327 365 390 504 617 818 1095 718 995 1699 2027 5 334 334 372 359 385 624 586 864 498 889 1255 1835 2566 6 227 240 164 328 265 492 467 505 821 606 644 1073 2159 7 126 139 126 38 177 215 38 442 1175 720 581 1112 2768 8 190 203 228 215 354 354 329 671 874 798 494 899 1165 9 139 164 113 76 151 340 3														
4 340 302 327 365 390 504 617 818 1095 718 995 1699 2027 5 334 334 372 359 385 624 586 864 498 889 1255 1835 2566 6 227 240 164 328 265 492 467 505 821 606 644 1073 2159 7 126 139 126 38 177 215 38 442 1175 720 581 1112 2768 8 190 203 228 215 354 354 329 671 874 798 494 899 1165 9 139 164 113 76 151 340 340 567 617 529 277 655 554 10 145 182 233 170 295 270 45														
5 334 334 372 359 385 624 586 864 498 889 1255 1835 2566 6 227 240 164 328 265 492 467 505 821 606 644 1073 2159 7 126 139 126 38 177 215 38 442 1175 720 581 1112 2768 8 190 203 228 215 354 354 329 671 874 798 494 899 1165 9 139 164 113 76 151 340 340 567 617 529 277 655 554 10 145 182 233 170 295 270 459 471 735 773 446 1075 622 11 220 220 270 308 333 409 547														
6 227 240 164 328 265 492 467 505 821 606 644 1073 2159 7 126 139 126 38 177 215 38 442 1175 720 581 1112 2768 8 190 203 228 215 354 354 329 671 874 798 494 899 1165 9 139 164 113 76 151 340 340 567 617 529 277 655 554 10 145 182 233 170 295 270 459 471 735 773 446 1075 622 11 220 220 220 270 308 333 409 547 710 597 622 723 798 12 126 163 151 213 239 213 264 </td <td></td>														
7 126 139 126 38 177 215 38 442 1175 720 581 1112 2768 8 190 203 228 215 354 354 329 671 874 798 494 899 1165 9 139 164 113 76 151 340 340 567 617 529 277 655 554 10 145 182 233 170 295 270 459 471 735 773 446 1075 622 11 220 220 220 270 308 333 409 547 710 597 622 723 798 12 126 163 151 213 239 213 264 452 477 477 402 465 590 13 132 195 132 69 207 333 257 <td></td>														
8 190 203 228 215 354 354 329 671 874 798 494 899 1165 9 139 164 113 76 151 340 340 567 617 529 277 655 554 10 145 182 233 170 295 270 459 471 735 773 446 1075 622 11 220 220 220 270 308 333 409 547 710 597 622 723 798 12 126 163 151 213 239 213 264 452 477 477 402 465 590 13 132 195 132 69 207 333 257 596 835 835 1337 1162 1526 14 56 94 119 69 182 620 821 <td></td>														
9 139 164 113 76 151 340 340 567 617 529 277 655 554 10 145 182 233 170 295 270 459 471 735 773 446 1075 622 11 220 220 220 270 308 333 409 547 710 597 622 723 798 12 126 163 151 213 239 213 264 452 477 477 402 465 590 13 132 195 132 69 207 333 257 596 835 835 1337 1162 1526 14 56 94 119 69 182 620 821 1259 1911 2788 3677 4893 9804 15 94 106 144 131 307 758 11														
10 145 182 233 170 295 270 459 471 735 773 446 1075 622 11 220 220 220 270 308 333 409 547 710 597 622 723 798 12 126 163 151 213 239 213 264 452 477 477 402 465 590 13 132 195 132 69 207 333 257 596 835 835 1337 1162 1526 14 56 94 119 69 182 620 821 1259 1911 2788 3677 4893 9804 15 94 106 144 131 307 758 1121 1697 2398 3212 4389 5278 10112 16 193 206 218 256 393 892														
11 220 220 220 270 308 333 409 547 710 597 622 723 798 12 126 163 151 213 239 213 264 452 477 477 402 465 590 13 132 195 132 69 207 333 257 596 835 835 1337 1162 1526 14 56 94 119 69 182 620 821 1259 1911 2788 3677 4893 9804 15 94 106 144 131 307 758 1121 1697 2398 3212 4389 5278 10112 16 193 206 218 256 393 892 1203 1827 2326 3498 4046 5480 10680 17 112 199 212 125 312 1184 </td <td></td> <td>l</td> <td></td> <td>l</td> <td></td>		l		l										
12 126 163 151 213 239 213 264 452 477 477 402 465 590 13 132 195 132 69 207 333 257 596 835 835 1337 1162 1526 14 56 94 119 69 182 620 821 1259 1911 2788 3677 4893 9804 15 94 106 144 131 307 758 1121 1697 2398 3212 4389 5278 10112 16 193 206 218 256 393 892 1203 1827 2326 3498 4046 5480 10680 17 112 199 212 125 312 1184 1583 1571 2593 3678 4613 5661 11184 18 336 -62 461 174 784 <														622
13 132 195 132 69 207 333 257 596 835 835 1337 1162 1526 14 56 94 119 69 182 620 821 1259 1911 2788 3677 4893 9804 15 94 106 144 131 307 758 1121 1697 2398 3212 4389 5278 10112 16 193 206 218 256 393 892 1203 1827 2326 3498 4046 5480 10680 17 112 199 212 125 312 1184 1583 1571 2593 3678 4613 5661 11184 18 336 -62 461 174 784 1195 1208 1755 1992 1992 2291 2141 3174 19 205 130 242 168 528														
14 56 94 119 69 182 620 821 1259 1911 2788 3677 4893 9804 15 94 106 144 131 307 758 1121 1697 2398 3212 4389 5278 10112 16 193 206 218 256 393 892 1203 1827 2326 3498 4046 5480 10680 17 112 199 212 125 312 1184 1583 1571 2593 3678 4613 5661 11184 18 336 -62 461 174 784 1195 1208 1755 1992 1992 2291 2141 3174 19 205 130 242 168 528 615 826 1174 1546 1745 1521 1571 2229														
15 94 106 144 131 307 758 1121 1697 2398 3212 4389 5278 10112 16 193 206 218 256 393 892 1203 1827 2326 3498 4046 5480 10680 17 112 199 212 125 312 1184 1583 1571 2593 3678 4613 5661 11184 18 336 -62 461 174 784 1195 1208 1755 1992 1992 2291 2141 3174 19 205 130 242 168 528 615 826 1174 1546 1745 1521 1571 2229														
16 193 206 218 256 393 892 1203 1827 2326 3498 4046 5480 10680 17 112 199 212 125 312 1184 1583 1571 2593 3678 4613 5661 11184 18 336 -62 461 174 784 1195 1208 1755 1992 1992 2291 2141 3174 19 205 130 242 168 528 615 826 1174 1546 1745 1521 1571 2229												3677		9804
17 112 199 212 125 312 1184 1583 1571 2593 3678 4613 5661 11184 18 336 -62 461 174 784 1195 1208 1755 1992 1992 2291 2141 3174 19 205 130 242 168 528 615 826 1174 1546 1745 1521 1571 2229	15		106	144		307		1121	1697	2398	3212	4389	5278	10112
17 112 199 212 125 312 1184 1583 1571 2593 3678 4613 5661 11184 18 336 -62 461 174 784 1195 1208 1755 1992 1992 2291 2141 3174 19 205 130 242 168 528 615 826 1174 1546 1745 1521 1571 2229	16	193	206	218		393	892	1203	1827	2326	3498	4046	5480	10680
18 336 -62 461 174 784 1195 1208 1755 1992 1992 2291 2141 3174 19 205 130 242 168 528 615 826 1174 1546 1745 1521 1571 2229	1 10	110	199	212	125	312	1184	1583	1571	2593	3678	4613		
19 205 130 242 168 528 615 826 1174 1546 1745 1521 1571 2229		112	1,77						1					
	17	I		461	174	784	1195	1208	1755	1992	1992	2291	2141	3174
20 228 204 315 327 673 1118 1105 1315 1525 1575 1809 1402 2217	17 18	336	-62											

S.5 G1B-West

Table S.5 Raw Concrete Surface Strains Data for Development Length Test G1B-West

Step	1	2	3	4	5	6	7	8	9	10	11	12
Load (Kips)	77	130	160	190	220	250	280	310	340	360	365	367

Gage								crostrain				
1	94	169	144	194	244	281	356	406	1144	1506	1731	1793
2	75	125	150	200	237	262	350	387	1437	1936	2224	2286
3	56	-6	56	219	281	269	343	443	1505	2317	2654	2741
4	63	113	125	150	213	225	275	338	1488	2175	2275	2313
5	50	113	125	163	200	250	301	388	864	1340	1440	1465
6	62	75	100	150	175	225	300	350	524	787	1099	1224
7	94	107	119	170	195	245	270	308	383	433	672	810
8	6	56	56	157	195	119	282	345	446	571	709	785
9	57	94	69	145	245	233	233	283	359	409	661	812
10	63	88	88	126	151	164	214	264	264	327	340	353
11	0	25	75	100	162	175	187	262	225	325	337	375
12	69	69	81	119	119	156	219	207	244	282	357	369
13	50	62	62	62	87	112	162	187	199	249	299	324
14	62	62	112	50	137	137	212	249	237	399	462	549
15	38	63	38	50	75	100	100	275	438	638	763	813
16	63	75	25	25	88	88	138	450	838	1150	1238	1375
17	50	63	50	75	113	100	138	700	1263	1588	1775	1850
18	25	37	25	50	75	75	87	699	1198	1435	1523	1585
19	6	31	19	81	181	306	468	1004	1353	1552	1627	542
20	56	69	56	143	218	330	480	791	953	1028	1052	1115
Gage								crostrain				
1	-56	-94	-44	-19	44	294	457	545	707	720	707	695
2	-88	-326	-288	-163	75	213	426	476	539	639	652	601
3	-13	13	13	150	288	488	550	725	1163	1376	1376	1301
4	0	75	-12	-12	25	150	225	849	1312	1749	1861	1786
5	6	-69	-6	44	81	257	219	895	1271	1671	1721	1734
6	25	63	-25	-75	25	213	226	877	1416	1729	1729	1830
7	-13	-13	-38	25	63	251	263	814	1053	1341	1328	1341
8	125	50	50	63	113	63	25	100	88	113	125	125
9	232	132	182	169	207	257	219	320	457	345	507	545
10	19	31	94	44	194	144	207	244	294	382	607	645
11	38	63	50	63	201	138	163	238	314	289	728	778
12	19	-57	-19	69	233	107	195	245	283	258	723	823
13	44	69	144	182	220	220	295	320	358	395	684	722
14	63	75	150	75	176	50	251	364	326	326	639	652
15	0	-13	63	88	138	138	301	326	502	1003	1141	1192
16	225	75	150	188	225	275	325	338	526	1014	1202	1239
17	132	-6	257	82	220	232	144	245	1588	2505	2706	2794
18	101	-63	-25	176	252	289	201	214	717	2378	2504	2617
19	157	119	144	107	295	245	270	433	1511	2100	2364	2213
20	107	31	132	182	220	245	471	295	1538	2078	2392	2341

S.6 G1C-East

Table S.6 Raw Concrete Surface Strains Data for Development Length Test G1C-East

Step	1	2	3	4	5	6	7	8	9	10	11
Load											
(Kips)	81	112	152	185	215	245	275	305	328	348	349

Gage					North S	ide CSS -	microstr	ains			
1	-119	-6	-19	256	431	568	606	856	693	681	681
2	-94	-44	31	319	482	607	720	920	1258	1445	1495
3	-25	113	88	414	627	689	652	1015	1341	1516	1579
4	31	82	132	420	633	696	872	1047	1398	1524	1612
5	-63	-50	13	75	88	50	75	125	638	1051	1288
6	-50	0	37	37	683	1566	2436	3890	4424	5431	5269
7	-12	37	62	124	757	1563	2432	3809	5149	7345	6849
8	25	62	112	149	808	1728	2562	3867	5135	7510	6938
9	12	-199	87	125	822	1719	2592	4386	5607	7600	6903
10	56	69	81	119	244	294	319	694	1307	2695	3233
11	50	163	175	200	275	325	488	1202	2654	5020	6434
12	44	6	69	181	156	193	356	1167	2852	5273	6471
13	69	81	169	232	257	282	407	758	2586	5104	6720
14	25	125	138	288	113	125	238	600	2501	5890	17432
15	0	38	-13	-25	150	138	326	414	714	1479	11557
16	38	38	113	251	264	289	402	1068	930	1457	11244
17	0	0	100	213	150	225	163	663	1051	2465	15578
18	-81	19	156	169	144	231	343	1205	2679	4265	8049
19	31	93	193	280	318	417	542	1663	2747	4492	8242
20	-69	44	118	181	218	280	492	1115	2410	4790	8265
Gage					South S	ide CSS -	- microstr	ains			
1	136	136	247	346	383	470	630	1113	2225	2905	7145
2	112	124	187	261	349	436	697	1556	2689	3038	7271
3	81	118	131	181	268	405	605	1378	2600	2912	7151
4	81	144	156	206	268	393	631	1143	1929	2179	11595
5	100	175	212	225	324	374	537	1236	1610	1435	7026
6	100	125	175	238	300	338	388	713	988	5603	16535
7	88	163	175	263	276	363	438	-438	1077	5661	16694
8	-19	157	169	107	245	232	433	709	960	5553	10334
9 .	138	226	289	302	390	452	578	628	616	4914	9991
10	88	126	151	151	239	365	428	566	503	302	428
11	119	107	145	208	233	296	396	522	2685	3188	2710
12	63	101	139	176	202	252	365	479	2759	3250	2797
13	-25	25	51	101	13	164	379	2061	5360	7749	7256
14	32	95	133	196	398	638	1534	3150	6370	8858	8378
15	0	50	101	126	379	593	1553	3131	4242	6148	6931
16	19	95	120	69	410	638	1496	3099	4021	6015	6015
17	82	132	170	522	1151	1830	2774	3013	3038	3277	3353
18	38	88	126	415	869	1284	1511	1775	2090	2014	2115
19	-6	19	57	383	735	1137	1375	1576	1551	1715	1802
20	-31	6	31	295	696	1072	1298	1474	1499	1637	1649

S.7 G1C-West

Table S.7 Raw Concrete Surface Strains Data for Development Length Test G1C-West

Step	1	2	3	4	5	6	7	8	9	10	11	12
Load (Kips	1 XII	110	140	155	184	215	240	261	276	287	295	296

Gage			1		NI.	orth Side	C88 ==	nicrostrain	na			
1	194	194	231	369	381	469	556	944	1769	2469	2694	3057
2	219	231	294	381	469	569	668	1056	1881	2693	2830	3037
3	219	243	268	368	418	518	581	1130	2042	2966	3153	3515
4	175	188	213	313	388	488	550	713	1013	1500	1600	1688
5	187	175	237	275	362	425	487	700	800	1049	1049	
6	200	250	275	337	425	500	562	700	875	1450	1662	775
	200	207	273			408		533				1700
7	182	107	220	320 295	383		483 446	496	496	973 1036	1462	1789
8	158	208	208	293	372	358 359	410	496	496 460		1965	10894
10	138	164	189	277	352	340	440	466	528	1002 617	1909	11211 10532
11	156	194	194	281	394	381	456	506	556	594	1208 844	
12	169	169	181	244	356	369	394	444	519	444	431	10110 668
13	149	187	224	336	461	436	498	573	698	2952	5568	6054
14	149	143	118	218	330	368	498	443	555	3087	5967	6553
	119	106			231	344	1132	1832	2583	5247		
15			6	106	200				2513		8586	9024
16	138	213	138	175		388	1088	1750		5288	8589	9089
17	112	125	100	162	200	412	1062	1711	2410	2897	3547	3622
18	62	50	12	237	537	1048	1809	2533	3369	3594	4218	3968
19 20	131	268	118	305	605	1004	916 1023	1054 1060	1166	1315	1390	1365
	175	137	162	362	661	948		nicrostrai	1198	1223	1260	1310
Gage	175	137	162	362	661	948	1023	1060	1198	1223	1260	1310
2	113	163	201	451	564	564	640	702	790	890	916	966
3	-6	132	94	445	520	533	596	646	746	871	934	947
4	88	63	75	100	213	963	1463	1976	2601	4940	5403	5390
5	75	62	25	100	674	1411	2047	2697	3296	5730	5630	5543
6	-13	50	75	150	751	1477	2115	2866	3918	6647	8837	9013
7	63	75	50	125	764	1540	2191	2904	3918	6672	9200	9363
8	106	106	144	169	570	695	820	1046	1346	1860	3901	4064
9	75	88	88	151	138	151	201	276	528	678	3467	3731
10	94	94	94	182	106	119	157	182	194	157	232	219
11	157	132	132	207	169	207	320	232	269	583	2137	7726
12	69	107	144	182	82	82	157	157	182	546	2531	8647
13	162	150	162	237	125	299	287	299	274	711	2645	12514
14	113	150	163	238	213	238	238	326	376	802	2869	12704
15	107	94	119	169	157	132	244	169	445	809	1147	5598
16	88	100	138	288	238	263	363	514	752	965	990	4725
17	95	120	158	233	208	203	271	460	662	952	1103	977
18	94	107	132	220	208	208	308	447	673	875	1064	1466
19	176	176	188	251	238	314	402	979	1443	1907	2133	2409
20	138	175	213	301	313	338	464	890	1328	1854	2118	2531
	136	1 1/3		201	213	220	707	0,0	1320	1037	2110	2331

S.8 G2A-East

Table S.8 Raw Concrete Surface Strains Data for Development Length Test G2A-East

Step	1	2	3	4	_ 5	6	7	8	9	10	11	12	13
Load (Kips)	100	151	181	211	244	274	304	334	364	394	425	439	440

1 37 62 50 87 286 436 709 896 1088 1244 1356 1356 1419 2							r 41 0	1. 000	•					
2	Gage	27	(0)	50	07						1011	4056	1056	
3														
4 94 106 144 94 194 181 869 1394 2282 2920 4282 4995 5508 5 31 94 107 94 182 458 521 772 1374 1863 3093 3808 4222 6 44 94 69 69 119 144 169 356 844 1207 2183 2658 2971 7 50 100 100 150 200 262 250 399 811 1161 2247 2696 3021 8 69 94 106 131 169 219 219 244 319 419 1195 1370 1433 9 150 212 249 312 362 437 449 499 574 649 1272 1609 1659 133 232 282 369 332 419 482 1196														
5 31 94 107 94 182 458 521 772 1374 1863 3093 3808 4222 6 44 94 69 69 119 144 169 356 844 1207 2183 2658 2971 7 50 100 100 150 200 262 250 399 811 1161 2247 2696 3021 8 69 94 106 131 169 219 219 244 319 419 1195 1370 1433 9 150 212 249 312 362 437 449 499 574 649 1272 1600 1659 10 100 125 113 138 225 255 263 288 426 501 1227 1402 142 11 119 169 157 194 232 282 <th< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></th<>														
6 44 94 69 69 119 144 169 356 844 1207 2183 2658 2971 7 50 100 100 150 200 262 250 399 811 1161 2247 2696 3021 8 69 94 106 131 169 219 219 244 319 419 1195 1370 1433 9 150 212 249 312 362 437 449 499 574 649 1272 1609 1659 10 100 125 113 138 225 275 263 288 426 501 1227 1402 1452 11 119 169 157 194 232 282 3369 332 419 482 1196 1459 159 12 106 156 193 243 268 380														
7 50 100 100 150 200 262 250 399 811 1161 2247 2696 3021 8 69 94 106 131 169 219 219 244 319 419 1195 1370 1433 9 150 212 249 312 362 437 449 499 574 649 1272 1609 1652 110 100 125 113 138 225 275 263 288 426 501 1227 1402 1452 11 119 169 157 194 232 282 369 332 419 482 1196 1459 1596 122 106 156 193 243 268 380 405 417 455 442 442 479 579 13 62 62 25 25 137 149 211 186 236 249 373 448 398 144 43 130 93 143 192 291 291 391 416 1209 1743 1991 2053 15 112 174 161 273 310 372 409 447 509 1278 1762 1985 2035 16 81 106 144 181 219 331 343 381 531 1268 1780 1980 2042 17 81 119 169 207 219 332 370 470 696 2325 3152 3640 888 138 163 163 1027 388 426 451 576 1453 1842 2105 2205 19 113 125 150 213 263 363 438 463 789 1716 2204 2580 2642 20 50 137 212 225 312 387 425 425 1161 2510 3471 4045 4158 Gage South Side CSS - microstrains 1 119 107 182 195 270 408 571 848 2066 2995 3924 4640 4866 22 31 44 4 94 82 56 194 320 458 859 1498 2113 2502 1398 44 63 88 101 176 201 226 452 427 905 2313 3067 3507 3771 63 38 38 165 167 6 1453 1842 2105 2205 3152 3152 3640 888 138 19 44 94 82 56 194 320 458 859 1498 2113 2502 1398 44 63 88 101 176 201 226 452 427 905 2313 3067 3507 3771 5428 31 19 444 94 82 56 194 320 458 859 1498 2113 2502 1398 44 63 88 101 176 201 226 452 427 905 2313 3067 3507 3771 63 363 63 63 63 190 164 291 316 455 544 1758 2277 2517 2795 85 13 38 165 241 114 228 329 228 798 1190 1431 1811 19 107 44 107 157 220 182 232 345 440 948 116 130 1229 1418 11 19 107 44 107 157 220 182 253 345 408 948 1162 1300 122 1418 11 19 107 44 107 157 220 182 258 345 408 948 1162 1300 122 1418 11 19 107 44 107 157 220 182 258 345 408 948 1162 1300 122 146 6 -44 69 81 56 119 94 169 131 181 457 494 444 15 6 -44 69 81 56 119 94 169 131 181 457 494 444 15 6 -44 69 81 56 119 94 169 131 181 457 494 444 15 6 -44 69 81 56 119 94 169 131 181 457 494 444 15 6 -44 69 81 56 119 94 169 131 181 457 494 444 15 6 -44 69 81 56 119 94 169 131 181 457 494 444 15 6 -44 69 81 56 119 94 169 131 181 457 494 444 15 6 -44 69 81 56 119 94 169 131 181 457 494 444 15														
8 69 94 106 131 169 219 219 244 319 419 1195 1370 1433 9 150 212 249 312 362 437 449 499 574 649 1272 1609 1659 10 100 125 113 138 225 275 263 288 426 501 1227 1402 1452 11 119 169 157 194 232 282 369 332 419 482 1196 1459 1596 12 106 156 193 243 268 380 405 417 455 442 442 479 579 13 62 62 -25 25 137 149 211 186 236 249 373 448 398 14 43 130 93 143 114 140 14														
9 150 212 249 312 362 437 449 499 574 649 1272 1609 1659 10 100 125 113 138 225 275 263 288 426 501 1227 1402 1452 11 119 169 157 194 232 282 369 332 419 482 1196 1459 1596 12 106 156 193 243 268 380 405 417 455 442 442 479 579 13 62 62 -25 25 137 149 211 186 236 249 373 448 398 14 43 130 93 143 192 291 291 391 416 1209 1743 1991 2053 15 112 174 161 273 310 372 409 447 509 1278 1762 1985 2035 16 81 106 144 181 219 331 343 381 531 1268 1780 1980 2042 17 81 119 169 207 219 332 370 470 696 2325 3152 3640 3803 18 88 138 163 163 1027 388 426 451 576 1453 1842 2105 2205 19 113 125 150 213 263 363 438 463 789 1716 2204 2580 2642 20 50 137 212 225 312 387 425 425 1161 2510 3471 4045 4158 Gage South Side CSS - microstrains 1 119 107 182 195 270 408 571 848 2066 2995 3924 4640 4866 2 31 -44 -94 19 -207 207 508 609 1839 3119 4223 5177 5428 3 19 -44 94 82 56 194 320 458 859 1498 2113 2502 1398 4 63 88 101 176 201 226 452 427 905 2313 3067 3507 3771 5 5 57 -44 6 -6 145 82 221 271 447 1380 2199 2161 2741 6 76 38 50 189 189 215 290 353 416 1679 2158 2486 2650 7 63 63 63 63 190 164 291 316 455 544 1758 2277 2517 2795 8 51 13 38 165 241 114 228 329 228 798 1190 1431 1811 19 107 44 19 57 195 183 284 359 460 435 561 1103 1229 1418 11 19 107 44 107 157 220 182 528 345 408 948 1162 1300 12 -6 44 19 57 195 183 284 359 460 435 561 1103 1229 1418 11 19 107 44 107 157 220 182 258 345 408 948 1162 1300 12 -6 44 19 57 195 183 284 359 460 435 561 1103 1229 1418 11 19 107 44 69 81 56 119 94 169 131 181 457 494 444 15 0 -25 -63 50 -38 50 63 125 175 363 1165 1617 1805 16 -6 -31 -56 118 6 -19 -31 31 455 841 1676 2162 2549 17 -112 -12 -50 -37 -25 50 62 37 -274 1159 2482 3683 388 19 112 62 12 99 236 409 409 682 918 1426 1885 2245 2109														
10														
11														
12														
13														
14														
15														
16														
17														
18 88 138 163 163 1027 388 426 451 576 1453 1842 2105 2205 19 113 125 150 213 263 363 438 463 789 1716 2204 2580 2642 20 50 137 212 225 312 387 425 425 1161 2510 3471 4045 4158 Gage South Side CSS - microstrains 1 119 107 182 195 270 408 571 848 2066 2995 3924 4640 4866 2 31 -44 -94 19 -207 207 508 609 1839 3119 4223 5177 5428 3 19 -44 94 82 56 194 320 458 859 1498 2113 2502 1398 4 63														
19														
Company Soluth Side CSS - microstrains 1 119 107 182 195 270 408 571 848 2066 2995 3924 4640 4866 2 31 -44 -94 19 -207 207 508 609 1839 3119 4223 5177 5428 3 19 -44 94 82 56 194 320 458 859 1498 2113 2502 1398 4 63 88 101 176 201 226 452 427 905 2313 3067 3507 3771 5 57 -44 6 -6 145 82 221 271 447 1380 2199 2161 2741 6 76 38 50 189 189 215 290 353 416 1679 2158 2486 2650 7 63 63														
Gage South Side CSS - microstrains 1 119 107 182 195 270 408 571 848 2066 2995 3924 4640 4866 2 31 -44 -94 19 -207 207 508 609 1839 3119 4223 5177 5428 3 19 -44 94 82 56 194 320 458 859 1498 2113 2502 1398 4 63 88 101 176 201 226 452 427 905 2313 3067 3507 3771 5 57 -44 6 -6 145 82 221 271 447 1380 2199 2161 2741 6 76 38 50 189 189 215 290 353 416 1679 2158 2486 2650 7 63 63													2580	
1 119 107 182 195 270 408 571 848 2066 2995 3924 4640 4866 2 31 -44 -94 19 -207 207 508 609 1839 3119 4223 5177 5428 3 19 -44 94 82 56 194 320 458 859 1498 2113 2502 1398 4 63 88 101 176 201 226 452 427 905 2313 3067 3507 3771 5 57 -44 6 -6 145 82 221 271 447 1380 2199 2161 2741 6 76 38 50 189 189 215 290 353 416 1679 2158 2486 2650 7 63 63 63 190 164 291 316<		50	137	212	225						2510	3471	4045	4158
2 31 -44 -94 19 -207 207 508 609 1839 3119 4223 5177 5428 3 19 -44 94 82 56 194 320 458 859 1498 2113 2502 1398 4 63 88 101 176 201 226 452 427 905 2313 3067 3507 3771 5 57 -44 6 -6 145 82 221 271 447 1380 2199 2161 2741 6 76 38 50 189 189 215 290 353 416 1679 2158 2486 2650 7 63 63 63 190 164 291 316 455 544 1758 2277 2517 2795 8 51 13 38 165 241 114 228	Gage													
3 19 -44 94 82 56 194 320 458 859 1498 2113 2502 1398 4 63 88 101 176 201 226 452 427 905 2313 3067 3507 3771 5 57 -44 6 -6 145 82 221 271 447 1380 2199 2161 2741 6 76 38 50 189 189 215 290 353 416 1679 2158 2486 2650 7 63 63 63 190 164 291 316 455 544 1758 2277 2517 2795 8 51 13 38 165 241 114 228 329 228 798 1190 1431 1811 9 32 6 183 233 158 271 359														4866
4 63 88 101 176 201 226 452 427 905 2313 3067 3507 3771 5 57 -44 6 -6 145 82 221 271 447 1380 2199 2161 2741 6 76 38 50 189 189 215 290 353 416 1679 2158 2486 2650 7 63 63 63 190 164 291 316 455 544 1758 2277 2517 2795 8 51 13 38 165 241 114 228 329 228 798 1190 1431 1811 9 32 6 183 233 158 271 359 384 435 964 1178 1494 1531 10 -44 19 57 195 183 284 359														
5 57 -44 6 -6 145 82 221 271 447 1380 2199 2161 2741 6 76 38 50 189 189 215 290 353 416 1679 2158 2486 2650 7 63 63 63 190 164 291 316 455 544 1758 2277 2517 2795 8 51 13 38 165 241 114 228 329 228 798 1190 1431 1811 9 32 6 183 233 158 271 359 384 435 964 1178 1494 1531 10 -44 19 57 195 183 284 359 460 435 561 1103 1229 1418 11 19 107 44 107 157 220 182	3		-44	94			1		458	859		2113	2502	1398
6 76 38 50 189 189 215 290 353 416 1679 2158 2486 2650 7 63 63 63 190 164 291 316 455 544 1758 2277 2517 2795 8 51 13 38 165 241 114 228 329 228 798 1190 1431 1811 9 32 6 183 233 158 271 359 384 435 964 1178 1494 1531 10 -44 19 57 195 183 284 359 460 435 561 1103 1229 1418 11 19 107 44 107 157 220 182 258 345 408 948 1162 1300 12 -6 44 19 270 220 282 220				101	176				427	905		3067	3507	3771
7 63 63 63 190 164 291 316 455 544 1758 2277 2517 2795 8 51 13 38 165 241 114 228 329 228 798 1190 1431 1811 9 32 6 183 233 158 271 359 384 435 964 1178 1494 1531 10 -44 19 57 195 183 284 359 460 435 561 1103 1229 1418 11 19 107 44 107 157 220 182 258 345 408 948 1162 1300 12 -6 44 19 270 220 282 220 345 646 571 1073 1486 1650 13 56 19 107 44 69 119 157		57										2199	2161	2741
8 51 13 38 165 241 114 228 329 228 798 1190 1431 1811 9 32 6 183 233 158 271 359 384 435 964 1178 1494 1531 10 -44 19 57 195 183 284 359 460 435 561 1103 1229 1418 11 19 107 44 107 157 220 182 258 345 408 948 1162 1300 12 -6 44 19 270 220 282 220 345 646 571 1073 1486 1650 13 56 19 107 44 69 119 157 257 282 345 1111 1312 1199 14 6 -44 69 81 56 119 94														2650
9 32 6 183 233 158 271 359 384 435 964 1178 1494 1531 10 -44 19 57 195 183 284 359 460 435 561 1103 1229 1418 11 19 107 44 107 157 220 182 258 345 408 948 1162 1300 12 -6 44 19 270 220 282 220 345 646 571 1073 1486 1650 13 56 19 107 44 69 119 157 257 282 345 1111 1312 1199 14 6 -44 69 81 56 119 94 169 131 181 457 494 444 15 0 -25 -63 50 -38 50 63													2517	2795
10 -44 19 57 195 183 284 359 460 435 561 1103 1229 1418 11 19 107 44 107 157 220 182 258 345 408 948 1162 1300 12 -6 44 19 270 220 282 220 345 646 571 1073 1486 1650 13 56 19 107 44 69 119 157 257 282 345 1111 1312 1199 14 6 -44 69 81 56 119 94 169 131 181 457 494 444 15 0 -25 -63 50 -38 50 63 125 175 363 1165 1617 1805 16 -6 -31 -56 118 6 -19 -31										228		1190	1431	1811
11 19 107 44 107 157 220 182 258 345 408 948 1162 1300 12 -6 44 19 270 220 282 220 345 646 571 1073 1486 1650 13 56 19 107 44 69 119 157 257 282 345 1111 1312 1199 14 6 -44 69 81 56 119 94 169 131 181 457 494 444 15 0 -25 -63 50 -38 50 63 125 175 363 1165 1617 1805 16 -6 -31 -56 118 6 -19 -31 31 455 841 1676 2162 2549 17 -112 -12 -50 -37 -25 50 62														
12 -6 44 19 270 220 282 220 345 646 571 1073 1486 1650 13 56 19 107 44 69 119 157 257 282 345 1111 1312 1199 14 6 -44 69 81 56 119 94 169 131 181 457 494 444 15 0 -25 -63 50 -38 50 63 125 175 363 1165 1617 1805 16 -6 -31 -56 118 6 -19 -31 31 455 841 1676 2162 2549 17 -112 -12 -50 -37 -25 50 62 37 -274 1159 2442 3052 3426 18 100 162 149 162 336 261 622	10	L										1103	1229	1418
13 56 19 107 44 69 119 157 257 282 345 1111 1312 1199 14 6 -44 69 81 56 119 94 169 131 181 457 494 444 15 0 -25 -63 50 -38 50 63 125 175 363 1165 1617 1805 16 -6 -31 -56 118 6 -19 -31 31 455 841 1676 2162 2549 17 -112 -12 -50 -37 -25 50 62 37 -274 1159 2442 3052 3426 18 100 162 149 162 336 261 622 796 1120 1692 2986 3683 3882 19 112 62 12 99 236 409 409														1300
14 6 -44 69 81 56 119 94 169 131 181 457 494 444 15 0 -25 -63 50 -38 50 63 125 175 363 1165 1617 1805 16 -6 -31 -56 118 6 -19 -31 31 455 841 1676 2162 2549 17 -112 -12 -50 -37 -25 50 62 37 -274 1159 2442 3052 3426 18 100 162 149 162 336 261 622 796 1120 1692 2986 3683 3882 19 112 62 12 99 236 409 409 682 918 1426 1885 2245 2109														1650
15 0 -25 -63 50 -38 50 63 125 175 363 1165 1617 1805 16 -6 -31 -56 118 6 -19 -31 31 455 841 1676 2162 2549 17 -112 -12 -50 -37 -25 50 62 37 -274 1159 2442 3052 3426 18 100 162 149 162 336 261 622 796 1120 1692 2986 3683 3882 19 112 62 12 99 236 409 409 682 918 1426 1885 2245 2109			<u></u>	L									1312	1199
16 -6 -31 -56 118 6 -19 -31 31 455 841 1676 2162 2549 17 -112 -12 -50 -37 -25 50 62 37 -274 1159 2442 3052 3426 18 100 162 149 162 336 261 622 796 1120 1692 2986 3683 3882 19 112 62 12 99 236 409 409 682 918 1426 1885 2245 2109	14	6	-44	1								457	494	444
17 -112 -12 -50 -37 -25 50 62 37 -274 1159 2442 3052 3426 18 100 162 149 162 336 261 622 796 1120 1692 2986 3683 3882 19 112 62 12 99 236 409 409 682 918 1426 1885 2245 2109	15	0			50					175	363	1165	1617	1805
17 -112 -12 -50 -37 -25 50 62 37 -274 1159 2442 3052 3426 18 100 162 149 162 336 261 622 796 1120 1692 2986 3683 3882 19 112 62 12 99 236 409 409 682 918 1426 1885 2245 2109	16	-6	-31									1676	2162	2549
19 112 62 12 99 236 409 409 682 918 1426 1885 2245 2109	17	-112	-12	-50	-37	-25	50	62	37	-274	1159	2442	3052	3426
19 112 62 12 99 236 409 409 682 918 1426 1885 2245 2109	18	100	162	149	162	336	261	622	796	1120	1692	2986	3683	3882
		112		12	99	236	409	409	682	918	1426			2109
20 -111 -12 -86 86 173 284 432 518 296 790 1086 1345 1370	20	-111	-12	-86	86	173	284	432	518	296	790	1086	1345	1370

S.9 G2A-West

Table S.9 Raw Concrete Surface Strains Data for Development Length Test G2A-West

Step	1	2	3	4	5	6	7	8	9	10	11	12
Load (Kips)	80	110	140	170	200	230	254	275	288	293	297	297

Gage	North Side CSS - microstrains											
1	19	31	106	156	144	156	406	431	556	668	981	1043
2	125	125	162	237	325	362	462	600	650	737	1149	1249
3	131	169	169	194	306	302	431					
4	200	250	300	350	375	275	499	518 562	581	606	1030	1105
5			150	200	250		363		475	712	1124	1236
6	163	150				325	381	463	450	475	588	725
	131	131	169 94	169 132	244	319		431	431	469	406	494
7	82 88	82	175		182	257	358 389	332	332	420	420	408
8		100		175	213	251		338	363	389	338	351
9	101	113	113	163	239	251	302	327	339	339	339	365
10	88	75	138	126	214	251	289	289	314	314	302	314
11	81	119	131	144	219	293	256	256	356	293	231	281
12	44 37	44 50	81 75	69 87	156	156	231 262	219	244	257	219	369
13	25	37	62	100	187 162	187	262	249 262	311 374	311 424	311 437	299
14 15	-31	-56	-94	-19	44	175 69	106	156	269			437
16	44	-36 44	- 94 81	81	131	144	169	194	319	406 382	381 382	344 382
17	-19	81	56	94	156	156	281	494	644	731	819	806
18	87	137	150	162	374	511	649	786	886	936	936	936
19	-12	125	87	150	312	387	561	699	798	811	798	786
20	25	62	62	112	262	399	511	623	711	773	760	760
	23	02	02	112		Side CS			/11	1/3	700	700
Gage 1	75	63	113	88	163	401	551	639	739	789	764	677
2	94	44	19	94	244	469	469	657	632	807	883	557
3	38	-13	38	0	188	400	526	613	676	763	888	876
4	56	6	81	-156	194	331	543	618	656	843	955	843
5	38	25	63	63	50	138	125	150	125	213	288	225
6	-6	-19	-6	19	6	94	81	119	-44	157	69	94
7	100	63	75	75	50	163	200	88	125	288	225	213
8	38	25	38	50	38	50	88	88	301	175	213	238
9	69	56	94	69	107	119	220	232	182	245	232	245
10	75	13	113	75	75	200	238	263	200	288	276	113
11	38	38	100	63	100	226	251	289	226	339	326	301
12	75	88	176	125	125	289	301	376	226	389	301	263
13	81	81	81	94	132	232	232	257	119	307	282	219
14	94	81	94	94	69	169	244	257	219	345	307	282
15	81	19	131	94	106	244	281	331	244	369	331	269
16	38	38	-13	63	113	-175	301	288	276	338	313	251
17	75	63	125	75	150	263	313	376	464	576	614	539
18	50	50	-251	75	151	276	301	402	402	515	565	528
19	119	107	169	132	207	207	383	458	445	533	621	558
20	82	56	144	107	119	295	345	433	408	533	496	445
	0Z	50	1-+4	10/	1 117	293	ر ادر	1 433	1 400		770	443

S.10 G2B-East

Table S.10 Raw Concrete Surface Strains Data for Development Length Test G2B-East

Step	1	2	3	4	5	6	7	8	9	10	11
Load (Kips)	100	151	184	218	248	278	308	338	369	398	425

Gage					North S	ide CSS	- microst	rains			
1	69	94	19	257	507	620	557	683	833	1058	1321
2	25	75	100	237	475	799	1336	1861	2423	2360	2548
3	88	138	113	200	213	338	851	1251	1726	1614	1651
4	19	94	144	131	169	356	868	1268	1880	3403	4477
5	62	125	162	187	175	437	912	1399	2049	3798	5072
6	69	132	144	182	232	257	69	307	546	2478	3707
7	94	144	182	194	232	320	345	320	683	2675	3840
8	81	194	244	207	257	370	357	420	533	946	1247
9	100	163	213	263	313	376	338	364	426	426	539
10	94	131	181	219	306	343	318	368	456	468	581
11	87	150	237	275	350	275	362	412	387	500	587
12	38	75	113	163	250	300	325	325	350	1213	1851
13	69	144	181	256	331	381	381	381	456	1307	1944
14	144	169	219	269	432	445	482	557	595	1384	2110
15	75	113	176	238	313	364	301	401	915	2019	2959
16	225	288	325	413	525	550	600	650	1126	1613	2051
17	138	213	225	263	400	400	413	438	1026	1501	2077
18	162	250	262	337	425	437	462	575	1624	2287	3111
19	119	181	218	306	418	468	530	692	1628	2177	3350
20	200	213	213	301	401	438	451	601	1466	2042	3132
Gage							- microst				
1	150	225	287	362	449	499	537	849	1585	2147	2983
2	100	237	250	349	424	449	474	1011	2495	3818	5277
3	200	200	287	300	1000	437	450	537	1700	2450	3274
4	144	194	244	306	319	331	394	444	1481	2181	2843
5	156	231	293	318	356	406	406	480	1603	2202	2876
6	156	181	219	231	331	369	356	344	756	1581	2244
7	243	256	256	343	418	455	356	393	468	1403	1990
8	118	181	218	268	318	330	343	368	442	1377	1975
9	268	293	318	418	393	443	430	492	654	1602	2362
10	143	168	230	280	318	342	355	367	342	504	679
11	87	124	124	211	236	224	211	261	298	410	609
12	218	230	255	305	392	342	305	218	342	753	1275
13	131	231	218	255	305	555	1066	1290	1913	3134	3969
14	206	193	243	281	218	792	805	1241	1815	3137	3948
15	131	144	182	232	244	507	908	1208	2410	2985	3774
16	50	125	125	175	150	438	950	1388	1925	2763	3263
17	94	106	143	181	193	243	305	493	480	355	318
18	93	131	156	181	405	529	-44	815	977	1077	1338
19	138	150	188	413	700	813	888	1126	1288	1388	1688
20	125	88	150	364	690	740	740	740	1041	1254	1505

S.11 G2B-West

Table S.11 Raw Concrete Surface Strains Data for Development Length Test G2B-West

Step	1	2	3	4	5	6	7	8	9	10	11	12
Load	100	150	180	210	240	270	300	322	334	341	342	328
(Kips)									55.	311	5,2	320

Gaga	North Side CSS - microstrains											
Gage	119	207	182	295	333					0455	0505	0160
2		175				345	1174	1940	2417	2455	2505	2467
	75		163	288	313	338	1215	1929	2392	2455	2429	2442
3	100	175	213	814	338	276	526	877	1140	1140	1178	1153
4	44	169	219	244	306	331	406	444	444	444	481	481
5	106	144	219	294	307	307	382	470	632	595	520	632
6	119	157	195	258	295	320	408	534	547	559	710	534
7	113	125	176	213	263	238	401	464	665	564	602	514
8	56	119	169	257	370	320	420	495	621	483	508	495
9	138	163	200	288	326	338	376	463	463	413	438	426
10	81	131	94	243	243	268	331	393	443	381	443	406
11	63	163	88	201	226	276	339	364	401	677	690	665
12	94	107	119	119	219	194	194	282	320	1085	1097	1110
13	94	132	132	169	232	232	307	383	408	1186	1161	1211
14	119	144	157	194	219	270	721	1097	1385	2063	2150	2000
15	106	106	106	156	193	306	717	1041	1303	1690	1653	1715
16	125	138	150	163	176	288	1154	1605	1931	1893	1806	1843
17	50	88	75	100	100	663	1402	1815	2065	2090	1977	1990
18	69	106	169	256	431	857	1257	1369	1294	1369	1219	1407
19	81	94	157	307	395	708	1122	1235	1322	1310	1285	1347
20	100	100	162	286	411	760	635	660	635	573	598	585
Gage								icrostrair				
1	50	125	113	301	401	840	966	1204	1442	1279	1204	1267
2	-19	69	56	206	332	594	870	1070	1145	1245	1107	1258
3	-50	-12	12	150	287	574	860	1210	1447	1609	1496	1596
4	31	69	143	168	168	243	643	1029	1254	1366	1341	1404
5	81	181	194	181	181	294	319	519	731	856	819	906
6	181	256	294	306	344	406	469	682	907	1007	1032	1119
7	88	138	138	188	201	226	276	376	439	439	439	464
8	81	106	106	131	194	256	294	356	394	406	381	431
9	31	69	107	144	182	220	295	320	358	295	282	307
10	31	82	94	94	170	207	257	295	345	283	257	295
11	50	213	151	188	251	377	352	339	414	377	377	427
12	101	164	201	214	327	390	466	516	579	730	768	793
13	100.	225	250	338	438	476	601	638	1077	1390	1390	1365
14	82	144	119	157	207	245	370	420	746	1160	1160	1160
15	113	225	263	275	413	413	588	588	938	1276	1326	1251
16	87	187	137	237	312	300	312	412	837	1000	987	975
17	-50	50	150	62	212	299	399	998	1222	1272	1235	1247
18	87	236	199	274	398	485	559	957	1405	1417	1430	1442
19	162	249	237	299	336	423	1482	2416	2890	3039	2952	2989
20	149	274	274	348	485	485	1467	2437	2860	2909	2872	2897
	لستنتسا						2.07	~ .5,	2000	2,0,	2012	2071

S.12 G2C-East

Table S.12 Raw Concrete Surface Strains Data for Development Length Test G2C-East

Step	1	2	3	4	5	6	7	8	9	10	11	12
Load												
(Kips)	100	150	180	210	241	270	300	330	353	364	367	358

Gage	North Side CSS - microstrains -25 -25 -38 63 75 263 288 326 339 326 312 220											
1	-25	-25	-38	63	75	263	288	326	339	326	313	339
2	12	0	12	50	337	887	1349	1749	1986	2024	1924	1849
3	-63	-75	-13	-25	225	563	1126	1877	2415	2402	2628	2740
4	19	119	131	106	393	780	1342	2079	2778	3302	3814	3851
5	-19	6	44	6	306	744	1357	2044	2794	3257	3870	3957
6	0	75	63	100	75	175	389	677	1191	1629	2356	2381
7	-19	106	507	420	507	457	495	695	1033	1609	1935	2023
8	19	-19	132	31	194	107	370	483	708	871	984	1034
9	-13	100	63	125	175	225	238	438	726	864	989	876
10	56	94	144	156	219	256	306	519	1119	1444	1519	1482
11	-6	-344	-244	-6	31	131	131	331	631	656	781	756
12	-37	112	50	125	187	287	237	625	1112	1387	1399	1474
13	50	100	113	200	263	325	363	688	1138	1425	1538	1525
14	113	113	163	238	338	413	451	689	1077	1340	1528	1528
15	44	144	144	219	282	320	395	746	1585	1936	2087	2036
16	131	156	181	244	307	1020	419	907	. 1583	1821	2009	1971
17	94	194	169	257	307	432	532	1584	2585	2998	3161	3136
18	25	150	137	262	350	387	487	1425	2312	2650	2687	2675
19	94	194	181	319	419	469	569	1419	1920	2257	2320	2320
20	138	163	200	401	451	576	1352	2691	3267	3543	3693	3618
Gage								rostrains				
1	212	299	312	362	412	512	711	1772	2895	3406	3681	3805
2	175	200	287	324	337	387	474	1297	2358	2857	3194	3281
3	150	213	288	338	375	450	513	1326	2377	2865	3165	3228
4	144	206	256	294	331	381	444	719	1031	1119	1194	1156
5	150	175	225	275	288	350	438	688	988	1113	1188	1163
6	112	125	200	250	262	325	425	612	887	999	1124	1187
7	175	175	237	300	325	362	462	924	1585	1835	2122	2122
8	131	168	193	255	255	293	330	579	916	1140	1265	1227
9	56	168	193	218	255	330	380	741	1451	1799	1949	1924
10	187	212	249	287	299	349	337	798	1471	1820	1970	1870
11	124	124	137	237	249	249	361	610	921	934	996	1008
12	99	99	124	162	211	211	311	559	821	945	995	982
13	125	149	174	262	249	237	672	1445	2192	2553	2727	2727
14	87	87	100	175	125	437	1673	2784	3708	4232	4606	4631
15	6	44	94	106	106	644	1469	2406	3256	3744	4069	4119
16	94	194	219	256	269	744	1632	2583	3433	3934	4271	4322
17	168	131	131	81	243	792	1154	1366	1466	1616	1803	1753
18	100	124	274	585	710	1145	884	959	1033	909	1145	1083
19	188	225	263	626	714	852	989	1127	1240	1302	1378	1353
20	-50	0	88	364	451	602	727	865	978	1053	1116	1040

S.13 G2C-West

Table S.13 Raw Concrete Surface Strains Data for Development Length Test G2C-West

Step	1	2	3	4	5	6	7	8	9	10
Load (Kips)	100	150	158	188	218	244	262	277	287	291

Gage	<u> </u>			Nort	h Side C	SS - micro	ostrains			······
1	157	-220	-144	69	19	94	144	1186	1838	1788
2	25	63	50	188	238	326	388	1504	2055	2018
3	81	94	219	244	307	395	395	1046	1410	1798
4	38	100	213	250	313	401	401	488	501	914
5	82	107	320	157	245	282	270	408	445	821
6	44	132	-44	82	182	257	195	282	395	697
7	-113	25	-25	50	125	163	301	326	376	313
8	13	100	125	75	251	238	188	225	463	576
9	0	75	38	163	150	275	150	225	350	275
10	25	125	187	237	299	299	312	412	449	462
11	-157	-69	-19	-56	6	-220	-82	31	220	94
12	628	703	653	778	828	916	929	941	954	1105
13	-38	163	489	188	339	238	389	301	564	502
14	-295	56	56	69	94	144	784	1097	846	1022
15	31	156	119	256	293	331	879	1254	1541	1690
16	-501	-38	-238	-50	125	225	476	914	1215	1352
17	-401	-263	-213	-226	150	-25	150	677	777	902
18	6	69	19	294	369	620	507	1058	1221	1334
19	-6	-31	-119	294	382	607	282	545	532	557
20	212	-12	-149	324	448	660	436	511	398	374
Gage						SS - micro				
1	44	44	56	257	433	596	496	534	559	571
2	75	25	75	275	463	613	525	550	538	563
3	69	81	94	330	518	692	667	705	692	667
4	13	-25	25	125	50	125	963	1263	1363	1413
5	56	44	56	94	144	206	1155	1455	1630	1792
6	31	44	56	94	119	132	1134	1523	1836	2024
7	38	63	75	113	138	188	1089	1453	1778	2004
8	75	87	87	100	162	225	275	362	550	675
9	31	69	56	94	132	169	194	220	358	470
10	50	75	125	151	163	238	238	238	326	339
11	50	63	63	113	138	201	213	201	264	289
12	101	38	88	227	227	252	365	328	403	416
13	-6	19	19	131	94	169	206	194	307	307
14	44	69	69	144	169	219	269	257	307	219
15	38	100	113	200	263	313	388	413	550	900
16	19	19	19	69	156	206	281	319	419	743
17	87	112	125	150	225	249	324	387	499	836
18	75	124	112	149	199	249	261	286	460	236
19	62	75	137	174	162	249	299	1331	1941	2103
20	62	112	149	199	211	273	336	1293	1926	2138

VITA

Lieutenant Colonel (LTC) Karl F. Meyer was born in San Diego, California on January 14, 1962. In 1984 he received a Bachelor of Science degree from the U.S. Military Academy at West Point and was commissioned a Second Lieutenant in the United States Army. He served as a platoon leader, company executive officer and battalion civil engineer in the 864th Engineer Battalion at Fort Lewis, Washington. While serving as a company commander in the 92nd Engineer Battalion at Fort Stewart, Georgia, LTC Meyer was deployed to the Persian Gulf region for Operations Desert Shield and Desert Storm where he was awarded the Bronze Star Medal. In 1993, he earned a Master of Science degree in Civil Engineering from the Georgia Institute of Technology. From 1993 through 1996, he served as an instructor and assistant professor in the Department of Civil and Mechanical Engineering at the U.S. Military Academy. In 1997, LTC Meyer graduated from the U.S. Army Command and General Staff College and was assigned to the 130th Engineer Brigade in Hanau, Germany where he served as the Brigade Executive Officer and Brigade S-3. In 1999, LTC Meyer was selected to be a permanent faculty member in the Department of Civil and Mechanical Engineering at the U.S. Military Academy and returned to the Georgia Institute of Technology to pursue a Doctor of Philosophy degree in civil engineering. LTC Meyer was awarded a Doctor of Philosophy in Civil Engineering in 2002. LTC Meyer holds a Professional Engineer license in the state of Virginia. He is married to the former Robin Carlene Heath of Stone Mountain, Georgia and has two children, Abigail and John.